NATIONAL GREENHOUSE GAS INVENTORY DOCUMENT OF THE CZECH REPUBLIC

SUBMISSION UNDER UNFCCC AND PARIS AGREEMENT

REPORTED INVENTORIES 1990–2024

Prague

March 2026

Czech Hydrometeorological Institute

Ministry of the Environment of the Czech Republic

Elaborated by institutions involved in National Inventory System:

KONEKO, CDV, CHMI, IFER, CRI, GCRI, CENIA
with contribution of MoE and OTE
Compiled by editors at CHMI

Title: National Greenhouse Gas Inventory Document of the Czech Republic (reported inventories 1990- 2024)
Contact: Jitka Slamova
Organization: Czech Hydrometeorological Institute
Address: Na Sabatce 17, Praha 4 – Komorany, 143 06 Czech Republic
E-mail: jitka.slamova@chmi.cz
ISBN: 978-80-7653-088-1
© Czech Hydrometeorological Institute, 2026

Authors of individual chapters

Editors		Risto Saarikivi	(CHMI)
		Barbora Koci	(CHMI)
		Jitka Slamova	(CHMI)
		Monika Filipenska	(CHMI)
Executive Summary		Jitka Slamova	(CHMI)
		Risto Saarikivi	(CHMI)
Chapter 1	Introduction and General Issues	Jitka Slamova	(CHMI)
		Risto Saarikivi	(CHMI)
		Barbora Koci	(CHMI)
		Tomas Hammerbauer	(CHMI)
		Eva Krtkova	(CHMI)
Chapter 2	Trend in Total Emissions	Jitka Slamova	(CHMI)
		Risto Saarikivi	(CHMI)
Chapter 3	Energy (CRT sector 1)	Barbora Votavova	(KONEKO)
		Andrea Vesela	(KONEKO)
		Leos Pelikan	(CDV)
		Zuzana Kacmarova	(CDV)
Chapter 4	Industrial Processes and Product Use (CRT sector 2)	Barbora Koci	(CHMI)
		Jitka Slamova	(CHMI)
Chapter 5	Agriculture (CRT sector 3)	Jana Beranova	(IFER)
		Jan Klir	(CARC)
		Jana Wollnerova	(CARC)
		Miroslav Trnka	(GCRI)
Chapter 6	LULUCF (CRT sector 4)	Emil Cienciala	(IFER)
		Radka Maskova	(IFER)
		Ondřej Cerny	(IFER)
		Alexander Ac	(GCRI)
Chapter 7	Waste (CRT sector 5)	Monika Filipenska	(CHMI)
		Risto Saarikivi	(CHMI)
Chapter 9	Indirect CO_2 and Nitrous oxide emissions	Risto Saarikivi	(CHMI)
Chapter 10	Recalculations and Improvements	Barbora Koci	(CHMI)
		Risto Saarikivi	(CHMI)
Annexes		Tomas Hammerbauer	(CHMI)
		Jitka Slamova	(CHMI)
		Eva Krtkova	(CHMI)
		Emil Cienciala	(IFER)
		Barbora Votavova	(KONEKO)
		Miroslav Havranek	(CENIA)
		Jana Beranova	(IFER)

The editors would like to acknowledge, that preparation of GHG Inventory is evolutionary process which could not have been accomplished today without the efforts of its former contributors. In particular, we wish to acknowledge the efforts of Jan Apltauer, Jan Blaha, Jiri Dufek, Pavel Fott, Jan Pretel, Ondrej Minovsky, Dusan Vacha, Miroslav Rehor, Martin Beck, Denitsa Svobodová, Beata Ondrusova, Marketa Klusackova, Ivana Kopecka, Vladimir Neuzil and Zuzana Roskova.

Contents

EXECUTIVE SUMMARY **7**

ES 1 VYKAZOVÁNÍ BILANCÍ EMISÍ A PROPADŮ SKLENÍKOVÝCH PLYNŮ V ČESKÉ REPUBLICE **8**

ES 2 BACKGROUND INFORMATION ON GREENHOUSE GAS (GHG) INVENTORIES AND CLIMATE CHANGE **9**

ES 3 SUMMARY OF NATIONAL EMISSION AND REMOVAL RELATED TRENDS **10**

ES 3.1 GHG INVENTORY 10

ES 4 OVERVIEW OF SOURCE AND SINK CATEGORY EMISSION ESTIMATES AND TRENDS **11**

ES 4.1 GHG INVENTORY 12

ES 5 OTHER INFORMATION **15**

ES 5.1 OVERVIEW OF EMISSION TRENDS OF OTHER GASES AND NH_3 15

ANNUAL INVENTORY SUBMISSION **17**

1 INTRODUCTION **18**

1.1 BACKGROUND INFORMATION ON GHG INVENTORIES AND CLIMATE CHANGE 18
1.2 A DESCRIPTION OF THE NATIONAL INVENTORY ARRANGEMENTS 20
1.3 INVENTORY PREPARATION, AND DATA COLLECTION, PROCESSING AND STORAGE 38
1.4 BRIEF GENERAL DESCRIPTION OF METHODOLOGIES (INCLUDING TIERS USED) AND DATA SOURCES USED 40
1.5 BRIEF DESCRIPTION OF KEY CATEGORIES 41
1.6 GENERAL UNCERTAINTY EVALUATION, INCLUDING DATA ON THE OVERALL UNCERTAINTY FOR THE INVENTORY TOTALS 45
1.7 GENERAL ASSESSMENT OF COMPLETENESS 45

2 TRENDS IN GREENHOUSE GAS EMISSIONS **47**

2.1 DESCRIPTION AND INTERPRETATION OF EMISSION TRENDS BY SECTOR 50

3 ENERGY (CRT SECTOR 1) **58**

3.1 OVERVIEW OF SECTOR 58
3.2 FUEL COMBUSTION ACTIVITIES (CRT 1.A) 63
3.3 FUGITIVE EMISSIONS FROM SOLID FUELS AND OIL AND NATURAL GAS AND OTHER EMISSIONS FROM ENERGY PRODUCTION (CRT 1.B) 141
3.4 CO_2 TRANSPORT AND STORAGE (CRT 1.C) 172

4 INDUSTRIAL PROCESSES AND PRODUCT USE (CRT SECTOR 2) **173**

4.1 OVERVIEW OF SECTOR 173
4.2 MINERAL INDUSTRY (CRT 2.A) 175
4.3 CHEMICAL INDUSTRY (CRT 2.B) 188
4.4 METAL INDUSTRY (CRT 2.C) 203
4.5 NON-ENERGY PRODUCTS FROM FUELS AND SOLVENT USE (CRT 2.D) 210
4.6 ELECTRONICS INDUSTRY (CRT 2.E) 215
4.7 PRODUCT USES AS SUBSTITUTES FOR OZONE DEPLETING SUBSTANCES (ODS) (CRT 2.F) 217
4.8 OTHER PRODUCT MANUFACTURE AND USE (CRT 2.G) 230
4.9 OTHER (CRT 2.H) 237
4.10 ACKNOWLEDGEMENT 237

5 AGRICULTURE (CRT SECTOR 3) **238**

5.1 OVERVIEW OF SECTOR 238
5.2 LIVESTOCK (CRT 3.1) 244
5.3 RICE CULTIVATION (ETF 3C) 275
5.4 AGRICULTURAL SOILS (CRT 3.D) 275
5.5 PRESCRIBED BURNING OF SAVANNAS (CRT 3.E) 291
5.6 FIELD BURNING OF AGRICULTURAL RESIDUES (CRT 3.F) 291
5.7 LIMING (CRT 3.G) 291
5.8 UREA APPLICATION (CRT 3.H) 294

5.9 ACKNOWLEDGEMENT 296
6 LAND USE, LAND-USE CHANGES AND FORESTRY (CRT SECTOR 4) 297
6.1 OVERVIEW OF SECTOR 297
6.2 INFORMATION ON APPROACHES USED FOR REPRESENTING LAND AREAS AND ON LAND-USE DATABASES USED FOR THE INVENTORY PREPARATION 300
6.3 LAND-USE DEFINITIONS AND THE CLASSIFICATION SYSTEMS USED AND THEIR CORRESPONDENCE TO THE LAND USE, LAND-USE CHANGE AND FORESTRY CATEGORIES 304
6.4 FOREST LAND (CRT 4.A) 307
6.5 CROPLAND (CRT 4.B) 330
6.6 GRASSLAND (CRT 4.C) 338
6.7 WETLANDS (CRT 4.D) 343
6.8 SETTLEMENTS (CRT 4.E) 346
6.9 OTHER LAND (CRT 4.F) 349
6.10 HARVESTED WOOD PRODUCTS (CRT 4.G) 350
6.11 ACKNOWLEDGEMENT 353
7 WASTE (CRT SECTOR 5) 354
7.1 OVERVIEW OF SECTOR 354
7.2 SOLID WASTE DISPOSAL (CRT 5.A) 355
7.3 BIOLOGICAL TREATMENT OF SOLID WASTE (CRT 5.B) 363
7.4 INCINERATION AND OPEN BURNING OF WASTE (CRT 5.C) 367
7.5 WASTEWATER TREATMENT AND DISCHARGE (CRT 5.D) 377
7.6 OTHER (CRT 5.E) 387
7.7 LONG-TERM STORAGE OF CARBON (CRT 5.F) 387
8 OTHER (CRT SECTOR 6) 389
9 INDIRECT CO_2 AND NITROUS OXIDE EMISSIONS 390
9.1 DESCRIPTION OF SOURCES OF INDIRECT EMISSIONS IN GHG INVENTORY 390
9.2 PRODUCTION OF INDIRECT EMISSIONS FROM PRECURSOR GASES 393
9.3 PRODUCTION OF INDIRECT CO_2 AND N_2O EMISSIONS FROM SOURCE CATEGORIES 396
9.4 METHODOLOGICAL ISSUES 397
9.5 UNCERTAINTIES AND TIME-SERIES CONSISTENCY 399
9.6 SOURCE-SPECIFIC QA/QC AND VERIFICATION 399
9.7 SOURCE-SPECIFIC RECALCULATIONS, INCLUDING CHANGES MADE IN RESPONSE TO THE REVIEW PROCESS AND IMPACT ON EMISSION TREND 399
9.8 SOURCE-SPECIFIC PLANNED IMPROVEMENTS, INCLUDING I RESPONSE TO THE REVIEW PROCESS 400
10 RECALCULATIONS AND IMPROVEMENTS 401
10.1 EXPLANATIONS AND JUSTIFICATIONS FOR RECALCULATIONS, INCLUDING IN RESPONSE TO THE REVIEW PROCESS 401
10.2 IMPLICATIONS FOR EMISSION LEVELS 409
10.3 IMPLICATIONS FOR EMISSION TRENDS, INCLUDING TIME-SERIES CONSISTENCY 414
10.4 PLANNED IMPROVEMENTS, INCLUDING IN RESPONSE TO THE REVIEW PROCESS 417
11 OTHER INFORMATION 422
REFERENCES 423
ABBREVIATIONS 437
LIST OF FIGURES 440
LIST OF TABLES 444
ANNEXES TO THE NATIONAL INVENTORY DOCUMENT 450
ANNEX 1 KEY CATEGORIES 451
ANNEX 2 ASSESSMENT OF UNCERTAINTY 485
ANNEX 3 DETAILED METHODOLOGICAL DESCRIPTIONS FOR INDIVIDUAL SOURCES OR SINK CATEGORIES 501

A 3.1 UPDATES OF THE COUNTRY SPECIFIC EMISSION AND OXIDATION FACTORS FOR DETERMINATION OF CO_2 EMISSIONS FROM COMBUSTION OF BITUMINOUS COAL AND LIGNITE (BROWN COAL) IN THE CZECH REPUBLIC 501
A 3.2 COUNTRY SPECIFIC CO_2 EMISSION FACTOR FOR LPG 508
A 3.3 COUNTRY SPECIFIC CO_2 EMISSION FACTOR FOR REFINERY GAS 509
A 3.4 COUNTRY SPECIFIC CO_2 EMISSION FACTOR FOR NATURAL GAS COMBUSTION 511
A 3.5 COUNTRY SPECIFIC CO_2 EMISSION FACTOR FOR LIME PRODUCTION 516
A 3.6 CBM-CFS3 MODEL – CALIBRATION, USE AND VERIFICATION 519
A 3.7 COLLECTION OF F-GASES ACTIVITY DATA IN THE CZECH REPUBLIC 539
A 3.8 AGRICULTURAL SOILS (ETF 3D) – ADDITIONAL INFORMATION ON CLIMATIC ANALYSIS 544

ANNEX 4 THE NATIONAL ENERGY BALANCE FOR THE MOST RECENT INVENTORY YEAR 549

A 4.1 ENERGY BALANCE 549
A 4.2 DIFFERENCES BETWEEN STATISTICAL DATA REPORTED IN EUROSTAT AND CZSO 556

ANNEX 5 ANY ADDITIONAL INFORMATION, AS APPLICABLE 561

A 5.1 IMPROVED RATIO NCV/GCV FOR NATURAL GAS 561
A 5.2 IMPROVED RATIO NCV/GCV FOR COKE OVEN GAS 562
A 5.3 NET CALORIFIC VALUES OF INDIVIDUAL TYPES OF FUELS IN THE PERIOD 1990–2023 562
A 5.4 OXIDATION FACTOR FOR WASTE INCINERATION (CRT SECTOR 5.C) 566
A 5.5 GENERAL QUALITY CONTROL PROTOCOL USED IN NIS 568
A 5.6 COMPLETENESS CHECK FOR CONTROLLING CRT TABLES AND DATA IN THE ETF REPORTING TOOL 576

Executive Summary

ES 1 Vykazování bilancí emisí a propadů skleníkových plynů v České republice

Jakožto jedna ze stran Rámcové Úmluvy OSN o změně klimatu má Česká republika povinnost připravovat a pravidelně aktualizovat národní inventarizace vykazování emisí a propadů skleníkových plynů. V souladu s článkem 13, odstavcem 7(a), Pařížské dohody poskytuje Česká republika národní inventurní zprávu o antropogenních emisích z jednotlivých zdrojů a o odstraňování skleníkových plynů. Národní inventurní zpráva se skládá z tohoto národního inventurního dokumentu (NID) a společných reportingových tabulek (CRTs). Česká republika hlásí informace uvedené v modalitách, postupech a pokynech (MPGs) bez využívání flexibilních možností, protože je zemí přílohy I. Kromě toho z členství v Evropské Unii plynou pro Českou republiku další požadavky, např. plnění povinností specifikovaných v Nařízení EU č. 2018/1999 a jeho prováděcích nažízeních (konkrétně Prováděcí nař. č. 2020/1208). Tato verze národní inventarizační zprávy prezentuje úrovně emisí skleníkových plynů pro časovou řadu 1990 až 2024 s důrazem na poslední vykazovaný rok, tedy 2024. Všechny dříve provedené změny ve vykazování jsou i nadále součástí tohoto dokumentu.

Inventarizace emisí a propadů skleníkových plynů byla připravena v souladu s metodickými pokyny Mezivládního panelu pro změnu klimatu: IPCC 2006 Guidelines a IPCC 2019 Refinement. Konkrétní využití této metodiky a využití územně specifických postupů je popsáno v jednotlivých kapitolách níže. V případě, že dojde ke zpřesnění metodických postupů, vyvstává v řadě případů potřeba přepočítat vykázané emise v celé časové řadě. Tím se udržuje konzistentní přístup k vykazování emisí.

Národní inventarizační zpráva je připravena podle požadavků metodického pokynu Rámcové Úmluvy OSN o změně klimatu.

Tato inventarizační zpráva používá pro vykazování emisí v CO_2 ekvivalentu potenciály globálního ohřevu dle 5. Hodnotící zprávy IPCC (Fifth Assessment Report – IPCC).

Obě části submise, kterými je Národní inventarizační dokument společně s oficiálními tabulkami pro reporting (CRT – Common Reporting Format), jsou každoročně odesílány k 15. březnu Evropské Komisi a k 15. dubnu sekretariátu Rámcové Úmluvy OSN o změně klimatu. Od roku 2024 jsou data odevzdávána ve formátu CRT (Common Reporting Tables).

ES 2 Background information on greenhouse gas (GHG) inventories and climate change

As a Party and Annex I country to the United Nations Framework Convention on Climate Change (UNFCCC), the Czech Republic is required to prepare national greenhouse gas (GHG) inventories annually. Pursuant to Article 13, paragraph 7(a), of the Paris Agreement, the Czech Republic provides a national inventory document of anthropogenic emissions by sources and removals by sinks of GHGs. The national inventory document consists of this national inventory document (NID) and the common reporting tables (CRTs). The Czech Republic reports the information referred to in Modalities, procedures and guidelines (MPGs) without using flexibility options as it is Annex I country. In addition, as a result of membership in the European Union (EU), the Czech Republic must also fulfil its reporting requirements concerning GHG emissions and removals under article 26 of the EU Governance Regulation. The national inventory document is submitted annually to the EU by the 15th of March and to the UNFCCC by the 15th of April, except in 2024, when submission to the UNFCCC was by the 31st of December.

This edition of National Inventory Document (NID) deals with national greenhouse gas inventories for the period 1990 to 2024 with specific accent on the latest year 2024 while keeping track of already implemented changes according to the previous versions. By the term Submission 2026 is meant emissions and removals of greenhouse gases for the time series 1990–2024 submitted in 2026.

Inventories of emissions and removals of greenhouse gases were prepared in accordance with the IPCC methodology: the 2006 IPCC Guidelines for national Greenhouse Gas Inventories (IPCC, 2006) and the 2019 Refinement (IPCC, 2019). Application of this general methodology on country specific circumstances is described in category-specific chapters. When a method used to estimate emissions is improved or when some gaps are identified, a need to recalculate the whole time series may arise in order to maintain consistency. This means that data presented this year can be changed in the next submission.

The National Inventory Document is elaborated in accordance with the UNFCCC reporting guidelines on annual inventories for Parties included in Annex I to the Convention (UNFCCC, 2013).

Submission is using the global warming potentials provided by the Fifth Assessment Report of the IPCC.

The Czech Republic declines any responsibility of errors caused by the UNFCCC ETF reporting tool, the latest version 1.30.5 of the ETF tool from the 9th of December 2025 was used for creating the submission.

ES 3 Summary of national emission and removal related trends

ES 3.1 GHG inventory

In 2024, the most important GHG in the Czech Republic was CO2 contributing 79.23% to total national GHG emissions and removals expressed in CO_2 eq. (incl. LULUCF), followed by CH_4 12.10% and N_2O 4.74%. PFCs, HFCs, SF_6 and NF_3 contributed for 3.93% to the overall GHG emissions in the country.

Tab. ES 1 provides data on GHG emissions in comparison of overall trend from 1990 to 2024. For overview of GHG emissions and removals by categories please see chapter ES 4.1.

Tab. ES 1 GHG emission/removal overall trends

	Base year	2024	Base year	2024	Trend
	[kt CO_2 eq.]		%		
CO_2 emissions without net CO_2 from LULUCF	164 337.86	77 221.89	85.06	80.26	-53.01
CO_2 emissions with net CO_2 from LULUCF	154 774.78	72 560.65	84.24	79.23	-53.12
CH_4 emissions without CH_4 from LULUCF	23 132.02	11 073.18	11.97	11.51	-52.13
CH_4 emissions with CH_4 from LULUCF	23 157.01	11 082.13	12.60	12.10	-52.14
N_2O emissions without N_2O from LULUCF	5 643.67	4 317.20	2.92	4.49	-23.50
N_2O emissions with N_2O from LULUCF	5 716.26	4 339.04	3.11	4.74	-24.09
F-gases	86.57	3598.51	0.04	3.93	
Total (without LULUCF)	193 200.12	96 210.79			-50.20
Total (with LULUCF)	183 734.62	91 580.33			-50.16
Total (without LULUCF, with indirect)	194 794.93	96 597.16			-50.41
Total (with LULUCF, with indirect)	185 329.44	91 966.70			-50.38

Over the period 1990–2024 CO_2 emissions and removals decreased by 53.12%, CH_4 emissions decreased by 52.14% during the same period mainly due to lower emissions from 1 Energy and 3 Agriculture; N_2O emissions decreased by 24.09% over the same period due to emission reduction in 3 Agriculture. Emissions of HFCs and PFCs increased by orders of magnitude, whereas SF_6 emissions kept steady trend over the whole period.

ES 4 Overview of source and sink category emission estimates and trends



Fig. ES 1 Sources and sinks of greenhouse gases in 1990 (kt CO_2 eq.)

ES 4.1 GHG inventory

Tab. ES 2 Overview of GHG emission/removal trends by CRT categories

	Base year kt CO_2 eq.	2024 kt CO_2 eq.	2024 Total share [%]	2024 Sectoral share [%]	Trend %
1. Energy	159752.16	72139.47	78.77	100.00	-54.84
A. Fuel combustion (sectoral approach)	149390.66	71223.64	77.77	98.73	-52.32
1. Energy industries	56830.03	31888.01	34.82	44.20	-43.89
2. Manufacturing industries and construction	47105.11	8864.87	9.68	12.29	-81.18
3. Transport	11270.32	20758.73	22.67	28.78	84.19
4. Other sectors	33990.91	9461.84	10.33	13.12	-72.16
5. Other	194.31	250.19	0.27	0.35	28.76
B. Fugitive emissions from fuels	10361.50	915.83	1.00	1.27	-91.16
1. Solid fuels	9163.83	538.91	0.59	0.75	-94.12
2. Oil and natural gas and other emissions from energy production	1197.66	376.92	0.41	0.52	-68.53
C. CO_2 transport and storage	NO	NO	NA	NA	0.00
2. Industrial Processes	17114.96	11102.40	12.12	100.00	-35.13
A. Mineral industry	4082.45	2475.60	2.70	22.30	-39.36
B. Chemical industry	2825.39	1665.00	1.82	15.00	-41.07
C. Metal industry	9811.61	3045.05	3.33	27.43	-68.96
D. Non-energy products from fuels and solvent use	125.56	118.55	0.13	1.07	-5.58
E. Electronic industry	NO	41.51	0.05	0.37	100.00
F. Product uses as ODS substitutes	NO	3491.55	3.81	31.45	100.00
G. Other product manufacture and use	269.95	264.03	0.29	2.38	-2.19
H. Other	NO	1.11	NA	NA	100.00
3. Agriculture	13013.57	7447.32	8.13	100.00	-42.77
A. Enteric fermentation	6523.38	3697.98	4.04	49.66	-43.31
B. Manure management	2514.73	761.71	0.83	10.23	-69.71
C. Rice cultivation	NA NO	NA NO	NA	NO	0.00
D. Agricultural soils	2630.22	2663.68	2.91	35.77	1.27
E. Prescribed burning of savannas	NA	NA	NA	NO	0.00
F. Field burning of agricultural residues	NA NO	NA NO	NA	NO	0.00
G. Liming	1236.71	132.49	0.14	1.78	-89.29
H. Urea application	108.53	191.47	0.21	2.57	76.41
I. Other carbon-containing fertilizers	NO	NO	NA	NA	0.00
J. Other	NA	NA	NA	NA	0.00
4. Land use, land-use change and forestry	-9465.50	-4630.46	-5.06	100.00	-51.08
A. Forest land	-8363.45	-2905.36	-3.17	62.74	-65.26
B. Cropland	284.93	97.51	0.11	-2.11	-65.78
C. Grassland	-188.59	-818.01	-0.89	17.67	333.76
D. Wetlands	-14.55	11.65	0.01	-0.25	-180.12
E. Settlements	496.64	269.18	0.29	-5.81	-45.80
F. Other land	NA NO	NA NO	NA	NO	0.00
G. Harvested wood products	-1680.47	-1285.43	-1.40	27.76	-23.51
H. Other	NO	NO	NA	NA	0.00
5. Waste	3319.42	5521.60	6.03	100.00	66.34
A. Solid waste disposal	2007.82	3824.24	4.18	69.26	90.47
B. Biological treatment of solid waste	IE NE	562.79	0.61	10.19	100.00
C. Incineration and open burning of waste	20.43	78.37	0.09	1.42	283.67
D. Waste water treatment and discharge	1291.18	1056.20	1.15	19.13	-18.20
E. Other	NO	NO	NA	NA	0.00
Total CO_2 equivalent emissions without land use, land-use change and forestry	193200.12	96210.79			-50.20
Total CO_2 equivalent emissions with land use, land-use change and forestry	183734.62	91580.33			-50.16
Total CO_2 equivalent emissions, including indirect CO_2, without land use, land-use change and forestry	194794.93	96597.16			-50.41
Total CO_2 equivalent emissions, including indirect CO_2, with land use, land-use change and forestry	185329.44	91966.70			-50.38

In 2024, 72 139.47 kt CO_2 eq. that are 78.77% of national total emissions (including 4 Land Use, Land-Use Change and Forestry) arose from 1 Energy; 98.73% of these emissions arise from fuel combustion activities. The most important sub-category of 1 Energy with 44.20% of total sectoral emissions in 2024 is 1.A.1 Energy Industries, 1.A.2 Manufacturing Industries and Construction responses for 12.29% and 1.A.3 Transport for 28.78% of total sectoral emissions. From 1990 to 2024 emissions from 1 Energy decreased by 54.84%. According the EEA provisional data, the main drivers for the recent 2019 - 2024 decrease in the Energy sector GHG emissions have been decrease in the primary energy consumption (PEC) of fossil solid fuel (-39.%), PEC gaseous fossil fuels (-19%) and increase in PEC renewable fuels (10%). Contrary to the positive development, PEC fossil liquid fuels increased (6%) (EEA, 2025).

2 Industrial Processes is the second largest category with 12.12% of total GHG emissions (including 4 Land Use, Land-Use Change and Forestry) in 2024 (11 102.40kt CO_2 eq.); the largest sub-category is 2.F Product Uses as ODS substitutes with 31.45% of sectoral share. From 1990 to 2024 emissions from 2 Industrial Processes decreased by -35.13%. In category 2.C Metal production, emissions fell sharply due to the final closure of one of the two largest steel producers in the Czech Republic. In category 2.A Mineral industry, ongoing reduced demand in the construction sector led to lower production of cement and lime, resulting in decreased process emissions. For category 2.F Use of fluorinated gases, the continued impact of EU regulation on F-gases contributed to reduced consumption of high-GWP gases and lower emissions.

3 Agriculture is the third largest category in the Czech Republic with 8.13% share of total GHG emissions (including 4 Land Use, Land-Use Change and Forestry) in 2024 (7 447.32 kt CO_2 eq.); 49.66% of these emissions arose from 3.A. Enteric fermentation and 35.77% arouse from 3.D Agricultural Soils. From 1990 to 2024 emissions from 3 Agriculture decreased by 42.77%. Total estimated emissions for 2024 are approximately 11% higher than those estimated for 2023. The increase in emissions is mainly due to the increase in the consumption of synthetic fertilizers, which was reflected in an increase in emissions in category 3D by approximately 28% compared to previous results (CHMI, 2025).

4 Land Use, Land-Use Change and Forestry is the only category where removals exceed emissions. Net removals from this category decreased from 1990 to 2024 by 51.08% to -4 630.46 kt CO_2 eq. The last inventory year reflects mainly the recovery path on forest land from the extreme calamity that peaked in 2020. Since then, both the share of salvage logging and the total harvest have decreased and are gradually approaching the levels common in pre-calamity years. This development reflects both the generally improved environmental conditions (despite objectively increased air temperatures in 2021–2024, precipitation remained sufficient to prevent serious drought), and likewise, importantly, significant forest management interventions in the Czech forestry sector (adaptation measures, prompt afforestation of clearcut sites, and promotion of species composition suited to the changing climate).

5 Waste contribution to the total GHG emissions is (including 4 Land Use, Land-Use Change and Forestry) 6.03% in 2024; 69.26% share of these emissions arose from 5.A Solid waste disposal. Emissions from 5 Waste increased from 1990 to 2024 by 66.34% to 5 521.60 kt CO_2 eq. The main drivers for increasing GHG emissions have been increased amount of degradable waste in landfills, subsector 5.A.1. Increase in total generated municipal waste has overweighted the benefits from increase in composting, subsector 5.B.1.



Fig. ES 2 Sources and sinks of greenhouse gases in 2024 (kt CO_2 eq.)

ES 5 Other information

ES 5.1 Overview of emission trends of other gases and NH_3

Emission estimates of other gases NO_X, CO, NMVOC, SO_2 and NH_3 for the period from 1990 to 2024 and the National Emission Ceilings (NEC) as set out in the 1999 Gothenburg Protocol to Abate Acidification, Eutrophication and Ground-level Ozone are presented in Tab. ES 3.

Tab. ES 3 Other gases totals for NO_X, CO, NMVOC, SO_X and NH_3 from 1990 to 2024 [kt]

	NO_X	CO	NMVOC	SO_X	NH_3
1990	762.34	2912.24	837.49	1753.82	10.01
1991	721.69	2843.54	763.63	1649.74	9.34
1992	676.01	2830.64	733.70	1381.96	8.77
1993	549.00	2588.12	691.12	1302.42	8.41
1994	455.72	2470.38	659.54	1158.97	8.36
1995	386.47	2288.44	601.38	1058.82	5.44
1996	365.88	2419.67	617.47	914.32	3.88
1997	338.24	2213.95	575.71	694.36	4.14
1998	323.05	1765.20	492.19	425.31	3.84
1999	271.22	1512.17	443.69	231.88	3.73
2000	278.30	1460.23	435.38	233.71	3.37
2001	280.44	1450.72	429.96	228.68	3.24
2002	276.31	1375.52	411.00	223.37	3.15
2003	282.90	1389.78	407.78	218.37	3.16
2004	285.31	1365.03	396.64	215.08	2.90
2005	285.55	1222.47	373.04	208.47	3.39
2006	281.39	1231.26	377.48	206.76	3.28
2007	283.73	1221.71	365.56	212.07	3.34
2008	268.16	1155.07	358.47	170.10	3.37
2009	253.07	1180.99	362.20	168.77	3.34
2010	247.71	1234.47	370.36	163.88	3.29
2011	236.65	1230.90	363.30	167.51	3.36
2012	224.77	1212.30	359.37	160.20	3.42
2013	212.35	1246.64	362.83	145.25	3.43
2014	207.02	1178.45	349.47	134.49	3.29
2015	201.51	1184.88	354.59	129.86	3.25
2016	191.72	1172.37	346.52	115.63	3.42
2017	186.70	1159.79	341.94	109.73	3.34
2018	176.47	1119.53	332.15	96.58	3.47
2019	164.75	1066.09	314.41	79.09	3.31
2020	148.51	1074.75	302.79	67.15	3.20
2021	152.55	1114.94	301.66	60.23	3.25
2022	145.27	1037.85	286.38	64.18	3.23
2023	130.51	847.46	245.03	48.46	3.04
2024	124.18	715.43	220.06	43.83	3.06
Trend %	**-83.71**	**-75.43**	**-73.72**	**-97.50**	**-69.37**
NEC	**286**	**-**	**220**	**265**	**101**

Emissions of other gases decreased from the period from 1990 to 2024: for NO_X by 83.71%, for CO by 75.43%, for NMVOC by 73.72% and for SO_2 by 97.50%. The most important emission source for other gases and NH_3 are fuel combustion activities. Indirect emissions are estimated from CH_4 too, for details see chapter 9 in Part 1: Annual inventory document.

Indirect CO_2 emissions decreased 75.77% from 1990 to 2024 and indirect N_2O emissions 84.88%. For detailed information, please see chapter 9 for the indirect CO_2 emissions.

Annual inventory submission

1 Introduction

1.1 Background information on GHG inventories and climate change

1.1.1 Climate change

Greenhouse gases (i.e. gases that contribute to the greenhouse effect) have always been present in the atmosphere, but in recent history the concentrations of a number of them are increasing as a result of human activity. Over the past century, the atmospheric concentrations of carbon dioxide (CO_2), methane (CH_4), nitrous oxide (N_2O) and halogenated hydrocarbons, i.e. greenhouse gases, have increased as a consequence of human activity. Greenhouse gases prevent the radiation of heat back into space and cause warming of the climate. According to the Fifth Assessment Report of the Intergovernmental Panel on Climate Change (IPCC, 2014), the atmospheric concentrations of CO_2 have increased by 40%, primarily from fossil fuels emissions and secondarily from net land use change emissions. CH_4 concentrations increased by 150% and N_2O concentrations have risen by 20%, compared with the pre-industrial era. Ground-level ozone also contributes to the greenhouse effect. The amount of ozone formed in the lower atmosphere has increased as a result of emissions of nitrogen oxides, hydrocarbons and carbon monoxide.

Relatively new, man-made greenhouse gases that are entering the atmosphere cause further intensification of the greenhouse effect. These include, in particular, a number of substances containing fluorine (F-gases), among them HFCs (hydrofluorocarbons). HFCs are used instead of ozone-layer-depleting CFCs (freons) in refrigerators and other applications, and their emissions are on rapid increase. Compared with carbon dioxide, all the other greenhouse gases occur at low (CH_4, N_2O) or very low concentrations (F-gases). On the other hand, these substances are more effective (per molecule) as greenhouse gases than carbon dioxide, which is the main greenhouse gas.

The threat of climate change is considered to be one of the most serious environmental problems faced by humankind. The globally averaged land and ocean surface temperature has risen by about 0.85 °C in the period 1880 to 2012 according to the IPCC 5AR, and it is now very likely that global mean sea surface temperature (SST) changed by 0.88 [0.68 to 1.01] °C from 1850–1900 to 2011–2020, and 0.60 [0.44 to 0.74] °C from 1980 to 2020 according the IPCC AR6 (IPCC, 2022). The increase of the average surface temperature of the Earth, together with the increase in the surface temperature of the oceans and the continents, will lead to changes in the hydrologic cycle and to significant changes in the atmospheric circulation, which drives rainfall, wind and temperature on a regional scale. This will increase the risk of extreme weather events, such as hurricanes, typhoons, tornadoes, severe storms, droughts and floods.

In consequence of scientific indications that human activities influence the climate and an increasing public awareness about local and global environmental issues during the middle of the 1980s, climate change became part of the political agenda. The *Intergovernmental Panel on Climate Change* (IPCC) was established in 1988 and, two years later, it concluded that anthropogenic climate change is a global threat and asked for an international agreement to deal with the problem. The *United Nations* started negotiations to create a *UN Framework Convention on Climate Change* (UNFCCC), which came into force in 1994. The long-term goal consisted in stabilizing the amount of greenhouse gases in the atmosphere at a level where harmful anthropogenic climate changes are prevented. Since UNFCCC came into force, the

Framework Convention has evolved and a Conference of the Parties (COP) is held every year. The most important addition to the Convention was negotiated in 1997 in Kyoto, Japan. The *Kyoto Protocol* established binding obligations for the Annex I countries (including all EU member states and other industrialized countries). Altogether, the emissions of greenhouse gases by these countries should be at least 5% lower during 2008–2012 compared to the base year of 1990 (for fluorinated greenhouse gases, 1995 can be used as a base year). In 2001 the Czech Republic ratified the *Kyoto Protocol* and it came into force on February 16, 2005, even though it has not been ratified by the United States.

Under the *Kyoto Protocol,* the Czech Republic was committed to decrease its emissions of greenhouse gases in the first commitment period, i.e. from 2008 to 2012, by 8% compared to the base year of 1990 (the base year for F-gases is 1995). During the second commitment period (CP2) of Kyoto Protocol, the EU, its member states and Iceland should reduce average annual emissions during 2013–2020 by 20% compared to base year.

Further, in 2015 the Paris Agreement was negotiated by the UNFCCC Parties. The Paris Agreement is a legally binding international treaty on climate change. Our reporting follows the requirements of the Paris Agreement and specifically negotiated modalities, procedures and guidelines (MPG) negotiated in Katowice, 2018.

1.1.2 Greenhouse gas inventories

As a Party and Annex I country to the United Nations Framework Convention on Climate Change (UNFCCC), the Czech Republic is required to prepare national greenhouse gas (GHG) inventories annually. Pursuant to Article 13, paragraph 7(a), of the Paris Agreement, the Czech Republic provides a national inventory document of anthropogenic emissions by sources and removals by sinks of GHGs. The national inventory document consists of this national inventory document (NID) and the common reporting tables (CRTs). The Czech Republic reports the information referred to in Modalities, procedures and guidelines (MPGs) without using flexibility options as it is Annex I country. In addition, as a result of membership in the European Union (EU), the Czech Republic must also fulfil its reporting requirements concerning GHG emissions and removals under article 26 of the EU Governance Regulation.

The *Czech Hydrometeorological Institute* (CHMI) was appointed in 1995 by the *Ministry of Environment* (MoE), which is the founder and supervisor of CHMI, to be the institution responsible for compiling GHG inventories. Thereafter, CHMI has been the official provider of Czech greenhouse gas emission data. The role of CHMI was improved following implementation of NIS in 2005, when CHMI was designated by MoE as the coordinating institution of the official national GHG inventory.

The inventory covers anthropogenic emissions of direct greenhouse gases CO_2, CH_4, N_2O, HFC, PFC, SF_6, NF_3 and indirect greenhouse gases NO_X, CO, NMVOC and SO_2. Indirect means that they do not contribute directly to the greenhouse effect, but that their presence in the atmosphere may influence the climate in various ways. As mentioned above, ozone (O_3) is also a greenhouse gas that is formed by the chemical reactions of its precursors: nitrogen oxides, hydrocarbons and/or carbon monoxide.

The obligations of the *Paris Agreement (PA)* and *its Enhanced Transparency Framework (ETF)* have led to an increased need for international super vision of the emissions reported by the parties. MPGs agreed in Katowice and the Paris Rulebook agreed in Glasgow therefore contains rules for how emissions should be estimated, reported and reviewed. Emissions of the direct greenhouse gases CO_2, N_2O, CH_4, HFCs, PFCs, SF_6 and NF_3 are calculated as CO_2 equivalents and added together to produce a national total. Together with the direct greenhouse gases, also the emissions of NO_X, CO, NMVOC and SO_2 are reported to UNFCCC.

Inventories of emissions and removals of greenhouse gases were prepared according to the IPCC methodology: *2006 Guidelines for National Greenhouse Gas Inventories (IPCC, 2006) and IPCC 2019*

Refinement (IPCC, 2019); application of this general methodology under country-specific circumstances is described in the sector-specific chapters. Since this submission the inventory was prepared using new updated methodology. Ale changes were conducted in the whole time-series. Details of specific changes are provided in specific chapters in this report. When a method used to estimate emissions is improved or when some gaps are identified, a need to recalculate the whole time series may arise in order to maintain consistency. This means that data presented this year can change in the next submission.

The National Inventory Document is elaborated in accordance with the UNFCCC reporting guidelines on annual inventories for Parties included in Annex I to the Convention (UNFCCC, 2013).

Submission is using the global warming potentials provided by the Fifth Assessment Report of the IPCC.

The current data submission (2026) for the EU contains all the data sets for 1990–2024 in the form of the official UNFCCC software called ETF Reporting Tool.

1.2 A description of the national inventory arrangements

1.2.1 Institutional, legal and procedural arrangements

The National Inventory System (NIS), as required by the *Kyoto Protocol* (Article 5.1) and by Regulation No. 525/2013/EC, has been in place since 2005. As approved by the *Ministry of Environment* (MoE), which is the single national entity with overall responsibility, the founder of CHMI and its superior institution.

The *Czech Hydrometeorological Institute* (CHMI), under the supervision of the *Ministry of the Environment*, is designated as the coordinating and managing organization responsible for the compilation of the national GHG inventory and reporting its results. The main tasks of CHMI consist in inventory management, general and cross-cutting issues, QA/QC, communication with the relevant UNFCCC and EU bodies, etc. Ms. Jitka Slámová is the responsible person at CHMI.

Sectoral inventories are prepared by sectoral experts from sector-solving institutions, which are coordinated and controlled by CHMI:

- KONEKO marketing Ltd. (KONEKO), Prague, is responsible for compilation of the inventory in sector 1. Energy, for stationary sources including fugitive emissions
- Transport Research Centre (CDV), Brno, is responsible for compilation of the inventory in sector 1. Energy, for mobile sources
- Czech Hydrometeorological Institute (CHMI), Prague, is responsible for compilation of the inventory in sector 2. Industrial Processes and Product Use and inventory in sector 5. Waste.
- Institute of Forest Ecosystem Research Ltd. (IFER), Jilove u Prahy, is responsible for compilation of the inventory in sectors 3. Agriculture and 4. Land Use, Land Use Change and Forestry
- Czech Agrifood Research Center (CARC), Prague, is co-responsible for compilation of the inventory in sector 3. Agriculture (IFER has the main responsibility)
- Global Change Research Institute of the Czech Academy of Sciences (GCRI), Brno, is co-responsible for compilation of the inventory in sector 3. Agriculture and in setor 4. Land Use, Land Use Change and Forestry (IFER has the main responsibility)
- Czech Environmental Information Agency (CENIA), Prague, is responsible for activity data of the inventory in sector 5. Waste.

Official submission of the national GHG Inventory is prepared by CHMI and approved by the *Ministry of Environment*. Moreover, the MoE secures contacts with other relevant governmental bodies, such as the *Czech Statistical Office*, the *Ministry of Industry and Trade* and the *Ministry of Agriculture*. In addition, the MoE provides financial resources for the NIS performance to the CHMI, which annually concludes long-term contracts with sector-solving institutions. In 2019 the national inventory system was enhanced by increased funding and inclusion of another two organisations, which were newly officially part of the NIS and are supporting the inventory in sectors 3. Agriculture (CARC) and 4. LULUCF (GCRI).



Fig. 1-1 Institutional arrangements of National Inventory System in the Czech Republic

1.2.2 Overview of inventory planning, preparation and management

UNFCCC, the *Paris Agreement* and the EU greenhouse gas monitoring mechanism require the Czech Republic to annually submit a *National Inventory Document* (NID) and *Common Reporting Format* (CRT) tables. The annual submission contains emission estimates for the second but last year, so the 2026 submission contains estimates for the calendar year of 2024. The organisation of the preparation and

reporting of the Czech greenhouse gas inventory and the duties of its institutions are explained in the previous section (1.2.1).

The preparation of the inventory includes the following three stages:

- inventory planning
- inventory preparation
- inventory management.

During the first stage, specific responsibilities are defined and allocated: as mentioned before, CHMI coordinates the national GHG inventory, including the planning period. Within the inventory system, specific responsibilities, "sector-solving institutions", are defined for the different source categories, as well as for all activities related to the preparation of the inventory, including QA/QC, data management and reporting.

During the second stage, the inventory preparation process, experts from sector-solving institutions collect activity data, emission factors and all the relevant information needed for final estimation of emissions. They also have specific responsibilities regarding the choice of methods, data processing and archiving. As part of the inventory plan, the NIS coordinator approves the methodological choice. Sector-solving institutions are also responsible for performing Quality Control (QC) activities that are incorporated in the QA/QC plan, (see Chapter 1.2.3). All data collected, together with emission estimates, are archived (see below) and documented for future reconstruction of the inventory.

In addition to the actual emission data, the background tables of the CRT are filled in by the sectoral experts, and finally QA/QC procedures, as defined in the QA/QC plan, are performed before the data are submitted to the UNFCCC.

For the inventory management, reliable data management to fulfil the data collecting and reporting requirements is necessary. As mentioned above, data are collected by the experts from the sector solving institutions and the reporting requirements increase rapidly and may change over time. The data and calculation spreadsheets are stored in a central network server at CHMI, which is regularly backed up to ensure data security. The inventory management includes a control system for all documents and data, for records and their archives, as well as documentation on QA/QC activities (see Chapter 1.2.3).

1.2.3 Quality assurance, quality control and verification plan

The QA/QC plan is an integrated part of the national inventory system. It ensures that the greenhouse gas inventories and reporting are of high quality and meet the criteria of timeliness, completeness, consistency, comparability, accuracy, transparency and improvement set for the annual inventories of greenhouse gases.

The objective of the national inventory system (NIS) is to produce high-quality GHG inventories. In the context of GHG inventories, high quality provides that both the structures of the national system (i.e. all institutional, legal and procedural arrangements) for estimating GHG emissions and removals and the inventory submissions (i.e. outputs, products) comply with the requirements, principles and elements rising from the UNFCCC, Kyoto Protocol, Paris Agreement, IPCC guidelines and EU reporting requirements (Regulation Eu 2018/1999). Annex 0 provides general form for QC procedures which is used in CR by each sectoral expert. Possible findings are examined and if possible corrected or included in Improvement plan for future submissions.

Annuall meetings are held with Slovak National Inventory team in order to discuss the similar difficulties that the both teams are facing while processing their GHG inventories. During the years several general

issues were cross-checked, for instance improving the cooperation in the field of QA/QC within the teams. Each year specific sectoral issues are presented and common approach is find to solve them. Since 2017 quatrolateral meetings also with national inventory teams from Hungary and Poland are organised. In 2018 the meeting was focused mainly on Waste issues and was held in Prague. In 2019 the meeting was organised in Poland and was focusing mainly on uncertainty issues and LULUCF. Due to the COVID pandemic, no meeting like this was organised in 2020. In 2022 the meeting was organised in online mode only with Slovak National Inventory team. In 2023 we have had bilateral meeting with Slovakian National inventory team held in Prague and in 2024 in Bratislava. In year 2025 the meeting was held in Budapest (HU) with Slovak, Polish and Hungarian National Inventory teams.

The QAQC Manual for the Czech Republic was created in cooperation with the sector experts in 2023 (Saarikivi, R., 2023). It serves as documented guidance under QA/QC Plan not only for the sector experts, but for all the relevant stakeholders. The QAQC Manual follows the 2006 IPCC GL requirements, but guidance is focusing more hands on information how to apply the 2006 IPCC GLs. It in sense documents the lessons learned in the QAQC field for sector experts to refer while preparing the submission. The documented guidance has arisen from the EU and the UNFCCC review experiences and from the sectoral findings while conducting sector-specific quality control procedures. Currently used version 1 QA/QC Manual was published just before the transformation to the ETF reporting tool. Version 2, which is under preparation, will document the lessons learned from actual guidance given during the transformation period to the ETF reporting tool and how to approach the IPCC 2019 Refinement methodological implementation, but also the latest lessons from the review processes. The NID covers the institutional-, general and sector specific QAQC arrangements, and cycle of planning improvements and preparation of the submission. Please, see also the QAQC Manual for further information on topic specific guidance for the Czech QAQC processes (Saarikivi R., 2023).

1.2.3.1 CHMI as a coordinating institution of QA/QC activities

The NIS coordinator (NIS manager) and QA/QC manager from the Czech Hydrometeorological Institute (CHMI) control and facilitate the quality assurance and quality control (QA/QC) process and nominate QA/QC guarantors from all sector-solving institutions. NIS coordinator cooperates with the archive administrator on implementation and documentation of all the QA/QC procedures.

The Czech NIS team, which consists of involved experts from CHMI and experts from sector-solving institutions, cooperates in addressing QA/QC issues and in development and improvement of QA/QC plan. QA/QC issues are discussed regularly (about four times in a year) between CHMI experts and sectoral expert on bilateral meetings. At least once a year a joint meeting for all involved experts is organised by CHMI (by NIS coordinator). The work of the Czech inventory team is regularly checked (at least three times per year) by the Ministry of Environment (MoE) at supervisory days. There NIS coordinator provides MoE with information about all QA/QC activities and consults the possibilities for any further improvements.

An electronic quality manual including e.g. guidelines, plans, templates and checklists has been developed by CHMI and is available to all participants of the national inventory system via the FTP server for NIS. All relevant documentations concerning QA/QC activities are achieved centrally at CHMI.

In addition to consideration of the special requirements of the guidelines concerning greenhouse gas inventories, the development of the inventory quality management system has followed the principles and requirements of the ISO 9001:2015 standard.

The CHMI ISO 9001:2015 working manual encompasses NIS segment, which is obligatory for relevant experts from CHMI and recommended also for experts from sector-solving institutions. NIS segment is developed in the form of flow-charts (diagrams) and consists of three sub-segments: (i) Planning and

management of GHG inventories (ii) Preparation of sectoral inventory (iii) Compilation of data and text outputs.

In this way the NIS segment defines the rules for cooperation between CHMI as coordinating institution and the experts from sector-solving institutions. It involves the phase of inventory planning (including QA/QC procedures) and gives instructions for the inventory compilation and for preparation of data and text outputs (CRT Tables, NID). All main principles mentioned above are incorporated also into the contracts between the CHMI and the sector-solving institutions.

Tab. 1-1 CHMI staff for QA/QC coordination

Person	Activity
Mr. Risto Saarikivi	Coordinator of all QA/QC activities carried out within NIS and QA/QC guarantor of "General and crosscutting issues"
Ms. Jitka Slamova	NIS coordinator, inventory compiler and archive administrator

1.2.3.2 Inventory process

The annual inventory process describes at a general level how the inventory is produced by the national system. The quality of the output is ensured by the inventory experts in the course of compilation and reporting, which consist of four main stages: planning, preparation, evaluation and improvement (Fig. 1-2). The quality control and quality assurance elements are integrated into the production system of the inventory; each stage of the inventory includes the relevant QA/QC procedures.

A clear set of documents is produced on the different work phases of the inventory. The documentation ensures the transparency of the inventory: it enables external evaluation of the inventory and, where necessary, its replication.



Fig. 1-2 Timeschedule of submissions and QA/QC prodedures

1.2.3.3 Procedures for data acquisition and communication with data suppliers

In general, collection of activity data is based mainly on the official documents of the Czech Statistical Office (CzSO), which are published annually, where the Czech Statistical Yearbook is the most representative example. The Czech Statistical Yearbook is published usually in the late November, but some relevant data tables appear even earlier on the CzSO website. In order to improve the process of data acquisition from CzSO, CHMI and CzSO concluded the Memorandum of understanding (2009), which is focused mainly on prompt delivery of energy statistics data and on closer cooperation on compilation of GHG inventory in this sector.

However for industrial processes, due to the Czech Act on Statistics, production data are not generally available when there are less than 4 enterprises in the whole country. In such cases, inventory compilers have to rely either on specific statistical materials, edited by sectoral associations or, in some cases, the inventory experts have to carry out relevant inquiries. In industrial process important source of data are also company EU ETS reports or annual company reports from Integrated system for fulfilling reporting obligations (ISPOP). Sector specific information concerning the data acquisition including the contact persons are given below, in the chapter “Sectoral specifications of QA/QC plan”.

The deadline for all data acquisition is 15 November. However, CzSO in some cases carries out data corrections which are presented later. In such cases it is not possible to include corrected data into the output for EU, which is submitted by 15 January and must be considered as a preliminary output of the

Czech national GHG inventory. However, practically all corrected data are incorporated into the final submission for UNFCCC (which is also resubmitted to EU).

1.2.3.4 Inventory principles – the framework for quality

The starting point for accomplishing a high-quality GHG inventory is consideration of the expectations and requirements directed at the inventory. The inventory principles defined in the UNFCCC and IPCC guidelines, that is, timeliness, completeness, consistency, comparability, accuracy, transparency and improvement, are dimensions of quality for the inventory and form the set of criteria for assessing the output produced by the national inventory system. In addition, the principle of continuous improvement is included.

1.2.3.5 Quality objectives as an integral part of planning the QC and QA procedures

The inventory planning stage includes the setting of quality objectives and elaboration of the QA/QC plan for the coming inventory preparation, compilation and reporting work. The setting of quality objectives is based on the inventory principles. Quality objectives are concrete expressions about the standard that is aimed at in the inventory preparation with regard to the inventory principles. The aim of objectives is to be appropriate and realistic while taking account of the available resources and other conditions in the operating environment. Where possible, quality objectives should be measurable.

The quality objectives regarding all calculation sectors for the inventory submissions are the following:

1) Continuous improvement
   - Treatment of review feedback is systematic
   - Improvements promised in the National Inventory Document (NID) are introduced
   - Improvement of the inventory should be systematic. An improvement plan for a longer time horizon focused on gradual implementation of higher tiers for almost all key categories is being developed.
2) Transparency
   - Archiving of the inventory is systematic and complete
   - Internal documentation of calculations supports emission and removal estimates
   - CRF Tables and the National Inventory Document (NID) include transparent and appropriate descriptions of emission and removal estimates and of their preparation.
3) Consistency
   - The time series are consistent
   - Data have been used in a consistent manner in the inventory.
4) Comparability
   - The methodologies and formats used in the inventory meet comparability requirements.
5) Completeness
   - The inventory covers all the emission sources, sinks and gases
6) Accuracy
   - The estimates are systematically neither greater nor less than the actual emissions or removals
   - The calculation is correct
   - Inventory uncertainties are estimated.

7) Timeliness
   - High-quality inventory documents reach their recipient (EU/UNFCCC) within the set time.

The quality objectives and the planned general QC and QA procedures regarding all the calculation sectors are recorded as the QA/QC plan. The QA/QC plan specifies the actions, the schedules for the actions and the responsibilities to attain the quality objectives and to provide confidence in the Czech national system's capability and implementation to perform and deliver high-quality inventories. The QA/QC plan is updated annually.

1.2.3.6 Quality control procedures

The QC procedures, which aim at attainment of the quality objectives, are performed by the experts during inventory calculation and compilation according to the QA/QC plan.

The QC procedures used in the Czech GHG inventory comply with the IPCC good practice guidance. General inventory QC checks (IPCC 2006 Guidelines, Table 6.1) include routine checks of the integrity, correctness and completeness of data, identification of errors and deficiencies and documentation and archiving of inventory data and quality control actions. In addition to general QC checks, category-specific QC checks including technical reviews of the source categories, activity data, emission factors and methods are applied on a case-by-case basis focusing on key categories and on categories where significant methodological and data revisions have taken place.

Once the experts have implemented the QC procedures, they complete the QA/QC form for each source/sink category, which provides a record of the procedures performed. Results of the completed QC checks are recorded in the internal documents for the calculation and archived in the expert organisations and at the CHMI (under responsibility of Ms. Jitka Slamova). Key findings are summarised in the sector-specific chapters of the NID.

Specifically, QC procedures in the sectors are organised as described below:

Each sector-solving institution – KONEKO, CDV, CHMI (Industrial processes), IFER, CARC, GCRI and CENIA – will suggest to the NIS coordinator/manager (CHMI, Ms. Jitka Slamova) their QA/QC guarantors, responsible for the compliance of all the QA/QC procedures in the given sector with the IPCC 2006 Guidelines and also with the QA/QC plan.

At the basic level of control (Tier 1) individual steps should be controlled according to the Table 6.1 (IPCC 2006). The first step is carried out by the person responsible for the respective sub-sector (auto-control). Then follows the 2nd step carried out by the expert familiar with the topic. The reporting on the realized controls is documented in a special form prepared by CHMI. The completed form with all the records of the carried out checks is, in case of QC, Tier 1, submitted to the NIS coordinating institution – CHMI, together with data outputs: (i) XML file generated by the ETF Reporting Tool, (ii) detailed calculation spreadsheet in MS Excel format, containing, in addition to all calculation steps also all activity data, emission factors and other parameters, as well as further supplementary data necessary for emission determination in the given category. All these files are then submitted to the central archive in CHMI. The records of the carried out QC checks, Tier 2, are submitted later (see the schedule below).

Sectoral QA/QC guarantor, in cooperation with the NIS coordinator, will assess the conditions for Tier 2 in the given sector (e.g. comparison with EU ETS data or with other independent sources). If everything is in order, the sectoral QA/QC guarantor organizes the QC check according to Tier 2.

CHMI, as the NIS coordinating institution, carries out mainly formal control of data outputs in the ETF reporting tool, similar to the "*Synthesis and Assessment*" control carried out by the UNFCCC Secretariat.

That means that CHMI controls the consistency of time series, and the possible IEF exceedance of the expected intervals (outliers), as well as the completeness and suitability of the use of notation keys and commentaries in ETF Reporting Tool (mainly in case of NE and IE), etc. The calculation files with detailed results are controlled in CHMI only randomly.

In addition, the QC activities directed to the Member States submissions under the European Community GHG Monitoring Mechanism (e.g. completeness checks, consistency checks) produce valuable information on errors and deficiencies that is taken into account before Czech final annual inventory submission to the UNFCCC.

1.2.3.7 Schedule for quality control procedures

In addition to the UNFCCC provisions and obligatory documents the EU member states have to observe the relevant EU legislation, in this case the Regulation (EU) 2018/1999 of the European Parliament and of the Council, concerning a mechanism for monitoring and reporting greenhouse gas emissions and for reporting other information at national and Union level relevant to climate change. Article 7 of the decision sets that the member countries have to submit the results of the respective national inventories, incl. the accompanying text to the European Commission up to 15 January. The schedule of the inventory and the follow-up schedule of QA/QC procedures must respect this.

Tab. 1-2 The schedule of QC activities – Tier 1 of the data output for EU (output deadline 15 January). The output for EU, after further controls (see below) and possible updates is used as the output for UNFCCC (deadline 15 September)

Time period	Activity	Responsible person
15–20 November	Final update of all detailed calculation sheets for the given category using the new data. Auto-control (1st step of QC procedure) carried out by the expert responsible for the given category.	Compiler of the category from the sector-solving institution
21–25 November	2nd step of QC procedure carried out by the expert from the sector-solving institution familiar with the topic	Expert from the sector-solving institution familiar with the topic
26-30 November	Data from the calculation sheets are submitted to the sectoral module of the ETF Reporting Tool and are controlled by the person responsible for the given category and by the expert from the sector-solving institution familiar with the topic.	Compiler of the category and the expert from the sector-solving institution familiar with the topic
1–5 December	Finalization of the QC control of the data output and completion of the control form for the given category	Sectoral QA/QC guarantor
6–10 December	Submission of all sectoral data outputs as well as records of the carried out QC procedures to CHMI	Main compiler of the sector-solving institution
10–15 December	Inventory compiler from CHMI (administrator of ETF Reporting Tool) receives all data files and the records from the sector-solving institution for archiving, carries out the formal control of data in the ETF tools. If necessary, the sectoral QA/QC expert is contacted to remedy possible drawbacks.	Inventory compiler from CHMI
16–20 December	Inventory compiler from CHMI (administrator of ETF Reporting Tool) carries out the final control of data in the ETF reporting tool and informs on the results the NIS coordinator who carries out independent control and informs MoE on the results.	NIS coordinator (manager
Up to 5 January	CRT Tables submission to MoE for the approval	MoE and Sector coordinating group

Time period	Activity	Responsible person
Up to 15 January	CRT Tables submitted to the European Commission within the reporting procedure pursuant to Article 26 of the Decision No. 2018/1999	MoE

The reporting pursuant to the Article 26 of the Decision No. 2018/1999 includes also the text output containing several NID elements. The text is created in the NIS coordinating institution (CHMI) and the control is carried out by the NIS coordinator. The text is submitted to MoE together with the CRT tables by 5 January.

The prepared output for the European Commission will contain only the QC procedures, Tier 1, realized by 5 January. The final submission for UNFCCC has the deadline by 15 April and thus the EU member states can carry out further controls (e.g. QC, Tier 2), and, if necessary, to further specify the results of their national inventories. The European Commission is informed about the final output for UNFCCC.

As mentioned above the sectoral QA/QC guarantor in cooperation with the NIS coordinator, will assess if the given sector meets the conditions for the application of the QC procedure, Tier 2. This assessment and discussion on the way of application will be carried out by 15 December. QC procedures, Tier 2, are then applied and controlled according to the similar schedule as presented in Tab. 1-2, however with the different deadline for the submission of the control results and the record of the carried out control to the coordinating institution, and namely by 15 February. If there are serious drawbacks, the competent representative of the sector-solving institution, together with the NIS coordinator, will consider the possibility of the correction of the data output for the given category prior to the final submission to UNFCCC (and simultaneously EU).

Similar procedure is applied in case of potential drawbacks detected within the control carried out by European Environmental Agency (EEA) on behalf of the European Commission. In this case the January data outputs will be corrected and included into the final submission for UNFCCC.

1.2.3.8 Quality assurance procedures

Quality assurance comprises a planned system of review procedures. The QA reviews are performed after the implementation of QC procedures to the finalised inventory. The inventory QA system comprises reviews and audits to assess the quality of the inventory and the inventory preparation and reporting process, to determine the conformity of the procedures taken and to identify areas where improvements could be made. While QC procedures are carried out annually and for all sectors, QA activities are expected to be performed by individual sectors and not so frequently. Each sector should be reviewed by the QA audit approx. once in three years as far as possible. Besides, QA activities should be focused mainly on key categories.

Peer reviews (QA – procedures) are sector or category-specific projects that are performed by external experts or expert groups. The reviewers should preferably be external experts who are independent of the inventory preparation. The objective of the peer review is to ensure that the inventory results, assumptions and methods are reasonable, as judged by those knowledgeable in the specific field. More detailed information about peer reviews will be given in the sector specific part of this QA/QC plan.

Peer reviews may also based on bilateral collaboration. For example, the Czech and Slovak GHG inventory teams have about once a year meetings to exchange information, experience and views relating to the preparation on the national GHG inventories. This collaboration also provides opportunities for bilateral peer reviews (QA audits). An example of such collaboration is the QA audit focused on General and crosscutting issues and on the Transport, which was carried out by Slovak GHG inventory experts in November 2009. The objectives of this QA review were (i) to judge suitability of General and crosscutting

issues (including uncertainty) and to check whether the used national approach for road transport is in line with the IPCC methodology, and (ii) to recommend improvements in both cases. Similar bilateral QA reviews concentrated more on individual sectors are planned for future with the expected frequency a one QA audit for about a fifth of sectors per year. Further, in later years the cooperation was focused on different sectors, i. e. Energy (2013), Agriculture and LULUCF (2015), IPPU and uncertainties (2016), Waste and QAQC procedures (2018) and LULUCF and uncertainties (2019). Due to the COVID pandemic, no peer review meeting was organised in 2020. In 2021 the meeting was organised, but only with Slovak National Inventory team in online mode focused on Energy, EU ETS data, QAQC procedures and cooperation with the air pollutant team regarding indirect emissions. In 2024 the billateral meeting with Slovaks was held in Bratislava, the main topics were QA/QC procedures, Energy - fugitive emission and new ETF reporting tool. In year 2025 the meeting was held in Budapest (HU) with Slovak, Polish and Hungarian National Inventory teams. Sectoral experts have expressed a need for in person peer cooperation with the Slovaks, Polish and Hungarian, and purpose is to continue in person meetings again in 2026.

The annual UNFCCC inventory reviews have similar and even more important impact on improving the quality of the national inventory. Therefore, the Czech team analyses very carefully the comments and recommendations of the international Expert Review Team (ERT) and strives to implement them as far as possible.

1.2.3.9 Implementation of QA/QC procedures in cases of recalculations

The QA/QC procedures described up to date are related particularly to standard situations, where the emission data from previous years remain unchanged and only emissions for the currently processed year are determined. The IPCC methodology requires that, in some cases, the emissions for previous years also be recalculated. These recalculations should be performed when an attempt is made to increase the accuracy by introducing a new methodology for the given category of sources or sinks, when more exact input data has been obtained or when consistent application of control procedures has revealed inadequacies in earlier emission determinations. In addition, recalculation should be performed in response to recommendations of the international inspection teams organized by the bodies of either the Secretariat of the UNFCCC or the European Commission.

While new data are available roughly ten or eleven months after the end of the monitored year for standard emission determinations for the previous year, reasons for recalculation mostly arise well beforehand. If the methodology is changed during recalculation, the task becomes far more difficult than in standard determination of the previous year, as the new method must be thoroughly studied and tested. In addition, in order to maintain consistency of the time series, the recalculation is generally introduced for the entire time period, i.e. beginning with the base year 1990. It is thus obvious that the danger of potential errors or omissions is greater in recalculation than in standard determination of the previous year using a well-tried methodology.

For these reasons, in recalculation, greater attention must be paid to QA/QC control mechanisms where, in addition to technical QC control (first step), it is necessary to employ more demanding control procedures (second step) and, where possible, also independent QA control by an expert not participating in the emission inventory in the given sector. While, for standardly performed QA/QC procedures, longer time validity is assumed, planning control procedures for recalculation must be tailored for the specific recalculation by the sector manager in cooperation with the NIS coordinator and QA/QC NIS guarantor.

Specific examples of recalculation are given in the sector-oriented chapters and in Chapter 10.

1.2.3.10 Final approval of the inventory before submission

Regarding the national GHG inventory submission to the UNFCCC, the same procedure will be applied as for the corresponding reporting to the EC. The following approval procedure is within the authorization of the Ministry of the Environment of the Czech Republic. The procedure involves that the report is sent by the Ministry of the Environment, well ahead via email, to the relevant ministries in the Czech Republic (e.g. Ministry of Finance, Ministry of Transport, Ministry of Foreign Affairs, Ministry of Education, Youth and Sports, etc.), organizations (e.g. Czech Environmental Inspectorate, Czech Environmental Information Agency, non-governmental organizations, etc.), as well as to the unions of different producers (e.g. Czech-Moravian Confederation of Trade Unions, Confederation of Industry of the Czech Republic, Association of Chemical Industry of the Czech Republic, Union of Czech and Moravian Production Co-operatives, Czech Cement Association, etc.) before the official submission to the UNFCCC for their comments and observations. This is the so called proceeding of external comments. Thereafter, comments and observations must be resolved by the Climate Change Department of the Ministry of the Environment in consultation with CHMI. Such procedure is in accordance with the Provision no. 11/06 of the Ministry of the Environment, regarding the procedure for preparation and hand-over of reporting information

1.2.3.11 Sectoral specifications of QA/QC plan

1.2.3.11.1 Energy – stationary combustion

KONEKO, Ltd is a sector-solving institution for this category.

The plan of QA/QC procedures in the company KONEKO Ltd. is based on the internal system of quality control ensuing from the general part of the QA/QC plan for GHG inventory in the Czech Republic and is harmonized with the QA/QC system in the Transport research centre (CDV). As the fundamental/primary data sources for the processing of activity data are based on the energy balance of the Czech Republic the main emphasis is given to a close cooperation with the Czech statistical office (CzSO). This cooperation is based on the contract between CHMI, as the NIS coordinator, and CzSO. CzSO is a state institution established for statistical data processing in the Czech Republic, which has its own control mechanisms and procedures to ensure data quality.

Sectoral guarantor of QA/QC procedures, Andrea Vesela (KONEKO manager):

- processes and updates the sectoral QA/QC plan
- organizes QC procedure (Tier 1)
- ensures QC procedure (Tier 2) and is responsible for its realization
- is responsible for the submission of all documents and data files for the storing in the coordinating institution
- suggests external experts for QA procedure
- is responsible for the compliance of all QA/QC procedures with the IPCC 2006 Guidelines and QA/QC plan.

Sectoral administrator, Barbora Votavova:

- ensures data input in the ETF Reporting Tool
- carries out auto-control (1st step of QC procedure, Tier 1)
- ensures and is responsible for the storing of documents

The QC procedures at the Tier 1 are related with the processing, manipulation, documentation, storing and transmission of information. The first step of the control (auto-control) is carried out by the expert responsible for the sectoral approach (Andrea Vesela), followed up by the control carried out by the QA/QC expert familiar with the topic (Barbora Votavova). At this control level (Tier 1) individual steps are controlled according to the table 6.1 (IPCC 2006).

Data transmission to the ETF Reporting Tool is carried out by the data administrator. After data transmission to the ETF Reporting Tool the control of correct data transmission based on the summary values of activity data and emission data is carried out. If there are any discrepancies, the erroneous data are detected and corrected without delay.

QC procedures at the Tier 2 are included upon the suggestion of the QA/QC sectoral guarantor after the consultation with the NIS coordinator. They are aimed mainly at the comparison with independent data sources that are not based on data processing from the CzSO energy balance. The relevant independent sources in the Czech Republic are represented by data published and verified within the EU Emission Trading Scheme (ETS) from the national system REZZO, used for the registration of ambient air pollutants, and based mainly on data collection from individual plants. In addition to emission data the REZZO database includes also activity data, independent of CzSO data. The way how to optimally use the above data sources is determined on the basis of systematic research and is covered in the national inventory improvement plan.

Also external employees of KONEKO familiar with the assessed topic participate in the QC procedures (Tier 2). The cooperation is based on ad hoc contracts ensured by the QA/QC sectoral guarantor. As already mentioned above, also experts from CzSO, closely cooperating with CHMI and KONEKO, take part in the control procedures.

The QA procedures are planned in a way described in the general part of the QA/QC plan, i.e. approximately once in three years.

The QA/QC staff members for this category (Energy – stationary combustion) are given in the following table:

Tab. 1-3 QA/QC staff members for Energy – stationary sources

Person	Activity
Ms. Andrea Vesela	Sectoral QA/QC guarantor responsible for the compliance of all QA/QC procedures with the IPCC 2006 Guidelines and QA/QC plan
Ms. Barbora Votavova	Emission calculation in stationary sources, auto-control (1st step of QC procedure, Tier 1)
Ms. Andrea Vesela	Control carried out by a colleague familiar with the topic (2nd step of QC procedure, Tier 1)
Ms. Andrea Vesela, Ms. Barbora Votavova	Control of the correct uploading of data from calculation sheets to the respective module of ETF Reporting Tool
External KONEKO employees (based on contract)	QC procedures, Tier 2
External expert	QA procedure assurance

1.2.3.11.2 Energy – mobile sources

Transport Research Centre (CDV) is a sector-solving institution for this category.

The plan of QA/QC procedures in CDV is based on the inner quality control procedure system, which is harmonized with the QA/QC system of KONEKO company. Since the transport sector belongs to the energy sector, there is a close co-operation of CDV and KONEKO in the field of energy and fuel consumption data

as well as specific energy data used (in MJ/kg fuel). The KONEKO company, in close co-operation with CzSO, ensures that the Transport Research Centre works with the most updated data about total energy and specific energy consumed.

Routine and consistent checks are performed to ensure data integrity, correctness, completeness and to identify and address errors. Documentation and archiving of all QC activities is carried out within CDV. QC activities include methods such as accuracy checks on data acquisition and calculations, and the use of approved standardised procedures for emission calculations, measurements, estimating uncertainties, archiving information and reporting. QC activities also include technical reviews of categories, activity data, emission factors, other estimation parameters, and methods. QA and verification are guaranteed in CDV by comparing activity data with world and European databases.

The sectoral expert from CDV is responsible for coordinating the institutional and procedural arrangements for inventory activities, including data collection from CzSO, deciding on emission factors (default or CS) and estimation of emissions from mobile sources. The uncertainty assessment is carried out also by the sectoral export. The last step is documentation and archiving of data.

The responsibilities for completing the QA/QC procedures for mobile sources are divided between the sectoral guarantor, sectoral expert, and external expert. The sectoral guarantor of QA/QC procedures for mobile sources (Mr. Leoš Pelikán) is responsible for the sectoral QA/QC plan and the compliance of all QA/QC procedures, provides for the QC procedure and is responsible for its implementation.

The sectoral expert from mobile sources (Ms. Zuzana Kačmárová) performs the emission calculations for the transport in emission model, provides for data import in the CRT table, provides for and is responsible for the storing of documents, carries out auto-control and control of data consistency, performs the uncertainty calculation, introduces improvements.

External expert (Ms. Vilma Jandová) controls in detail timeliness, completeness, consistency, comparability, and transparency.

The QA/QC staff members for this category (Energy – mobile sources) are given in the following table:

Tab. 1-4 QA/QC staff members for Energy – mobile sources

Person	Activity
Mr. Leoš Pelikán (Head of Sustainable Transport Section)	Sectoral QA/QC guarantor responsible for the compliance of all QA/QC procedures with the 2006 IPCC Guidelines and QA/QC plan.
Ms. Zuzana Kačmárová	Inventory compiler for transport sector. Calculations of emissions from traffic based on emission model, auto-control (1st step of QC procedure, Tier 1). Uploading data from the detailed emission calculation model to the ETF Reporting tool, control of the final "implied emission factors", control of data consistency
Ms. Vilma Jandová (Transport yearbook compiler)	Control carried out by a colleague familiar with the topic (2nd step of QC procedure, Tier 1)

1.2.3.11.3 Energy – fugitive emissions

KONEKO, Ltd is a sector-solving institution for this category.

The plan of QA/QC procedures in the KONEKO Ltd. is based on the internal system of quality control resulting from the general part of the QA/QC plan of the GHG inventory in the Czech Republic. As the basic data sources for activity data are taken from the Mining Yearbook and are supplemented and controlled by the data from the source part of the energy balance of the Czech Republic, the main emphasis is given to a close cooperation with the CzSO. This cooperation is ensured by the contract between CHMI as the

NIS coordinator, and CzSO. CzSO is a state institution established for the processing of statistical data in the Czech Republic and as such it uses its own control mechanisms and procedures to ensure data quality.

Sectoral guarantor for QA/QC procedures, Andea Vesela (KONEKO manager)

- develops and updates the sectoral QA/QC plan
- organizes the QC procedure (Tier 1 and Tier 2) and is responsible for the compliance of all QA/QC procedures with the IPCC 2006 Guidelines and the QA/QC plan
- suggests external experts for QA procedures
- is responsible for the submission of all documents and calculation sheets for the storing in the coordinating institution

Sectoral administrator, Barbora Votavova:

- ensures the uploading of data to ETF Reporting Tool
- carries out auto-control (1st step of QC procedure, Tier 1)
- ensures and is responsible for the storing of documents

QC procedures at Tier 1 are related to the processing, manipulation, documentation, storing and transmission of information. The first step of the control (auto-control) is carried out by the expert responsible for the sectoral approach (Barbora Votavová) and is followed by the control of the QA/QC colleague familiar with the topic (Andrea Veselá). At this control level (Tier 1), the individual steps are controlled according to the table 6.1 (IPCC 2006).

Data transfer to the ETF Reporting tool is carried out by the data administrator. After data transmission to the ETF Reporting Tool the control of correct transmission based on the summary values of activity data and emission data is carried out. If there are any discrepancies, the erroneous data are detected and corrected without delay.

The QC procedures at Tier 2 are included on the proposal of the sectoral QA/QC guarantor after the consultation with the NIS coordinator. They are aimed mainly at the comparison with independent data sources. The relevant independent sources in the Czech Republic are represented by data published in the Mining Yearbook, the source part of the energy balance of the Czech Republic, by the separate examinations in the gas industry plants and in the companies, mining the energy raw materials.

The QA procedures are planned as described in the general part of the QA/QC plan, i.e. approx. in three-year cycles.

The QA/QC staff members for this category (1.B Fugitive emissions) are given in the following table:

Tab. 1-5 QA/QC staff members for Energy – fugitive emissions

Person	Activities
Ms. Andrea Vesela	Sectoral QA/QC guarantor responsible for the compliance of all QA/QC procedures with the IPCC 2006 Guidelines and the QA/QC plan.
Ms. Barbora Votavova	Calculations of fugitive emissions in coal mining, oil and gas industry, auto-control (1st step of QC procedure, Tier 1).
Ms. Andrea Vesela	Control of an expert familiar with the topic (2nd step of QC procedure, Tier 1) and QC, Tier 2
Ms. Andrea Vesela **Ms. Barbora Votavova**	Control of the correct data input from calculation sheets to the respective module of ETF Reporting Tool
External expert	Ensuring the QA procedure

1.2.3.11.4 Industrial processes and product use

Czech Hydrometeorological Institute (CHMI) is a sector-solving institution for this category. The guarantor of the QA/QC procedures in this sector is Ms. Barbora Koci and Ms. Jitka Slamova.

The plan of QA/QC procedures is in compliance with NIS general QA/QC plan and is based on the overall CHMI ISO 9001:2015 quality standards, namely process No. 2462 "Sectoral GHG inventory – Industrial processes". This process consists of two parts (a) 24621 "Data processing and emissions estimates" and (b) 24622 "Update of the National Inventory Document".

The QA/QC system is based on the inner quality control procedure system with inter-sectoral cooperation mainly with KONEKO on the field of non-energy use of fossil fuels in the sectors Chemical Industry and Iron and Steel and with Ministry of the Environment and Czech Accreditation Institute on the field of EU ETS data processing and verification.

The QA/QC system is based on the inner quality control procedure system with inter-sectoral cooperation: As for non-energy use of fossil fuels in 2.B and 2.C the relevant QA/QC procedures at the CHMI are performed in cooperation with KONEKO company. Besides, close cooperation with the Ministry of the Environment, as a competent authority for EU ETS, and with the Czech Accreditation Institute is developed for the usage of the EU ETS data for implementation of the QC Tier 2 procedures.

Activity data are supplied mostly by state statistical bodies (CzSO, Ministries etc.) which have their own control mechanisms to ensure quality of published data. In the case of EU ETS, the use of data is consulted with appropriate professional association (e.g. Czech Cement Association). In the case of F-gases, different sources of data are used (import/export statistics, direct questionnaire to all importers/exporters, MoE questionnaire on F-gases use) and compared.

The inner quality assurance and quality control procedure consists of the setting of responsible person for emission calculation and quality check. Summary of involved experts is given in the following table. In general, the responsibility is divided between the persons who implement the IPCC methodology and control the results, data consistency and documentation process.

The QA/QC staff members for this category (Industrial processes and solvent and other product use) are given in the following table:

Tab. 1-6 QA/QC staff members for Industrial processes and solvent and other product use

Sector	Emission Estimate and the first step of QC procedure, Tier 1 (auto-control)	QC, Tier 1 (the second step of QC procedure)	QC, Tier 2 – verification
2.A	Ms. Barbora Koci	Ms. Jitka Slamova	Ms. Eva Krtkova
2.B	Ms. Jitka Slamova	Ms. Barbora Koci	Ms. Eva Krtkova
2.C	Ms. Barbora Koci	Ms. Jitka Slamova	Ms. Eva Krtkova
2.D	Ms. Jitka Slamova	Ms. Barbora Koci	Ms. Andrea Vesela
2.E	Ms. Jitka Slamova	Ms. Barbora Koci	Mr. Martin Beck
2.F	Ms. Barbora Koci	Ms. Jitka Slamova	Mr. Martin Beck
2.G	Ms. Barbora Koci	Ms. Jitka Slamova	Ms. Eva Krtkova

1.2.3.11.5 Agriculture

The Institute of Forest Ecosystem Research (IFER) is a sector-solving institution for this category. The experts (Dr. Klír, Dr. Wollnerová) representing the Czech Agrifood Research Center (CARC)) have joined the team since 2019. These experts have been also involved in the QA/QC procedures.

The sector specific QA/QC plan for Agriculture is an integral part of the general QA/QC plan. The agricultural greenhouse gas inventory is compiled by the experienced expert from the IFER, including performing auto-control. Direct inputs and independent controlling were performed by the experts from CARC (Chapters Manure Management and Agricultural Soils).

The Slovak agricultural experts (SHMI) also participate in discussions concerning inventory improvements.

The procedure of inventory compiling is initiated by IFER where all necessary data, obtained from the Czech Statistical Office (CzSO), are inserted into the excel spreadsheets. The excel files are then checked by other IFER experts. All differences are discussed and if necessary also corrected.

Ministry of Agriculture of the Czech Republic, Czech University of Life Sciences, Institute of Animal Science Prague, Research Institute for Cattle Breeding, Research Institute of Agricultural Engineering, Institute of Agricultural Economics and Czech Hydrometeorological Institute are the additional institutions contributing information used in agriculture sector inventory.

For calculation of CS EF for cattle (Tier 2) some specific parameters, not available from CzSO, are needed. The appropriate values in calculation spreadsheets are updated at IFER replacing the older ones. This work is archived by sector expert (IFER).

The final checked and verified data are transferred into the ETF Reporting Tool. The CRT tables are sent to the NIS coordinator for the final checking and approval. All information used for the preparation of the inventory document is archived by the author and by the NIS coordinator.

The QA/QC staff members for this category (Agriculture) are given in the following table:

Tab. 1-7 QA/QC staff members for Agriculture

Person	Activity
Ms. Jana Beranova (IFER)	Sector QA/QC guarantor Emission estimation in Agriculture sector (1st step of QC procedure, auto-control) Checking of CRT tables and time-series consistency
Mr. Emil Cienciala (IFER)	QC verification of other expert familiar with agricultural problem (2nd step of QC procedure)
Experts from CARC	Consultation of QA/QC procedures and GHG estimation

1.2.3.11.6 LULUCF

Institute of Forest Ecosystem Research (IFER) is a sector-solving institution for this category.

The sector specific QA/QC plan for LULUCF is an integral part of the general QA/QC plan. The LULUCF greenhouse gas inventory is compiled by an experienced expert from the IFER, including auto-control procedure. The sector specific QC, Tier 1 was prepared by another LULUCF expert team member with help from other sectoral experts.

The procedure of inventory compiling is initiated by IFER. IFER collects the required data from the Czech Statistical Office (CzSO), the Czech Office for Surveying, Mapping and Cadastre (COSMC) and the Czech Forestry Institute (CFI; earlier named as Forest Management Institute - FMI) The latter two institutes provide country specific information used for Tier 2 and Tier 3 inventory estimates. COSMC provides the annually updated areas for all land-use categories. CFI reports the recent data on forests (harvest, increment, felling, etc.) that are used in the land-use categories involving forest land. The preparatory calculation is mostly performed in excel spreadsheets and in some instances in the specific software application prepared by IFER. Tier 3 estimates are facilitated by CBM-CFS3 modelling tool (Kurz et al. 2009, Kull et al. 2019). All files are then checked by other IFER experts. All differences are discussed and if

necessary, appropriate corrections are made. The appropriate values in calculation spreadsheets and other software are updated at IFER replacing the older ones. This work is archived by an IFER expert.

The final data files including the checked and verified data are transferred into the ETF Reporting Tool. The sectoral CRT tables are sent to the NIS coordinator for the final checking and approval. All information used for the preparation of the inventory document is archived by the author and by the NIS coordinator.

The QA/QC staff members for this category (LULUCF) are given in the following table:

Tab. 1-8 QA/QC staff members for LULUCF

Person	Activity
Mr. Emil Cienciala (IFER)	Sectoral QA/QC guarantor and expert with overall technical responsibility for the LULUCF inventory Emission estimation in LULUCF sector, 1st step of QC procedure (auto-control) Checking of CRT tables and time-series consistency
Ms. Radka Maskova (IFER) **Mr. Ondrej Cerny (IFER)** **Mr. Alexander Ac (GCRI)**	Emission estimation in LULUCF sector, 2nd step of QC procedure Technical assistance and consultations Technical assistance and consultations
Ms. Jana Beranova (IFER)	Technical verification of emission factors and time series in the LULUCF sector
CFI (Czech Forestry Institute)	Selected data on forests
COSMC	Selected cadastral data
Experts from GCRI	Consultation of QA/QC procedures and GHG estimation

1.2.3.11.7 Waste

Czech hydrometerological instituion is a sector-solving institution for this sector and CENIA, Czech Environmental Information Agency (CENIA) is an institution responsible for activity data for this sector.

The sectoral plan of QA/QC procedures is in compliance with the NIS general QA/QC plan. The inner quality assurance and quality control procedure consists of the setting of responsible persons for emission calculation – Ms. Monika Filipenska (autumn 2024) with support from Mr. Havranek. (CENIA), who implemented the IPCC methodology and calculated emission till 2020. Since 2021 Ms. Kopecká (CENIA) and updates the methodologies. From autumn 2022, the agenda was gradually handed over to Petr Bažil, who performed the calculation of the emissions for the reference year 2021 and 2022. Mr. Risto Saarikivi supervises the results and their consistency.

Activity data are supplied mostly by state statistical bodies (CzSO, Ministries, CENIA etc.) which have their own control mechanisms to ensure the quality of published data. It is beyond the scope of this sector review to list them all as they are used by the whole NIS.

ETF Reporting Tool is filled by Ms. Filipenska, further the consistency between sector worksheets, CRT and NID are controlled by the sectoral expert (Tier 1 auto-control) and a reviewer from NIS coordination team. Mr. Havránek helps with solving issues and proposes and recommends improvements. He has a long-time experience in this sector. Worksheets and all activity data are stored (so far indefinitely) by NIS coordinator. Cross-cutting issues from this sector are discussed regularly with the experts from the relevant sectors (Energy, Agriculture etc.).

Some findings from waste greenhouse gas inventories are published in scientific publications, in papers, articles or in various project reports which gives the additional layer of QA/QC for this particular sector.

The QA/QC staff members for this category (Waste) are given in the following table:

Tab. 1-9 QA/QC staff members for Waste

Person	Activity
Ms. Monika Filipenska	Sector guarantor of QA/QC implementation. 1st step of QC procedure, Tier 1 and Tier 2 (auto-control)
Mr. Risto Saarikivi	2nd step of QC procedure, Tier 1 and Tier 2

1.2.3.11.8 Template for documentations of performed QC procedures

For the documentation of the QC procedures the uniform blank with the respective "*check-list*" is used. All used templates of the form are attached (see the Annex).

1.2.4 Changes in the national inventory arrangements since previous annual GHG inventory submission

In the Czech national inventory team there was a change of coordinator and national inventory compiler and there is anew sector experts for Waste. The main pillars of the national inventory system declared in the Czech Republic's Initial Report under the Parits Agreement are operational and running.

1.3 Inventory preparation, and data collection, processing and storage

1.3.1 Activity data collection

Collection of activity data is based mainly on the official documents of the *Czech Statistical Office* (CzSO), which are published annually, where the *Czech Statistical Yearbook* is the most representative example. However for industrial processes, because of the *Czech Act on Statistics*, production data are not generally available when there are fewer than 4 enterprises in the whole country. In such cases, inventory compilers have to rely either on specific statistical materials edited by sectoral associations or, in some cases, inventory experts have to carry out the relevant inquiries. In a few cases, the Czech register of individual sources and emissions, called REZZO, is utilized as source of activity data.

Emission estimates from Sector 1.A Fuel Combustion Activities are based on the official Czech Energy Balance, compiled by the *Czech Statistical Office*. Data from the Czech Energy balance are processed both in the Reference Approach (TPES - primary sources data are used) and in the Sectoral Approach (data for fuel transformations and final consumptions). However, in the latter case, some additional data are required (e.g. data on transportation statistics).

Recently data from EU ETS system are used as well. For the purposes of Energy sector are these data used more for control purposes, more detailed information is given in relevant chapter for Energy sector. Furthermore, for the emission estimates in IPPU sectors are EU ETS data used in much higher extend. For some subcategories, e.g. Cement Production or Lime Production is these data used for the complete inventory; in the subcategories is EU ETS data used for improving emission factors and data. These improvements are listed in the Improvement Plan.

Furthermore across different sectors are used specific sectoral associations. In each chapter for subsectors are listed data providers for the specific subsectors.

1.3.2 Data processing and storage

Data Sector 1.A Fuel Combustion Activities are processed by the system of interconnected spreadsheets, compiled in MS Excel following "Worksheets" presented in IPCC 2006 Guidelines, Vol. 2. Workbook. The system is extended by incorporating sheets with modified energy balance: these sheets represent an input data system. This system was recently a bit modified to be more transparent.

Also, in the majority of other sectors, data are processed in a similar way - by using a system of joined spreadsheets taken from the *Workbook* and slightly modified in order to respect national circumstances. The following examples of such cases of processing can be mentioned: agriculture, waste, fugitive emissions. For LULUCF, a specific spreadsheet system is used, respecting the national methodology.

Archiving of the inventory is carried out annualy, the archive consists of the all necessary calculation sheets and models including relevant background information, methodologies descriptions and sectoral chapters as well as the whole final inventory. The archive is stored in the official archive depository at CHMI, is backed up 3x times on different servers and in regularly saved in the overall CHMI archive.

Archiving process scheme

The NIS coordinator is responsible for the administration and functioning of the archive. The archiving system is administered in accordance with the provisions of the Kyoto Protocol and the IPPC methodological recommendations.

The archiving system was updated in 2017. Currently the archive is stored at secure ftp with access only for the inventory coordinator and IT responsible expert. The archiving servers are backed up 3 times on secure servers owned by CHMI.

Material archived by the sector-solving organizations

- Input data in unmodified form
- Files for transformation of original data to calculation sheets (if used)
- Calculation sheets
- Outputs from ETF Reporting Tool
- Outputs from QA/QC
- Other relevant documents

Material archived by the coordinator

- All administrative agenda with text outputs (contracts, orders, invoices)
- Important correspondence related to the operation and functioning of NIS
- Outputs from QA/QC
- Other relevant documents

Structural arrangements of the NIS Archive

The archiving system contains and connects 4 individual units.

1) The archive of the sector-solving organization
   - Functionality and administration are based on contracts with the sector-solving organizations
   - Administration is provided by the sectoral organizations

2) Central storage site for sharing material in the context of NIS
   - Storage site accessible at private ftp
   - Administered by the NIS coordinator
   - Contains working materials for current submissions intended for archiving
3) Central closed archive of the NIS Coordinator
   - Internal central archive, administered by the NIS coordinator
   - Contains all the officially archived materials
   - The content of the archive is stored in duplicate on special media designed for data archiving
   - The archive is located in the seat of the coordinator (CHMI – Prague Komořany)
   - Entries in the archive are always performed as of 30 June of the relevant year of submission and a detailed records of them is also archived.
   - Entries in the archive are also performed after the end of re-submissions or during any other unplanned intervention into the database or text part of already archived submissions.
   - Prior to archiving, data for archiving must be checked and authorized by the QA/QC guarantor of the relevant sectoral organization.
4) Central accessible archive
   - Mirror image of the central closed archive, available on the internet
   - Does not contain sensitive documents, but does contain a complete list of archived files
   - Available at http://portal.chmi.cz
   - Administered by the NIS coordinator
   - Updating corresponds to the entries in the Central closed archive, available a maximum of 3 working days after completion of archiving.

1.4 Brief general description of methodologies (including tiers used) and data sources used

The methods used in the Czech greenhouse gas inventory are consistent with the IPCC methodology, which has been prepared for the purpose of compilation of national inventories of anthropogenic GHG emissions and removals. The 2006 IPCC Guidelines for National Greenhouse Gas Inventories (IPCC, 2006) and the 2019 Refinement (IPCC, 2019) are used for the inventory submission.

Depending on the complexity of the calculation and types of emission factors used (generally recommended - *default*, country-specific, site-specific and technology-specific), the approaches described in the IPCC methodology consist of three tiers. Tier 1 is typically characterized by simpler calculations, based on the basic statistical data and on the use of generally recommended emission factors (*default*) of global or continental applicability, tabulated directly in above mentioned methodical manuals.

Tier 2 is based on sophisticated calculation and usually requires more detailed and less accessible statistical data. The emission factors (country-specific or technology-specific) are usually derived using calculations based on more complex studies and better knowledge of the source. Even in these cases, it is sometimes possible to find the necessary parameters for the calculation in IPCC manuals. Procedures in Tier 3 are usually considered to consist in procedures based on the results of direct measurements carried out under local conditions and locally parameterized models.

Methods of higher tiers should be applied mainly for key categories. Key categories (key source categories) are defined as categories that cumulatively contribute 90% or more to the overall uncertainty either in level or in trend. Apparently, procedures in higher tiers should be more accurate and should better reflect reality. However, they are more demanding in all respects, and especially they are more expensive. An overview of the methods and emission factors used by the Czech Republic for estimation of emissions of greenhouse gases is given in the CRT Table "Summary 3".

All direct GHG emissions can also be expressed in terms of total (or aggregated) values, which are calculated as a sum of the emissions of the individual gases multiplied by the Global Warming Potential values (GWP). GWP correspond to the factor by which the given gas is more effective in absorption of terrestrial radiation than CO_2 (1 for CO_2, 28 for CH_4 and 265 for N_2O). The total amount of F-gases is relatively small compared to CO_2, CH_4 and N_2O; nevertheless their GWP values are larger by 2-4 orders of magnitude.

Emissions of the precursors NO_X, CO, NMVOC, NH_3 and SO_2, which are covered primarily by the *Convention on Long-Range Transboundary Air Pollution* (CLRTAP) and are labeled as Other emssions in the ETF tool, are also reported. These air pollutants are compiled for the purposes of CLRTAP by NFR (*New Format of Reporting*) by another team at CHMI. Thus emissions of precursors in the GHG inventory (CRT) have been fully taken over and transferred from NFR to CRT. A detailed description of the methodology used to estimate emissions of *precursors* is provided in the *Czech Informative Inventory Report (IIR), Submission under the UNECE/CLRTAP Convention* (submitted annually by 15th February) and shortly in chapter 9 of the NID. Chapter 9 has detailed description of indirect CO_2 emissions estimated based on the precursor gases or Other gases and the CRT table 6 has a summary of the reported Other emissions and resulting indirect CO_2 emissions. Addition to above Other gases, also indirect CO_2 emissions are derived from CH_4. Methodology applied is from the 2006 IPCC GLs (IPCC, 2006).

Methodical aspects are described in a greater detail in sector-oriented Chapters 3 to 8 and in Chapter 10 "Recalculations and Improvements". Chapter 10 also deals with the reactions of the Czech team to the comments and recommendations of the recent international review organised by UNFCCC and improvements implemented in this submission.

1.5 Brief description of key categories

In accordance with MPG para 25 and IPCC 2006 Guidelines (IPCC, 2006) the key category analysis is conducted. IPCC 2006 Guideline provides two approaches for key kategory analysis. Approach 1 assesses the influence of various categories of sources and sinks on the level and the trend, of the national greenhouse gas inventory. Key categories are those that, when summed together in descending order of magnitude, add up to 95% of the total level or trend. The procedure of the Approach 2 is based on the results of the uncertainty analysis. The key categories were considered to be those whose cumulative contribution is less than 90%.

In the current submission the key categories were identified using both Approach 1 (treshold 95 %) and Approach 2 (treshold 90%) for both level and trend assessment. The key categories are identify for the base year 1990 and the latest reporting year 2024, including and excluding LULUCF categories.

The overview of the key categories for Approach 1 are presented in Tab. 1-10 (incl. LULUCF) and Tab. 1-11 (excl. LULUCF) and for Approach 2 in Tab. 1-12(incl. LULUCF) and Tab. 1-13(excl. LULUCF).

Tab. 1-10 Identification of key categories by level assessment (LA) and trend assessment (TA) for 2024 evaluated with LULUCF (Approach 2)

IPCC Source Categories	GHG	Cumulative Total (LA, %)	Cumulative Total (TA, %)	KC type
IPCC Source Categories	CO_2	39.58	94.98	LA
1.A.1 Energy industries - Solid Fuels	CO_2	90.84	76.61	TA
1.A.2 Manufacturing Industries and Construction - Solid Fuels	CO_2	88.87	96.29	LA
1.A.2 Manufacturing Industries and Construction - Gaseous Fuels	CO_2	76.78	80.40	LA, TA
1.A.2 Manufacturing Industries and Construction - Other Fossil Fuels	CO_2	50.02	68.31	LA, TA
1.A.3.b Road Transportation	N_2O	54.13	71.40	LA, TA
1.A.3.b Road Transportation	CO_2	85.56	60.35	LA, TA
1.A.4 Other Sectors - Solid Fuels	CH_4	93.56	78.64	TA
1.A.4 Other Sectors - Solid Fuels	CO_2	78.63	87.86	LA, TA
1.A.4 Other Sectors - Gaseous Fuels	CH_4	74.80	81.85	LA, TA
1.A.4 Other Sectors - Biomass	CH_4	79.86	54.16	LA, TA
1.B.1.a Coal Mining and Handling	CH_4	83.45	90.33	LA, TA
1.B.2.b Fugitive Emissions from Fuels - Oil and Natural Gas - Natural Gas	CO_2	70.02	84.47	LA, TA
2.B.8 Petrochemical and Carbon Black Production	CO_2	72.52	83.18	LA, TA
2.C.1 Iron and Steel Production	F-gases	26.72	45.44	LA, TA
2.F.1 Refrigeration and Air conditioning	CH_4	58.10	92.49	LA
3.A Enteric Fermentation	N_2O	84.51	96.74	LA
3.B Manure Management	N_2O	67.50	85.70	LA, TA
3.D.1 Direct N_2O Emissions From Managed Soils	N_2O	82.26	91.00	LA
3.D.2 Indirect N_2O Emissions From Managed Soils	CO_2	96.27	89.65	TA
3.G Liming	CO_2	90.24	92.92	LA
3.H Urea application	CO_2	33.30	25.61	LA, TA
4.A.1 Forest Land remaining Forest Land	CO_2	87.41	93.32	LA
4.A.2 Land converted to Forest Land	CO_2	86.52	88.77	LA, TA
4.C.1 Grassland remaining Grassland	CO_2	81.07	98.42	LA
4.C.2 Land converted to Grassland	CO_2	89.56	99.03	LA
4.E.2 Land converted to Settlements	CO_2	44.98	64.97	LA, TA
4.G Harvested wood products	CH_4	16.52	36.42	LA, TA
5.A Solid Waste Disposal	CH_4	64.58	74.14	LA, TA
5.B Biological treatment of solid waste	CH_4	61.49	86.81	LA, TA
5.D Wastewater treatment and discharge	N_2O	88.17	94.35	LA
5.D Wastewater treatment and discharge	CO_2	39.58	94.98	LA

Tab. 1-11 Identification of key categories by level assessment (LA) and trend assessment (TA) for 2024 evaluated without LULUCF (Approach 2)

IPCC Source Categories	GHG	Cumulative Total (LA, %)	Cumulative Total (TA, %)	KC type
1.A.1 Energy industries - Solid Fuels	CO_2	30.47	92.48	LA
1.A.1 Energy industries - Solid Fuels	N_2O	89.21	99.48	LA
1.A.2 Manufacturing Industries and Construction - Solid Fuels	CO_2	86.99	66.26	LA, TA
1.A.2 Manufacturing Industries and Construction - Gaseous Fuels	CO_2	86.18	94.11	LA
1.A.2 Manufacturing Industries and Construction - Other Fossil Fuels	CO_2	74.99	75.31	LA, TA
1.A.3.b Road Transportation	CO_2	44.96	48.93	LA, TA
1.A.3.b Road Transportation	N_2O	56.39	53.94	LA, TA
1.A.4 Other Sectors - Solid Fuels	CO_2	83.84	38.09	LA, TA
1.A.4 Other Sectors - Solid Fuels	CH_4	90.63	69.54	LA, TA
1.A.4 Other Sectors - Liquid Fuels	CO_2	89.94	95.19	LA
1.A.4 Other Sectors - Gaseous Fuels	CO_2	77.51	83.85	LA, TA
1.A.4 Other Sectors - Biomass	CH_4	72.30	80.09	LA, TA
1.B.1.a Coal Mining and Handling	CH_4	79.19	14.08	LA, TA
1.B.2.b Fugitive Emissions from Fuels - Oil and Natural Gas - Natural Gas	CH_4	82.42	87.95	LA, TA
2.B.2 Nitric Acid Production	N_2O	96.20	86.84	TA

IPCC Source Categories	GHG	Cumulative Total (LA, %)	Cumulative Total (TA, %)	KC type
2.B.8 Petrochemical and Carbon Black Production	CO_2	69.20	82.16	LA, TA
2.C.1 Iron and Steel Production	CO_2	21.93	43.54	LA, TA
2.F.1 Refrigeration and Air conditioning	F-gases	13.33	28.09	LA, TA
3.A Enteric Fermentation	CH_4	38.10	90.03	LA, TA
3.B Manure Management	CH_4	85.23	85.38	LA, TA
3.B Manure Management	N_2O	88.48	97.49	LA
3.D.1 Direct N_2O Emissions From Managed Soils	N_2O	50.80	72.48	LA, TA
3.D.2 Indirect N_2O Emissions From Managed Soils	N_2O	80.81	89.02	LA, TA
3.G Liming	CO_2	91.27	77.75	TA
3.H Urea application	CO_2	87.74	91.45	LA
5.A Solid Waste Disposal	CH_4	61.97	58.27	LA, TA
5.B Biological treatment of solid waste	CH_4	65.77	62.27	LA, TA

Tab. 1-12 Identification of key categories by level assessment (LA) and trend assessment (TA) for 2024 evaluated with LULUCF (Approach 1)

IPCC Source Categories	GHG	Cumulative Total (LA, %)	Cumulative Total (TA, %)	KC type
1.A.1 Energy industries - Solid Fuels	CO_2	27.75	84.63	LA, TA
1.A.1 Energy industries - Liquid Fuels	CO_2	95.75	94.37	TA
1.A.1 Energy industries - Gaseous Fuels	CO_2	77.20	78.64	LA, TA
1.A.2 Manufacturing Industries and Construction - Solid Fuels	CO_2	71.50	34.27	LA, TA
1.A.2 Manufacturing Industries and Construction - Liquid Fuels	CO_2	91.11	76.20	LA, TA
1.A.2 Manufacturing Industries and Construction - Gaseous Fuels	CO_2	57.66	82.80	LA, TA
1.A.2 Manufacturing Industries and Construction - Other Fossil Fuels	CO_2	92.56	90.34	LA, TA
1.A.3.b Road Transportation	CO_2	47.55	17.42	LA, TA
1.A.4 Other Sectors - Solid Fuels	CO_2	83.01	46.25	LA, TA
1.A.4 Other Sectors - Solid Fuels	CH_4	98.30	87.92	TA
1.A.4 Other Sectors - Liquid Fuels	CO_2	85.70	88.60	LA, TA
1.A.4 Other Sectors - Gaseous Fuels	CO_2	53.15	66.45	LA, TA
1.A.4 Other Sectors - Biomass	CH_4	89.35	91.44	LA, TA
1.B.1.a Coal Mining and Handling	CH_4	93.03	62.25	LA, TA
1. Energy (indirect CO_2 emissions)	CO_2	98.88	93.46	TA
2.A.1 Cement Production	CO_2	84.44	97.47	LA
2.A.2 Lime Production	CO_2	94.65	96.95	LA
2.A.4 Other Process Uses of Carbonates	CO_2	92.09	92.48	LA, TA
2.B.1 Ammonia Production	CO_2	93.45	98.95	LA
2.B.2 Nitric Acid Production	N_2O	98.96	94.80	TA
2.B.8 Petrochemical and Carbon Black Production	CO_2	87.87	89.21	LA, TA
2.C.1 Iron and Steel Production	CO_2	74.48	80.76	LA, TA
2.F.1 Refrigeration and Air conditioning	F-gases	68.44	70.44	LA, TA
3.A Enteric Fermentation	CH_4	65.05	91.97	LA, TA
3.B Manure Management	CH_4	95.40	93.91	TA
3.B Manure Management	N_2O	95.03	98.74	LA
3.D.1 Direct N_2O Emissions From Managed Soils	N_2O	81.49	87.22	LA, TA
3.D.2 Indirect N_2O Emissions From Managed Soils	N_2O	90.54	95.22	LA, TA
3.G Liming	CO_2	98.43	90.90	TA
4.A.1 Forest Land remaining Forest Land	CO_2	79.45	57.85	LA, TA
4.A.2 Land converted to Forest Land	CO_2	89.97	95.59	LA
4.C.1 Grassland remaining Grassland	CO_2	94.26	92.98	LA, TA
4.C.2 Land converted to Grassland	CO_2	93.86	99.37	LA
4.G Harvested wood products	CO_2	86.97	86.07	LA, TA
5.A Solid Waste Disposal	CH_4	61.42	73.71	LA, TA
5.B Biological treatment of solid waste	CH_4	91.60	89.79	LA, TA
5.D Wastewater treatment and discharge	CH_4	88.72	95.96	LA

Tab. 1-13 Identification of key categories by level assessment (LA) and trend assessment (TA) for 2024 evaluated without LULUCF (Approach 1)

IPCC Source Categories	GHG	Cumulative Total (LA, %)	Cumulative Total (TA, %)	KC type
1.A.1 Energy industries - Solid Fuels	CO_2	29.32	85.00	LA, TA
1.A.1 Energy industries - Liquid Fuels	CO_2	95.97	94.07	TA
1.A.1 Energy industries - Gaseous Fuels	CO_2	81.59	78.01	LA, TA
1.A.2 Manufacturing Industries and Construction - Solid Fuels	CO_2	75.56	39.87	LA, TA
1.A.2 Manufacturing Industries and Construction - Liquid Fuels	CO_2	91.92	75.16	LA, TA
1.A.2 Manufacturing Industries and Construction - Gaseous Fuels	CO_2	60.94	82.84	LA, TA
1.A.2 Manufacturing Industries and Construction - Other Fossil Fuels	CO_2	93.45	89.98	LA, TA
1.A.3.b Road Transportation	CO_2	50.25	20.28	LA, TA
1.A.4 Other Sectors - Solid Fuels	CO_2	85.36	53.81	LA, TA
1.A.4 Other Sectors - Solid Fuels	CH_4	98.40	87.16	TA
1.A.4 Other Sectors - Liquid Fuels	CO_2	88.20	87.94	LA, TA
1.A.4 Other Sectors - Gaseous Fuels	CO_2	56.17	63.82	LA, TA
1.A.4 Other Sectors - Biomass	CH_4	90.72	91.25	LA, TA
1.B.1.a Coal Mining and Handling	CH_4	93.95	58.93	LA, TA
1. Energy (indirect CO_2 emissions)	CO_2	98.88	93.02	TA
2.A.1 Cement Production	CO_2	86.86	97.25	LA
2.A.2 Lime Production	CO_2	94.81	96.65	LA
2.A.4 Other Process Uses of Carbonates	CO_2	92.95	92.46	LA, TA
2.B.1 Ammonia Production	CO_2	94.39	99.06	LA
2.B.2 Nitric Acid Production	N_2O	98.97	94.58	TA
2.B.8 Petrochemical and Carbon Black Production	CO_2	89.16	88.66	LA, TA
2.C.1 Iron and Steel Production	CO_2	78.71	80.46	LA, TA
2.F.1 Refrigeration and Air conditioning	F-gases	72.33	68.46	LA, TA
3.A Enteric Fermentation	CH_4	68.75	91.87	LA, TA
3.B Manure Management	CH_4	95.60	93.55	TA
3.B Manure Management	N_2O	95.21	98.73	LA
3.D.1 Direct N_2O Emissions From Managed Soils	N_2O	83.75	86.34	LA, TA
3.D.2 Indirect N_2O Emissions From Managed Soils	N_2O	91.32	95.07	LA, TA
3.G Liming	CO_2	98.53	90.62	TA
5.A Solid Waste Disposal	CH_4	64.91	72.27	LA, TA
5.B Biological treatment of solid waste	CH_4	92.44	89.33	LA, TA
5.D Wastewater treatment and discharge	CH_4	90.05	95.50	LA

On the whole, 37 (Approach 1) and 31 (Approach 2) key categories were identified either by level assessment or by trend assessment. A summary of the assessed numbers concerning key categories is given in Tab. 1-14. Complete tables for key category analysis are presented in Annex 1 of this report.

Tab. 1-14 Figures for key categories assessed

	Approach 1	Approach 2
Key categories (KC) with LULUCF	37	**31**
KC identified by LA	31	**28**
KC identified by TA	30	**21**
KC identified by LA + TA concurrently	24	**18**
KC identified by only LA	7	**10**
KC identified by only TA	6	**3**
Key Categories (KC) without LULUCF:	32	**27**
KC identified by LA	26	**25**
KC identified by TA	27	**21**
KC identified by LA + TA concurrently	21	**19**
KC identified by only LA	5	**6**
KC identified by only TA	**6**	**2**

1.6 General uncertainty evaluation, including data on the overall uncertainty for the inventory totals

Uncertainty analysis characterizes the extent (i.e. possible interval) of results for the entire national inventory and for its individual components. Knowledge of the individual and overall uncertainties enables compilers of emission inventories better understanding of the inventory process, which encompasses collection of suitable input data and their evaluation. Uncertainty analysis also help in identifying those categories of emission sources and sinks that contribute most to the overall uncertainty and thus establish priorities for further improvement of the quality of the data.

A method of uncertainty determination based on the error propagation method (Tier 1), using calculation sheets obtained according to the prescribed methodology (IPCC, 2006), has been used in the Czech national inventory for a number of years. The accuracy of the calculation algorithm has been sufficiently verified, uncertainty in the activity data and emission factors for the individual categories are updated every submission. Experts from CHMI and all the contributing sectoral organizations are participating in this work. The individual experts investigated the uncertainty parameters coming under their field of work and proposed new ones or defended the original ones in discussions. Details are described in relevant subchapters.

Uncertainty analysis using Approach 1, which is presented in this volume of NID, employs the same source categorization as used in key categories assessment. Actual results of the uncertainty analysis for 2024 after above mentioned revision of the input parameters are given in Annex 2.

Further, uncertainty bases are yearly evaluated for LULUCF, Waste and Energy sector, which are then used for the overall uncertainty analysis.

Results of uncertainty assessment were obtained (i) for all sectors including LULUCF and (ii) for comparison also for all sectors without LULUCF. The estimated overall uncertainty in level assessment (case with LULUCF) reached 3.60%. The corresponding uncertainty in trend is 1.81%. For the case without LULUCF the estimated overall uncertainty in level assessment is 2.75% and 1.66% in trend.

The same source categories used in key sources assessment have also been used even in uncertainty analysis. In this way, the uncertainty analysis result was used later Approach 2 key source analysis. The uncertainty analysis is provided in Annex 2 tables.

1.7 General assessment of completeness

CRT Table 9 (Completeness) has been used to give information on the aspect of completeness. This part of the text includes additional information. All the categories of sources and sinks included in the IPCC Guidelines are covered. No additional sources and sinks specific to the Czech Republic have been identified. Both direct GHGs as well as precursor gases are covered by the Czech inventory. The geographic coverage is complete.

The ETF tool completeness check is applied to evaluate the completeness of each reported sector, please see the Annex A 5.6 for the results and for further information, including completenss issues arising from the ETF tool bugs. Czechia does not take responsibility of empty cells, missing notation keys, missing Tier and method parameters in the CRTs caused by the ETF tool. Every new ETF tool hot fix during submission period trickers QC check on estimates and completeness to maintain consistent, accurate and complete inventory. More of the found ETF bugs, please see the Annex 5.6.

1.7.1 Notation keys

The sources and sinks not considered in the inventory but included in the IPCC Guidelines are clearly indicated and the reasons for this exclusion are explained in Documentation box in ETF Reporting Tool and in relevant chapter of NID. In addition, the notation keys presented below are used to fill in the blanks in all the CRT Tables. Notation keys are used according to the paragraph 31 of the MPGs.

Allocations to categories may differ from Party to Party. The main reasons for different category allocations are different allocations in the national statistics, insufficient information on the national statistics, national methods, and the impossibility of disaggregating the reported emission values.

IE (included elsewhere):

"IE" is used for emissions by sources and removals by sinks of greenhouse gases that have been estimated but included elsewhere in the inventory instead of in the expected source/sink category. Where "IE" is used in the inventory, the CRT completeness table (Table 9) indicates where (in the inventory) these emissions or removals have been included. This deviation from the expected category is explained.

NE (not estimated):

"NE" is used for existing emissions by sources and removals by sinks of greenhouse gases that have not been estimated. Where "NE" is used in an inventory for emissions or removals, both the NID and the CRT completeness table indicate why the emissions or removals have not been estimated. For emissions by sources and removals by sinks of greenhouse gases marked by "NE", check-ups are in progress to establish if they actually are "NO" (not occurring). As part of the improvement programme of the inventory, it is planned that these source or sink categories will be either estimated or allocated to "NO".

Overview of not estimated (NE) categories of sources and sinks and categories included elsewhere (IE) and the relevant explanations are given in CRT Table 9.

2 Trends in greenhouse gas emissions

The GHG emissions trend generally shows a decline formost of the period 1990–2024. Historicaly the emission trend was influence by transformation of centrally planned economy to market driven economy (1990–1995), in years 2007–2009 by economy recession, in years 2011–2015 by government subsidies to renewables, solar power and biogas recovery facilities in the landfills. A steeper decreasing trend in national total emissions can be observed until the subsidised were removed and the trend starts to fluctuate and even increase slightly, but having a clear decreasing trend again from the 2017 to the current reporting year. In 2020 the emissions decreased in comparison with previous year. This decrease was caused mainly by the decrease in emissions from Energy sector which was affected by COVID-19 pandemic situation. In 2021 the emissions had slightly increased, but continued decreasing again in 2022, due to the energy crisis. Please see details in the respective chapter of the NID. GHG emission trend shows significant decline (approx. 16% of Total emissions incl. LULUCF) in year 2023 compare to the previous years. This decline is attributed to the ongoing transformation of the energy sector, which includes a gradual reduction in fossil fuel combustion, increasing energy efficiency and a gradual shift to renewable energy sources. The emissions are also influenced by decreasing industrial activity in Czechia and the fact that since 2023 LULUCF sector started to be sink of CO_2 again. In year 2024 the decreasing trend continued.

Tab. 2-1 presents a summary of GHG emissions excl. bunkers emissions for the period from 1990 to 2024. For CO_2, CH_4 and N_2O the base year is 1990; for F-gases the base year is 1995.

Tab. 2-1 GHG emissions from 1990–2024 excl. bunkers [kt CO_2 eq.]

	CO_2[1]	CH_4[3]	N_2O[3]	HFCs	PFCs	NF_3	SF_6	Total emissions[4]	
								excl. LULUCF	incl. LULUCF
1990	164337.86	23157.01	5716.26				86.57	194794.93	185329.44
1991	148968.86	21946.85	5219.40				86.40	177564.83	166295.75
1992	145781.90	20349.91	4321.45		NO		87.77	171774.91	160130.74
1993	140196.89	19931.34	4358.18				88.96	165837.70	153430.98
1994	132733.07	18814.87	4206.34				90.09	157067.94	146008.29
1995	131684.62	18517.88	5267.28	86.89	0.01	NA.NO	91.13	156844.91	145482.30
1996	135082.83	18450.35	5060.81	215.49	0.68	NA.NO	101.06	160072.93	148924.83
1997	131003.25	17965.35	4740.99	389.02	1.62	NA.NO	98.81	155317.88	145185.97
1998	125771.24	17297.75	4569.50	529.49	1.54	NA.NO	97.67	149381.86	139618.38
1999	116716.53	16592.41	4123.24	636.10	1.08	NA.NO	98.72	139217.01	129225.48
2000	127287.63	15290.68	4660.41	800.04	4.43	NA.NO	111.56	149112.09	138219.22
2001	127221.06	14571.64	5797.83	998.32	9.15	NA.NO	101.67	149591.58	138635.33
2002	124040.92	14314.15	5256.64	1098.75	15.17	NA.NO	124.74	145718.22	134903.25
2003	127646.13	14148.73	3446.97	1212.19	8.36	NA.NO	148.80	147440.70	137084.65
2004	128366.13	13676.52	4809.91	1343.12	12.41	NA.NO	124.00	149140.18	139103.02
2005	125766.10	14300.54	4869.48	1347.92	14.38	NA.NO	113.09	147274.62	137103.09
2006	126585.52	14461.39	4733.70	1600.80	29.02	NA.NO	108.09	148414.89	139375.25
2007	128416.75	13944.16	4718.97	1958.20	27.20	NA.NO	96.42	150007.19	141295.89
2008	122978.81	14083.92	4203.46	2213.63	37.05	NA.NO	91.18	144439.87	134411.95
2009	115020.88	13381.30	4260.71	2233.98	42.14	NA.NO	91.53	135767.82	125937.86
2010	117509.07	13196.49	4933.45	2450.62	44.34	0.14	85.11	138920.32	129826.49
2011	115229.63	13030.65	4022.87	2659.95	8.08	0.55	91.07	135724.29	125881.63
2012	111321.85	12965.92	4301.22	2764.27	6.17	0.83	94.92	132096.83	121911.39
2013	106760.87	12567.39	4869.70	2893.55	4.18	1.32	85.37	127768.19	118171.32
2014	104273.60	12656.37	4406.34	3071.86	3.12	2.22	82.14	125087.44	115541.53
2015	105023.18	12659.96	3568.84	3324.47	2.11	2.01	80.47	125242.07	115619.06
2016	106661.54	12243.34	4517.87	3542.93	1.78	2.01	80.82	127597.50	119123.58
2017	107777.56	12144.82	4461.08	3749.91	1.97	3.12	76.10	128728.81	122146.98
2018	106363.46	12104.57	3349.42	3815.01	2.07	2.91	72.54	126211.65	125328.57
2019	101037.17	11894.75	3684.96	3838.60	1.57	2.36	69.91	120989.59	127137.57
2020	91709.06	11322.32	4313.02	3747.41	0.97	2.02	67.16	111629.80	121051.42

	CO_2[1]	CH_4[3]	N_2O[3]	HFCs	PFCs	NF_3	SF_6	Total emissions[4]	
								excl. LULUCF	incl. LULUCF
2021	96657.29	11567.53	4492.89	3724.51	30.95	1.46	79.38	117032.39	122854.28
2022	95069.67	11509.85	3822.17	3623.67	47.86	1.95	75.58	114572.29	116806.05
2023	83259.41	11125.06	3754.35	3572.46	63.25	2.08	74.18	102239.88	98483.40
2024	77221.89	11082.13	4339.04	3492.05	36.52	3.54	66.40	96597.16	91966.70
%[2)]	-53.01	-52.13	-24.09	4011.29	710531.85	NA	-23.29	-50.41	-50.38

Note: Global warming potentials (GWPs) used (100 years time horizon): CH_4 = 28; N_2O = 265; SF_6 = 23 500; NF_3 = 16 100; HFCs and PFCs consist of different substances, therefore GWPs have to be calculated individually depending on substances

[1]GHG emissions excluding emissions/removals from LULUCF

[2] relative to base year

[3]incl. LULUCF

[4] incl.indirect emissions

GHG emissions and removals have significantly decreased in the period 1990–1995, mainly driven by the economy transition and pursuing major dropdown in heavy industry activities in the country. The fast decrease has stopped around 150 000 kt CO_2 eq. and continues fluctuating to year 2007 (see Fig. 2-1) when the emission started again decreasing. From 2007 to 2024 the total GHG emissions (incl. indirect emissions and incl. LULUCF) decreased by approximately 34.91% or -49 329.19kt CO_2 eq. resulting in total emissions of 91 966.70kt CO_2 eq. The total emissions excluding LULUCF decreased by 31% or -53 410 kt CO_2 eq. The difference in the trend between including/excluding LULUCF is caused by huge increase in emissions from LULUCF in recent years, however in the year 2023 the trend in LULUCF started to change and LULUCF is again the sink of GHG emissions.

The total GHG emissions and removals in 2024 were -50.38% below the base year level incl. LULUCF and indirect emissions and -50.41%, when excl. LULUCF.



Fig. 2-1 Total trend of GHG emissions, [kt CO_2 eq.]

In 1989 then Czechoslovak economy was one of the centrally planned economies with high level of monopolization. All economic processes were controlled through central planning. For all practical purposes, there was no real market and this situation resulted in an ever deepening economic and technological lag which resulted in high energy and material inefficiency. Since 1989 to the present the economy transformed successfully to a developed market-driven economy. The transformation led to a decline in production, investment in environmental protection, energy efficiency, fuel switch and increasing use of renewable energy. Greenhouse gases emission trend between 2007 and 2009 and supposedly up to present days passed through significant change driven mainly by economic recession. The decline is also evident in 2020 caused by COVID-19 pandemic. In the following year 2021 there was a slight increase of emission as the economy restarted after the pandemic. In year 2023 there was a significant drop in emissions mainly due to the decrease of emissions in energy sector and due to the

LULUCF being again sink of CO_2 emissions. In year 2024 the decreasing trend continued, the Total emissions incl. LULUCF decreased by 7 % compared to year 2023, correspondingly in the 1. Energy sector, emissions decreased by 6.1% from 2023 to 2024. According the EEA provisional data, the main drivers for the recent 2019 - 2024 decrease in the Energy sector GHG emissions have been decrease in the primary energy consumption (PEC) of fossil solid fuel (-39.%), PEC gaseous fossil fuels (-19%) and increase in PEC renewable fuels (10%). Contrary to the positive development, PEC fossil liquid fuels increased (6%) (EEA, 2025)

2.1 Description and interpretation of emission trends by sector

2.1.1 Description and interpretation of emission trends by gas



Fig. 2-2 Trend in CO_2, CH_4 and N_2O emissions 1990–2024 in index form (base year = 100%) and Trend in HFCs, PFCs (1995–2024) and SF_6 (1990–2024) actual emissions in index form (base year = 100%)

The major greenhouse gas in the Czech Republic is CO_2, which represents 80.3% of total GHG emissions in 2024, compared to 85.06% in the base year (excl. indirect emissions, excl. LULUCF). It is followed by CH_4 (11.5% in 2024, 11.97% in the base year), N_2O (4.5% in 2024, 2.92% in the base year) and F-gases (3.9% in 2024, 0.04% in 1990). The trend of individual GHG emissions relative to emissions in the respective base years is presented in Fig. 2-2.

CO_2

CO_2 emissions have been rapidly decreasing in early 90's, from 1994 to 2010 the emissions have kept at average of 74% of the amount produced in 1990. Inter-annual decrease in CO_2 emissions (excl. LULUCF, excl. indirect emissions) from 2010 to 2024 by 33% results the total decrease of 53.12% from 1990 to 2024. Quoting in absolute figures, CO_2 emissions and removals decreased from 154 774.78 to 72560. 65kt CO_2 in the period from 1990 to 2024, mainly due to lower emissions from the 1 Energy category (mainly 1.A.1 Energy Industry, 1.A.2 Manufacturing Industries & Construction, 1.A.4.a Commercial/Institutional and 1.A.4.b Residential).



Fig. 2-3 Percentual share of GHGs (Y-axis begins at 70% - part of CO_2 share is hidden)

The main source of CO_2 emissions is fossil fuel combustion; within the 1.A Fuel Combustion category, 1.A.1 Energy Industry and 1.A.4 Other sectors are the most important. CO_2 emissions increased remarkably between 1990 and 2024 from the 1.A.3 Transport category from 11 077.84 to 20 394.25 kt CO_2 eq.

CH_4

CH_4 emissions share decreased almost steadily during the period from 1990 to 2004, from 2004 to 2008 methane fluctuated around 60% of its base year emissions. After year 2008 the emissions steadily decreased. In 2024 CH_4 emissions were 52.13% below the base year level (excl. LULUCF), mainly due to lower contribution of 1.B Fugitive Emissions from Fuels and emissions from 3 Agriculture and despite increase from the 5 Waste category. The main sources of CH_4 emissions are 1.B Fugitive Emissions from Fuels (solid fuel), 3.A Enteric Fermentation and 5.A Solid Waste Disposal on Land.

N_2O

N_2O emissions strongly decreased from 1990 to 1994 by 26.66% over this period and then shows slow decreasing trend with inter-annual fluctuation. N_2O emissions decreased between 1990 and 2024 from 5 643.67 to 4317.20 kt CO_2 eq. (excl. LULUCF). In 2024 N_2O emissions were 23.5% below the base year level, mainly due to lower emissions from 3 Agriculture and 2.B Chemical Industry.

The main source of N_2O emission is category 3.D Agricultural Soils (others less important sources are 1.A Fossil Fuel Combustion and 2 Industrial Processes – 2.G Other product manufacture and use).

HFCs

HFCs actual emissions increased remarkably between 1995 and 2024 from 86.89 to 3 492.05 kt CO_2 eq. The rapid increase of emissions was driven mainly by increased consumption of HFCs in subcategory 2.F.1 Refrigeration and Air Conditioning. In 2024, HFCs emissions were more than 40-times higher than in the base year 1995.

The main sources of HFCs emissions are 2.F Product Uses as ODS substitutes (specifically above mentioned subcategory 2.F.1 Refrigeration and Air Conditioning). HFCs and PFCs have not been imported and used before 1995.

PFCs

PFCs emissions rapidly increased between 1995 and 2010 from 0.01-44.34 kt CO_2 eq. Since 2010, PFCs emissions were decreasing up to 2020 (0.97 kt CO_2 eq.). Rapid decrease of emissions is caused by reduced consumption of PFCs. Since 2021 the emissions started to increase again, the emissions in 2024 were 36.52 kt CO_2 eq.

The main sources of PFCs emissions are 2.E Semiconductor Manufacture.

SF_6

SF_6 emissions in 1990 accounted for 86.57 kt CO_2 eq. Between 1990 and 2024 they inter-annually fluctuated with maximum of 148.8 kt CO_2 eq. In 2024 SF_6 reached amount of 66.40 kt CO_2 eq., the level was 23.29% lower than the base year (1990).

The main sources of SF_6 emissions is 2.G Other product manufacture and use.

NF_3

With the technological progress a new gas is used since 2010 in semiconductor manufacturing. NF_3 is a gas, used mainly for manufacturing of LCD displays, solar panels and etching semiconductors. Base year for this gas is 1995. In 2024 the emissions of NF_3 equalled to 3.54 kt CO_2 eq.

2.1.2 Description and interpretation of emission trends by categories

Tab. 2-2 presents a summary of GHG emissions by categories for the period from 1990 to 2024:

- Category 1 Energy
- Category 2 Industrial Processes and Product Use
- Category 3 Agriculture
- Category 4 Land Use, Land-Use Change and Forestry
- Category 5 Waste



Fig. 2-4 Emission trends in 1990–2024 by categories in index form (base year = 100)

The dominant category is the 1 Energy, which caused for 78.77% of total GHG emissions in 2024 (86.95% in 1990) incl. LULUCF and indirect emissions, followed by the sectors 2 Industrial Processes and Product Use and 3 Agriculture, which caused for 12.12% and 8.13% of total GHG emissions in 2024 (9.32% and 7.08% in 1990, resp.), 5 Waste sector covered 6.03% (1.81% in 1990) and 4 LULUCF category prevailed again the emission removal -5.06% (-5.15% in 1990). The trend of GHG emissions by categories is presented in Fig. 2-4 (indexed relative to the base year).

Tab. 2-2 Summary of GHG emissions by category 1990–2024 [kt CO_2 eq.]

	1 Energy	2 IPPU	3 Agriculture	4 LULUCF	5 Waste
1990	159752.16	17114.96	13013.57	-9465.50	3319.42
1991	147179.39	13767.72	11704.45	-11269.09	3482.86
1992	142764.51	14522.54	9688.64	-11644.18	3468.80
1993	138535.31	13350.95	9048.33	-12406.73	3542.85
1994	129476.17	14606.73	7979.85	-11059.65	3689.59
1995	128866.78	14160.27	8867.08	-11362.61	3671.07
1996	131600.09	14955.76	8558.25	-11148.10	3698.76
1997	126430.94	15981.49	7858.48	-10131.91	3815.72
1998	120694.49	16137.76	7413.52	-9763.48	3934.44
1999	113420.24	13547.39	7194.79	-9991.53	3933.21
2000	121525.45	15136.99	7443.59	-10892.87	3979.80
2001	121405.35	14424.09	8698.59	-10956.25	4118.03
2002	118247.47	14193.37	8123.85	-10814.96	4230.67
2003	120765.06	15280.35	6117.96	-10356.05	4377.37
2004	120510.56	16253.37	7196.30	-10037.15	4314.12
2005	119734.20	14912.31	7353.20	-10171.53	4361.10
2006	119746.70	16048.29	7246.09	-9039.64	4421.95
2007	120600.40	16781.81	7386.85	-8711.30	4334.60
2008	115445.47	16676.96	6900.33	-10027.93	4534.61
2009	109438.24	14034.38	6880.12	-9829.95	4628.91
2010	110840.87	14883.30	7572.65	-9093.83	4872.67
2011	108268.95	15220.12	6622.24	-9842.67	4891.67
2012	104547.81	14980.85	6871.32	-10185.43	5010.19
2013	99448.09	14858.56	7630.83	-9596.87	5207.75
2014	96552.85	15662.01	7050.56	-9545.90	5186.46
2015	97621.39	15397.23	6332.36	-9623.01	5268.79
2016	98977.98	15471.84	7237.79	-8473.93	5324.87

	1 Energy	2 IPPU	3 Agriculture	4 LULUCF	5 Waste
2017	99872.63	15703.35	7244.10	-6581.84	5356.90
2018	97789.24	16268.70	6205.35	-883.07	5409.25
2019	92902.73	15559.64	6570.47	6147.98	5456.58
2020	83686.54	14781.83	7196.96	9421.62	5456.62
2021	87553.60	16137.47	7340.24	5821.89	5484.80
2022	86758.28	15013.37	6775.89	2233.76	5546.84
2023	76851.89	12700.61	6691.58	-3756.48	5574.45
2024	72139.47	11102.40	7447.32	-4630.46	5521.60
[1]%	-6.13	12.58	-11.29	-23.27	0.95
[2]%	-54.84	-35.13	-42.77	-51.08	66.34
[1] *Difference relative to previous year*					
[2] *Difference relative to base year*					

Tab. 2-3 Overview of trends in categories and subcategories [kt CO_2 eq.]

GREENHOUSE GAS SOURCE AND SINK CATEGORIES	1990	1995	2000	2005	2015	2020	2024
Total (net emissions)	183734.62	144202.59	137192.96	136189.28	114996.77	120543.57	91580.33
1. Energy	159752.16	128866.78	121525.45	119734.20	97621.39	83686.54	72139.47
A. Fuel combustion (sectoral approach)	149390.66	120136.06	115201.92	114239.32	94618.75	82465.33	71223.64
1. Energy industries	56830.03	61734.87	62034.93	63138.26	53665.00	41595.47	31888.01
2. Manufacturing industries and construction	47105.11	24464.51	23422.11	18842.92	9867.20	10272.00	8864.87
3. Transport	11270.32	10441.59	12254.33	17365.70	17559.85	17858.62	20758.73
4. Other sectors	33990.91	23278.38	17312.56	14620.69	13151.85	12420.02	9461.84
5. Other	194.31	216.70	177.99	271.75	374.85	319.22	250.19
B. Fugitive emissions from fuels	10361.50	8730.72	6323.53	5494.89	3002.64	1221.22	915.83
1. Solid fuels	9163.83	7803.36	5344.83	4493.39	2316.25	743.58	538.91
2. Oil and natural gas and other emissions from energy production	1197.66	927.35	978.70	1001.49	686.39	477.64	376.92
2. Industrial Processes	17114.96	14160.27	15136.99	14912.31	15397.23	14781.83	11102.40
A. Mineral industry	4082.45	3019.09	3633.37	3345.75	3084.24	3218.44	2475.60
B. Chemical industry	2825.39	2694.75	2828.76	2706.44	2066.89	1619.90	1665.00
C. Metal industry	9811.61	7981.27	7434.79	7080.15	6496.16	5796.14	3045.05
D. Non-energy products from fuels and solvent use	125.56	103.75	140.30	120.85	141.57	130.22	118.55
E. Electronic industry	NO	NO	11.16	6.17	5.20	4.51	41.51
F. Product uses as ODS substitutes	NO	86.90	802.15	1357.29	3326.21	3747.86	3491.55
G. Other product manufacture and use	269.95	269.95	269.95	269.95	269.95	269.95	269.95
H. Other	NO	NO	0.37	0.36	0.57	0.97	1.11
3. Agriculture	13013.57	8867.08	7443.59	7353.20	6332.36	7196.96	7447.32
A. Enteric fermentation	6523.38	4230.72	3565.44	3334.82	3424.34	3519.76	3697.98
B. Manure management	2514.73	1724.91	1541.96	1285.26	718.26	757.32	761.71
D. Agricultural soils	2630.22	2686.33	2102.41	2519.52	1751.01	2599.04	2663.68
G. Liming	1236.71	115.86	117.89	67.18	171.20	164.87	132.49
H. Urea application	108.53	109.27	115.88	146.42	267.54	155.97	191.47
4. Land use, land-use change and forestry	-9465.50	-11362.61	-10892.87	-10171.53	-9623.01	9421.62	-4630.46
A. Forest land	-8363.45	-10630.29	-9637.19	-8751.82	-9013.41	12476.66	-2905.36
B. Cropland	284.93	261.55	247.08	206.62	202.47	96.84	97.51
C. Grassland	-188.59	-484.83	-631.66	-636.42	-619.58	-662.59	-818.01
D. Wetlands	-14.55	-25.32	12.77	-2.37	6.21	26.43	11.65
E. Settlements	496.64	343.47	387.01	446.28	278.98	276.44	269.18
G. Harvested wood products	-1680.47	-827.19	-1270.88	-1433.82	-477.68	-2792.16	-1285.43
5. Waste	3319.42	3671.07	3979.80	4361.10	5268.79	5456.62	5521.60
A. Solid waste disposal	2007.82	2440.80	2830.43	3072.49	3582.05	3689.00	3824.24
B. Biological treatment of solid waste	IE.NE	IE.NE	IE.NE	61.36	506.42	569.63	562.79
C. Incineration and open burning of waste	20.43	59.97	51.22	107.20	106.36	113.37	78.37
D. Waste water treatment and discharge	1291.18	1170.29	1098.15	1120.05	1073.95	1084.63	1056.20
Memo items:							
International bunkers	674.58	583.49	498.01	977.37	904.39	349.06	1377.21
Aviation	674.58	583.49	498.01	977.37	904.39	349.06	1377.21
CO_2 emissions from biomass	6445.39	5788.68	6658.55	8758.22	16540.55	19218.63	18388.84
Long-term storage of C in waste disposal sites	15558.30	19691.70	24677.97	30258.81	41699.66	47428.97	52311.52
Indirect N_2O	982.36	499.47	352.96	358.04	245.18	179.74	150.34
Indirect CO_2	1594.82	1279.72	1026.27	913.82	622.29	507.85	386.37
Total CO_2 equivalent emissions without LULUCF	193200.12	155565.20	148085.83	146360.81	124619.78	111121.95	96210.79
Total CO_2 equivalent emissions with LULUCF	183734.62	144202.59	137192.96	136189.28	114996.77	120543.57	91580.33
Total CO_2 equivalent emissions, including indirect CO_2, without LULUCF	194794.93	156844.91	149112.09	147274.62	125242.07	111629.80	96597.16
Total CO_2 equivalent emissions, including indirect CO_2, with LULUCF	185329.44	145482.30	138219.22	137103.09	115619.06	121051.42	91966.70

Energy (IPCC Category 1)

The trend for GHG emissions from 1 Energy category shows decreasing trend of emissions. They strongly decreased from 1990 to 1994 and then fluctuated by 2002. After 2002 they stayed relatively stable by 2007. In the period 2002–2007 emissions kept around 120 000 kt CO_2 eq. Emissions have continued to decline since 2007. Total decrease between 1990 and 2024 is 54.84% from 159 752.16-72 139.47 kt CO_2 eq.



Fig. 2-5 Trends in Energy by categories 1990–2024 (Mt CO_2 eq.)

Between 2023 and 2024 emissions from category 1 Energy decreased by -6.13%.

From the total 72 139.47 kt CO_2 eq. in 2024 98.73% comes from 1.A Fuel Combustion, the rest are 1.B Fugitive Emissions from Fuels (mainly Solid Fuels). 1.B Fugitive Emissions from Fuels used to be the larest source of CH_4, since 2011 the 5.A Solid waste disposal and since 2013. 3.A. Enteric fermentation dominated. In 2024 emission of CH_4 from category 1.B. was 8% of all CH_4 emissions in 2024.

CO_2 emissions from fossil fuels combustion (category 1.A Energy) are the main source in Czech Republic's inventory with a share of 96.6% in total emissions from Energy sector. CO_2 emissions from category 1 Energy contributes for 76.1% to total GHG emissions, CH_4 for 1.9% and N_2O for 0.75% in 2024 (excl. LULUCF).

Industrial Processes and Product Use (IPCC Category 2)

GHG emissions from the 2 Industrial Processes and Product Use category fluctuated with decreasing trend during the whole period 1990 to 2024. In early 90's emissions decreased rather rapidly. They reached decade minimum in 1993 and since then they have fluctuated. By the end of nineties they reached their decade minimum due to global economic recession. Between 1990 and 2024, emissions from this category decreased by 35.13%. In 2024 emissions amounted for 11 102.40 kt CO_2 eq.



Fig. 2-6 Trends in IPPU by categories 1990–2024 (Mt CO_2 eq.)

The main categories in the 2 Industrial Processes and Product Use category are 2.F Product Uses as ODS substitutes (31.45%), 2.C Metal Industry (27.4%), 2.A Mineral Industry (22.3%) and 2.B Chemical Industry (15%) of the sectoral emissions in 2024 (Fig. 2-6).

The most important GHG of the 2 Industrial Processes and Product Use category was CO_2 with 64.23% of sectoral emissions, followed by F-gases (31.78%).

Agriculture (IPCC Category 3)

GHG emissions from the category 3 Agriculture decreased relatively steadily over the period from 1990 to 2003 and then fluctuated. In 2003 emissions reached minimum level which was 53% below the base year level.

Agriculture amounted to 7 447.32 CO_2 eq. in 2024 which corresponds to 8.1% of national total emissions (excl. indirect emissions, excl. LULUCF). The most important sub-category 3.A Enteric Fermentation (CH_4 emissions) contributed by 49.66% to sectoral total in 2024, followed by the 3.D Agricultural Soils (N_2O emissions, 35.77%).



Fig. 2-7 Trends in Agriculture by categories 1990–2024 (Mt CO_2 eq.)

3 Agriculture is the largest source for N_2O and second largest source for CH_4 emissions (70.39% of total emissions of N_2O and 36.72% of total emissions of CH_4, excl. LULUCF). However its emission trend steadily decreases over the whole observed period.

Land Use, Land-Use Change and Forestry (IPCC Category 4)

GHG removals from the 4 Land Use, Land-Use Change and Forestry category vary through the whole time series with maximum of -12 406.73 kt CO_2 eq. in 1993 and minimum in 2020 (9 421.62 kt CO_2 eq.).

Emissions and removals amounted to -4 630.46 kt CO_2 eq. in 2024, which corresponds to 5% of total national emissions.

In the period from 2019–2022 the LULUCF did not work as the sink for CO_2. Starting with 2015 the removals decreased and resulted in emissions since 2019. The situation is caused by the extreme drought-induced accelerating bark-beetle outbreak calamity experienced in the Czech forestry in the recent years (since 2015).

LULUCF category is again from the year 2023 the sink for CO_2.



Fig. 2-8 Trends in LULUCF by separate source and sink categories 1990–2024 (Mt CO_2 eq.)

Waste (IPCC Category 5)

GHG emissions from category 5 Waste substantially increased during the whole period. In 2024 emissions amounted for 5 521.60 kt CO_2 eq., which is 66.34% above the base year level. The increase of emissions is mainly due to higher emissions of CH_4 from 5.A Solid Waste Disposal and due higher emissions in 5.D Waste water treatment and discharge. The share of category 5 Waste in total emissions was 6.03% in 2024.



Fig. 2-9 Trends in Waste by categories 1990–2024 (Mt CO_2 eq.)

The main source is solid 5.A Solid Waste Disposal, which accounted for 69.26% of sectoral emissions in 2024, followed by 5.D Wastewater Treatment and Discharge (19.13%) and 5.B Biological treatment of solid waste (10.2%). Trends of the separate sub-categories in Waste sector can be observed on Fig. 2-9.

93.9% of all emissions from Waste category are CH_4 emissions; CO_2 contributes by 1.28% and N_2O by 4.82%.

2.1.3 Description and interpretation of emission trends of indirect greenhouse gases and SO_2

Description of trends of emissions of indirect greenhouse gases is provided in Chapter 9.

3 Energy (CRT Sector 1)

3.1 Overview of sector

The Czech Republic's energy sector is driven by fossil fuel combustion in stationary and mobile sources; however, fugitive emissions are also an important source of emissions. The two main categories are 1.A Fuel Combustion and 1.B Fugitive Emissions from Fuels.

Activity data are based on the energy balance of the Czech Republic prepared by the Czech Statistical Office (CzSO). Data from the energy balance form the basic framework for processing greenhouse gas emissions from combustion in stationary and mobile sources. Greenhouse gas emissions from stationary sources are calculated from the activity data and the emission factors.

Processing of the activity data is based on the total energy balance of the Czech Republic. The energy balance is prepared by CzSO and divided into issues for Solid Fuels, Liquid Fuels, Natural Gas, renewable energy sources and heat and electrical energy production. Information on the energy balance forms the basis for preparing a database of activity data in the Reference and Sectoral Approaches. The Reference Approach is based on data from the source part of the energy balance; the Sectoral Approach involves the data processing on fuel consumption in a structure corresponding to the requirements of the IPCC categorisation.

Default emission factors from the IPCC methodology have been for key categories gradually substituted by country-specific emission factors.

Inventories of CO_2, CH_4 and N_2O emissions from subsector 1.A.3 Transport use the CDV model for mobile sources. This model is fully harmonised with activity data from the official CzSO Energy balance mentioned above.

Fugitive emissions in sector 1.B are determined by calculation from activity data and country-specific or default emission factors. The activity data are obtained mainly from the official CzSO energy balance. The sector statistics and annual targeted surveys are used in special cases, when data missing or are insufficient.

The Czech Republic declines any responsibility of errors caused by the UNFCCC ETF reporting tool, the latest version 1.30.5 of the ETF tool from the 9th of December 2026 was used for creating the submission. CRT table cells, which do not affect the national total, may still have an empty cell instead of NA or NO and have Tier and method parameters missing in the automated summary sheets due to bugs in the ETF reporting tool even sector background table white cells have been sussesfully filled by the sector expert. For more information on completeness and the ETF bugs, please see Annex 5.6.

3.1.1 Key categories in sector 1 Energy

Combustion processes included in category 1.A make a decisive contribution to total emissions of greenhouse gases. All CO_2, CH_4 and N_2O emissions are derived from the combustion of fossil, biofuels and/or other fuels in stationary and mobile sources.

Overall, 18 key sources have been identified in sector 1, the most important of which are the first 4 in Tab. 3-1. This sources contributes 61% to total greenhouse gas emissions (without LULUCF).

It is apparent from the table that the first four categories are of fundamental importance for the level of greenhouse gas emissions in the Czech Republic and the combustion of Solid Fuels constitutes a decisive source. This consists primarily of the combustion of Solid Fuels for electricity production and heat supply. Another important category consists of the combustion of Liquid Fuels in the transport sector and the combustion of Natural Gas has approximately the same importance. This corresponds mostly to the direct heat production for buildings in the private and public sector and households. Consequently, increased attention is paid to it.

The results of the inventory, including the activity data, are submitted in the standard CRT format. For direct greenhouse gases, the consumption of fuels and "implied" emission factors are also given. However, for stationary sources, the fuel consumption is given in the CRT format in aggregated structure, i.e. Solid, Liquid and Gaseous Fuels according to IPCC definition. All the CRT Tables in sector 1.A were appropriately completed for the entire required interval of 1990 to 2024.

Tab. 3-1 Overview of key categories in 1 Energy (2024)

Category	Gas	KC A1	KC A2	KC A1[1]	KC A1[2]	KC A2[1]	KC A2[2]	% of total GHG[1]	% of total GHG [2]
1.A.1 Energy industries - Solid Fuels	CO_2	LA, TA	LA	Yes	Yes	Yes	Yes	30.81	29.32
1.A.3.b Road Transportation	CO_2	LA, TA	LA, TA	Yes	Yes	Yes	Yes	21.99	20.93
1.A.4 Other Sectors - Gaseous Fuels	CO_2	LA, TA	LA, TA	Yes	Yes	Yes	Yes	6.22	5.92
1.A.2 Manufacturing Industries and Construction - Gaseous Fuels	CO_2	LA, TA	LA	Yes	Yes	Yes	Yes	5.00	4.76
1.A.2 Manufacturing Industries and Construction - Solid Fuels	CO_2	LA, TA	LA, TA	Yes	Yes	Yes	Yes	3.40	3.23
1.A.1 Energy industries - Gaseous Fuels	CO_2	LA, TA		Yes	Yes			3.03	2.88
1.A.4 Other Sectors - Solid Fuels	CO_2	LA, TA	LA, TA	Yes	Yes	Yes	Yes	1.69	1.61
1.A.4 Other Sectors - Liquid Fuels	CO_2	LA, TA	LA	Yes	Yes		Yes	1.41	1.34
1.A.4 Other Sectors - Biomass	CH_4	LA, TA	LA, TA	Yes	Yes	Yes	Yes	0.70	0.67
1.A.2 Manufacturing Industries and Construction - Liquid Fuels	CO_2	LA, TA		Yes	Yes			0.63	0.60
1.A.2 Manufacturing Industries and Construction - Other Fossil Fuels	CO_2	LA, TA	LA, TA	Yes	Yes	Yes	Yes	0.53	0.50
1.B.1.a Coal Mining and Handling	CH_4	LA, TA	LA, TA	Yes	Yes	Yes	Yes	0.52	0.49
1.A.1 Energy industries - Liquid Fuels	CO_2	TA		Yes	Yes			0.39	0.37
1.B.2.b Fugitive Emissions from Fuels - Oil and Natural Gas - Natural Gas	CH_4		LA, TA			Yes	Yes	0.38	0.36
1.A.3.b Road Transportation	N_2O		LA, TA			Yes	Yes	0.37	0.35
1.A.4 Other Sectors - Solid Fuels	CH_4	TA	LA, TA	Yes	Yes	Yes	Yes	0.15	0.14
1.A.1 Energy industries - Solid Fuels	N_2O		LA				Yes	0.12	0.12
1. Energy (indirect CO_2 emissions)	CO_2	TA		Yes	Yes			0.10	0.10

KC: key category
[1] including LULUCF
[2] excluding LULUCF

3.1.2 Emissions Trends

CO_2 emissions from the 1.A sector decreased by 53% from 147 Mt CO_2 in 1990 to 70 Mt CO_2 in 2024. Furthermore, CO_2 emissions from the 1.B sector decreased by 88% from 545 kt in 1990 to 64 kt in 2024, as well as CH_4 emissions from 1.B sectors decreased by 91% from 351 kt in 1990 to 30 kt in 2024. Fig. 3-1 indicates an overall trend in CO_2 and CH_4 emissions in the whole time series for both sectors. Furthermore, Fig. 3-1 provides data for trends in 1 Energy for each gas reported in the sector.



Fig. 3-1 Trend total CO_2 (Sectoral Approach) in 1.A and trend of CO_2 and CH_4 from 1.B sector in period 1990 – 2024

Tab. 3-2 Emissions of greenhouse gases and their trend from 1990–2024 from IPCC Category 1 Energy

	CO_2 [kt]	CH_4 [kt]	N_2O [kt]
1990	147 187	425.77	2.43
1991	135 699	388.68	2.25
1992	132 143	358.49	2.20
1993	127 557	371.53	2.17
1994	119 000	353.52	2.18
1995	118 585	346.06	2.23
1996	121 299	345.82	2.33
1997	116 444	334.81	2.31
1998	111 185	318.10	2.28
1999	104 727	288.64	2.31
2000	113 955	247.49	2.42
2001	114 732	219.20	2.02
2002	111 767	212.42	2.01
2003	114 407	207.39	2.08
2004	114 373	199.32	2.10
2005	113 126	216.32	2.08
2006	112 931	223.48	2.10
2007	114 244	206.38	2.18
2008	109 133	205.37	2.12
2009	103 783	183.02	2.00
2010	105 491	171.91	2.02
2011	103 044	167.21	2.05
2012	99 458	162.55	2.03
2013	94 964	141.12	2.01
2014	91 976	142.00	2.27
2015	93 100	138.20	2.46
2016	94 767	124.79	2.71
2017	95 873	116.03	2.83
2018	93 975	109.24	2.85
2019	89 356	100.27	2.79
2020	80 710	80.79	2.70
2021	84 391	85.99	2.85

	CO_2 [kt]	CH_4 [kt]	N_2O [kt]
2022	83 802	78.53	2.86
2023	74 303	66.08	2.64
2024	69 697	62.82	2.58
Trend 1990/2024	**-53%**	**-85%**	**-6%**

3.1.2.1 Emission trends by subcategories

The individual subsectors have different contributions to trends in emissions. Fig. 3-2 illustrates the trends in emissions on the example of CO_2 emissions and the share of CO_2 emissions in different subsectors in 2024.

The greatest increase in emissions was recorded in subsector 1.A.3 Transport between 1990 and 2007 when emissions increased by 66%. In absolute values, this corresponded to an increase from 11 Tg CO_2 in 1990 to 18 Tg in 2007. A slight decrease has been apparent since 2008, while between 2014 and 2019 is an apparent slight increase to 1.8 Tg. In 2020 and 2021, a slight decrease is evident due to the COVID-19 pandemic. After that, the emissions increase slightly again to 2 Tg in 2024. Emissions from subsector 1.A.1 Energy Industries are almost constant with slight fluctuations over the entire period. The decrease observed in 2020–2022 can be attributed to the COVID-19 pandemic and the war in Ukraine. This was followed by a slight increase in 2023, reflecting the stabilization of the economy and industrial activity. A similar trend is observed in category 1.A.2. The greatest reduction occurred in subsectors 1.A.2 and 1.A.4 from 47 and 32 Tg CO_2 in 1990 to 9 and 9 Tg CO_2 in 2024, respectively.



Fig. 3-2 Share and development of CO_2 emissions from 1990–2024 in individual sub-sectors; share of CO_2 emissions in individual subsectors in 2024 [kt]

Fig. 3-3 demonstrates that the fugitive emissions from Solid fuels also indicate a substantial decrease in the whole time series, i.e. 89% for CO_2 emissions and 95% for CH_4 emissions. Fugitive CH_4 emissions from Oil and Natural Gas also indicate a decrease of 69% in the time series. Fugitive CO_2 emissions from Oil and Natural Gas indicate an increase, although, these emissions are of minor importance in the whole submission.

The trends for different subcategories are also presented in Tab. 3-3.



Fig. 3-3 CO_2 and CH_4 trend from the sector Fugitive Emissions from Solid Fuels and from the sector Fugitive Emissions from Oil and Natural Gas.

Tab. 3-3 Total GHG emissions in [kt CO_2 equivalent] from 1990–2024 by subcategories of Energy

	1	1.A	1.A.1	1.A.2	1.A.3	1.A.4	1.A.5	1.B	1.B.1	1.B.2
1990	159 752	149 391	56 830	47 105	11 270	33 991	194	10 361	9 164	1 198
1991	147 179	137 746	55 452	39 853	10 207	32 078	156	9 434	8 404	1 030
1992	142 765	133 987	54 626	43 890	10 626	24 644	201	8 778	7 825	953
1993	138 535	129 313	54 297	36 746	10 189	27 892	188	9 222	8 288	934
1994	129 476	120 662	54 818	29 181	11 117	25 332	214	8 814	7 896	919
1995	128 867	120 136	61 735	24 465	10 442	23 278	217	8 731	7 803	927
1996	131 600	122 920	66 489	24 250	10 669	21 301	210	8 680	7 678	1 002
1997	126 431	117 949	62 782	24 057	10 652	20 261	197	8 482	7 486	996
1998	120 694	112 462	60 652	21 702	12 039	17 897	172	8 233	7 182	1 050
1999	113 420	105 924	58 200	18 504	12 161	16 894	165	7 496	6 467	1 029
2000	121 525	115 202	62 035	23 422	12 254	17 313	178	6 324	5 345	979
2001	121 405	115 884	64 217	20 876	13 026	17 603	162	5 522	4 597	924
2002	118 247	112 887	62 770	19 995	13 489	16 392	240	5 361	4 385	976
2003	120 765	115 568	62 422	19 934	15 369	17 600	244	5 197	4 285	911
2004	120 511	115 548	62 541	19 567	16 078	17 090	272	4 962	4 113	850
2005	119 734	114 239	63 138	18 843	17 366	14 621	272	5 495	4 493	1 001
2006	119 747	114 056	62 588	18 542	17 662	15 011	253	5 691	4 686	1 004
2007	120 600	115 402	66 235	16 657	18 613	13 557	339	5 198	4 198	1 000
2008	115 445	110 285	61 506	16 072	18 477	13 862	367	5 161	4 242	919
2009	109 438	104 999	57 437	15 780	17 801	13 626	355	4 439	3 472	967
2010	110 841	106 767	62 175	12 112	16 796	15 364	320	4 074	3 074	1 000
2011	108 269	104 333	61 893	11 144	16 627	14 292	377	3 936	3 001	935
2012	104 548	100 771	59 023	10 798	16 339	14 302	308	3 777	3 016	761
2013	99 448	96 375	55 201	10 261	16 212	14 400	301	3 073	2 363	710
2014	96 553	93 418	53 768	9 731	16 775	12 831	313	3 135	2 428	707
2015	97 621	94 619	53 665	9 867	17 560	13 152	375	3 003	2 316	686
2016	98 978	96 387	54 429	9 605	18 270	13 681	403	2 591	1 908	683
2017	99 873	97 593	53 647	10 470	18 796	14 219	460	2 279	1 594	685
2018	97 789	95 709	52 934	10 220	18 993	13 242	320	2 080	1 400	680
2019	92 903	91 099	49 176	9 780	19 159	12 683	300	1 804	1 135	669
2020	83 687	82 465	41 595	10 272	17 859	12 420	319	1 221	744	478
2021	87 554	86 273	41 006	12 972	19 072	12 853	370	1 280	732	548
2022	86 758	85 653	42 779	11 343	19 547	11 713	272	1 105	634	471
2023	76 852	75 922	35 674	10 160	20 034	9 810	244	930	557	372
2024	72 140	71 224	31 888	8 865	20 759	9 462	250	916	539	377
Total Trend 1990–2024	**-55%**	**-52%**	**-44%**	**-81%**	**84%**	**-72%**	**29%**	**-91%**	**-94%**	**-69%**

3.2 Fuel combustion activities (CRT 1.A)

3.2.1 Comparison of the sectoral approach with the reference approach

In addition to the Sectoral approach (SA), used commonly for the determination of greenhouse gas emissions from sector 1.A, the IPCC methodology requires also performing a Reference Approach (RA), whose main objective is to control the estimation of the CO_2 emissions in the Sectoral approach. The calculation does not require a lot of input activity data, since the reference approach requires only the basic values included in the source section of the national energy balance (primary sources) and some additional information. It provides information only on total CO_2 emissions without any further division into consumer sectors.

From the 2015 submission onward, it is required to use the Reference Approach in line with IPCC 2006 Guidelines (IPCC, 2006). The old reference approach (IPCC 1997) used the concept of "long-term stored carbon" (stored carbon), for some non-energy fuels. Whereas a new one uses a broader concept of "excluded carbon", which includes the stored carbon as well as carbon used and emitted as CO_2 in other sectors along with 1.A (most often in sector 2 IPPU). This means that from the total carbon, calculated on the base of apparent domestic consumption (Apparent consumption, AC) is deducted the "excluded carbon". It is mainly the case of carbon contained in fossil fuels used: (i) as raw materials for further treatment in the industry (feedstocks), (ii) as reductants and (iii) as non-energy products. Overview of materials, containing "excluded carbon" is given in Tab. 3-4.

Tab. 3-4 Products used as feedstocks, reductants, and for non-energy products (IPCC, 2006)

Feedstocks	**Naphtha**
	LPG (propane - butane)
	Oils used as feedstocks
	Refinery gas
	Natural gas
	Ethane
Reductants	**Metallurgical coke and petroleum coke**
	Coal and coal tar/pitch
	Natural gas
Non-energy products	**Bitumen**
	Lubricants
	Paraffin waxes
	White spirit

For fuels used in other sectors, than Energy sector – 1.A (i.e. non-energy fuels: for example, coke or naphtha), it is necessary to know, what quantity of certain material is used outside 1.A (e.g. feedstock or reductant).

In the Czech national inventory above mentioned "excluded carbon" is considered for counting in the case of the following substances:

- Naphtha
- Bitumen
- Paraffin waxes
- Oils used for the production of hydrogen by partial oxidation (further for ammonia)
- White spirit

In Tab. 3-5 and Tab. 3-6 are reported values, set by the reference approach for the years 1990, 1995, 2000, 2005, 2010, 2015, 2020, 2021, 2022, 2023 and 2024 and a comparison between the reference and sectoral

approach for the same years. Tab. 3-7 summarises the comparison for all periods. In the majority of cases, relative differences are less than 2%.

Tab. 3-5 Activity data in energy units [TJ], used in reference and sectoral approach for basic groups of fossil fuels

Year	Type of fossil fuels	Apparent Consumption [PJ]	Carbon excluded [PJ]	Reference approach [PJ]	Sectoral approach [PJ]	(RA-SA)/SA [%]
1990	Liquid Fuels	358.54	71.77	286.78	296.23	-3.19
	Solid Fuels	1 315.08	86.73	1 228.36	1 179.22	4.17
	Gaseous Fuels	219.91		219.91	205.43	7.05
	Other Fuels	0.26		0.26	0.26	0.00
	Total	**1 893.79**	**158.49**	**1 735.30**	**1 681.14**	**3.22**
1995	Liquid Fuels	321.28	96.96	224.31	232.82	-3.66
	Solid Fuels	937.64	71.03	904.15	866.61	4.33
	Gaseous Fuels	274.74		274.74	260.80	5.35
	Other Fuels	0.65		0.65	0.68	-4.15
	Total	**1 534.31**	**167.99**	**1 403.86**	**1 360.91**	**3.16**
2000	Liquid Fuels	312.99	87.58	225.41	240.00	-6.08
	Solid Fuels	901.78	66.29	835.48	822.67	1.56
	Gaseous Fuels	314.52		314.52	305.05	3.10
	Other Fuels	1.28		1.28	1.39	-7.92
	Total	**1 530.56**	**153.87**	**1 376.69**	**1 369.11**	**0.55**
2005	Liquid Fuels	387.91	111.37	276.54	292.25	-5.38
	Solid Fuels	847.06	75.47	771.58	762.94	-1.12
	Gaseous Fuels	323.04		323.04	318.87	-1.29
	Other Fuels	5.69		5.69	5.69	0.08
	Total	**1 563.70**	**186.84**	**1 376.86**	**1 379.76**	**-0.21**
2010	Liquid Fuels	370.18	99.60	270.58	277.43	-2.47
	Solid Fuels	780.54	71.50	709.05	703.19	0.83
	Gaseous Fuels	338.54	3.80	334.74	309.77	8.06
	Other Fuels	5.89		5.89	6.20	-4.96
	Total	**1 495.16**	**174.90**	**1 320.26**	**1 296.59**	**1.83**
2015	Liquid Fuels	354.66	81.87	272.78	278.53	-2.06
	Solid Fuels	682.81	73.80	609.01	595.94	2.19
	Gaseous Fuels	272.02	4.02	268.00	263.17	1.83
	Other Fuels	8.14		8.14	8.56	-4.84
	Total	**1 317.63**	**159.69**	**1 157.94**	**1 146.21**	**1.02**
2020	Liquid Fuels	354.36	83.90	270.46	272.58	-0.78
	Solid Fuels	511.35	63.57	447.79	452.69	-1.08
	Gaseous Fuels	305.36	4.00	301.36	298.28	1.03
	Other Fuels	10.01		10.01	10.55	-5.16
	Total	**1 181.08**	**151.46**	**1 029.62**	**1 034.09**	**-0.43**
2021	Liquid Fuels	388.72	99.98	288.74	292.95	-1.44
	Solid Fuels	536.05	70.59	465.45	465.84	-0.08
	Gaseous Fuels	327.17	3.45	323.72	320.43	1.03
	Other Fuels	9.62		9.62	10.13	-5.04
	Total	**1 261.56**	**174.02**	**1 087.54**	**1 089.35**	**-0.17**
2022	Liquid Fuels	395.33	98.22	297.11	298.16	-0.35
	Solid Fuels	561.26	62.34	498.92	486.85	2.48
	Gaseous Fuels	266.25	2.59	263.66	260.92	1.05
	Other Fuels	9.48		9.48	9.94	-4.64
	Total	**1 232.32**	**163.15**	**1 069.17**	**1 055.86**	**1.26**
2023	Liquid Fuels	387.67	84.18	303.49	305.73	-0.73
	Solid Fuels	449.93	51.87	398.06	398.17	-0.03
	Gaseous Fuels	241.75	2.21	239.54	233.08	2.77
	Other Fuels	9.92		9.92	10.35	-4.14
	Total	**1 089.26**	**138.26**	**951.00**	**947.33**	**0.39**
2024	Liquid Fuels	399.13	84.73	314.40	315.54	-0.36

Year	Type of fossil fuels	Apparent Consumption [PJ]	Carbon excluded [PJ]	Reference approach [PJ]	Sectoral approach [PJ]	(RA-SA)/SA [%]
	Solid Fuels	392.75	38.62	354.13	339.12	4.43
	Gaseous Fuels	241.33	2.59	238.74	236.24	1.06
	Other Fuels	9.42		9.42	9.85	-4.39
	Total	**1 042.63**	**125.94**	**916.69**	**900.74**	**1.77**

Tab. 3-6 Results for CO_2 emissions (kt) according to reference approach and comparison with sectoral approach

Year	Type of fossil fuels	Apparent Consumption [kt CO_2]	Carbon excluded [kt CO_2]	RA [kt CO_2]	SA [kt CO_2]	(RA-SA)/SA [%]
1990	Liquid Fuels	26 349.67	5 392.23	20 957.44	22 056.62	-4.98
	Solid Fuels	126 345.49	9 279.67	117 065.82	113 360.35	3.27
	Gaseous Fuels	11 990.12	0.00	11 990.12	11 200.98	7.05
	Other Fuels	24.04		24.04	24.04	0.00
	Total	**164 709.32**	**14 671.90**	**150 037.42**	**146 642.01**	**2.32**
1995	Liquid Fuels	23 430.72	7 196.52	16 234.20	17 163.79	-5.42
	Solid Fuels	89 857.92	7 600.34	82 257.58	86 592.46	-5.01
	Gaseous Fuels	15 110.05	0.00	15 110.05	14 343.44	5.34
	Other Fuels	59.83		59.83	61.98	-3.48
	Total	**128 458.53**	**14 796.86**	**113 661.67**	**118 161.68**	**-3.81**
2000	Liquid Fuels	22 778.85	6 481.09	16 297.76	17 567.22	-7.23
	Solid Fuels	86 605.17	7 093.20	79 511.97	79 108.45	0.51
	Gaseous Fuels	17 297.33	0.00	17 297.33	16 776.79	3.10
	Other Fuels	117.00		117.00	125.38	-6.68
	Total	**126 798.35**	**13 574.29**	**113 224.05**	**113 577.85**	**-0.31**
2005	Liquid Fuels	28 354.46	8 282.18	20 072.29	21 540.01	-6.81
	Solid Fuels	81 117.70	7 749.76	73 367.94	73 181.95	0.25
	Gaseous Fuels	17 764.59	0.00	17 764.59	17 535.52	1.31
	Other Fuels	500.73		500.73	501.09	-0.07
	Total	**127 737.48**	**16 031.93**	**111 705.55**	**112 758.57**	**-0.93**
2010	Liquid Fuels	27 100.68	7 393.62	19 707.06	19 962.98	-1.28
	Solid Fuels	74 538.37	7 295.57	67 242.80	67 549.56	-0.45
	Gaseous Fuels	18 714.77	210.14	18 504.63	17 124.50	8.06
	Other Fuels	512.00		512.00	535.46	-4.38
	Total	120 865.81	14 899.33	105 966.49	105 172.49	0.75
2015	Liquid Fuels	26 058.47	6 134.38	19 924.09	20 020.53	-0.48
	Solid Fuels	65 248.36	7 544.72	57 703.64	57 527.58	0.31
	Gaseous Fuels	15 068.08	223.06	14 845.02	14 579.00	1.82
	Other Fuels	702.53		702.53	734.51	-4.35
	Total	**107 077.44**	**13 902.15**	**93 175.29**	**92 861.61**	**0.34**
2020	Liquid Fuels	25 990.24	6 234.08	19 756.16	19 589.08	0.85
	Solid Fuels	48 912.60	6 467.61	42 444.99	43 590.54	-2.63
	Gaseous Fuels	16 947.97	221.52	16 726.45	16 556.15	1.03
	Other Fuels	845.80		845.80	887.43	-4.69
	Total	**92 696.61**	**12 923.20**	**79 773.40**	**80 623.20**	**-1.05**
2021	Liquid Fuels	28 573.84	7 407.94	21 165.90	21 013.32	0.73
	Solid Fuels	51 096.23	7 175.98	43 920.25	44 644.34	-1.62
	Gaseous Fuels	18 137.63	191.45	17 946.18	17 765.23	1.02
	Other Fuels	841.23		841.23	880.24	-4.43
	Total	**98 648.92**	**14 775.37**	**83 873.56**	**84 303.13**	**-0.51**
2022	Liquid Fuels	28 965.19	7 258.71	21 706.48	21 398.82	1.44
	Solid Fuels	53 597.72	6 281.96	47 315.76	46 931.04	0.82
	Gaseous Fuels	14 850.32	144.43	14 705.89	14 543.73	1.11
	Other Fuels	813.15		813.15	849.03	-4.23
	Total	**98 226.38**	**13 685.11**	**84 541.27**	**83 722.63**	**0.98**
2023	Liquid Fuels	28 426.97	6 257.34	22 169.63	21 931.46	1.09
	Solid Fuels	42 908.97	5 121.20	37 787.77	38 379.95	-1.54

Year	Type of fossil fuels	Apparent Consumption [kt CO_2]	Carbon excluded [kt CO_2]	RA [kt CO_2]	SA [kt CO_2]	(RA-SA)/SA [%]
	Gaseous Fuels	13 524.15	123.60	13 400.55	13 028.68	2.85
	Other Fuels	861.58		861.58	894.33	-3.66
	Total	**85 721.67**	**11 502.15**	**74 219.53**	**74 234.42**	**-0.02**
2024	Liquid Fuels	29 316.58	6 297.00	23 019.58	22 657.15	1.60
	Solid Fuels	37 630.87	3 786.07	33 844.80	32 904.04	2.86
	Gaseous Fuels	13 535.18	145.35	13 389.82	13 237.13	1.15
	Other Fuels	801.35		801.35	834.38	-3.96
	Total	**81 283.98**	**10 228.42**	**71 055.56**	**69 632.71**	**2.04**

Tab. 3-7 Apparent consumption in energy units (PJ) used in reference and sectoral approach for all fossil fuels and corresponding results for CO_2 emissions (kt)

Year	Appar. cons. [PJ]	Carbon excluded [PJ]	Reference approach [PJ]	Sectoral approach [PJ]	(RA-SA)/SA [%]	Activity data [kt CO_2]	Carbon excluded [kt CO_2]	Reference approach [kt CO_2]	Sectoral approach [kt CO_2]	(RA-SA)/SA [%]
1990	1 893.79	158.49	1 735.30	1 681.14	3.22	164 709	14 672	150 037	146 642	2.32
1991	1 702.58	114.01	1 588.57	1 553.39	2.27	148 049	10 766	137 283	135 218	1.53
1992	1 640.02	120.19	1 519.83	1 540.14	-1.32	140 211	11 327	128 884	131 672	-2.12
1993	1 579.18	108.30	1 470.88	1 493.01	-1.48	134 585	10 250	124 335	127 108	-2.18
1994	1 511.02	130.62	1 380.40	1 394.97	-1.04	127 864	12 125	115 739	118 568	-2.39
1995	1 534.31	167.99	1 366.32	1 398.46	-2.30	128 459	14 797	113 662	118 162	-3.81
1996	1 576.75	174.02	1 402.74	1 448.53	-3.16	130 456	15 311	115 145	120 885	-4.75
1997	1 591.93	171.18	1 420.75	1 396.81	1.71	132 368	15 251	117 117	116 027	0.94
1998	1 542.54	167.22	1 375.32	1 348.16	2.01	127 082	14 935	112 147	110 790	1.22
1999	1 424.49	149.05	1 275.43	1 281.17	-0.45	115 474	12 876	102 598	104 365	-1.69
2000	1 530.56	153.87	1 376.69	1 369.11	0.55	126 798	13 574	113 224	113 578	-0.31
2001	1 555.74	151.23	1 404.50	1 389.08	1.11	127 887	13 262	114 625	114 344	0.25
2002	1 537.36	158.85	1 378.51	1 356.20	1.64	126 239	14 023	112 215	111 380	0.75
2003	1 558.48	167.48	1 391.01	1 389.49	0.11	128 122	14 871	113 251	114 029	-0.68
2004	1 527.10	195.67	1 331.43	1 394.02	-4.49	124 541	17 064	107 477	114 005	-5.73
2005	1 563.70	186.84	1 376.86	1 379.76	-0.21	127 737	16 032	111 706	112 759	-0.93
2006	1 591.18	196.82	1 394.37	1 378.92	1.12	130 360	17 090	113 270	112 541	0.65
2007	1 591.56	187.37	1 404.19	1 387.60	1.20	131 364	16 424	114 939	113 886	0.92
2008	1 530.32	192.37	1 337.95	1 333.70	0.32	125 143	16 524	108 619	108 783	-0.15
2009	1 406.91	158.87	1 248.05	1 265.42	-1.37	114 661	13 513	101 147	103 474	-2.25
2010	1 495.16	174.90	1 320.26	1 296.59	1.83	120 866	14 899	105 966	105 172	0.75
2011	1 416.33	167.38	1 248.95	1 254.85	-0.47	115 981	14 343	101 638	102 726	-1.06
2012	1 364.61	170.23	1 194.39	1 214.90	-1.69	111 078	14 512	96 566	99 139	-2.60
2013	1 356.65	167.65	1 189.00	1 169.07	1.70	110 255	14 393	95 862	94 714	1.21
2014	1 292.57	179.77	1 112.79	1 127.78	-1.33	105 018	15 384	89 634	91 726	-2.28
2015	1 317.63	159.69	1 157.94	1 146.21	1.02	107 077	13 902	93 175	92 862	0.34
2016	1 320.37	134.20	1 186.16	1 172.52	1.16	106 821	12 048	94 773	94 560	0.23
2017	1 350.81	173.75	1 177.06	1 190.99	-1.17	108 362	14 651	93 711	95 698	-2.08
2018	1 340.86	178.17	1 162.69	1 165.57	-0.25	107 986	15 082	92 904	93 823	-0.98
2019	1 294.49	174.09	1 120.41	1 123.55	-0.28	102 996	14 572	88 424	89 231	-0.90
2020	1 181.08	151.46	1 029.62	1 034.09	-0.43	92 697	12 923	79 773	80 623	-1.05
2021	1 261.56	174.02	1 087.54	1 089.35	-0.17	98 649	14 775	83 874	84 303	-0.51
2022	1 232.32	163.15	1 069.17	1 055.86	1.26	98 226	13 685	84 541	83 723	0.98
2023	1 089.26	138.26	951.00	947.33	0.39	85 722	11 502	74 220	74 234	-0.02
2024	1 042.63	125.94	916.69	900.74	1.77	81 284	10 228	71 056	69 633	2.04

In the years 1990, 1992, 1993, 1994, 1995, 1996, 2004, 2009, 2012, 2014, 2017 and 2024 the difference between reference and sectoral approach is higher than 2%. These differences are mainly caused by statistical differences (SD), as in Tab. 3-8. The ratio between RA and SA did not decrease under 2% even though SD was subtracted for some years. This effect can be caused by stock changes which have not been

properly reported to CzSO. This assumption is based on the minimal difference between RA and SA for the surrounding years. In 2024, the CZSO 2025 reported higher-than-usual distribution losses. After accounting for statistical differences and distribution losses, the resulting difference for 2024 was 1.83%.

Tab. 3-8 Explanation of high differece between reference and sectoral approach

Years	(RA-SA)/SA [%]	Statistical diffrences (SD) [TJ]	Share SD from sectoral approach [%]	(RA-SA)/SA without SD [%]
1990	2.32	63 291.46	3.64	-1.33
1992	-2.12	12 102.61	0.75	-2.87
1993	-2.18	-7 624.00	-0.49	-1.69
1994	-2.39	-15 358.79	-1.05	-1.33
1995	-3.81	-9 474.04	-0.65	-3.16
1996	-4.75	-6 487.71	-0.43	-4.32
2004	-5.73	-14 375.19	-0.98	-4.75
2009	-2.25	-13 943.30	-1.01	-1.24
2012	-2.60	-3 619.83	-0.27	-2.33
2014	-2.28	6 451.82	0.50	-2.78
2017	-2.08	-3 891.90	-0.29	-1.79
2024	2.04	-373.30	-0.03	2.08

3.2.2 International bunker fuels

In the Czech Republic, this corresponds only to the storage of Kerosene Jet Fuel for international air transport since the Czech Republic does not have an ocean fleet.

Basic activity data are available in the CzSO energy balance (CzSO, 2025). Tab. 3-9 gives the amount of stored Kerosene Jet Fuel.

Tab. 3-9 Kerosene Jet Fuel in international bunkers

Year	1990	1991	1992	1993	1994	1995	1996	1997	1998	1999	2000	2001	2002	2003	2004
[TJ/year]	7 344	6 040	6 996	5 823	7 257	7 820	5 603	5 217	4 902	5 633	6 665	6 762	6 976	8 432	12 070
Year	**2005**	**2006**	**2007**	**2008**	**2009**	**2010**	**2011**	**2012**	**2013**	**2014**	**2015**	**2016**	**2017**	**2018**	**2019**
[TJ/year]	13 182	14 073	14 462	14 895	14 246	13 120	12 990	12 297	11 864	12 254	12 341	13 250	14 852	17 147	17 537
Year	**2020**	**2021**	**2022**	**2023**	**2024**										
[TJ/year]	4 763	6 408	11 085	14 289	18 792										

3.2.3 Feedstocks and non-energy use of fuels

The methodology (IPCC, 2006) sets the borders between the Energy and Industrial Processes and Product Use (IPPU) sectors. Compared to the previous methodology version (IPCC, 1997), emissions from non-energy use of fuels are reported mainly in sector 2 – IPPU. To prevent double-counting or omitting of resources it is necessary to check the completeness of CO_2 emissions in the sectors 1.A (Energy – combustion) and 2 – IPPU, for those kinds of fuels used for energy and non-energy purposes.

Non-energy fuels are divided into three categories:

1) **Raw materials for the chemical industry (Feedstocks)**. These fossil fuels are used particularly in organic compound production and to a lesser extent in the production of inorganic chemicals (e.g. ammonia) and their derivatives. For organic substances normally part of the carbon in the feedstock remains largely stored in these products. Typical examples of raw materials are the feedstocks for the petrochemical industry (naphtha), natural gas, or different types of oils (e.g. the hydrogen production for the subsequent production of ammonia by partial oxidation).

2) **Reductants**. Carbon is used as a reductant in metallurgy and inorganic technologies. Unlike the previous case, when using fossil fuel as a reductant only a minimal amount of carbon remains long fixed in the products and the larger part of the carbon is oxidised during the reduction process. A typical example of a reductant is metallurgical coke.

3) **Non-energy products**. Non-energy products are materials, derived from fuels in refineries or coke plants, which, unlike the previous two cases, are used directly for their conventional physical properties, specifically, it is about lubricants (lubricating oils and petrolatum), diluents and solvents, bitumen (for covering roads and roofs) and paraffin. In category IPPU emissions of CO_2 and other GHG occur only to a limited extent (e.g. during the oxidation of lubricants and paraffin). Substantial emissions occur during their recovery and disposal by incineration (in the sector Energy and Waste).

Emissions from feedstocks in the chemical industry are reported in subsector 2.B, from reductants primarily in subsector 2.C and from non-energy products, used mainly for different purposes, than incineration (e.g. lubricating oils) in subsector 2.D.

The energy balance of the Czech Republic by Regulation No 1099/2008 of the European Parliament and of the Council on energy statistics distinguishes various types of fuels in their use for energy and non-energy purposes. Different kinds of fuels with a high proportion of non-energy use in the Czech Republic are listed below.

Some types of liquid fuels are designed mainly for non-energy use. This is primarily naphtha, for which CzSO indicates, since 2001, that virtually the entire amount is consumed for non-energy purposes by the chemical industry, mainly as petrochemicals (2.B). Less significant is the non-energy use of LPG. Since Naphtha is a major feedstock, the emission from sector 2.B.8 Petrochemical and Carbon Black Production is reported in the CRT Table 1.A(d) as arising from this feedstock. Following the recommendation of the 2019 review the emissions from non-energy use of fuels from LPG and Gas/Diesel are reported in the CRT 1AD as well. There was a salient decrease in Ethylene production in 2016 after the accident in 2015 (see also Chapter 4), when the rest of the LPG was used for other petrochemical production.

Another important type of liquid fuel consumed for non-energy purposes of fuels is a group marked as Other Oils. Their most significant share is Other Petroleum Products, which finds application in the production of hydrogen by partial oxidation with steam for subsequent production of ammonia and part of it is also used as a Solvent Use. In 2025, the consumption of Other Petroleum Products for non-energy purposes (particularly in sub-sectors 2.B, 2.D) was 13 PJ. CO_2 produced during ammonia production (2.B.1) is reported in Table 1.A(d) under Other Oil. The remaining Other Oil for non-energy use is processed for the Solvents. Following the IPCC 2006 Gls., from Solvent Use (2.D.3) there is no CO_2 produced.

Less important categories are White Spirit and Paraffin Wax, which are only used for non-energy purposes in 2.D and naturally their consumption is small compared to Other Petroleum Products.

The liquid fuels, used especially for non-energy purposes, include also bitumen, whose consumption in 2024 was 20 PJ and lubricants with a consumption in 2024 of 6 PJ. While in the case of using bitumen there are no emissions of CO_2 (Stored carbon), in the case of lubricant use, annually a part is oxidized to CO_2 (Reported in 2.D.1). Consequently, CO_2 reported in Table 1.A(d) under Lubricants is the CO_2 which is arising in 2.D.1.

Solid fuels for non-energy purposes are mainly used as reductants. These include coke (Coke Oven Coke), which in 2024 was used 22 PJ in the production of iron and steel (2.C.1). Consequently, CO_2 reported in Table 1.A(d) under Coke Oven Coke is the CO_2 which is arising in 2.C.1 from Metallurgical coke use. In the Other bituminous coal was used 7 PJ for non-energy use in 2024. Other bituminous coal was used as a reductant in 2.C.1 as well.

Natural gas (NG) is also a feedstock in many countries. In the Czech Republic, it has been happening recently; since 2008 the CzSO indicates that approximately 1% of the annual consumption of natural gas in the Czech Republic is used for non-energy purposes in the chemical industry. This non-energy use is reported under 2.B.10.

Fuels for non-energy use are not accounted for in the Sectoral approach in category 1.A. In the Reference approach, NEU is deducted from the apparent consumption as excluded carbon (see. Sub-chapter "CO_2 reference approach and comparison with the sectoral approach").

Tab. 3-10 lists calorific values of the energy balance calculation of CzSO and default emission factors used in the reference approach.

Tab. 3-10 Net calorific values and emission factors of feedstocks

Non-energy Fuels	NCV	EF
	[GJ/kt]	[t CO_2/TJ]
LPG	45 945[1)]	65.86[1)]
Naphtha	43 600	73.30
Gas/Diesel Oil	42 600	74.10
White Spirit	40 193	73.30
Lubricants	40 193	73.30
Bitumen	40 193	80.70
Paraffin Wax	40 193	73.30
Petroleum Coke	39 400	97.50
Other Petroleum Products	38 495	73.30
Refinery Gas	46 023	55.08[1)]
Coke Oven Coke	28 087[2)]	107.00

1) *country-specific value*
2) *used in blast furnaces*

3.2.4 Methodological issues

The chapter describes procedures applied for emission estimates from combustion sources in general. Each chapter for specific subcategories then contains (if applicable) particular procedures respective to these sources.

The data for the whole time series was constructed based on data from the CzSO Questionnaire (CzSO, 2025), where the data on fuel consumption are provided in various ways. Data are available for Solid and Liquid Fuels in mass units (kt p.a.), where the net caloric values of these fuels are also tabulated. The consumption of gaseous fuels derived from fossil fuels is given in TJ p.a. Natural Gas is in thousand m^3 and the consumption in TJ is also tabulated; however, in this case, it is calculated using the gross caloric value. The Energy balance in mass units (kt p.a.) for the last reported year (2024) is given in Annex 4, Tab. A4 1 – Tab. A4 7.

Since the 2012 submission net calorific values for Liquid Fuels for the whole time series are available. The waxes are now assumed correct (agreed by CzSO) and therefore used to converse activity data natural units to energy units. Except for the official NCV provided by CzSO country specific NCVs are used, for Refinery Gas and LPG.

The principles of preparation of the emission inventory are further specified in detail for the individual phases of data preparation and processing and subsequent utilisation of the results of calculations with subsequent data storage.

In response to encouragement from ARR 2019 E.9, a comparison was conducted to identify differences between CRT data and IEA/Eurostat data and to provide explanations for these differences. The main discrepancies arise from the use of different net calorific values (NCVs) for the conversion from kt to TJ, the absence of certain fuels in the IEA/Eurostat data, and the application of different GCV/NCV conversion coefficients for natural gas. For more details see Annex 4.

3.2.4.1 Collection of activity data

In a collection of activity data, all the background data are stored at the workplace of the sector compiler, where possible in electronic form. These consist primarily of datasets obtained from CzSO as officially submitted data for drawing up the activity data. The dataset for the last reported year is given in Annex 4, Annex 4, Tab. A4 1 – Tab. A4 7; similar datasets for the whole time series are stored in the archive of the sectoral expert.

If the data are taken from the Internet, the relevant passages (texts, tables) are stored in separate files with a designation of the website where they were obtained and the date of acquisition.

Data taken from printed documents are suitably cited, the written documents are stored in printed form at the workplace of the sector compiler and, where possible, the relevant passages (texts, tables) are scanned and stored in electronic form.

When the stage is completed, all the stored data are transferred to electronic media (CD, external HD, flash disks, etc.) and stored with the sector compiler; the most important working files that contain data sources, calculation procedures and the final results are submitted in electronic form for storage at the coordination workplace.

In case EU ETS data are used, the original forms are stored in an archive of the national inventory system coordinator and officially at the Ministry of Environment.

3.2.4.2 Conversion of activity data to the ETF format

The activity data are converted from the energy balance to the ETF structure in the EXCEL format. Each working file has a “Title page” as the first sheet. Using an interconnected system of Excel files a computational model was created for emission estimates from stationary sources in Energy sector. The Title page shall contain particularly the following information:

- the name and description of the file
- the author of the file
- the date of creation of the file
- the dates of the latest up-dating in order
- the source of the data employed
- description of the transfer of specific data from the source files
- the means of aggregation of the database employed in the conversion
- explanations and comments.

Separate computational files for each kind of fuel are used, which are then interconnected with the final computational files, where are data is transferred in the specific subcategories and the computation of emission estimates is carried out. The operational part of the files contains the whole computational approach for the estimation of CO_2, CH_4 and N_2O emissions, which includes the following steps:

- complete division of data about the consumption of each kind of fuel from the Energy balance provided by CzSO into the structure compatible with ETF Reporting Tool (for purposes of Sectoral and Reference Approaches)
- complete set of NCV for specific kinds of fuels and emission and oxidation factors (if applicable)
- computation of emission estimates
- summation of activity data and emissions for each group of fuels (solid, liquid, gaseous etc.) into specific subcategories

Outputs from the computational model are datasets that can be imported into ETF Reporting Tool. All computational sheets are managed in whole time-series and units of input and output values are recorded as well.

3.2.4.3 Calculations of emissions

Original activity data are provided in kilotons. Therefore, the conversion to energy units, terajoules, is necessary. Calorific values for conversion are in Annex 5. Coke Oven Gas, Gas Works Gas and biofuels are given directly in terajoules in the CzSO Questionnaires (CzSO, 2025), however, the data were calculated using the gross calorific values, so it is necessary to recalculate these values to net calorific values.

Natural Gas is provided in the statistic reporting in the CzSO Questionnaire (CzSO, 2025) in thousand m^3 and TJ; however, the data in TJ is determined using the gross caloric value. The volume reported by CzSO in thousand m^3 is related to the „trade conditions“, i.e. temperature 15°C and pressure 101.3 kPa.

CzSO converts gross and net calorific value by coefficient NCV/GCV = 0.9. Research to develop a methodology for precise coefficient value determination was conducted in 2014. Details about the research and methodology NCV/GCV are in A 4.1.

It was found (see A 4.1), that the ratio NCV/GCV for natural gas can be very preciously described by linear dependence

$$\frac{NCV}{GCV} = (0.001011 \cdot GCV) + 0.863274$$

where NCV and GCV are expressed in MJ/m^3 in the reference temperatures of 15 ˚C (i.e. trade conditions). However, an improved value of the ratio NCV/GCV is similar to the IPCC default value of 0.9. For example, the NCV = 34.533 MJ/m^3 corresponds to the ratio NVC/GCV=0.9021 calculated from the equation above. This equation was applied to convert NCV from GCV for all time.

For the calculation of CO_2 emissions are used emission factors, which are either provided in the 2006 IPCC Guidelines (IPCC, 2006) or determined as country-specific emission factors. Since CO_2 emission factors depend on the quality of specific fuel, the values of emission factors are listed in the chapters below. Default emission factors from the IPCC methodology have been for key categories gradually substituted by country-specific emission factors. Moreover, CO_2 emission factors from lignite (brown coal) and bituminous coal, the previous country-specific emission factors were refined by up-to-date national data in this submission. A description of country-specific emission factors including ways of their evaluations is in Annex 3.

CH_4 and N_2O emissions from fuel combustion from stationary sources are considered key categories in some subcategories. Therefore, work is currently underway to develop country-specific emission factors for these emissions. Until these factors are established, default values from the 2006 IPCC Guidelines (IPCC,

2006) are applied, contrary to CO_2 emission factors. CH_4 and N_2O emission factors are in the specific subchapters for specific subcategories.

General CO_2 emission factors and NCV are provided in Tab. 3-11. With regards that values in the following table are used in the Czech Republic companies with an obligation to report their emission to Emission Trade System – EU ETS (which is a market-based approach to controlling pollution by providing economic incentives for achieving reductions in the emissions of pollutants), values of country-specific EF are expressed as a 5-years mean i.e. the mean of years 2020–2024. This adjustment decreases inaccuracies in emission reporting to EU ETS, which are caused by time discrepancies (companies will use the values for reporting year 2025).

Tab. 3-11 Net calorific values (NCV), CO_2 emission factors and oxidation factors used in the submission 2026

Fuel (2006 IPCC Guidelines definitions)	NCV [TJ/kt]	CO_2 EF [a] [t CO_2/TJ]	Oxidation factor	CO_2 EF [b] [t CO_2/TJ]
Crude Oil	42.500	73.300	1	73.300
Gas/Diesel Oil	43.122	74.100	1	74.100
Residual Fuel Oil	39.500	77.400	1	77.400
LPG [d]	45.945	65.860	1	65.860
Naphtha	43.600	73.300	1	73.300
Bitumen	40.193	80.700	1	80.700
Lubricants	40.193	73.300	1	73.300
Petroleum Coke	39.400	97.500	1	97.500
Other Oil	38.626	73.300	1	73.300
Coking Coal [d]	29.315	93.572	1	93.572
Other Bituminous Coal [d]	26.764	94.049	0.9707	91.294
Lignite (Brown Coal) [d]	13.995	99.067	0.9846	97.542
Brown Coal Briquettes	23.046	97.500	0.9846	95.999
Coke Oven Coke	27.961	107.000	1	107.000
Coke Oven Gas TJ/mill. m^3) [c]	16.901	44.400	1	44.400
Natural Gas (TJ/Gg) [d]	48.536	55.749	1	55.749
Natural Gas (TJ/mill. m^3) [d], [e]	34.992	55.749	1	55.749

a) Emission factor without oxidation factor
b) Resulting emission factor with oxidation factor
c) TJ/mill. m^3, t= 15 °C, p = 101.3 kPa
d) Country specific values of CO_2 EFs and oxidation factors
e) GCV for Natural Gas (5 years mean) 38.773 TJ/mill. m^3 and NCV/GCV (5 years mean) 0.902

3.2.5 Uncertainties and time-series consistency

The emission inventory is based on 2 types of data accompanied by different levels of uncertainty:

- Activity data (consumption of individual kinds of fuels)
- Emission factors

Extensive research was carried out in 2020 to obtain new, more accurate uncertainty values. The results are below and in Annex 2.

Activity data

Information on fuel consumption is taken from CzSO (CzSO, 2025).

Uncertainties:

CzSO does not explicitly state the uncertainties in the published data. However, the uncertainty differs for the individual groups of data – statistical reports from the individual enterprises (economic units with more

than 20 employees); consumption by the population is calculated based on models and reports by suppliers of network energy (gas, electricity), production of the individual kinds of fuels (especially automotive fuels) and customs reports (imports, exports); the remainder is calculated so that the fuel consumption is balanced. Each step has a different level of uncertainty. Overall, the uncertainty in Natural Gas activity data should be lower than Solid Fuels activity data since Natural Gas is measured more accurately than Solid Fuels.

Uncertainties also arise during data processing. CzSO obtains data in mass units – tons per year (1st level of uncertainty). The resultant balance is expressed in energy units – TJ p.a. Recalculation from mass units to energy units must be performed using the fuel calorific value. The calorific value determination brings uncertainties from the method employed (mostly laboratory expertise) (2nd level of uncertainty). The average fuel calorific value valid for all of the Czech Republic must be determined for each kind of fuel. Because the calorific value differs substantially in dependence on the mine location, it is necessary to determine the average calorific value based on a weighted average – 3rd level of uncertainty.

In 2020, an extensive study updated uncertainties in the Energy sector. The study follows that the lowest uncertainties of activity data should be expected in the 1.A.1. sector since all individual enterprises in this sector are the economic units with more than 20 employees, which means that all fuel consumption is subject to a questionnaire of the CzSO. Higher uncertainties should be expected in sector 1.A.2. These are numerous small individual enterprises, of which only a certain number are the economic units. The highest uncertainties should be expected in sector 1.A.4. This is a diverse group of sources scattered throughout the Czech Republic with relatively small economic units.

Due to the high variability between subcategories described above, the uncertainties were set for each type of fuel and the specific subcategory e.g., the uncertainty of 1.A.1.a-Solid fuels, 1.A.1.a-Natural Gas, etc. Three independent experts' estimates of 'basic' uncertainties were done in detail scale described in this paragraph and then experts estimated averaged. To determine uncertainties on the coarser scale (e.g., 1.A.1 or 1.A.2) is used weighted average, where fuel consumption (TJ) is used as a weight in calculation (for details see Veselá et al. 2020).

For specific uncertainties of activity data used for introduction into the trend in total national emissions see Annex 2.

Emission factors

The above-mentioned study updated the uncertainties of EF as well. Country-specific EF for calculation of CO_2 emissions is used for the most important type of fuels in the Czech Republic's inventory (Brown Coal+Lignite, Bituminous Coal, Coking Coal, Gas Work Gas, Natural Gas, Refinery Gas and LPG). The rest of fuel uses default EF, from which the most important for inventory is Coke and Fuel Oil. The country-specific EF is determined with knowledge of fuel carbon content and net caloric values. In this case, the uncertainties depend on the accuracy of laboratory determination of net calorific values and laboratory analyses of fuels, where low uncertainties could be expected. Because Coke and Fuel oils (in which we use default EF) have a very stable composition (carbon content), regardless of national specifics, it can be considered that these fuels have the same composition all over the world and low uncertainties could be expected.

Generally, the formation of CH_4 and N_2O is widely unexplored, it is necessary to consider high uncertainties (up to hundreds per cent). According to our internal results it is yet unconfirmed that CH_4 emissions at small and large equipment significantly differed.

EF uncertainties were determined by the same methodology as AD uncertainties i.e. average of three independent experts estimated 'basic' uncertainties (see above or for details Veselá et al. 2020).

For specific uncertainties of emission factors used for introduction into the trend in total national emissions see Annex 2.

Time - series consistency

The time series consistency is regularly monitored by the sector compiler and evaluated as an instrument for revealing potential errors. As the sector compilers create the data time series from external CzSO data, they cannot affect the variation in the time series of activity data during processing.

However, feedback to the primary data processor does exist. If an anomaly is identified in the time series, CzSO is informed about this fact and is requested to explain.

So far, no means have been found for consistent and systematic verification of the consistency of time series at CzSO and analysis of the causes of fluctuations. Rather than elementary errors, preliminary analysis indicates that the anomalies are caused solely by the methodology for ordering the statistical data in the energy balance structure. Assignment of the statistical data on fuel consumption to the individual energy balance chapters is performed by the valid methodology according to CZ-NACE (the former Czech equivalent was OKEC – Branch Classification of Economic Activities). The CZ-NACE code is assigned to economic entities based on their Id.No. (Identification Numbers). This can result in substantial inter-annual changes in the individual subcategories.

Example:

The decisive CZ-NACE code for entity A is for chemical production. He operates a large boiler with a substantial fraction of fuel in the entire 1.A.2.c subsector. The energy production is split into independent entity B, whose main activity is the production and supply of heat. In the final analysis, the reported fuel consumption is shifted from 1.A.2.c to 1.A.1.a.

In the Czech Republic, the 1990s and beginning of the 20th century were a period when a route to rational utilization of means of production was sought and changes in the ownership structure of energy-production facilities were quite frequent. Consequently, the consistency of the time series is interrupted in some subcategories. Justification for the exact causes of each such change lies outside the current capabilities of the sector compiler.

Changes in the consistency of the time series of emission data must follow changes in activity data. If different anomalies occur, these anomalies are verified and any errors in the determination of the emission data are immediately eliminated.

Other Fuels (ETF 1.A.1.a) - Uncertainties and time-series consistency

The time series comes from two data sources – the time-series was reproduced by MIT and data about current incineration comes from ISOH (Information System of Waste Management). There are no country-specific uncertainties yet, as all the factors but activity data used in the equations are default IPCC factors.

3.2.6 QA/QC and verification

The general QA/QC plan was formulated since the last submission and is presented in Chapter 1.2.3. The QA/QC procedures applied in the company KONEKO Ltd. are based on the QA/QC plan for GHG inventory in the Czech Republic and are harmonized with the QA/QC system of the CDV. As the basic data sources for the processing of activity data are based on the energy balance of the Czech Republic the main emphasis is given to close cooperation with the Czech Statistical Office (CzSO). This cooperation is based on the contract between CHMI, the NIS coordination workplace, and CzSO. CzSO is a state institution

established for statistical data processing in the Czech Republic, which has its own control and verification mechanisms and procedures to ensure data quality.

Sectoral guarantor and administrator of QA/QC procedures, Andrea Vesela (KONEKO manager):

- processes and updates the sectoral QA/QC plan
- organizes QC procedure
- ensures verification procedures and is responsible for its realization
- is responsible for the submission of all documents and data files for storing in the coordinating institution and suggests external experts for QA procedure
- ensures data input in the ETF Reporting Tool
- carries out auto-control – control of input data and primary computations
- ensures and is responsible for the storing of documents

The QC procedures are related to the processing, manipulation, documentation, storing and transmission of information. The first step of the control is carried out by the expert responsible for the Sectoral Approach (Andrea Veselá), followed up by the control carried out by the QA/QC experts familiar with the topic (Barbora Votavová, external employee of KONEKO). At this control level, individual steps are controlled according to the official QA/QC methodology (IPCC, 2006). To minimize technical errors both in ETF and in NID we set up automatically connect for values transcription. In this way, we connect files of CzSO, all computation files, QA/QC files and files for creation tables for ETF Reporting Tool.

Data transmission to the ETF Reporting Tool is accomplished by the data administrator. After data transmission to the ETF Reporting Tool, the control of correct data transmission based on the summary values of activity data and emission data is carried out. If there are any discrepancies, the erroneous data are detected and corrected.

Verification procedures are included upon the suggestion of the QA/QC sectoral guarantor after the consultation with the NIS coordinator. They are aimed mainly at the comparison with independent data sources that are not based on data processing from the CzSO energy balance. The relevant independent sources in the Czech Republic are represented by data published and verified within the EU Emission Trading Scheme (ETS), from the national system REZZO, used for the registration of ambient air pollutants, and based mainly on data collection from individual plants. In addition to emission data, the REZZO database includes also activity data, independent of CzSO data. The way how to optimally use the above data sources has to be determined based on systematic research and will be covered in the national inventory improvement plan.

An external employee of KONEKO (Barbora Votavová) familiar with the assessed topic participates in the QC procedures. The cooperation is based on ad hoc contracts ensured by the QA/QC sectoral guarantor. As already mentioned above, also experts from CzSO, closely cooperating with CHMI and KONEKO, take part in the control procedures.

The QA procedures are planned in a way described in the general part of the QA/QC plan, i.e. approximately once in three years.

Other QC procedures were performed using data indicators which should have the same course as the reported value. Where these data are available, details of this QC are given in the following figures.

3.2.7 Public electricity and heat production (CRT 1.A.1.a)

This category is divided into 3 subcategories:

- Electricity Generation (ETF 1.A.1.a.i)
- Combined Heat and Power Generation (ETF 1.A.1.a.ii)
- Heat Plants (ETF 1.A.1.a.iii)

This division is used in the new methodology (IPCC, 2006). Due to the activity data (from CzSO) inconsistency, it was decided not to make the activity data division into three subcategories as is above. The activity data are moving from one subcategory to another one according to new rules and for the Energy sector, it would mean to do recalculations almost every year. The sum of the data in 1.A.1.a category remains the same. Therefore, the data will be reported as a sum in the category 1.A.1.a.i.

The fraction of CO_2 emissions from sector 1.A.1 equalled 48% in 2024 in the whole Energy sector (1.A) – combustion of fuels.

In 2024, the fraction of CO_2 emissions in subsector 1.A.1.a equalled 96% of total CO_2 emissions in sector 1.A.1.

Under source category 1.A.1.a the energy balance includes district heating stations and electricity and heat production of public power stations.

This category encompasses all facilities that produce electric energy and heat supplies, where this production is their main activity and they supply their products to the public mains. From the total installed capacity of electricity generation 18.8 GWe in 2024, 10.4 GWe are accounted for thermal power plants:

Nuclear	4 290	MWe
Hydro	2 150	MWe
Solar photovoltaic	1 565	MWe
Wind	363	MWe
Combustible fuels	10 401	MWe
Total capacity	**18 803**	**MWe**

In the final energy balance of CzSO (CzSO, 2025), the consumption of the individual kinds of fuels in this sector is reported in the section Transformation Sector under the items:

- Main Activity Producer Electricity Plants
- Main Activity Producer CHP Plants
- Main Activity Producer Heat Plants

The category includes consumption of all kinds of fuels in enterprises covered by the NACE Rev. 2:

35.11 Production of electricity

35.30 Steam and air conditioning supply (production, collection and distribution of steam and hot water for heating, power and other purposes)

The volume of production of electricity and heat and the structure of the sources are shown in the following overview.

Electricity production (GWh)	**73 900**
Main activity producer electricity plants	58 573

Main activity producer CHP plants	7 354
Autoproducer electricity plants	2 584
Autoproducer CHP plants	5 362
Heat production (TJ)	**96 644**
Main activity producer CHP plants	62 820
Main activity producer heat plants	18 415
Autoproducer CHP plants	6 824
Autoproducer heat plants	7 583

Fig. 3-4 presents an overview of the development of CO_2 emissions in source category 1.A.1.a. CO_2 emissions indicate a stable trend with only a few oscillations in the whole time series. For a few years back it can be seen that CO_2 emissions have decreasing trend.

The trend in emissions is mainly shaped by the development and structures of the electricity generation installations involved since these installations account for the majority of the pertinent emissions. As is clear from the figure, Solid Fuels are the main driving force for emissions in this source category. Brown Coal and Lignite are the most important, with a total consumption of 256 PJ, corresponding to 41 062 kt CO_2/year on average for the whole 1990–2024 period.

Since 2007, the country-specific emission factor for Brown Coal + Lignite have been applied. For the year 2024, the coutry-specific emission factor for Brown Coal + Lignite was 26.92 t C/TJ, whhile a country-specific emission factor of 25.73 t C/TJ for Other Bituminous Coal and Coking Coal has been used to calculate CO_2 emissions. In 2015 was conducted research to update these emission factors. A detailed description of the research is provided in Annex 3. As mentioned above, this means that approximately 95% of the emissions from fuels in this category were determined using country-specific emission factors, i.e. at the level of Tier 2.



Fig. 3-4 Development of CO_2 emissions in 1.A.1.a category

Since submission in 2014 country-specific oxidation factors for Other Bituminous Coal, Brown Coal and Lignite and Brown Coal Briquettes were applied. A detailed description of the research is given in Annex 3.

The item Other Fuels in Fig. 3-4 represents waste consumption for waste incineration.

3.2.7.1 Category description (CRT 1.A.1.a.i)

The structure of fuels, their consumption, used emission factors and emissions of individual greenhouse gases are shown in the following outline.

1.A.1.a, 2024								
Structure of Fuels	**Activity**	**CO_2**			**CH_4**		**N_2O**	
	data	**EF**	**OxF**	**Emission**	**EF**	**Emission**	**EF**	**Emission**
	[TJ]	**[t CO_2/TJ]**	**[-]**	**[kt]**	**[kg CH_4/TJ]**	**[kt]**	**[kg N_2O/TJ]**	**[kt]**
Rafinery Gas	552.28	55.08	1	30.42	1	0.00055	0.1	0.00006
LPG	321.62	65.86	1	21.18	1	0.00032	0.1	0.00003

1.A.1.a, 2024								
Structure of Fuels	Activity data	CO_2			CH_4		N_2O	
		EF	OxF	Emission	EF	Emission	EF	Emission
	[TJ]	[t CO_2/TJ]	[-]	[kt]	[kg CH_4/TJ]	[kt]	[kg N_2O/TJ]	[kt]
Heating and Other Gasoil	127.80	74.10	1	9.47	3	0.00038	0.6	0.00008
Fuel Oil - Low Sulphur	237.00	77.40	1	18.34	3	0.00071	0.6	0.00014
Other Bituminous Coal	20 865.26	95.07*)	0.9707*)	1 925.56	1	0.02087	1.5	0.03130
Brown Coal + Lignite	256 500.63	100.78*)	0.9846*)	25 451.07	1	0.25650	1.5	0.38475
Brown Coal Briquets	1.30	99.74*)	0.9846*)	0.12	1	0.00000	1.5	0.00000
Coke oven gas	3 484.62	44.40	1	154.72	1	0.00348	0.1	0.00035
Natural Gas	46 019.45	56.08*)	1	2 581.00	1	0.04602	0.1	0.00460
Waste - fossil fraction	3 489.60	91.70	1	320.00	30	0.10469	4	0.01396
Waste - biomass fraction	5 234.40	100.00	1	523.44	30	0.15703	4	0.02094
Wood/Wood Waste	27 517.51	112.00	1	3 081.96	30	0.82553	4	0.11007
Gaseous Biomass	1768.54	54.60	1	96.56	1	0.00177	0.1	0.00018
Total year 2024	**328 109.94**			**30 511.89**		**1.41785**		**0.56645**
Total year 2023	360 352.16			33 216.70		1.37370		0.60345
Index 2024/2023	0.91			0.91		1.03		0.94
Total year 1990	568 512.77			54 560.85		0.61880		0.81167
Index 2024/1990	0.58			0.55		2.29		0.70

*) *Country specific data*

Liquid Fuels play a minor role in the electricity supply of the Czech Republic. They are used for auxiliary and supplementary firing in power stations – for instance stabilization of burners. The use of Liquid Fuels has decreased by more than half since 1990.

Natural Gas (NG) plays a role in this source category. Use of NG does not exhibit a substantially oscillating trend. At the beginning of the period, it shows an increasing trend, but later only minor changes were observed, which can be considered insignificant. Between the years 1994 and 1995, the share of gaseous fuels in total consumption was 1.8 and 2.4%, which corresponds to a fluctuation of 0.6% in terms of all fuels in the sector. Such fluctuations are common and are based on the fuel market as well as on legislative requirements.

The origin of the data, the emission factors used and the method of calculating the level of emissions for the individual gases are presented in detail in the following outline.

2024							
Structure of Fuels	Source of Activity data	Emission factors			Method used		
		CO_2	CH_4	N_2O	CO_2	CH_4	N_2O
Rafinery Gas	CzSO	CS	D	D	Tier 2	Tier 1	Tier 1
LPG	CzSO	CS	D	D	Tier 2	Tier 1	Tier 1
Heating and Other Gasoil	CzSO	D	D	D	Tier 1	Tier 1	Tier 1
Fuel Oil - Low Sulphur	CzSO	D	D	D	Tier 1	Tier 1	Tier 1
Other Bituminous Coal	CzSO	CS	D	D	Tier 2	Tier 1	Tier 1
Brown Coal + Lignite	CzSO	CS	D	D	Tier 2	Tier 1	Tier 1
Brown Coal Briquets	CzSO	D	D	D	Tier 1	Tier 1	Tier 1
Coke oven gas	CzSO	D	D	D	Tier 1	Tier 1	Tier 1
Natural Gas	CzSO	CS	D	D	Tier 2	Tier 1	Tier 1
Waste - fossil fraction	ISOH, MTI	D	D	D	Tier 1	Tier 1	Tier 1
Waste - biomass fraction	ISOH, MTI	D	D	D	Tier 1	Tier 1	Tier 1
Wood/Wood Waste	CzSO	D	D	D	Tier 1	Tier 1	Tier 1
Gaseous Biomass	CzSO	D	D	D	Tier 1	Tier 1	Tier 1

3.2.7.1.1 Other Fuels (CRT 1.A.1.a.i): Waste Incineration for energy purposes

This category consists of emissions caused by incineration of municipal solid waste for energy purposes. Originally this chapter was part of 5.C Waste Incineration but, based on the suggestion of ICR (in-country review), this chapter was shifted to the energy sector. This chapter is prepared by CENIA, Czech Environmental Information Agency – the organization responsible for the Waste sector. If the waste is incinerated to obtain energy in a dedicated facility (i.e., a waste incineration plant), it is reported to the Energy sector. All other waste is reported in the waste category.

The source of data about waste incineration is (V)ISOH -(Public) information system of waste management of the MoE. (V)ISOH contains bottom-up data from waste management companies (individual data) and it is consistently used as a data source by the waste sector as well. It is obligatory to report into this system and about 60 thous. subjects report in the system each year. Data in (V)ISOH are cross-checked between subjects and on selected cases verified by Czech Environmental Inspection where discrepancies appear. Data in (V)ISOH are based on evidence, and data from other sources are based on statistics. (V)ISOH is the official data source for national environmental policies, their design and evaluation. Waste incineration in inventory is split between the energy and waste sectors in a way that all waste (predominantly municipal solid waste) that is incinerated in so-called ZEVO´s (waste incinerator with energy use) is accounted for in the energy sector, rest of incinerated waste is accounted in the waste sector.



Fig. 3-5 trend of GHG emissions from waste incineration for energy purposes

This category consists of emissions of CO_2 from incinerated fossil carbon in MSW and emissions of methane and N_2O from incineration of MSW as it is shown in Fig. 3-5.

Tab. 3-12 shows four municipal solid waste (MSW) incineration plants in the Czech Republic. One is located in Prague (ZEVO Malesice), one in Brno (SAKO), one in Liberec (Termizo) and the newest one since 2016 in Plzeň (ZEVO Plzeň, Chotíkov). MSW is sometimes co-incinerated in other facilities, too.

Tab. 3-12 Capacity of municipal waste incineration plants in the Czech Republic, 2023

Incinerator (city)	Capacity (kt) 2024
TERMIZO (Liberec)	96
Pražské služby a.s. (Praha)	330
SAKO a.s. (Brno)	248
Plzeňská teplárenská a.s. (Plzeň)	120

There are also several dozen facilities incinerating or co-incinerating waste without energy use. This waste is reported under 5C.

3.2.7.2 Uncertainties and time-series consistency (CRT 1.A.1.a)

See chapter 3.2.5.

3.2.7.3 Category-specific QA/QC and verification (CRT 1.A.1.a)



Fig. 3-6 The ratio between the total consumption of fuels from the heat sources in the category 1.A.1.a and overall energy production

Fig. 3-6 shows the correlation of fuel consumption in category 1.A.1.a and total gross electricity and heat production. Total energy production should have a similar trend to total fuel consumption in category 1.A.1.a.

Throughout the whole time, it is possible to see a good correlation between the total fuel consumption and gross energy production. There are minor fluctuations, caused by variations in the ratio between the electricity and the amount of heat produced.

For additional information please see chapter 3.2.6.

3.2.7.3.1 Other Fuels (CRT 1.A.1.a.ii): Waste Incineration for energy purposes

Waste incineration is reported in the energy but in NID it is still managed under the waste sector and for this particular chapter all relevant QA/QC procedures are described in the waste chapter.

3.2.7.4 Category-specific recalculations (CRT 1.A.1.a)

Based on minor changes in activity data (V)ISOH, fuel consumptions of Waste for the year 2023 were corrected. See the differences in the Tab. 3-13. Based on changes in activity data (CzSO, 2025), fuel consumption and emission of Biomass for the year 2022, 2023 were corrected. See the differences in the Tab. 3-14. Due to the minor changes in GCV of Natural Gas (CzSO, 2025), Gaseous fuels were recalculated for the years 2010-2023. The highest difference was -0.11 % in CO_2 emission in 2016; all other changes were at the second decinal place or smaller, therefore these changes are not shown in specific table.

Tab. 3-13 Changes after recalculation in 1.A.1.a for Waste.

Fuel consumption		**2023**
Submission 2025	TJ	3 376.40
Submission 2026	TJ	3 380.40
Difference	TJ	4.00
Submission 2026	%	0.12
CO_2 emission		**2023**
Submission 2025	kt	309.62
Submission 2026	kt	309.98
Difference	kt	0.37
Submission 2026	%	0.12
CH_4 emission		**2023**
Submission 2025	kt	0.1013
Submission 2026	kt	0.1014
Difference	kt	0.0001
Submission 2026	%	0.1185
N_2O emission		**2023**
Submission 2025	kt	0.0135

Submission 2026	kt	0.0135
Difference	kt	0.0000
Submission 2026	%	0.1185

Tab. 3-14 Changes after recalculation in 1.A.1.a for Biomass.

Fuel consumption		**2022**	**2023**
Submission 2025	TJ	32 048.26	26 962.34
Submission 2026	TJ	32 197.66	32 032.94
Difference	TJ	149.40	5 070.60
Submission 2026	%	0.47	18.81
CO_2 emission		**2022**	**2023**
Submission 2025	kt	3 440.81	2 919.85
Submission 2026	kt	3 455.75	3 426.91
Difference	kt	14.94	507.06
Submission 2026	%	0.43	17.37
CH_4 emission		**2022**	**2023**
Submission 2025	kt	0.91	0.76
Submission 2026	kt	0.92	0.91
Difference	kt	0.00	0.15
Submission 2026	%	0.49	20.06
N_2O emission		**2022**	**2023**
Submission 2025	kt	0.12	0.10
Submission 2026	kt	0.12	0.12
Difference	kt	0.00	0.02
Submission 2026	%	0.49	20.07

3.2.7.5 Category-specific planned improvements (CRT 1.A.1.a)

Furthermore, attention will be focused on determining the country-specific emission factors for other fuels, while considering the significance of the individual types of fuel.

3.2.8 Petroleum refining (1.A.1.b)

3.2.8.1 Category description (CRT 1.A.1.b)

The structure of fuels, their consumption, used emission factors and emissions of individual greenhouse gases are shown in the following outline.

1.A.1.b, 2024								
Structure of Fuels	**Activity**	**CO_2**			**CH_4**		**N_2O**	
	data	**EF**	**OxF**	**Emission**	**EF**	**Emission**	**EF**	**Emission**
	[TJ]	**[t CO_2/TJ]**		**[kt]**	**[kg CH_4/TJ]**	**[kt]**	**[kg N_2O /TJ]**	**[kt]**
Refinery Gas	4970.48	55.08*)	1	273.75	1	0.00497	0.1	0.00050
Natural Gas	3353.83	56.08*)	1	188.10	1	0.00335	0.1	0.00034
Total year 2024	**8324.31**			**461.85**		**0.00832**		**0.00083**
Total year 2023	9519.43			527.64		0.00952		0.00095
Index 2024/2023	0.87			0.88		0.87		0.87
Total year 1990	8705.45			492.56		0.01017		0.00124
Index 2024/1990	0.96			0.94		0.82		0.67

*) *Country specific data*

The origin of the data, emission factors used and the method for calculating the emissions for each gas are in detail in the following outline.

2024			
Structure of Fuels	**Source of**	**Emission factors**	**Method used**

	Activity data	CO_2	CH_4	N_2O	CO_2	CH_4	N_2O
Refinery Gas	CzSO	CS	D	D	Tier 2	Tier 1	Tier 1
Natural Gas	CzSO	CS	D	D	Tier 2	Tier 1	Tier 1

This category includes all facilities that process raw petroleum imported into this country as their primary raw material. Domestic petroleum constitutes approximately 1% of the total amount in 2023. All fuels used in the internal refinery processes, and internal consumption (reported by companies as "own use") for the production of electricity and heat and heat supplied to the public mains are included in emission calculations in this subcategory. This corresponds primarily to the ORLEN UNIPETROL RPA Ltd. company in the Czech Republic. The company changed its name in the year 2017 from Česká rafinérská Inc. Fugitive CH_4 emissions are included in category 1.B.2.a Fugitive Emissions from Fuels - Oil.

The fraction of CO_2 emissions in subsector 1.A.1.b in CO_2 emissions in sector 1.A.1 equalled 1% in 2024. It contributed 0.7% to CO_2 emissions in the whole Energy sector.

In the CzSO Questionnaire (CzSO, 2025), the consumption of the individual kinds of fuels in this sector is reported under the item:

- Refinery Fuel
- Relevant NACE Rev. 2 code: 19.20 - Manufacture of refined petroleum products

Starting with submission in 2013, the greenhouse gas emissions from the combustion of refinery gas are estimated using country-specific emission factors. A detailed description of the research carried out in 2013 is provided in Annex 3 of this NID. The default emission factors were used for the rest of the liquid fuels. A country-specific emission factor is used also for Natural Gas – see the outlines at the beginning of each subchapter.

Fig. 3-7 shows an overview of emissions trends in source category 1.A.1.b.

No consumption of Solid Fuels occurred in this category, with the exception of the years 1993-1995. In those years, a low consumption of Gas Works Gas was reported based on data from CzSO (2025).



Fig. 3-7 Development of CO_2 emissions in 1.A.1.b category

Liquid Fuels are of the greatest importance and exhibit an increasing trend in the whole period. The fluctuations that have occurred over the years can be explained as resulting from differences in production quantities (see also Fig. 3-8). The maximum production equal to 716 kt CO_2 occurred in 2008, followed by a value of 697 kt CO_2 in 2006. Thereafter, production decreased to the resulting level of 357 kt CO_2 in 2015, resp. 274 kt CO_2 in 2024. There was an apparent decrease in Ethylene production in 2016 after the accident in 2015 when the rest of the LPG was used for other petrochemical production. The explanation of the ethylene production decrease is already included in NID in the respective chapter in the IPPU sector.

The second greatest role is played by Natural Gas, with emissions in the range of 238 kt CO_2 in 2004 and 360 kt CO_2 in 1997 resulting in a decrease to 188 kt CO_2 in 2024.

3.2.8.2 Methodological issues (CRT 1.A.1.b)

Basic methodological approaches were presented in the section 3.2.4. In Chapter 3.2.8. no specific approaches were used for performing QA/QC in category 1.A.1.b.

3.2.8.3 Uncertainties and time-series consistency (CRT 1.A.1.b)

See chapter 3.2.5.

3.2.8.4 Category-specific QA/QC and verification (CRT 1.A.1.b)

Fig. 3-8 compares fuel consumption in sector 1.A.1.b with the total amount of crude oil processed in the Czech Republic in separate years.



Fig. 3-8 Comparison of fuel consumption in the sector 1.A.1.b and amount of crude oil processed

The figure shows that since 2000 the relation between the amount of crude oil processed and the amount of fuel used is in line. In the period from 1990 to 2000, it is clear that the specific energy consumption for processing crude oil was lower than at present, and went through certain fluctuations. They were driven by the fact that in this period the production capacity of both refineries was expanded (Litvinov and Kralupy nad Vltavou) towards deeper crude oil processing (especially using cracking units since the end of the 90s).

The other QA/QC procedures were performed as described in chapter 3.2.6.

3.2.8.5 Category-specific recalculations (CRT 1.A.1.b)

Due to the minor changes in GCV of Natural Gas (CzSO, 2025), Gaseous fuels were recalculated for the years 2010 and 2023. The highest difference was -0.11 % in CO_2 emission in 2016; all other changes were at the second decinal place or smaller, therefore these changes are not shown in specific table.

3.2.8.6 Category-specific planned improvements (CRT 1.A.1.b)

No further improvements in this subcategory are currently planned.

3.2.9 Manufacture of solid fuels and other energy industries (CRT 1.A.1.c)

This category is divided into two subcategories:

- Manufacture of Solid Fuels (1.A.1.c.i)
- Other Energy Industries (1.A.1.c.ii)

Given that this division is used in the new methodology (IPCC, 2006) and the fact that there are no precise data for more detailed classification, in this submission, the data is reported as a summary in category CRT 1.A.1.c.i. Production of briquettes, which would fall under 1.A.1.c.i in the Czech Republic has been

terminated and in terms of the share of the emissions, this production had, it was negligible and further accurate data on fuel consumption in this category are now hardly accessible.

3.2.9.1 Category description (CRT 1.A.1.c.i)

The structure of fuels, their consumption, the emission factors and emissions of various greenhouse gases are shown in the following outline.

1.A.1.c, 2024								
Structure of Fuels	Activity	CO_2			CH_4		N_2O	
	data	EF	OxF	Emission	EF	Emission	EF	Emission
	[TJ]	[t CO_2/TJ]		[kt]	[kg CH_4/TJ]	[kt]	[kg N_2O/TJ]	[kt]
Heating and Other Gasoil	85.20	74.10	1	6.31	3	0.00026	0.6	0.00008
Brown Coal + Lignite	5 507.57	100.78*)	0.9846*)	546.48	1	0.00551	1.5	0.00826
Coke Oven Gas	3 665.84	44.40	1	162.76	1	0.00367	0.1	0.00037
Natural Gas	104.82	56.08*)	1	5.88	1	0.00010	0.1	0.00005
Total year 2024	**9 363.44**			**721.44**		**0.00953**		**0.00876**
Total year 2023	17 309.55			1 415.04		0.01748		0.01825
Index 2024/2023	0.54			0.51		0.55		0.48
Total year 1990	28 984.58			1 516.42		0.03348		0.00824
Index 2024/1990	0.32			0.48		0.28		1.06

*) *Country specific data*

The table shows that while the index for 2024/1990 of fuel consumption is 0.32, the same index for CO_2 emissions is significantly higher. This was caused by the high proportion of coke oven gas in the fuel structure 1990, which had a relatively low emission factor. Later, the part of coke oven gas was reallocated to other subsectors (1.A.1.a and 1.A.2.a). Even more markedly the high proportion of coke oven gas, combined with a relatively low emission factor, compared to other fuels, occurred in N_2O emissions.
The origin of the data, the emission factors used and the method of calculating the level of emissions for each gas are presented in detail in the following outline.

2024							
Structure of Fuels	Source of Activity data	Emission factors			Method used		
		CO_2	CH_4	N_2O	CO_2	CH_4	N_2O
Heating and Other Gasoil	CzSO	D	D	D	Tier 1	Tier 1	Tier 1
Brown Coal + Lignite	CzSO	CS	D	D	Tier 2	Tier 1	Tier 1
Coke Oven Gas	CzSO	D	D	D	Tier 1	Tier 1	Tier 1
Natural Gas	CzSO	CS	D	D	Tier 2	Tier 1	Tier 1

This category includes all facilities that process Solid Fuels, from mining through coking processes to secondary fuel production, such as Brown-Coal Briquettes, and Coke Oven Gas. It also includes fuels for the production of electrical energy and heat for internal consumption (reported by companies as “own use”).

Many companies in the Czech Republic that belong to this category. These are mainly companies performing underground and surface mining of coal and its subsequent processing, located near coal deposits. The category also included Coke plants and the production of Gas Works Gas. Other energy industries, such as facilities for extraction of Natural Gas and Petroleum are of minor importance in the Czech Republic.

The visible decrease for 2021 was caused by shutting down the fuel combine Vřesová producing Gas Works Gas from brown coal. Due to this effect, there was an increase in coal in the Czech market, which led to higher consumption of Lignite in Manufacturing industries and construction (1.A.2). The decrease for 2024 was caused mainly by lower industrial production activity, particularly in the metallurgical industry in the Ostrava region. Rapid decreased was observed under the item Coal Mines in the CzSO Questionare (CzSO, 2025).



Fig. 3-9 Development of CO_2 emissions in 1.A.1.c.i category

The fraction of CO_2 emissions in subsector 1.A.1.c in CO_2 emissions in sector 1.A.1 was equal to 2% in 2024. It contributed only 1% to CO_2 emissions in the Energy sector 1.A.

In the CzSO Questionnaire (CzSO, 2025), the consumption of the individual kinds of fuels in this sector is reported in the capture Energy Sector under the items:

- Coal Mines
- Oil and Gas Extraction
- Coke Ovens (Energy)
- Patent Fuel Plants (Energy)
- BKB Plants (Energy)
- Non-specified (Energy)

There are embodied the fuels of the economic part according to NACE Rev. 2

- 05.10 Mining of Hard Coal
- 05.20 Mining of Lignite
- 06.10 Extraction of Crude Oil
- 06.20 Extraction of Natural Gas
- 19.20 Manufacture of refined petroleum products (this class also includes: the manufacture of Peat Briquettes, Hard-coal and Lignite fuel Briquettes)

Fig. 3-9 provides an overview of emission trends in source category 1.A.1.c. The figure clearly shows the sharp increase in emissions from 1995 to 2012. Coal usage predominated in the period followed by the consumption of Gas Works Gas and Coke Oven Gas. The use of Liquid Fuels and Natural Gas is small in this category. The sharp increase in fuel consumption in 1995 depends on the economic situation of the respective companies, where the fuels are used. The Czech Republic is using official data reported by the official reporting authority in the Czech Republic and not even this authority would have updated data for the activity data which occurred 20 years ago.

Sokolovská Uhelná Inc. makes the greatest contribution to the consumption of Solid fuels. The section for processing Brown Coal was established in 1950 and produced Gas Works Gas and other chemical products. Officially, this combine plant ended in 1974 when it moved under the Hnědouhelné doly a briketárny company. Together with this step was established Fuel Combine Vřesová. The new combined-cycle power station started to operate in 1996. This power station was closed in September 2020 (http://www.suas.cz).

Between 1990 and 1995, the production of Coal Gas, which was distributed in the Czech Republic by Gas Work Vřesová, was gradually phased out. In Fig. 3-9 can be seen a decline in the production of Coal Gas and the starting up of production of Gas Works Gas for the production of electricity and the supply the heat. Pipelines used to distribute Coal Gas at that time were converted for Natural Gas and took over the role for its long-distance transport and local distribution. Coke Oven Gas is produced in the Ostrava area where the Coke Plants are operating.

3.2.9.2 Methodological issues (CRT 1.A.1.c.i)

The fuel consumption in the Vřesová Fuel combine plays a dominant role in fuel consumption in this category. This fuel is used for its gasification process, as well as for the production of technological steam, which enters into the process as a raw material. The produced high-pressure synthesis gas is then purified by acidic components (CO_2 and H_2S) and is used for power generation and supplied heat. From a methodological point of view, the whole combined production is divided into two parts – consumption of produced Gas Work Gas (and associated GHG emissions) for the production of electricity and heat and fuel consumption for technological purposes (input coal to produce technological steam).To include CO_2 emissions and other greenhouse gases produced from the gasification of pressure gas, it was necessary to replace the consumption of Gas Work Gas in the model with coal, which enters the process. The emission factor for lignite was used to calculate CO_2 where total coal consumption in the technological part of the process was used as the activity data.

The amount of coal that was used for the production of technological steam is not directly accessible from the CzSO energy balance. Data from the CHMI REZZO national emission database was used to determine the amount of coal. The quantity of coal for the production of technological steam is given in Tab. 3-15. This table will not be further actualized as all next years will have zero consumption of lignite.

Tab. 3-15 Consumption of Lignite for production of technological steam in Fuel combine Vřesová 1995–2023

Year	1995	1996	1997	1998	1999	2000	2001	2002	2003	2004	2005
Lignite [kt/year]	1 439	1 596	1 536	1 571	1 588	1 651	1 715	1 746	1 856	1 931	2 064
Year	2006	2007	2008	2009	2010	2011	2012	2013	2014	2015	2016
Lignite [kt/year]	2 003	2 088	2 107	1 938	2 044	2 094	2 117	1 994	1 951	2 013	2 005
Year	2017	2018	2019	2020	2021	2022	2023				
Lignite [kt/year]	2 140	2 054	1 904	1 449	2	0	0				

This amount of coal is in the data calculation of CzSO included in the total fuel consumption in the sector "Transformation - autoproducer heat plants". To avoid double counting the quantity of coal, the amount was deducted from the other calculations in the model for fuels used in autoproducers.

No other specific approaches were used in this category.

3.2.9.3 Uncertainties and time-series consistency (CRT 1.A.1.c.i)

See chapter 3.2.5.

3.2.9.4 Category-specific QA/QC and verification (CRT 1.A.1.c.i)

Fig. 3-10 contains a comparison between the consumption of lignite in sector 1.A.1.c (data from the REZZO national emission database) and the total amount of lignite, entering the transformation process (gasified coal) in the Czech Republic (data CzSO) in the period 1995–2024.

Apart from the early years, when the combined cycle was starting to reach its full power (1995 to 1998), the trends of the two curves are very similar. The minor fluctuations are caused by annual climatic influences; the technological steam is also used as a heating medium in the entire company and its consumption also depends on the average annual temperatures.



Fig. 3-10 Comparison of lignite consumption for steam production and gasification

As a QA/QC procedure for this part of the calculations utilized the internal expertise of experts from the Department of Emissions and Sources at CHMI. Other procedures were performed as described in chapter 3.2.6.

3.2.9.5 Category-specific recalculations (CRT 1.A.1.c.i)

Based on minor changes in Activity data in Solid Fules for 2023 (CzSO, 2025) the fuel consumption and emissions were corrected, see Tab. 3-16. Due to the minor changes in GCV of Natural Gas (CzSO, 2025), Gaseous fuels were recalculated for the years 2010-2023. The highest difference was -0.11 % in CO_2 emission in 2016; all other changes were at the second decinal place or smaller, therefore these changes are not shown in specific table.

Tab. 3-16 Changes after recalculation in 1.A.1.c.i for Solid fuels.

Fuel consumption		**2023**
Submission 2025	TJ	17 109.38
Submission 2026	TJ	17 129.27
Difference	TJ	19.89
Submission 2026	%	0.12
CO_2 emission		**2023**
Submission 2025	kt	1 401.44
Submission 2026	kt	1 403.41
Difference	kt	1.97
Submission 2026	%	0.14
CH_4 emission		**2023**
Submission 2025	kt	0.0171
Submission 2026	kt	0.0171
Difference	kt	0.0000
Submission 2026	%	0.1163
N_2O emission		**2023**
Submission 2025	kt	0.0182
Submission 2026	kt	0.0182
Difference	kt	0.0000
Submission 2026	%	0.1643

3.2.9.6 Category-specific planned improvements (CRT 1.A.1.c.ii)

Currently, there are no planned improvements in this category.

3.2.10 Manufacturing industries and construction – Iron and Steel (CRT 1.A.2.a)

3.2.10.1 Category description (CRT 1.A.2.a)

The structure of fuels, consumption, emission factors and emissions of individual greenhouse gases are in the following outline.

1.A.2.a, 2024								
Structure of Fuels	**Activity**	**CO_2**			**CH_4**		**N_2O**	
	data	**EF**	**OxF**	**Emission**	**EF**	**Emission**	**EF**	**Emission**
	[TJ]	**[t CO_2/TJ]**		**[kt]**	**[kg CH_4/TJ]**	**[kt]**	**[kg N_2O /TJ]**	**[kt]**
Anthracite	643.52	98.30	1	63.26	10	0.00644	1.5	0.00097
Other Bituminous Coal	9.52	94.14*)	0.9707*)	0.87	10	0.00010	1.5	0.00040
Brown Coal + Lignite	265.56	99.74*)	0.9846*)	26.08	10	0.00266	1.5	0.00479
Coke	3 194.97	107.00	1	341.86	10	0.03195	1.5	0.01079
Coke Oven Gas	2 229.95	44.40	1	99.01	1	0.00223	0.1	0.00022
Natural Gas	6 519.66	56.08*)	1	365.66	1	0.00652	0.1	0.00065
Wood/Wood Waste	3.58	112.00	1	0.40	30	0.00011	4.0	0.00001
Total year 2024	**12 863.17**			**896.73**		**0.04999**		**0.01784**
Total year 2023	17 431.92			1 349.45		0.00357		0.01325
Index 2024/2023	0.74			0.66		13.99		1.35
Total year 1990	155 319.22			14 860.68		1.39496		0.20941
Index 2024/1990	0.08			0.06		0.04		0.09

*) *Country specific data*

The origin of the data, the emission factors used and the method of calculating the level of emissions for each gas are in the following outline.

2024							
Structure of Fuels	**Source of Activity data**	**Emission factors**			**Method used**		
		CO_2	**CH_4**	**N_2O**	**CO_2**	**CH_4**	**N_2O**
Anthracite	CzSO	D	D	D	Tier 1	Tier 1	Tier 1
Other Bituminous Coal	CzSO	CS	D	D	Tier 2	Tier 1	Tier 1
Brown Coal + Lignite	CzSO	CS	D	D	Tier 2	Tier 1	Tier 1
Coke	CzSO	D	D	D	Tier 1	Tier 1	Tier 1
Coke Oven Gas	CzSO	D	D	D	Tier 1	Tier 1	Tier 1
Natural Gas	CzSO	CS	D	D	Tier 2	Tier 1	Tier 1
Wood/Wood Waste	CzSO	D	D	D	Tier 1	Tier 1	Tier 1

This category includes manufacturing in the area of pig iron (blast furnaces), rolling steel, cast iron, steel and alloys and is related only to ferrous metals. In the CzSO Questionnaire (CzSO, 2025), the consumption of the individual kinds of fuels in this sector is reported in section Industry Sector under the item: Iron and Steel. There are embodied fuels of economic part according to NACE Rev. 2 Iron and steel: NACE Divisions 24.1 – 24.3 and 24.51, 24.52.

The fraction of CO_2 emissions in subsector 1.A.2.a in CO_2 emissions in sector 1.A.2 equalled 10% in 2024. It contributed only 1% to CO_2 emissions in the whole Energy sector.

Important facilities belonging to this category are ArcelorMittal Ostrava (changed its name to Liberty Ostrava a.s. in 2021), a.s. and Třinecké železárny a.s. Both metallurgical plants include iron ore sinter production, blast furnaces, coke production, iron processing in oxygen converters for steel and casting of



Fig. 3-11 Development of CO_2 emissions in source category 1.A.2.a

steel in electric furnaces and in tandem furnaces. Production of steel using the Siemens-Martin process was stopped before 1990.

The graph in Fig. 3-11 shows an apparent sharp reduction in emissions in the early 90s, mainly due to the loss of markets, following the sharp political changes in the country. At the same time, a decrease in emissions was caused by the new legislation on air pollution and other environmental components. Gradual implementation and introduction of new, more stringent requirements for the protection of the environment is reflected in the decrease in emissions from about 1998. In the course of emissions after 2000, the competition of metallurgical plants in countries outside of Europe caused an impact. Minor fluctuations are caused by market demand and to a lesser extent, the necessary restructuring undertaken in individual companies. The deacrese in 2024 is cause by production limitations due to reconstruction at Třinecké železárny a.s. and a reduction in production at Liberty Ostrava a.s.

Further, Fig. 3-11 shows that the main proportion of CO_2 emissions is due to the use of fossil fuels, which are dominant in this sector.

3.2.10.2 Methodological issues (CRT 1.A.2.a)

All CO_2 emissions from metallurgical coke used in blast furnaces are reported under the Industrial processes sector (2.C.1) and estimated from the amount of carbon in the coke (see Chapter 0). Most of the blast furnace and converter gas is combusted in the two metallurgical plants (complexes) and only partly is used elsewhere. At present, we incapable of identifying the exact amount of these gases combusted outside metallurgical complexes. In order to prevent double-counting, we report all CO_2 emissions coming from metallurgical coke under 2.C.1. As a consequence, we do not calculate any CO_2 emissions from the blast furnace and converter gas.

3.2.10.3 Uncertainties and time-series consistency (CRT 1.A.2.a)

See chapter 3.2.5.

3.2.10.4 Category-specific QA/QC and verification (CRT 1.A.2.a)



Fig. 3-12 The trend in the manufacture of agglomerates of iron ore and iron, in comparison with the development of fuel consumption in the sector 1.A.2.a

As a basic indicator for verification of fuel consumption in the sector of production of pig iron and steel, it is necessary to consider the indicators of the overall production of agglomerates of iron ore and pig iron. This is due to their high energy intensity. Fig. 3-12 shows the relationship between fuel consumption and total production of sinter and iron in mill. tons.

Fig. 3-12 shows that the fuel consumption decreases faster than the actual production. This is due to the gradual reduction of overall energy intensity throughout the metallurgical industry. This trend was particularly evident in the early 90s when there was a major restructuring of production. This restructuring enabled, after the decline in 1990 and 1993, to return the volume of production almost to the level of 1990, but the decrease in total fuel consumption went further. Additional reductions in energy intensity are evident then until the end of the period.

Generally accepted methods of QA/QC are described in section 3.2.6.

3.2.10.5 Category-specific recalculations (CRT 1.A.2.a)

Based on minor changes in activity data in CzSO, 2025, fuel consumptions of Solid fules for the year 2023 were corrected. See the differences in the Tab. 3-17. Due to the minor changes in GCV of Natural Gas (CzSO, 2025), Gaseous fuels were recalculated for the years 2010-2023. The highest difference was -0.002 % in CO_2 emission in 2016; all other changes were smaller, therefore these changes are not shown in specific table.

Tab. 3-17 Changes after recalculation in 1.A.2.a for Solid fuels.

Fuel consumption		**2023**
Submission 2025	TJ	11 264.6071
Submission 2026	TJ	11 265.1937
Difference	TJ	0.5866
Submission 2026	%	0.0052
CO_2 emission		**2023**
Submission 2025	kt	1 004.4034
Submission 2026	kt	1 004.4600
Difference	kt	0.0566
Submission 2026	%	0.0056
CH_4 emission		**2023**
Submission 2025	kt	0.0851
Submission 2024	kt	0.0851
Difference	kt	0.0000
Submission 2026	%	0.0069
N_2O emission		**2023**
Submission 2025	kt	0.0126
Submission 2024	kt	0.0126
Difference	kt	0.0000
Submission 2026	%	0.0070

3.2.10.6 Category-specific planned improvements (CRT 1.A.2.a)

We are planning to find data to identify portions of both blast furnace and converter gases, which are combusted outside metallurgical complexes (see 3.2.10.2).

3.2.11 Manufacturing industries and construction – Non-Ferrous Metals (1.A.2.b)

3.2.11.1 Category description (CRT 1.A.2.b)

The structure of fuels, consumption, emission factors and emissions of individual greenhouse gases are in the following outline.

1.A.2.b, 2024								
Structure of Fuels	Activity	CO_2			CH_4		N_2O	
	data	EF	OxF	Emission	EF	Emission	EF	Emission
	[TJ]	[t CO_2/TJ]		[kt]	[kg CH_4/TJ]	[kt]	[kg N_2O /TJ]	[kt]
Brown Coal + Lignite	12.30	99.74*)	0.9846*)	1.21	10	0.00012	1.5	0.00002
Coke	122.32	107.00	1	13.09	10	0.00122	1.5	0.00018
Natural Gas	2 247.60	56.08*)	1	126.06	1	0.00225	0.1	0.00022
Total year 2024	**2 382.23**			**140.35**		**0.00359**		**0.00043**
Total year 2023	2 376.73			139.52		0.00357		0.00042
Index 2024/2023	1.00			1.01		1.01		1.01
Total year 1990	1 476.34			101.96		0.00572		0.00081
Index 2024/1990	1.61			1.38		0.63		0.52

*) *Country specific data*

The origin of the data, the emission factors used and the method of calculating the level of emissions for the individual gases are shown in detail in the following outline.

2024							
Structure of Fuels	Source of	Emission factors			Method used		
	Activity data	CO_2	CH_4	N_2O	CO_2	CH_4	N_2O
Brown Coal + Lignite	CzSO	CS	D	D	Tier 2	Tier 1	Tier 1
Coke	CzSO	D	D	D	Tier 1	Tier 1	Tier 1
Natural Gas	CzSO	CS	D	D	Tier 2	Tier 1	Tier 1

This category encompasses combustion processes in various areas of non-ferrous metals production. In the Czech Republic, this corresponds mainly to foundry processes; primary production of non-ferrous metals is not performed on an industrial scale in the Czech Republic. In the CzSO Questionnaire (CzSO, 2025), the consumption of the individual kinds of fuels in this sector is reported in the section Industry Sector under the item:

Non-Ferrous Metals



Fig. 3-13 Development of CO_2 emissions in source category 1.A.2.b

There are embodied the fuels of the economic part according to NACE Rev. 2

Non-ferrous metals: NACE Divisions 24.4, 24.53, 24.54

An important facility that belongs to this category is Kovohutě Příbram. The fraction of CO_2 emissions in subsector 1.A.2.b in CO_2 emissions in sector 1.A.2 equalled 2% in 2024. It contributed only 0.2% to CO_2 emissions in the whole Energy sector. Therefore, the sector is of the least importance in the sector of Fuel combustion according to its emissions of greenhouse gases.

The following figure (Fig. 3-13) provides an overview of CO_2 emissions in the various sub-source categories in 1.A.2.b.

The trend of CO_2 emissions corresponds to the trend of consumption of individual types of fuels. After a decline in the early 90s, the recovery in the industry caused a sharp increase in emissions by. The recovery of the industry has happened in this sector, especially due to the increase in demand for parts, made of ferrous metals in the emerging automotive industry. The decrease in emissions at the end of the period was caused by the crisis between 2008 and 2012, as well as the reduction of the energy intensity of production. This is also related to a shift from fossil fuels in favour of natural gas. This effect can be seen especially in the year 2021. However, due to the war in Ukraine, Natural gas consumption is decreasing again, see the year 2022 and 2023. Furthermore, electrical energy is increasingly used for heating the melting furnaces, which has a positive impact on greenhouse gas emissions.

3.2.11.2 Methodological issues (CRT 1.A.2.b)

In this subcategory, specific methodologies are not used - a description of the general procedures - see Section 3.2.4.

3.2.11.3 Uncertainties and time-series consistency (CRT 1.A.2.b)

See chapter 3.2.5.

3.2.11.4 Category-specific QA/QC and verification (CRT 1.A.2.b)

In this subcategory, specific methodologies are not used - a description of the general procedures - see Section 3.2.6.

3.2.11.5 Category-specific recalculations (CRT 1.A.2.b)

Based on the change of activity data of Solid fuels (CzSO, 2025), the fuel consumption and emissions were corrected, see Tab. 3-18. Due to the minor changes in GCV of Natural Gas (CzSO, 2025), Gaseous fuels were recalculated for the years 2010-2023. The highest difference was -0.11 % in CO_2 emission in 2016; all other changes were smaller, therefore these changes are not shown in specific table.

Tab. 3-18 Changes after recalculation in 1.A.2.b for Solid fuels.

Fuel consumption		2023
Submission 2025	TJ	132.92
Submission 2026	TJ	132.95
Difference	TJ	0.04
Submission 2026	%	0.03
CO_2 emission		2023
Submission 2025	kt	13.99
Submission 2026	kt	14.00
Difference	kt	0.004
Submission 2026	%	0.025
CH_4 emission		2023
Submission 2025	kt	0.0013
Submission 2026	kt	0.0013
Difference	kt	0.000
Submission 2026	%	0.0276
N_2O emission		2023
Submission 2025	kt	0.0002
Submission 2026	kt	0.0002
Difference	kt	0.0000
Submission 2026	%	0.0276

3.2.11.6 Category-specific planned improvements (CRT 1.A.2.b)

Currently there are no planned improvements in this category.

3.2.12 Manufacturing industries and construction – Chemicals (1.A.2.c)

3.2.12.1 Category description (CRT 1.A.2.c)

The structure of fuels, consumption, emission factors and emissions of individual greenhouse gases are in the following outline.

1.A.2.c, 2024								
Structure of Fuels	Activity data	CO_2 EF	CO_2 OxF	CO_2 Emission	CH_4 EF	CH_4 Emission	N_2O EF	N_2O Emission
	[TJ]	[t CO_2/TJ]		[kt]	[kg CH_4/TJ]	[kt]	[kg N_2O/TJ]	[kt]
LPG	237.79	65.86*)	1	15.66	1	0.00024	0.1	0.00002
Fuel Oil High Sulphur	79.00	77.40	1	6.11	10	0.00024	0.6	0.00005
Other Oil	3 266.89	73.30	1	239.46	3	0.00980	0.6	0.00196
Other Bituminous Coal	0.67	94.14*)	0.9707*)	0.06	10	0.00001	1.5	0.00000
Brown Coal + Lignite	16 631.13	99.74*)	0.9846*)	1 633.31	10	0.16631	1.5	0.02495
Natural Gas	10 783.59	56.08*)	1	604.80	1	0.01078	0.1	0.00108
Wood/Wood Waste	142.09	112.00	1	15.91	30	0.00426	4.0	0.00057
Gaseous Biomass	670.34	54.60	1	36.60	1	0.00067	0.1	0.00007
Total year 2024	**30 999.07**			**2 499.41**		**0.19231**		**0.02869**
Total year 2023	35 472.30			2 952.05		0.24678		0.03697
Index 2024/2023	0.87			0.85		0.78		0.78
Total year 1990	33 576.71			2 996.37		0.26480		0.03975
Index 2024/1990	0.92			0.83		0.73		0.72

*) *Country specific data*

The origin of the data, the emission factors used and the method of calculating the level of emissions for the individual gases are shown in detail in the following outline.

2024							
Structure of Fuels	Source for	Emission factors			Method used		
	Activity data	CO_2	CH_4	N_2O	CO_2	CH_4	N_2O
LPG	CzSO	CS	D	D	Tier 2	Tier 1	Tier 1
Fuel Oil High Sulphur	CzSO	D	D	D	Tier 1	Tier 1	Tier 1
Other Oil	CzSO	D	D	D	Tier 1	Tier 1	Tier 1
Other Bituminous Coal	CzSO	CS	D	D	Tier 2	Tier 1	Tier 1
Brown Coal + Lignite	CzSO	CS	D	D	Tier 2	Tier 1	Tier 1
Natural Gas	CzSO	CS	D	D	Tier 2	Tier 1	Tier 1
Wood/Wood Waste	CzSO	D	D	D	Tier 1	Tier 1	Tier 1
Gaseous Biomass	CzSO	D	D	D	Tier 1	Tier 1	Tier 1

This subcategory includes all the processes in the organic and inorganic chemical industry and all related processes, incl. petrochemistry. The petrochemical plants are linked to two major refinery enterprises in Litvinov (Unipetrol RPA, sro) and Kralupy (Synthos Kralupy as). Due to the historical linkage between the two units, it is challenging to determine the fuel combusted in the refinery and petrochemical parts of the two plants separately. Furthermore, other major plants for processing organic chemistry products are in operation in the Czech Republic (DEZA a.s. Meziříčí – processing of coal tar, SYNTHESIA a.s. Pardubice - basic organic chemistry) and several factories for manufacturing of inorganic products (SPOLANA a.s. Neratovice, SPOLCHEMIE a.s. Ústí nad Labem, PRECHEZA a.s. Přerov and others). The largest plants are also equipped with energy resources, with a significant share of electricity and heat (autoproducers); this results in relatively high consumption of fossil fuels (see Fig. 3-14). Heat is generated using abundant natural gas and, to a lesser extent, liquid fuels or, in some cases, electrical energy. In total, the national emission database recorded 1,000 production units that fall within sector 1.A.2.c. The fluctuation in fuel consumption is influenced by many factors, including economic development, the production plan of companies and their stocks, meteorological conditions and efforts to reduce the energy intensity of processes in the chemical industry.)

In the CzSO Questionnaire (CzSO, 2025), the consumption of the individual kinds of fuels in this sector is reported in the section Industry Sector under the item:

- Chemical (including Petrochemical)

There are embodied the fuels of the economic part according to NACE Rev. 2:

Chemicals: NACE Division 20

The fraction of CO_2 emissions in subsector 1.A.2.c in CO_2 emissions in sector 1.A.2 equalled 29% in 2024. It contributed 4% to CO_2 emissions in the whole Energy sector.



Fig. 3-14 Development of CO_2 emissions in source category 1.A.2.c

The following figure (Fig. 3-14) provides an overview of CO_2 emissions in the sub-category 1.A.2.c.

The course of CO_2 emissions is not directly related to the volume of chemical production, since it is primarily emissions from burning fossil fuels to produce electricity and heat (autoproducers). For this reason, the development of emissions in time cannot be commented on.

3.2.12.2 Methodological issues (CRT 1.A.2.c)

Given that in the IPCC 2006 Gl. (IPCC, 2006) is used an updated approach to the allocation of feedstocks and non-energy use of fuels into IPPU. The new distribution of liquid fuels is to be considered as category specific methodological issue. This methodological approach is in the same time based on the new reallocation of fuel consumption for energy and non-energy use in the questionnaire from CzSO, 2024. The reallocation of feedstocks and non-energy use of fuels in IPPU is in details described in chapter 3.2.3.

Other methodological approaches were applied as in the other subcategories, and their description is provided in chapter 3.2.4.

3.2.12.3 Uncertainties and time-series consistency (CRT 1.A.2.c)

See chapter 3.2.5.

3.2.12.4 Category-specific QA/QC and verification (CRT 1.A.2.c)

In this category, no specific QA/QC procedures were used. Given that the fuel consumption in this sector, reported directly, is not related to the production volume of chemicals, there cannot be used the relevant comparison with specific commodities.

Description of the QA/QC procedures is given in chapter 3.2.6.

3.2.12.5 Category-specific recalculations (CRT 1.A.2.c)

Based on the change of activity data of Solid fuels (CzSO, 2025), the fuel consumption and emissions were corrected, see Tab. 3-19. Due to the minor changes in GCV of Natural Gas (CzSO, 2025), Gaseous fuels were recalculated for the years 2010-2023. The highest difference was -0.11 % in CO_2 emission in 2016; all other changes were on the second decimal places or smaller, therefore these changes are not shown in specific table.

Tab. 3-19 Changes after recalculation in 1.A.2.c for Solid fuels

Fuel consumption		**2023**
Submission 2025	TJ	22 136.14
Submission 2026	TJ	22 324.02
Difference	TJ	187.89
Submission 2026	%	0.85
CO_2 emission		**2023**
Submission 2025	kt	2 156.36
Submission 2026	kt	2 154.71
Difference	kt	-1.65
Submission 2026	%	-0.08
CH_4 emission		**2023**
Submission 2025	kt	0.2214
Submission 2026	kt	0.2232
Difference	kt	0.0019
Submission 2026	%	0.8488
N_2O emission		**2023**
Submission 2025	kt	0.0332
Submission 2026	kt	0.0335
Difference	kt	0.0003
Submission 2026	%	0.8488

3.2.12.6 Category-specific planned improvements (CRT 1.A.2.c)

Currently there are no planned improvements in this category.

3.2.13 Manufacturing industries and construction – Pulp, Paper and Print (1.A.2.d)

3.2.13.1 Category description (CRT 1.A.2.d)

The structure of fuels, their consumption, used emission factors and emissions of individual greenhouse gases are shown in the following outline.

1.A.2.d, 2024								
Structure of Fuels	Activity	CO_2			CH_4		N_2O	
	data	EF	OxF	Emission	EF	Emission	EF	Emission
	[TJ]	[t CO_2/TJ]		[kt]	[kg CH_4/TJ]	[kt]	[kg N_2O/TJ]	[kt]
LPG	142.67	65.86*)	1	9.40	1	0.00014	0.1	0.00001
Fuel Oil High Sulphur	158.00	77.40	1	12.23	10	0.00047	0.6	0.00009
Other Bitumenous Coal	4.20	94.14*)	0.9707*)	0.38	10	0.00004	1.5	0.00001
Brown Coal + Lignite	1 490.75	99.74*)	0.9846*)	146.40	10	0.01491	1.5	0.00224
Natural Gas	3 492.18	56.08*)	0.9846*)	195.86	1	0.00349	0.1	0.00035
Wood/Wood Waste	21 763.21	112.00	1	2 437.48	30	0.65290	4.0	0.08705
Gaseous Biomass	9 734.08	54.60	1	531.48	1	0.00973	0.1	0.00097
Total year 2024	**5 287.80**			**364.27**		**0.68169**		**0.09073**
Total year 2023	7 127.34			508.49		0.61373		0.08179
Index 2024/2023	0.74			0.72		1.11		1.11
Total year 1990	25 900.78			2 285.33		0.18784		0.02890
Index 2024/1990	0.20			0.16		3.63		3.14

*) *Country specific data*

The origin of the data, the emission factors used and the method of calculating the level of emissions for the individual gases are shown in details in the following outline.

2024							
Structure of Fuels	Source of	Emission factors			Method used		
	Activity data	CO_2	CH_4	N_2O	CO_2	CH_4	N_2O
LPG	CzSO	CS	D	D	Tier 2	Tier 1	Tier 1
Fuel Oil High Sulphur	CzSO	D	D	D	Tier 1	Tier 1	Tier 1
Other Bitumenous Coal	CzSO	CS	D	D	Tier 2	Tier 1	Tier 1
Brown Coal + Lignite	CzSO	CS	D	D	Tier 2	Tier 1	Tier 1
Natural Gas	CzSO	CS	D	D	Tier 2	Tier 1	Tier 1
Wood/Wood Waste	CzSO	D	D	D	Tier 1	Tier 1	Tier 1
Gaseous Biomass	CzSO	D	D	D	Tier 1	Tier 1	Tier 1

This subcategory includes all manufacturing processes related to the production of paper, cardboard and print in printing plants. There are two primary paper production factories in the Czech Republic (JIP - Papírny Větřní, a. s., Mondi Štětí a.s.) with a high consumption of waste wood from production processes. The other plants select the kind of fuel on the basis of the same criteria as the rest of the processing industry.

In the CzSO Questionnaire (CzSO, 2025), the consumption of the individual kinds of fuels in this sector is reported in the section Industry Sector under the item:

Paper, Pulp and Printing

There are embodied the fuels of economic part according to NACE Rev. 2

Pulp, paper and print: NACE Divisions 17 and 18

The fraction of CO_2 emissions in subsector 1.A.2.d in CO_2 emissions in sector 1.A.2 equalled 4% in 2024. It contributed 1% to CO_2 emissions in the whole Energy sector.



Fig. 3-15 Development of CO_2 emissions in source category 1.A.2.d

From the graph on Fig. 3-15 is clear that at the end of the 90s there was significant substitution, therefore used fossil fuels (primarily lignite) with wood and later biogas. Both biofuels represent waste products from the production of paper and pulp from the two largest plants in the Czech Republic. Following the decline in 2003 and 2004, the consumption of fuels after 2005 was relatively stable, while the share of biofuels further increased.

Biofuel consumption has a beneficial effect on the production of CO_2, which is included in the balance of greenhouse gases. In Fig. 3-15 is shown the development of CO_2 emissions from fossil fuels and biomass only in sector 1.A.2.d.

3.2.13.2 Methodological issues (CRT 1.A.2.d)

No specific methodological approaches were applied in this subcategory, otherwise see chapter 3.2.6.

3.2.13.3 Uncertainties and time-series consistency (CRT 1.A.2.d)

See chapter 3.2.5.

3.2.13.4 Category-specific QA/QC and verification (CRT 1.A.2.d)

No specific methods for QA/QC in this category were used - otherwise see chapter 3.2.7.4.

3.2.13.5 Category-specific recalculations (CRT 1.A.2.d)

Based on the change of activity data of Solid fuels (CzSO, 2025), the fuel consumption and emissions were corrected, see the Tab. 3-20. Due to the minor changes in GCV of Natural Gas (CzSO, 2025), Gaseous fuels were recalculated for the years 2010-2023. The highest difference was -0.11 % in CO_2 emission in 2016; all other changes were on the second decimal places or smaller, therefore these changes are not shown in specific table.

Tab. 3-20 Changes after recalculation in 1.A.2.d for Solid fuels

Fuel consumption		2023	CH_4 emission		2023
Submission 2025	TJ	2 616.20	Submission 2025	kt	0.0262
Submission 2026	TJ	2 620.58	Submission 2026	kt	0.0262
Difference	TJ	4.37	Difference	kt	0.0000
Submission 2026	%	0.17	Submission 2026	%	0.1671

CO_2 emission		2023	N_2O emission		2023
Submission 2025	kt	252.49	Submission 2025	kt	0.0039
Submission 2026	kt	252.91	Submission 2026	kt	0.0039
Difference	kt	0.42	Difference	kt	0.0000
Submission 2026	%	0.17	Submission 2026	%	0.1671

3.2.13.6 Category-specific planned improvements (CRT 1.A.2.d)

Currently there are no planned improvements in this category.

3.2.14 Manufacturing industries and construction – Food Processing, Beverages and Tobacco (1.A.2.e)

3.2.14.1 Category description (CRT 1.A.2.e)

The structure of fuels, their consumption, used emission factors and emissions of individual greenhouse gases are shown in the following outline.

1.A.2.e, 2024								
Structure of Fuels	Activity data	CO_2			CH_4		N_2O	
		EF	OxF	Emission	EF	Emission	EF	Emission
	[TJ]	[t CO_2/TJ]		[kt]	[kg CH_4/TJ]	[kt]	[kg N_2O/TJ]	[kt]
LPG	475.58	65.86*)	1	31.32	1	0.00048	0.1	0.00005
Heating and Other Gasoil	60.86	74.10	1	4.51	3	0.00018	0.6	0.00004
Fuel Oil - High Sulphur	158.00	77.40	1	12.23	3	0.00047	0.6	0.00009
Other Bituminous Coal	433.21	93.83*)	0.9707*)	39.59	10	0.00433	1.5	0.00065
Brown Coal + Lignite	1 999.50	98.03*)	0.9846*)	196.37	10	0.01999	1.5	0.00300
Coke	222.01	107.00	1	23.75	10	0.00222	1.5	0.00033
Natural Gas	10 529.81	56.08*)	1	590.56	1	0.01053	0.1	0.00105
Wood/Wood Waste	78.92	112.00	1	8.84	30	0.00237	4.0	0.00032
Gaseous Biomass	6 084.92	54.60	1	322.61	1	0.00591	0.1	0.00059
Total year 2024	**13 878.96**			**898.33**		**0.04666**		**0.00614**
Total year 2023	14 324.61			948.70		0.05324		0.00718
Index 2024/2023	0.97			0.95		0.88		0.85
Total year 1990	37 616.46			2 988.18		0.21342		0.03226
Index 2024/1990	0.37			0.30		0.22		0.19

*) *Country specific data*

The origin of the data, the emission factors used and the method of calculating the level of emissions for the individual gases are shown in details in the following outline.

2024							
Structure of Fuels	Source of Activity data	Emission factors			Method used		
		CO_2	CH_4	N_2O	CO_2	CH_4	N_2O
LPG	CzSO	CS	D	D	Tier 2	Tier 1	Tier 1
Heating and Other Gasoil	CzSO	D	D	D	Tier 1	Tier 1	Tier 1
Fuel Oil - High Sulphur	CzSO	D	D	D	Tier 1	Tier 1	Tier 1
Other Bituminous Coal	CzSO	CS	D	D	Tier 2	Tier 1	Tier 1
Brown Coal + Lignite	CzSO	CS	D	D	Tier 2	Tier 1	Tier 1
Coke	CzSO	D	D	D	Tier 1	Tier 1	Tier 1
Natural Gas	CzSO	CS	D	D	Tier 2	Tier 1	Tier 1
Wood/Wood Waste	CzSO	D	D	D	Tier 1	Tier 1	Tier 1
Gaseous Biomass	CzSO	D	D	D	Tier 1	Tier 1	Tier 1

This subcategory includes all manufacturing processes related to the production of foodstuffs, beverages and foodstuff preparations. The subcategory also includes fuel consumption in the tobacco industry. The nature of the production processes permits the use of a relatively high fraction of biofuels, especially towards the end of the period.

In the CzSO Questionnaire (CzSO, 2025), the consumption of the individual kinds of fuels in this sector is reported in the section Industry Sector under the item:



Fig. 3-16 Development of CO_2 emissions from fossil fuels combustion in source category 1.A.2.e

Food, Beverages and Tobacco

There are embodied the fuels of economic part according to NACE Rev. 2

Food processing, beverages and tobacco: NACE Divisions 10, 11 and 12

The fraction of CO_2 emissions in subsector 1.A.2.e in CO_2 emissions in sector 1.A.2 equalled 10% in 2024. It contributed 1% to CO_2 emissions in the whole Energy sector.

The following figure provides an overview of fuels consumption in the sub-category in 1.A.2.e.

It is obvious from the graph in Fig. 3-16 that natural gas is the dominant fuel over the entire time series with quite balanced consumption. The high share of fossil fuels at the beginning of the period reduced continuously and with replacement of fossil fuels by solid and gaseous biofuels towards the end of this period. The overall amount of fuel consumed decreased until 2008. Since 2008 there has been an increase in fuel consumption, which is covered by increasing consumption of biofuels, in response to the development of the financial crisis in the period at the end of the first decade of the 21st century. Since 2014 the consumption was stable with fluctuation in 2017 – 2022.

Biofuel consumption has a beneficial effect on the production of CO_2, which is included in the balance of greenhouse gases. Fig. 3-16 shows the development of CO_2 emissions from fossil fuels and biomass only in sector 1.A.2.e.

3.2.14.2 Methodological issues (CRT 1.A.2.e)

No specific methodological approaches were applied in this subcategory, otherwise see chapter 3.2.6.

3.2.14.3 Uncertainties and time-series consistency (CRT 1.A.2.e)

See chapter 3.2.5.

3.2.14.4 Category-specific QA/QC and verification (CRT 1.A.2.e)

No specific methods for QA/QC in this category were used - otherwise see chapter 3.2.7.4.

3.2.14.5 Category-specific recalculations (CRT 1.A.2.e)

Based on the change of activity data of Solid fuels (CzSO, 2025), the fuel consumption and emissions were corrected, see the Tab. 3-21. Due to the minor changes in GCV of Natural Gas (CzSO, 2025), Gaseous fuels were recalculated for the years 2010-2023. The highest difference was -0.11 % in CO_2 emission in 2016; all other changes were on the second decimal places or smaller, therefore these changes are not shown in specific table.

Tab. 3-21 Changes after recalculation in 1.A.2.e for Solid fuels

Fuel consumption		2023	CH_4 emission		2023
Submission 2025	TJ	3 369.17	Submission 2025	kt	0.0337
Submission 2026	TJ	3 373.76	Submission 2026	kt	0.0337
Difference	TJ	4.59	Difference	kt	0.0000
Submission 2026	%	0.14	Submission 2026	%	0.1362
CO_2 emission		2023	N_2O emission		2023
Submission 2025	kt	324.77	Submission 2025	kt	0.0051
Submission 2026	kt	325.21	Submission 2026	kt	0.0051
Difference	kt	0.44	Difference	kt	0.0000
Submission 2026	%	0.14	Submission 2026	%	0.1362

3.2.14.6 Category-specific planned improvements (CRT 1.A.2.e)

Currently there are no planned improvements in this category.

3.2.15 Manufacturing industries and construction – Non-metallic Minerals (1.A.2.f)

3.2.15.1 Category description (CRT 1.A.2.f)

The structure of fuels, their consumption, used emission factors and emissions of individual greenhouse gases are shown in the following outline.

1.A.2.f, 2024								
Structure of Fuels	Activity	CO_2			CH_4		N_2O	
	data	EF	OxF	Emission	EF	Emission	EF	Emission
	[TJ]	[t CO_2/TJ]		[kt]	[kg CH_4/TJ]	[kt]	[kg N_2O/TJ]	[kt]
LPG	190.23	65.86*)	1	12.5	1	0.00019	0.1	0.00002
Heating and Other Gasoil	121.71	74.10		9.0	1	0.00037	0.6	0.00007
Fuel Oil - Low Sulphur	39.50	77.40	1	3.1	3	0.00012	0.6	0.00002
Fuel Oil - High Sulphur	197.50	77.40	1	15.3	3	0.00059	0.6	0.00012
Other Bituminous Coal	2 021.45	93.83*)	0.9707*)	184.7	10	0.02021	1.5	0.00303
Brown Coal + Lignite	109.03	98.03*)	0.9846*)	10.7	10	0.00109	1.5	0.00016
Coke	1 226.48	107.00	1	131.2	10	0.01226	1.5	0.00184
Coal Tars	74.78	80.70	1	6.0	10	0.00075	1.5	0.00011
Brown Coal Briquets	1 215.93	97.50	0.9846*)	116.7	10	0.01216	1.5	0.00182
Coke Oven Gas	74.34	44.40	1	3.3	1	0.00007	0.1	0.00001
Natural Gas	19 298.94	56.08*)	1	1 082.4	1	0.01930	0.1	0.00193
Other fuels - liquid	437.90	74.32*)	1	32.5	30	0.01314	4	0.00175
Other fuels - solid	5 487.82	81.79*)	1	448.8	30	0.16463	4	0.02195
Wood/Wood Waste	3 630.67	112.00	1	406.6	30	0.10892	4	0.01452
Total year 2024	**30 495.61**			**2 056.38**		**0.35381**		**0.04737**
Total year 2023	31 758.09			2 190.21		0.39088		0.05244
Index 2024/2023	0.96			0.94		0.91		0.90
Total year 1990	59 962.36			4 527.12		0.29373		0.04487

Index 2024/1990	0.51	0.45	1.20	1.06

*) *Country specific data*

The origin of the data, the emission factors used and the method of calculating the level of emissions for the individual gases are shown in details in the following outline.

2024							
Structure of Fuels	**Source of Activity data**	**Emission factors**			**Method used**		
		CO_2	**CH_4**	**N_2O**	**CO_2**	**CH_4**	**N_2O**
LPG	CzSO	CS	D	D	Tier 2	Tier 1	Tier 1
Heating and Other Gasoil	CzSO	D	D	D	Tier 1	Tier 1	Tier 1
Fuel Oil - Low Sulphur	CzSO	D	D	D	Tier 1	Tier 1	Tier 1
Fuel Oil - High Sulphur	CzSO	D	D	D	Tier 1	Tier 1	Tier 1
Other Bituminous Coal	CzSO	CS	D	D	Tier 2	Tier 1	Tier 1
Brown Coal + Lignite	CzSO	CS	D	D	Tier 2	Tier 1	Tier 1
Coke	CzSO	D	D	D	Tier 1	Tier 1	Tier 1
Coal Tars	CzSO	D	D	D	Tier 1	Tier 1	Tier 1
Brown Coal Briquets	CzSO	D	D	D	Tier 1	Tier 1	Tier 1
Coke Oven Gas	CzSO	D	D	D	Tier 1	Tier 1	Tier 1
Natural Gas	CzSO	CS	D	D	Tier 2	Tier 1	Tier 1
Other fuels - liquid	ETS, CzSO	CS	D	D	Tier 2	Tier 1	Tier 1
Other fuels - solid	ETS, CzSO	CS	D	D	Tier 2	Tier 1	Tier 1
Wood/Wood Waste	CzSO	D	D	D	Tier 1	Tier 1	Tier 1

Category 1.A.2.f now comprises all industrial processes for the treatment of non-minerals raw materials and products such as cement, lime, burnt building materials and refractory materials, ceramics, glass etc. Category 1.A.2.f was established by dividing the original category into 2 groups, i.e. in 1.A.2.g are included remained sources of greenhouse gases from the category "Manufacturing industries and construction."

The category is characterized by high energy intensity, and for it is also typical consumption "Other fuels" that are burned at the cement works furnaces. The cement kilns in the Czech Republic are the only one facility (except the industrial waste incinerators reported in sector 5 Waste), in which it is allowed incinerating waste, respectively an alternative fuel made from waste.

In the CzSO Questionnaire (CzSO, 2025), the consumption of the individual kinds of fuels in this sector is reported in the section Industry Sector under the item:

Non-Metallic Minerals

There are embodied the fuels of economic part according to NACE Rev. 2:

NACE Divisions 23

23 Manufacture of other non-metallic mineral products
- 23.1 Manufacture of glass and glass products
- 23.2 Manufacture of refractory products
- 23.4 Manufacture of other porcelain and ceramic products
- 23.5 Manufacture of cement, lime and plaster

The fraction of CO_2 emissions in subsector 1.A.2.f in CO_2 emissions in sector 1.A.2 equalled 23% in 2024. It contributed 3% to CO_2 emissions in the whole Energy sector.

Between the most important businesses are included mainly cement (a total of 5 facilities), which are operated in the northern, central and eastern Bohemia and Central Moravia and lime (a total of 3 facilities) in southern and eastern Bohemia and North Moravia.



Fig. 3-17 Production of the most important mineral products

Total production of the most important mineral products is shown in the graph on Fig. 3-17.

Fig. 3-18 provides an overview of fuels consumption and CO_2 emissions in the sub-category in 1.A.2.f.



Fig. 3-18 Development of CO_2 emissions in source category 1.A.2.f

The graph shows the evolution of CO_2 emissions, that has the same pattern as the fuel consumption. The high consumption of fossil fuel at the beginning of the period decreased gradually, and it is evident that the most important fuel in this sector is natural gas. The high consumption of fossil fuels gradually was declining and liquid fuels, from 2002 gradually were replaced by alternative fuels (Other fuels). The increase in fuel consumption between 2005 and 2008, was interrupted by the crisis development of the economy and after some recovery in 2010–2011, followed by another decline. From 2014 was recorded slight increase and from 2016 slight decrease. Slight increase since 2017 can be observed for biomass and followed the decrease after 2021.

3.2.15.2Methodological issues (CRT 1.A.2.f)

The category of Non-Metallic Minerals reports consumption of alternative fuels (Other fuels). The compilation consumption balance and the determination of the emission factors are different from the procedures used for other fuels, as described in section 3.2.4. The basic source of information is the EU ETS database, where the emission factors for different types of alternative fuels are available. The resulting processed data on consumption of alternative fuels is further corrected according to the data on the server of the Union of cement and lime manufacturers (www.svcement.cz). Quite extense recalculation were done for the year 2020, based on the change of the methodology. Biocomponent was separately added to the 1.A.2.f category since 2003. It was found out that in the CzSO questionnaire "CZECH_RENEWABLE" is sheet "IndWaste", which actually contain a mixture of fossil and bioparticles, although these data are marked as non-ren (information from the Ministry of Industry and Trade). The proportion of the biocomponent was calculated as a linear decrease from 50 % to zero. This procedure must be used, as there was a very low proportion of solid biofuels in this subcategory, which is gradually growing. The linear decrease between 2003 and 2012 must be chosen because today there is no longer any basis for determining the share of the bio-component in alternative fuels. Due to the refinement of solid and liquid other fossil fuels calculations quite steady consumption in years were achieved. Alternative fuel consumption is shown in Tab. 3-22.

Tab. 3-22 Consumption of alternative fuels in sector 1.A.2.f

[TJ/year]	2003	2004	2005	2006	2007	2008	2009	2010	2011
Solid fuels	2 424	3 200	3 517	3 398	3 726	3 222	3 236	3 224	3 885
Liquid fuels	1 266	1 156	589	1 014	240	557	682	708	661
Total	3 690	4 356	4 105	4 412	3 966	3 779	3 918	3 932	4 546
[TJ/year]	2012	2013	2014	2015	2016	2017	2018	2019	2020
Solid fuels	2 279	2 904	3 739	4 640	5 512	5 448	6 182	6 769	6 435
Liquid fuels	1 029	1 138	1 153	1 022	1 091	978	1 257	1 118	687
Total	3 309	4 042	4 893	5 662	6 603	6 426	7 438	7 887	7 122
[TJ/year]	2021	2022	2023	2024					
Solid fuels	6 192	5 945	6 192	5 488					
Liquid fuels	582	582	350	438					
Total	6 773	6 527	6 542	5 926					

Emission factors for calculating CO_2 emissions are based on the consumption of fuel (solid, liquid fuels). The resulting emission factor corresponds to the relative representation of individual types of fuels. In Tab. 3-23 is shown an overview of emission factors used for solid and liquid alternative fuels in different years. It can be seen that the EF is quite stable.

Tab. 3-23 CO_2 emission factors used in the consumption of alternative fuels in sector 1.A.2.f

[t CO_2/TJ]	2003	2004	2005	2006	2007	2008	2009	2010	2011
Solid fuels	87.55	87.46	88.54	84.54	78.26	80.98	79.14	85.23	85.78
Liquid fuels	75.42	75.80	75.09	76.16	73.00	71.93	70.42	81.21	77.40
[t CO_2/TJ]	2012	2013	2014	2015	2016	2017	2018	2019	2020
Solid fuels	92.61	87.46	87.52	84.98	85.20	84.83	85.43	83.31	82.26
Liquid fuels	80.08	78.75	78.78	79.30	77.91	76.79	78.86	77.81	75.64
[t CO_2/TJ]	2021	2022	2023	2024					
Solid fuels	86.58	84.33	84.72	81.79					
Liquid fuels	75.21	71.93	77.09	74.32					

For the calculation of CH_4 and N_2O emissions were used default emission factors in line with the IPCC 2006 Gl. (IPCC 2006), for the entire time series 2003–2024 (Tab. 3-24).

Tab. 3-24 Emission factors for CH_4 and N_2O emissions used in the consumption of alternative fuels sector 1.A.2.f

EF [kg/TJ]	CH_4	N_2O
Solid fuels	30	4
Liquid fuels	30	4

3.2.15.3 Uncertainties and time-series consistency (CRT 1.A.2.f)

See chapter 3.2.5.

3.2.15.4 Category-specific QA/QC and verification (CRT 1.A.2.f)



Fig. 3-19 Trends in production of mineral products compared with the development of fuel consumption in the sector 1.A.2.f

As a basic indicator for verification of fuel consumption in the sector of production of pig iron and steel, should be regarded indicators of the overall production of basic goods such as cement, lime, clay tiles and roof tiling or glass and fine ceramics. This is a relatively large mass flows, which also exhibit high energy demands (Fig. 3-18). Comparison of total production and total fuel consumption in the sub sector 1.A.2.f is shown in Fig. 3-19.

The basic trend flow of production of mineral products in total corresponds well with the total fuel consumption. Given that this is a rough comparison, it might be that the minor variations are caused by different specific energy intensities of the individual kinds of mineral products.

Other QA/QC procedures are set out in section 3.2.6.

3.2.15.5 Category-specific recalculations (CRT 1.A.2.f)

Based on the change of activity data of Solid fuels – Brown Coal + Lignite and Coke (CzSO, 2025), the fuel consumption and emissions were corrected, see the Tab. 3-25. Due to the minor changes in GCV of Natural Gas (CzSO, 2025), Gaseous fuels were recalculated for the years 2010-2023. The highest difference was -0.11 % in CO_2 emission in 2016; all other changes were on the second decimal places or smaller, therefore these changes are not shown in specific table.

Tab. 3-25 Changes after recalculation in 1.A.2.f for Solid Fuels

Fuel consumption		2023	CH_4 emission		2023
Submission 2025	TJ	5 243.54	Submission 2025	kt	0.0517
Submission 2026	TJ	5 485.12	Submission 2026	kt	0.0541
Difference	TJ	241.58	Difference	kt	0.0024
Submission 2026	%	4.61	Submission 2026	%	4.6762
CO_2 emission		2023	N_2O emission		2023
Submission 2025	kt	499.42	Submission 2025	kt	0.0077
Submission 2026	kt	525.31	Submission 2026	kt	0.0081
Difference	kt	25.89	Difference	kt	0.0004
Submission 2026	%	5.18	Submission 2026	%	4.6787

3.2.15.6 Category-specific planned improvements (CRT 1.A.2.f)

Currently there are no planned improvements in this category.

3.2.16 Manufacturing industries and construction – Other (1.A.2.g)

3.2.16.1 Category description (CRT 1.A.2.g)

The structure of fuels, their consumption, used emission factors and emissions of individual greenhouse gases are shown in the following outline.

1.A.2.g, 2024								
Structure of Fuels	Activity data	CO_2			CH_4		N_2O	
		EF	OxF	Emission	EF	Emission	EF	Emission
	[TJ]	[t CO_2/TJ]		[kt]	[kg CH_4/TJ]	[kt]	[kg N_2O/TJ]	[kt]
LPG	1 664.52	65.86*)	1	109.62	1	0.00166	0.1	0.00017
Heating and Other Gasoil	243.43	77.40	1	18.04	3	0.00073	0.6	0.00015
Fuel Oil - high Sulphur	1 027.00	77.40	1	79.49	3	0.00308	0.6	0.00062
Anthracite	0.32	98.30	1	0.03	10	0.00000	1.5	0.00000
Other Bitumenous Coal	4.95	93.83*)	0.9707*)	0.45	10	0.00005	1.5	0.00001
Brown Coal + Lignite	457.03	98.03*)	0.9846*)	44.88	10	0.00457	1.5	0.00069
Coke	36.58	107.00	1	3.91	10	0.00037	1.5	0.00005
Brown Coal Briquets	285.64	97.50	0.9846*)	27.42	10	0.00286	1.5	0.00043
Coke Oven Gas	0.03	44.40	1	3.30	1	0.00000	0.1	0.00000
Natural Gas	28 910.49	56.08*)	1	1 621.45	1	0.02891	0.1	0.00289
Wood/Wood Waste	8 733.73	112.00	1	978.18	30	0.26201	4	0.03493
Total year 2024	**32 629.99**			**1 908.60**		**0.30424**		**0.03993**
Total year 2023	33 837.19			1 962.28		0.30672		0.04007
Index 2024/2023	0.96			0.97		0.99		1.00
Total year 1990	232 304.69			19 063.89		1.80697		0.26619
Index 2024/1990	0.14			0.10		0.17		0.15

*) *Country specific data*

The origin of the data, the emission factors used and the method of calculating the level of emissions for the individual gases are shown in details in the following outline.

2024							
Structure of Fuels	Source of Activity data	Emission factors			Method used		
		CO_2	CH_4	N_2O	CO_2	CH_4	N_2O
LPG	CzSO	CS	D	D	Tier 2	Tier 1	Tier 1
Fuel Oil - Low Sulphur	CzSO	D	D	D	Tier 1	Tier 1	Tier 1
Fuel Oil - High Sulphur	CzSO	D	D	D	Tier 1	Tier 1	Tier 1
Antracit	CzSO	D	D	D	Tier 1	Tier 1	Tier 1
Other Bituminous Coal	CzSO	CS	D	D	Tier 2	Tier 1	Tier 1
Brown Coal + Lignite	CzSO	CS	D	D	Tier 2	Tier 1	Tier 1
Coke	CzSO	D	D	D	Tier 1	Tier 1	Tier 1
Brown Coal Briquets	CzSO	D	D	D	Tier 1	Tier 1	Tier 1
Coke Oven Gas	CzSO	D	D	D	Tier 1	Tier 1	Tier 1
Natural Gas	CzSO	CS	D	D	Tier 2	Tier 1	Tier 1
Wood/Wood Waste	CzSO	D	D	D	Tier 1	Tier 1	Tier 1

This subcategory includes the remaining enterprises in the processing industry not included in subcategories 1.A.2.a to 1.A.2.f. This is an energy-demanding branch with fuel consumption, such as the textile and leather industry, wood processing and subsequent production processes, the entire machine industry, incl. production of means of transport and the construction industry.

In the CzSO Questionnaire (CzSO, 2025), the consumption of the individual kinds of fuels in this sector is reported in the section Industry Sector under the item:

- Transport Equipment
- Machinery

- Mining (excluding fuels) and Quarrying
- Wood and Wood Products
- Construction
- Textiles and Leather
- Non-specified (Industry)

There are embodied the fuels of economic part according to NACE Rev. 2 Other: NACE Divisions 05 – 09, 13 – 16, 21 – 22, 25 – 33 and 41 – 43.

The fraction of CO_2 emissions in subsector 1.A.2.g in CO_2 emissions in sector 1.A.2 equalled 22% in 2024. It contributed 3% to CO_2 emissions in the whole Energy sector. Overall emissions have exhibited a decrease since 1990. At the beginning of the period, Solid Fuels were of major importance, but this has constantly decreased until 2020. Liquid fuels have also constantly decreased in importance since 1990. Natural Gas is also important fuel in this category. This importance of NG can be seen as a slight increase for the year 2021.

The graph in Fig. 3-20 shows that the beginning of the period was characterised by highly energy-intensive types of industrial processes in this category. Social changes occurring in the Czech Republic in the early 90s resulted in energy-saving measures being introduced by newly privatized enterprises. Together, these influences led to an end to inefficient production and suppression of consumption, particularly of fossil fuels, which were the dominant fuels at the beginning of the period and virtually disappeared by 2005, when they were replaced by biomass. At the same time, the importance of liquid fuels decreased. All this was reflected very significantly by a decline in the CO_2 emissions (and other greenhouse gases). This is the category with the largest relative decrease in CO_2 emissions from 1990 to 2024 (90% decrease).



Fig. 3-20 Development of CO_2 emissions in source category 1.A.2.g

3.2.16.2 Methodological issues (CRT 1.A.2.g)

Sector specific methodological approaches were not used, the general approaches are given in chapter 3.2.4.

3.2.16.3 Uncertainties and time-series consistency (CRT 1.A.2.g)

See chapter 3.2.5.

3.2.16.4 Category-specific QA/QC and verification (CRT 1.A.2.g)

See chapter 3.2.6.

3.2.16.5 Category-specific recalculations (CRT 1.A.2.g)

Based on the change of activity data of Solid fuels (CzSO, 2025), the fuel consumption and emissions were corrected, see the Tab. 3-26. Due to the minor changes in GCV of Natural Gas (CzSO, 2025), Gaseous fuels were recalculated for the years 2010-2023. The highest difference was -0.11 % in CO_2 emission in 2016; all other changes were on the second decimal places or smaller, therefore these changes are not shown in specific table.

Tab. 3-26 Changes after recalculation in 1.A.2.g for Solid Fuels.

Fuel consumption		2023	CH_4 emission		2023
Submission 2025	TJ	1 165.45	Submission 2025	kt	0.0117
Submission 2026	TJ	1 041.53	Submission 2026	kt	0.0104
Difference	TJ	-123.91	Difference	kt	-0.0012
Submission 2026	%	-10.63	Submission 2026	%	-10.6321
CO_2 emission		2023	N_2O emission		2023
Submission 2025	kt	112.55	Submission 2025	kt	0.0017
Submission 2026	kt	100.59	Submission 2026	kt	0.0016
Difference	kt	-11.96	Difference	kt	-0.0002
Submission 2026	%	-10.63	Submission 2026	%	-10.6321

3.2.16.6 Category-specific planned improvements (CRT 1.A.2.g)

Currently there are no planned improvements in this category.

3.2.17 Transport (1.A.3)

For purposes of greenhouse gas emissions calculations, all vehicles are differentiated according to transport mode and vehicle category. Vehicle categories in road transport are further differentiated based on the fuel used, segment and emission standard that the vehicle must meet. The vehicle categories in non-road transport are not so detailed.

Activity data (AD) for road transport are calculated by combining data from Czech Car Registry (CCR) and from Database of Technical Control Stations (TCS). The result is traffic performance for each category in vehicle kilometres per year. These data are entered into COPERT 5.9 calculation program (see chapter 3.2.17.3).

The data required for calculation of emissions from non-road transport (aviation, railways, navigation) are fuel consumption statistics provided by Czech Statistical Office (CzSO) and respective activity data (see chapters 3.2.17.2, 3.2.17.4, 3.2.17.5).

The vehicle categories of mobile sources are the following:

Domestic Aviation (CRT 1.A.3.a)

- airplanes fuelled by aviation gasoline,
- airplanes fuelled by jet kerosene.

Road Transport (CRT 1.A.3.b)

- motorcycles, mopeds, micro-cars, quad & ATVs (L-category):
    - conventional, Euro 1 – Euro 5,
    - petrol, diesel,
- passenger cars (PCs):

  - PRE ECE, ECE 15/00-01, ECE 15/02, ECE 15/03, ECE 15/04, conventional, improved conventional, open loop, Euro 1 – Euro 6,
  - petrol, petrol hybrid, petrol PHEV, diesel, diesel PHEV, LPG bifuel, CNG bifuel, battery electric,
- light duty vehicles (LDVs):
  - conventional, Euro 1 – Euro 6,
  - petrol, diesel, battery electric,
- heavy duty vehicles (HDVs):
  - conventional, Euro I – Euro VI,
  - petrol, diesel, CNG,
- buses:
  - conventional, EEV, Euro I – Euro VI,
  - diesel, diesel hybrid, biodiesel, CNG, battery electric.

Railways (CRT 1.A.3.c)

- diesel locomotives: line-haul, shunting, rail cars,
- steam locomotives: bituminous coal, lignite.

Domestic Navigation (CRT 1.A.3.d)

- slow-speed diesel vessels,
- high-speed diesel vessels,
- steam turbine vessels.

3.2.17.1Methodological issues



Fig. 3-21 Annual fuel consumption by mode of transport

The methodology for road transport emissions calculation in the Czech Republic is based on COPERT 5 methodology (see chapter 3.2.17.3). In non-road transport, we work with emission factors (EF) in [$g.kg^{-1}$] which are derived from 2006 IPCC Guidelines and EMEP/EEA Emission Inventory Guidebook (EIG) 2023. AD entered to CRTs must be converted to TJ. The fuel consumption is converted from weight to energy units using the country-specific (CS) fuel calorific value which is variable thorough years. Therefore, IEF time series depend on EF in [$g.kg^{-1}$] as well as on the trend of calorific values. In case of road transport, all is done automatically in COPERT 5.9. Emission factors used for calculations are described in the following chapters. Calorific values used for calculations in the transport sector are presented in the table below.

Tab. 3-27 Calorific values of fuels in [MJ/kg] (source: CzSO)

Fuel	2001	2002	2003	2004	2005	2006	2007	2008	2009	2010	2011	2012
Gasoline	43.300	43.300	43.300	43.300	43.300	43.817	43.800	43.839	44.165	44.235	44.308	44.302
Diesel Oil	41.920	41.940	41.929	41.873	41.829	42.779	42.749	42.870	42.976	43.037	42.985	42.958
LPG	44.321	44.340	44.368	44.337	44.337	45.803	45.803	43.826	43.817	43.822	43.814	43.800
CNG	48.551	48.604	48.566	48.532	48.536	48.726	48.816	48.805	48.856	49.035	49.013	48.900
Bioethanol	27.000	27.000	27.000	27.000	27.000	27.000	27.000	27.000	27.000	27.000	27.000	27.000
Biodiesel	37.000	37.000	37.000	37.000	37.000	37.000	37.000	37.000	37.000	37.000	37.000	37.000
Aviation Gasoline	43.800	43.800	43.793	43.790	43.790	43.790	43.790	43.790	43.790	43.790	43.790	43.790
Jet Kerosene	42.800	42.800	42.800	42.800	42.800	43.300	43.300	43.300	43.300	43.300	43.300	43.300
Bituminous Coal	22.294	22.720	22.273	23.472	21.061	22.493	21.267	23.348	25.786	28.570	28.405	28.104
Lignite	12.874	12.926	12.973	13.339	13.680	15.498	13.000	13.503	13.859	15.454	15.081	15.176

Fuel	2013	2014	2015	2016	2017	2018	2019	2020	2021	2022	2023	2024
Gasoline	44.315	44.433	44.487	44.203	44.400	44.432	44.645	44.625	44.387	44.479	44.404	44.718
Diesel Oil	42.962	42.991	42.943	42.957	42.949	42.935	42.957	43.037	43.219	43.175	43.144	43.034
LPG	43.800	43.800	43.800	43.800	43.800	43.800	43.800	43.800	43.800	43.800	43.800	43.800
CNG	49.076	49.157	49.281	49.423	49.353	49.332	49.300	49.327	49.311	52.132	52.437	52.693
Bioethanol	27.000	27.000	27.000	27.000	27.000	27.000	27.000	27.000	27.000	27.000	27.000	27.000
Biodiesel	37.000	37.000	37.000	37.000	37.000	37.000	37.000	37.000	37.000	37.000	37.000	37.000
Aviation Gasoline	43.790	43.790	43.790	43.790	43.790	43.790	43.790	43.790	43.790	43.790	43.790	43.790
Jet Kerosene	43.300	43.300	43.300	43.300	43.300	43.300	43.300	43.300	43.300	43.300	43.300	43.300
Bituminous Coal	28.769	28.251	26.999	24.941	26.567	27.536	26.325	27.743	27.426	26.323	26.809	26.697
Lignite	15.550	15.183	15.524	16.141	14.502	14.814	14.666	15.088	15.507	15.813	15.484	15.610

In the following table, activity data by mode of transport are presented, a graphical comparison is shown in Fig. 3-21.

Tab. 3-28 Annual fuel consumption by mode of transport

Year	Aviation		Road Transport					Railways			Navigation
	Aviation Gasoline	Jet Kerosene	Gasoline	Diesel Oil	LPG	CNG	Biomass	Diesel Oil	Coal	Biomass	Diesel Oil
	[TJ]	[TJ]	[TJ]	[TJ]	[TJ]	[TJ]	[TJ]	[TJ]	[TJ]	[TJ]	[TJ]
2000	131	8 256	79 849	74 320	2 852	97	2 480	4 440	NO	NO	213
2001	88	8 774	81 709	82 490	2 792	97	1 842	4 066	NO	NO	335
2002	131	7 576	82 572	89 449	2 838	97	2 586	3 942	NO	NO	168
2003	131	10 186	90 190	105 858	2 884	146	2 480	3 857	NO	NO	168
2004	131	13 097	89 882	116 052	3 015	146	1 275	3 810	NO	NO	251
2005	88	13 610	88 234	134 997	3 104	146	106	3 848	14	NO	209
2006	88	14 116	87 337	144 125	3 298	146	727	4 107	15	NO	257

2007	88	14 809	91 068	152 062	3 527	195	1 204	4 061	13	NO	214
2008	88	15 675	87 711	152 630	3 506	244	4 469	4 501	14	NO	171
2009	88	14 332	85 513	148 030	3 243	293	7 913	4 083	14	NO	215
2010	88	13 423	77 643	142 052	3 374	343	9 374	3 959	15	NO	172
2011	44	13 293	74 631	142 625	3 418	392	12 140	3 869	15	NO	129
2012	88	12 384	69 521	144 163	3 767	489	11 136	3 737	15	NO	215
2013	88	11 951	65 326	146 325	3 898	736	11 205	3 652	16	NO	86
2014	88	12 341	64 672	153 477	4 292	1 032	12 817	3 697	43	NO	129
2015	131	12 427	65 189	162 918	4 336	1 528	12 000	3 607	43	NO	129
2016	131	13 380	67 188	170 188	4 336	2 076	11 874	3 308	41	283	172
2017	131	15 025	66 436	177 498	4 205	2 320	12 440	3 436	41	248	172
2018	131	17 320	66 485	180 101	4 030	2 615	12 273	3 435	28	212	129
2019	131	17 710	66 462	182 470	3 854	3 106	13 602	3 308	13	177	215
2020	88	4 850	60 390	171 420	3 241	3 157	14 872	2 927	8	177	172
2021	88	6 495	62 791	186 566	3 285	3 205	13 623	2 852	11	212	173
2022	88	11 171	65 626	190 164	3 723	3 174	12 848	3 109	13	212	130
2023	88	14 376	69 660	193 083	3 898	3 226	12 146	2 977	11	141	173
2024	88	18 922	72 810	200 019	3 723	3 262	13 423	2 926	13	177	129

3.2.17.2Aviation (CRT 1.A.3.a, 1.D.1.a)

Burning processes in air transport are quite different from those in land and water transport. This is caused by its operation in a wider range of atmospheric conditions (namely by substantial changes in atmospheric pressure, air temperature, and humidity). These variables are changing vertically with an altitude and horizontally with air masses. The categories 1.A.3.a (domestic aviation) and 1.D.1.a (international aviation) are reported with respect to distinctive flight phases: LTO (Landing/Take-off up to 3 000 feet) and CRUISE (above 3 000 feet). Emissions from helicopters used for public and private purposes are included in this category. Emissions from military aircrafts and helicopters are not included as they are reported in the category 1.A.5.b Military: Mobile Combustion.

3.2.17.2.1Methodological issues

For IFR flights, bottom-up data from EUROCONTROL were used in time series 2005 to present year. Time series 1990–2004 was estimated by extrapolation of EUROCONTROL fuel consumption with the help of fuel consumption from Czech Oil questionnaire provided by CzSO. CO_2 and N_2O emissions were calculated based on EUROCONTROL implied emission factors, CH_4 emissions based on 2006 IPCC Guidelines. IFR LTO/CRUISE ratios were obtained from EUROCONTROL (Tab. 3-29).

For VFR flights, ratio between LTO and CRUISE was obtained from Civil Aviation Authority (CAA) as their expert judgement because there is no database for VFR flight characteristics in CZ. The same EFs used for IFR flights were applied to fuel consumption from CzSO Czech Oil questionnaire.

Fuel consumption of helicopters was also obtained from CzSO, ratio between LTO and CRUISE from CAA. The EFs for IFR flights were applied to helicopter fuel consumption as well. VFR and helicopter LTO and CRUISE ratios are presented in the Tab. 3-29.

To ensure comparability of statistics, fuel consumption of aviation is aligned to jet kerosene and aviation gasoline consumption on national level as per Czech Oil questionnaire.

Tab. 3-29 Ratio of fuel usage between LTO and CRUISE flight mode in 2024

Subsector	Flight Mode	Ratio
1.A.3.a (IFR)	LTO	0.307
	CRUISE	0.693
1.A.3.a (VFR, Helicopters)	LTO	0.900
	CRUISE	0.100
1.D.1.a	LTO	0.125
	CRUISE	0.875

Activity data



Fig. 3-22 Annual jet kerosene consumption in aviation according to flight mode

Activity data are gained from CzSO and EUROCONTROL. Data are divided between LTO and CRUISE flight mode according to ratio which is stated in the Tab. 3-29. The total consumption of jet kerosene in the Czech Republic is divided into five categories (Domestic Aviation, International Aviation, Army, Industry and Commercial and Public Services). The jet kerosene consumption as well as relevant emissions from categories Army, Industry, Commercial and Public Services are not reported in CRT 1.A.3 Transport, but in sectors 1.A.5.b, 1.A.2.g and 1.A.4.a respectively. AD for domestic and international aviation are gained from EUROCONTROL (IFR flights) and from CzSO (VFR flights and helicopters). Fig. 3-22 presents jet kerosene consumption according to flight mode.

Emission factors

The emission factors for IFR flights are applied at Tier 2 for CO_2 and Tier 3 for N_2O. For both gases, the EFs are derived from EUROCONTROL data. The same CO_2 and N_2O EFs are applied to VFR flights and helicopters as those used for IFR flights.

The CH_4 EF is applied at the Tier 1 level for all flights. It is based on the annual calorific value of aviation fuel (updated every year according to the Czech Oil Questionnaire submitted to the EEA) and on the default CH_4 EF (kg/TJ) provided in the 2006 IPCC Guidelines for aviation. EUROCONTROL data were previously used to estimate CH_4 emissions; however, these data reported zero CH_4 emissions for IFR cruise, which resulted

in unrealistically high implied emission factors. As no more accurate national data source is available, the 2006 IPCC default values have been applied to all flights, in line with UNFCCC review recommendation.

Tab. 3-30 Emission factors for CO_2, CH_4 and N_2O for aviation in [g.kg^{-1}] of fuel in 2024

Subsector	Fuel Type	EF CO_2	EF CH_4	EF N_2O
		[g.kg^{-1}]	[g.kg^{-1}]	[g.kg^{-1}]
Aviation - LTO	Aviation Gasoline	3050	0.022	0.086
Aviation - CRUISE	Aviation Gasoline	3050	0.022	0.086
Aviation - LTO	Jet Kerosene	3150	0.022	0.086
Aviation - CRUISE	Jet Kerosene	3150	0.022	0.086

Emissions



Fig. 3-23 Emissions of CO_2, CH_4 and N_2O from aviation

CO_2 emissions from domestic air transport make a very small contribution to overall emissions from aviation (2% in average in years 2005–2024) as they are mainly limited to flights between the five largest airports in the Czech Republic (Prague, Brno, Karlovy Vary, Pardubice and Ostrava). Similarly to road transport, the consumption of aircraft fuels is not centrally monitored by the Czech Statistical Office. Aircrafts are mainly fuelled by jet kerosene, and these are producing most of the emissions from aviation. GHG emissions from aviation gasoline consumption are specifically related to small aircrafts used in agriculture, sports and for recreational activities. Small aircrafts fuelled by aviation gasoline include VFR flights. There are no small aircrafts fuelled by jet kerosene for VFR flights in the Czech Republic.

Fig. 3-23 shows GHG emissions from aviation in the Czech Republic. The emissions were decreasing from 2009 to 2013 as a result of the economic crisis. From 2014, the emissions were increasing until a huge drop in 2020 and 2021 caused by COVID-19 pandemic situation. Since 2022, the emissions were growing each year sharply and reached almost 1 400 kt in 2024 which is highest value in the entire time series 1990-2024.

3.2.17.3 Road Transportation (CRT 1.A.3.b)

This category covers all GHG emissions from motor road transport in the Czech Republic. It includes all private as well as public transport except for agricultural, forest and military transport which are reported in separate categories. Emissions are calculated for the following vehicle categories: passenger cars (PCs), light duty vehicles (LDVs), heavy duty vehicles (HDVs), buses and L-category vehicles. The vehicle categories are further broken down by type of fuel, segment and emission standard.

3.2.17.3.1 Methodological issues

The appropriate distribution of vehicles is necessary to assign a relevant emission factor. Sector CRT 1.A.3.b Road transportation is split into four subsectors:

- 1.A.3.b.i Passenger Cars,
- 1.A.3.b.ii Light Duty Vehicles,
- 1.A.3.b.iii Heavy Duty Vehicles and Buses,
- 1.A.3.b.iv Mopeds and Motorcycles.

For estimation of road transport emissions, COPERT 5.9 model was used. COPERT is based on 2023 EMEP/EEA Emission Inventory Guidebook and 2006 IPCC Guidelines, and it also incorporates results of several technology, research and police assessment projects. Model is being updated regularly (usually a new version each year). Crucial input for emission calculations in COPERT 5 are country-specific activity data – number of vehicles, average annual mileage, and total annual mileage assigned to corresponding COPERT vehicle categories.

Other important variables are:

- CS meteorological information,
- EU average information about driver behaviour (trip length, trip duration, average speed on different roads etc.),
- technical parameters of vehicles (technologies for emissions reduction, A/C in vehicles, tank size, number of axles…),
- fuel quality and composition of fuel,
- calorific value of fuels (from CzSO),
- H:C and O:C ratios,
- share of fossil fraction in biodiesel,
- ETBE content in biogasoline.

This is only a brief summary. Full description of COPERT 5 program is to be found in COPERT Documentation. Detailed methodology of COPERT 5 application in Czechia is described in Pelikán and Brich, 2017 and Pelikán and Brich, 2018.

Activity data

AD for COPERT program are being gained from two large databases – Czech Car Registry (CCR) and Database of Technical Control Stations (TCS). CCR contains information about number and technical details of vehicles registered in particular categories in CZ. TCS defines annual traffic performance for a particular vehicle. By combining these two databases, it is possible to obtain number of vehicles, average annual mileage, total annual mileage and lifetime cumulative mileage for all COPERT categories which are relevant in CZ. Results are in full accuracy four years before the actual reported year. The reason is that new vehicles in CZ must undertake the first technical control four years after registering in CCR. To get accurate average annual mileage and emissions estimates, it is necessary to recalculate results 4 years retrospectively every year.

The method for activity data calculation in Czech conditions was developed by Brich in 2014 and certified by Czech Ministry of Transport. It's constantly being updated. The last improvement was performed in 2024 in order to better approximate estimated traffic performance to reality. Non-operated vehicles were excluded from vehicle activity calculations. As a non-operated vehicle is considered a vehicle which does not have technical control registered in the last 10 years. From such vehicles, only the ones with VIN code linkable to data in Database of Technical Control Stations were marked as unambiguously non-operated. This approach was applied to passenger cars, light duty vehicles, heavy duty vehicles and buses. For motorcycles, all non-operated vehicles were deducted because most of Euro 3 and older motorcycles do not have VIN code and if the above-mentioned approach was used, it would cause unreasonably high mean activity in these subcategories.

Calculated AD along with other above-mentioned input variables are then entered into COPERT 5 which calculates fuel consumption and emissions for all vehicle categories. Final fuel consumption is automatically aligned to total fuel consumption on national level as per CzSO.

Fig. 3-24 shows trend of fuel consumption after 2000. General rising trend of fuel consumption by PCs and LDVs in the Czech Republic is in line with the trend in the whole Europe. There is an obvious influence of economic crisis between 2009 and 2013 on fossil fuels consumption (Tab. 3-31). From 2014, the consumption of main fossil fuels started to increase again. In 2017, almost 10% lower prices of diesel and gasoline fortified the further increase of fossil fuels consumption. The consumption of gasoline fluctuated around 90 000 TJ from 2003 to 2009, but then it was significantly declining until 2014 when it fell under 65 000 TJ. This decline was caused by the downward trend in average fuel consumption of modern passenger cars. From 2015 to 2023, gasoline consumption has been fluctuating between 65 000–70 000 TJ. Exceptions are years 2020 and 2021 influenced by COVID situation, when it dropped to around 60 000 TJ. However, it reached the pre-pandemic level already the next year and exceeded 70 000 TJ in 2024. Diesel fuel consumption was steadily growing from 2000 until 2008 when economic crisis started. After the crisis, steep increase began in 2014 and was related to economic growth and growing popularity of diesel PCs. Due to COVID pandemic, diesel consumption dropped to 171 420 TJ in 2020. In 2021, it sharply increased to 186 566 TJ. The increase has been continuing since then and exceeded 200 000 TJ in 2024.



Fig. 3-24 Trend of fuel consumption according to vehicle categories

Bioethanol was almost not used, and biodiesel was only used in a small share in Czech Republic before 2008. Bioethanol started to be added to all gasoline in the amount of 2% since 1 January 2008. The share of bioethanol as a renewable resource in gasoline reached 4.1% in 2010 and the share of fatty acid methyl esters (FAME) in diesel oil reached 6% in 2010 and both values did not change for more than 10 years. Since the reduction of fossil fuels consumption and the increasing share of biocomponents have a favourable impact on CO_2 emissions, lower taxes for blends with high percentage of biodiesel were implemented in 2015. This allowed the increase of biodiesel consumption which reached more than 12 600 TJ in 2020. The highest consumption of bioethanol was before COVID pandemic in 2019 (3 078 TJ), but it shows no specific long-term trend. Total share of biofuels in overall road transport fuel consumption was quite stable thorough the years (5% in average). In 2022, the end of mandatory blending of

biocomponents was approved by Czech government and this caused a decrease in both biodiesel and bioethanol consumption. In 2024, the mandatory share of bioethanol in gasoline was increased from 5% to 10% in the Czech Republic as part of the implementation of European Renewable Energy Directive III. As a result, bioethanol consumption rose sharply–by almost 50% compared with 2023.

Tab. 3-31 Fuel consumption in road transport in the Czech Republic

Year	Gasoline	Diesel Oil	LPG	CNG	Biodiesel	Bioethanol
	[TJ]	[TJ]	[TJ]	[TJ]	[TJ]	[TJ]
2000	79 849	74 320	2 852	97	2 590	0
2001	81 709	82 490	2 792	97	1 924	0
2002	82 572	89 449	2 838	97	2 701	0
2003	90 190	105 858	2 884	146	2 590	0
2004	89 882	116 052	3 015	146	1 332	0
2005	88 234	134 997	3 104	146	111	0
2006	87 337	144 125	3 298	146	703	54
2007	91 068	152 062	3 527	195	1 258	0
2008	87 711	152 630	3 506	244	3 145	1 458
2009	85 513	148 030	3 243	293	5 698	2 457
2010	77 643	142 052	3 374	343	7 252	2 430
2011	74 631	142 625	3 418	392	10 027	2 538
2012	69 521	144 163	3 767	489	9 176	2 349
2013	65 326	146 325	3 898	736	9 361	2 241
2014	64 672	153 477	4 292	1 032	10 508	2 754
2015	65 189	162 918	4 336	1 528	9 768	2 646
2016	67 188	170 188	4 336	2 076	10 286	2 025
2017	66 436	177 498	4 205	2 320	10 397	2 484
2018	66 485	180 101	4 030	2 615	10 138	2 565
2019	66 462	182 470	3 854	3 106	10 989	3 078
2020	60 390	171 420	3 241	3 157	12 654	2 754
2021	62 791	186 566	3 285	3 205	11 803	2 322
2022	65 626	190 164	3 723	3 174	10 656	2 646
2023	69 660	193 083	3 898	3 226	9 953	2 619
2024	72 810	200 019	3 723	3 262	9 990	3 861

CNG buses have been used from 1994 and CNG PCs from 2006 in the Czech Republic. The steep increase of CNG consumption in 2012 was caused by subsidies from public resources to encourage the use of CNG buses. Other subsidies were determined for CNG LDVs and PCs which were used by local authorities what resulted in steady increase of CNG consumption, and it is continuing to the present. LPG consumption was continuously growing until 2016. After 2016, it began to decrease what was probably caused by low prices of diesel and gasoline, and also thanks to the introduction of new alternative fuels in the last years. Since 2022, LPG consumption has been rising again due to overall fuel consumption rise as well as rising prices of diesel and gasoline.

Emission factors

Emission factors are COPERT based. EFs for CO_2 are on Tier 2 level and for CH_4 and N_2O on Tier 3 level. In general, EFs for all GHGs are composed from hot EFs, cold EFs and they are additionally dependent on vehicle category and driving mode (share of urban, rural, highway driving).

Tab. 3-32 Implied EFs for CO_2 for road transport

Year	Gasoline	Diesel Oil	LPG	CNG	Biomass
	[t/TJ]	[t/TJ]	[t/TJ]	[t/TJ]	[t/TJ]
2010	70.41	73.11	68.95	56.23	74.75
2011	70.27	73.20	68.96	56.25	75.03
2012	70.27	73.24	68.98	56.38	75.01
2013	70.25	73.24	68.98	56.18	75.08
2014	70.05	73.19	68.98	56.09	74.99
2015	69.94	73.27	68.98	55.95	74.95
2016	70.43	73.25	68.98	55.79	75.25
2017	70.10	73.26	68.98	55.86	75.08
2018	70.02	73.28	68.98	55.89	75.02
2019	69.70	73.25	68.98	55.93	74.92
2020	69.72	73.11	68.98	55.89	75.15
2021	70.13	72.80	68.98	55.91	75.25
2022	69.97	72.88	68.98	52.89	75.04
2023	70.10	72.93	68.98	52.58	74.99
2024	69.61	73.12	68.98	52.32	74.57

EFs for CO_2 count with using A/C, SCR, and lubricant consumption. Implied EFs are additionally dependent on calorific value of fuel (kg/TJ) because input data about primary fuel consumption provided by CzSO are only available in 'kt' units. Therefore, the primary fuel consumption must be recalculated to 'TJ' units with the help of the fuel energy content (calorific value) which is updated based on the Czech Oil questionnaire for EEA every year. CO_2 IEF also depends on country-specific H:C and O:C ratios which were calculated based on the laboratory analysis (Černý, 2018). The rest of the parameters (A/C usage, SCR, and lubricant consumption) are influencing how CO_2 production is distributed between fuel combustion and other processes. This is implemented in COPERT methodology which is in line with EMEP/EEA Emission Inventory Guidebook (EIG) 2023. Implied EFs for CO_2 from year 2010 are shown in the Tab. 3-32.

Tab. 3-33 Implied EFs for CH_4 for road transport

Year	Gasoline	Diesel Oil	LPG	CNG	Biomass
	[kg/TJ]	[kg/TJ]	[kg/TJ]	[kg/TJ]	[kg/TJ]
2010	15.87	1.97	10.54	57.43	8.44
2011	15.36	1.77	10.42	52.39	6.89
2012	15.06	1.62	10.30	43.58	6.69
2013	14.84	1.49	10.25	40.85	6.25
2014	14.22	1.32	9.95	36.92	6.23
2015	13.62	1.19	9.90	36.42	6.03
2016	12.87	1.07	9.92	33.03	4.62
2017	12.24	1.03	9.81	33.80	4.97
2018	11.50	0.95	9.67	32.06	4.83
2019	10.54	0.91	9.54	32.39	4.76
2020	10.04	0.92	9.59	21.36	3.94
2021	9.35	0.89	9.68	19.55	3.48
2022	8.88	0.88	9.54	18.60	3.82
2023	8.20	0.88	9.48	18.42	3.71

2024	7.08	1.44	9.25	17.21	4.57

In the Tab. 3-33 and Tab. 3-34, there are shown implied EFs for CH_4 and N_2O for road transport from year 2010.

Tab. 3-34 Implied EFs for N_2O for road transport

Year	Gasoline	Diesel Oil	LPG	CNG	Biomass
	[kg/TJ]	[kg/TJ]	[kg/TJ]	[kg/TJ]	[kg/TJ]
2010	1.91	2.29	2.28	4.11	2.78
2011	1.83	2.44	2.20	3.99	2.86
2012	1.73	2.58	2.07	3.39	2.96
2013	1.64	2.70	1.96	3.24	3.04
2014	1.55	3.91	1.87	3.05	4.11
2015	1.46	4.59	1.78	3.20	4.68
2016	1.37	5.48	1.73	2.86	5.65
2017	1.28	5.82	1.68	2.99	5.82
2018	1.17	5.97	1.60	2.96	5.87
2019	1.04	5.77	1.53	3.09	5.56
2020	0.95	6.03	1.44	2.08	5.99
2021	0.88	5.94	1.36	1.94	5.99
2022	0.84	5.94	1.26	1.86	5.78
2023	0.79	5.70	1.17	1.81	5.48
2024	0.75	5.66	1.08	1.73	5.04

CO_2 emissions



Fig. 3-25 Emissions of CO_2 from road transport according to subcategories

Carbon dioxide emissions were calculated based on the fuel consumption in all COPERT vehicle categories which are relevant in CZ. COPERT separately calculates emissions from hot engines, cold engines, emissions originated from A/C and SCR usage (diesel cars) and emissions originated from lubricant consumption during burning processes. Emissions from lubricants combusted in 2-stroke moped and motorcycle engines are reported within 1.A.3.b.iv subcategory according to 2006 IPCC Guidelines and based on EIG 2023 and COPERT methodology.

A gradually increasing share of transport in total CO_2 emissions in the Czech Republic became evident during the 90´s and this trend continued until 2007. Individual road and freight transport made the greatest contribution to energy consumption in road transport (see Fig. 3-25). It is obvious, according to the methodology of calculation of CO_2 emissions described above, that trend in CO_2 emissions copies trend in fuel consumption (see Fig. 3-26). A decrease in emissions of carbon dioxide from road transport was recorded in 2008 for the first time. In the same year, a downward trend started which continued until 2013

(Jedlička et al., 2014). From 2014 till 2019, emissions from road transport were growing and reached almost 18 500 kt of CO_2 in 2019. The next year, there was a decrease to around 17 000 kt due to COVID situation. It was the first drop in CO_2 emissions after the economic crisis. The emissions jumped back to the value before COVID in 2021 and exceeded 20 000 kt in 2024. The carbon dioxide emissions trend is primarily a result of the changes in the traffic performance by gasoline and diesel cars. According to the Fig. 3-26, the CO_2 emissions from road transport are following the trend of energy consumption. There are no disproportions. Small fluctuations can be caused by the fact that EFs are calculated based on a slightly variable calorific value of a particular fuel. These values are given by CzSO every year. Other factor is that CO_2 emissions are dependent on the ratio of energy consumption of a particular type of fuel.



Fig. 3-26 Comparison of energy consumption and CO_2 emissions from road transport

CH_4 emissions

Methane emissions derived from road transport-related greenhouse gas emissions have being successfully mitigated in Czech Republic. Trend in CH_4 emission production according to subcategories are shown in Fig. 3-27. The annual trend in these emissions is constantly decreasing and is very similar to other hydrocarbon emissions which are limited in accordance with Euro regulations. New vehicles must substantially fulfil higher Euro standards for hydrocarbons than older vehicles (currently the Euro 6 standard for passenger cars and Euro VI for heavy duty vehicles and buses). The greatest problems are associated with a slow renewal of the car fleet. Average age of personal cars was 16.48 years, and average age of trucks was 18.67 years in 2024 (SDA, 2026). Car park renewal in CZ is still in progress and older vehicles are frequently used in the construction and food industries. The potential problem in CH_4 emissions could be growing share of CNG vehicles (especially



Fig. 3-27 Emissions of CH_4 from road transport according to subcategories

buses from 2012). CNG is composed of approx. 98% of CH_4. On the other hand, CNG is beneficial for other GHGs and pollutants.



Fig. 3-28 Comparison of energy consumption and CH_4 emissions from road transport

Fig. 3-28 shows the opposite trend in emission production of CH_4 and energy consumption in road transport The continuous decrease started in 1996 when the Euro 2 / Euro II standard was implemented. The decrease in the following years was intensified by toughening the THC limits by Euro 4 standard in 2005. Another cause of the downward trend is an increasing ratio of diesel passenger cars which produce less CH_4. After economic crisis, energy consumption has been continuously growing since 2014 (except for the year 2020 due to COVID pandemic) but CH_4 emissions have been still decreasing. In 2020, emissions even fell under 1 kt for the first time thanks to car fleet renewal. In 2024, the emissions increased slightly due to overall growth of the energy consumption.

N_2O emissions

Trend in N_2O emissions production according to subcategories is shown in Fig. 3-29. There is a huge drop in emissions after 2000 which was related to catalyst modernization and Euro 3 standard implementation. Similarly to carbon dioxide emissions, the next decrease of nitrous oxide emissions started in 2008 as a consequence of reduced consumption of gasoline and diesel oil due to economic crisis and lower traffic performance. In 2014, N_2O emissions increased significantly. The increase is connected with Euro 6/VI standard implementation, related methodological changes (see chapter 10.1.1.2), and a rapid growth of Euro 6/VI vehicle share on overall traffic performance, especially in the following three years. New vehicles exhibit higher N_2O emissions compared to older models because they are equipped with 3-way catalytic converters which reduce only NO_X emissions. More N_2O emissions are produced as a side effect of NO_x reduction. This is partially suppressed in new vehicles because of a lower fuel consumption. However, the increase of emissions is also fortified by higher fuel consumption which is influenced by the progress in the national economy and by increase in a transport of goods and material. In 2020, there was a slight decrease due to COVID situation, but the emissions jumped back to higher than pre-pandemic values already the next year. The



Fig. 3-29 Emissions of N_2O from road transport according to subcategories

increase of N_2O emissions is being mitigated by modernization of car fleet. However, the modernization is quite slow in the Czech Republic, and the average age of vehicles is still high (see above).



Fig. 3-30 Comparison of energy consumption and N_2O emissions from road transport

In the last years, except for 2020 influenced by COVID, N_2O emissions have been increasing. The main reason is growing share of vehicles with high N_2O emissions as described above. Consequently, N_2O emissions from mobile sources represent higher contribution than CH_4 emissions. The most important source of N_2O emissions from mobile sources are heavy duty vehicles. Fig. 3-30 shows a trend in N_2O emissions from road transport compared to the energy consumption trend. Between years 2009 and 2013, there was more significant decreasing trend in N_2O emissions compared to fuel consumption. This effect could be related to introduction of more advanced emission control technologies.

3.2.17.4Railways (CRT 1.A.3.c)

3.2.17.4.1Methodological issues

The Czech railway sector is undergoing a long-term modernization process aimed at making electricity the primary energy source for rail transport. The total volume of transport declined which was caused by a significant drop in freight transport. In the recent years, the share of electric traction has stayed approximately at the value 86% of total railway traffic volumes.

Railway power stations that generate traction current are allocated to the stationary component of the energy sector (1.A.1.a) and are therefore not discussed further in this text. Apart from electric power, diesel fuel is the only other significant energy source used by trains.

In 2023 submission, new methodology for calculation of railway emissions from diesel oil (Pelikán et al., 2021) was introduced which increased detail and accuracy of calculation from Tier 1 to Tier 2 level as per EIG 2023. Based on the new activity data obtained from Czech Railway Administration (Správa železnic), České dráhy (ČD) and CzSO, national diesel fuel consumption statistics were broken down by locomotive type in order to apply three different sets of emission factors (EIG, 2023). There are three diesel locomotive categories:

- line-haul locomotives,
- shunting locomotives,
- rail-cars.

Calculation of railway emissions from diesel consists of three main steps:

1) Rail traffic performance calculation – Average traffic performance of line-haul locomotives and rail-cars is calculated based on the latest available data from Správa železnic for profile weeks in the given year. In each category, the five most frequent locomotives and their share on rail traffic performance in brtkm is defined. Final value is weighted traffic performance of these locomotives. Shunting locomotive traffic performance is based on the study Perůtka et al., 2020. The latest data for shunting locomotives are available for the year 2022.

2) Calculation of traction diesel consumption – Specific traction diesel consumption is calculated for each locomotive category. Final traction diesel consumption is a product of activity data and specific traction diesel consumption. Based on this value, share of each locomotive category on the total rail diesel fuel consumption given by CzSO is set.
3) EFs application – Tier 2 EFs are applied on final diesel consumption calculated for each category.

Steam locomotives are operated in the Czech Republic as well. However, their contribution to emissions is very small as they only serve as tourist attractions. EFs used for calculation of railway emissions from coal are on Tier 1 level according to 2006 IPCC Guidelines.

Activity data

Activity data about rail traffic performance were obtained from Czech Railway Administration (Správa železnic) and from the major Czech railway operators ČD and ČD Cargo. Data about national fuel consumption were provided by CzSO. Regular railway operation uses diesel oil. Coal is only used within historical rides, and the percentage of its consumption is very small.

In general, diesel consumption by railways has a slightly decreasing trend from 2000. The only exception were years 2005–2008. After this period, the fuel consumption fell to 84 kt in 2015 and then oscillated around 80 kt because of the economic crisis and replacement of diesel-powered locomotives with electric ones. Since 2016, biodiesel has been used as well. Its share on the total railway diesel consumption has been 8% in average. Non-bio diesel consumption dropped under 70 kt in years 2020 and 2021 due to restrictions during COVID pandemic. It increased in the following year but has been decreasing since 2023 because of the decline in rail freight transport.

Coal (lignite) began to be used on Czech railways for historical rides in 2005. From 2014, bituminous coal was used too. Total coal consumption has been decreasing since 2018. The reason is no consumption of lignite from 2018. Both diesel and coal consumption increased in 2022 as the result of general return to pre-pandemic traffic performance and has been around 0.5 kt since then.

Tab. 3-35 Fuel consumption by railways

Year	Non-bio Diesel Oil [kt]	Biodiesel [kt]	Coal [kt]
2000	104.0	0.0	0.0
2001	97.0	0.0	0.0
2002	94.0	0.0	0.0
2003	92.0	0.0	0.0
2004	91.0	0.0	0.0
2005	92.0	0.0	1.0
2006	96.0	0.0	1.0
2007	95.0	0.0	1.0
2008	105.0	0.0	1.0
2009	95.0	0.0	1.0
2010	92.0	0.0	1.0
2011	90.0	0.0	1.0
2012	87.0	0.0	1.0
2013	85.0	0.0	1.0
2014	86.0	0.0	2.0
2015	84.0	0.0	2.0

2016	77.0	8.0	2.0
2017	80.0	7.0	2.0
2018	80.0	6.0	1.0
2019	77.0	5.0	0.5
2020	68.0	5.0	0.3
2021	66.0	6.0	0.4
2022	72.0	6.0	0.5
2023	69.0	4.0	0.4
2024	68.0	5.0	0.5

Emission factors

The emission factors for diesel oil are Tier 2 for all GHGs. CO_2 EF is country-specific, CH_4 and N_2O EFs are applied according to EIG 2023. EFs for coal for CO_2, CH_4 and N_2O are Tier 1. They are based on calorific value of fuel (updated every year as per Czech Oil questionnaire for EEA) and EF [$kg.TJ^{-1}$] stated in 2006 IPCC Guidelines for railways (see Tab. 3-36).

Tab. 3-36 Emission factors for CO_2, CH_4 and N_2O for railways in [$g.kg^{-1}$] of fuel in 2024

Locomotive type	Fuel Type	EF CO_2 [$g.kg^{-1}$]	EF CH_4 [$g.kg^{-1}$]	EF N_2O [$g.kg^{-1}$]
Line-haul	Diesel Oil	3 146	0.182	0.024
Shunting	Diesel Oil	3 146	0.176	0.024
Rail-cars	Diesel Oil	3 146	0.179	0.024
Steam	Coal	2 553	0.053	0.040

Emissions



Fig. 3-31 Trend in emissions of CO_2, CH_4 and N_2O from railways

Emissions from railways are strongly dependent on fuel consumption due to the methodology. GHG emissions are given in the Fig. 3-31. The sharpest decrease in emissions was happening until 1994. This was related to the decrease of freight transport because of significantly lower coal mining intensity compared to period before 1989. Next factor was electrification of core network and modernization of rolling stock during these years. In the following years, GHG emissions were slightly decreasing except for period 2005–2008 when an increase connected with economic growth was recorded. After 2008, the emissions were decreasing again due to economic crisis. Since 2014, GHG emissions were fluctuating depending on traffic performance in the particular year. In 2020 and 2021, they dropped to approx. 210 kt due to COVID pandemic. In 2022, GHG emissions from diesel oil rose to 227 kt and from coal to 1.3 kt what was related to post-pandemic traffic performance increase. However, they dropped already the next year and continued to decrease in 2024. Emissions from burning coal have been produced by usage for historical rides since 2005 but they have only minor share (1%) on overall railway emissions.

3.2.17.5 Domestic Navigation (CRT 1.A.3.d)

3.2.17.5.1 Methodological issues

Primary data on fuels available in CzSO or in other statistics do not allow a proper differentiation into national and international navigation on inland waterways in the Czech Republic. Due to this fact and also because share of the international navigation is very low, all activity data are allocated to CRT 1.A.3.d Domestic Navigation.

CzSO only provides data about diesel oil fuel consumption in domestic navigation. There is no national source on petrol consumption data in the required detail and structure, therefore only emissions produced from vessels with diesel engines are calculated. Electric vessels are also not considered as the emissions are generated during electricity production, so they are to be reported within stationary sources, similarly as in rail transport.

In 2025 submission, a new methodology for calculation of emissions from domestic navigation (Kačmárová and Pelikán, 2024) was applied. This allowed to increase detail and accuracy from Tier 1 to Tier 2 level for CO_2 and other pollutants. Based on the new data about installed engine power obtained from Czech State Navigation Administration (SPS), the fleet was divided into three categories in accordance with Tier 2 technology specific approach as per EIG 2023:

- vessels with slow-speed diesel engines,
- vessels with high-speed diesel engines (small and recreational boats),
- vessels with steam turbines.

Activity data

Total fuel consumption by domestic navigation is very low (see Tab. 3-37). The CzSO have been providing data about diesel oil consumption since 1997. The data before 1997 are based on the CzSO expert judgement.

Tab. 3-37 Fuel consumption by domestic navigation

Diesel Oil [kt]			
2000	*5*	***2012***	*5*
2001	*8*	***2013***	*2*
2002	*4*	***2014***	*3*
2003	*4*	***2015***	*3*
2004	*6*	***2016***	*4*
2005	*5*	***2017***	*4*
2006	*6*	***2018***	*3*
2007	*5*	***2019***	*5*
2008	*4*	***2020***	*4*
2009	*5*	***2021***	*4*
2010	*4*	***2022***	*3*
2011	*3*	***2023***	*4*
		2024	*3*

The total diesel oil consumption is divided into the above-mentioned vessel categories based on their percentual share on the total installed engine power. Emissions are calculated with the help of emission factors for each category (see below).

Emission factors

CO_2 emission factor for inland navigation vessels as well as for small and recreational boats is on Tier 2 level. This EF is country specific as country-specific H:C and O:C ratios were applied.

CH_4 and N_2O are on Tier 1 level. Neither the 2006 IPCC Guidelines nor EIG 2023 provides specific N_2O and CH_4 EFs for inland navigation. The Tier 1 default CH_4 and N_2O emission factors from the 2006 IPCC Guidelines actually apply to diesel engines using heavy fuel oil. Since no emission factors are provided for diesel engines using diesel oil (and no other relevant source is available), the default emission factors for heavy fuel oil are used for diesel oil too. EFs in g/kg further depend on fuel calorific value which is updated every year based on Czech Oil Questionnaire for EEA.

Tab. 3-38 Emission factors of CO_2, CH_4 and N_2O for domestic navigation in [g.kg^{-1}] of fuel in 2024

Subsector	Fuel Type	EF CO_2	EF CH_4	EF N_2O
		[g.kg^{-1}]	[g.kg^{-1}]	[g.kg^{-1}]
Domestic Navigation	Diesel Oil	3 146	0.301	0.086

Note: In case of GHGs, EFs are the same for each vessel category.

Emissions

Emissions from domestic navigation are strongly dependent on fuel consumption. Values are quite fluctuating because of irregularities in traffic performance on Czech inland waterways. Overall GHG emissions are given in the Fig. 3-32.



Fig. 3-32 Trend in emissions of CO_2, CH_4 and N_2O from domestic navigation

3.2.17.6Other Transport (CRT 1.A.3.e)

The consumption of Natural Gas to power compressors for transit gas pipelines is included in this subcategory under mobile combustion sources but it is actually a stationary combustion source. This consumption is reported in the IEA – CzSO (CzSO, 2022) Questionnaire in the Transport Sector section under the item:

Pipeline Transport

There are embodied the fuels of economic part according to NACE Rev. 2 Pipeline Transport: NACE Divisions 35.22, 49.50.

3.2.17.7 Uncertainties in Transport (CRT 1.A.3.)

Uncertainties were calculated in compliance with chapter A.5 'Uncertainties' of EIG 2023. The uncertainties were evaluated for the entire time series (1990–2024) and for all reported categories (see Annex 2). Uncertainties of national GHG emissions within transport sector are given in Tab. 3-39.

Tab. 3-39 Uncertainty data for transport from uncertainty analysis

IPCC Source Category	GHG	Base Year Emissions (1990)	Year 2024 Emissions	Contribution to Variance by Category in Year 2024
		[kt]	[kt]	[%]
1A3 Transport	CO_2	11 742	22 727	0.78
	CH_4	90.16	28.15	32.36
	N_2O	107.27	345.58	58.63

3.2.17.8 Source-specific QA/QC and verification

QC carried out in the Transport Research Centre (CDV) is based on routine and consistent checks to ensure data integrity, correctness, and completeness to identify and address errors. Documentation and archiving of all QC activities is carried out. QC activities include methods such as accuracy checks on data acquisition and calculations, and the use of approved standardised procedures for emission calculations, measurements, estimating uncertainties, archiving information and reporting. QC activities also include technical reviews of categories, activity data, emission factors, other estimated parameters and methods. QA and verification of activity data is guaranteed in the CDV by comparing activity data with world and European databases and third person checks.

An inventory compiler is responsible for coordinating the institutional and procedural arrangements of inventory activities. These cover data collection from the CzSO, deciding of usage of emissions factors (according to CS or EIG) and estimation of emissions from mobile sources. The uncertainty assessment is carried out by the inventory compiler too. The last step is a documentation and archiving of data. The inventory compiler designs responsibilities for implementation QA/QC procedures among persons not directly involved in the compilation of inventory and among organizations.

A QA/QC plan is a fundamental element of a QA/QC and verification system. The plan of QA/QC procedures in the CDV is based on the inner quality control procedure system, which is harmonised with the QA/QC system of Czech Hydrometeorological Institute (CHMI). Since the transport sector belongs to the energy sector, there has been a close cooperation between CDV and CHMI in the field of energy and fuel consumption data as well as specific energy data used in calculations in units [$MJ.kg^{-1}$] of fuel. The CHMI in close cooperation with CzSO ensure that the Transport Research Centre works with the most updated data about total energy and specific energy consumed.

3.2.17.8.1 QA/QC activities

QC Activities:

- Checking criteria for the selection of activity data, emission factors and other estimated parameters are documented.
- Checking that emissions and removals are calculated correctly.
- Checking that parameters and units are correctly recorded and that appropriate conversion factors are used.
- Checking the integrity of database files.
- Checking for consistency in data between categories.
- Checking that the movement of inventory data among processing steps is correct.
- Checking that uncertainties in emissions and removals are estimated and calculated correctly.
- Checking time series consistency.

QA Activities:

- Checking completeness (confirming that estimates are reported for all categories, all years, all subcategories and confirm that entire category of mobile sources is being covered).
- Trend checks (checking value of implied emission factors and unusual, unexplained trends noticed for activity data or other parameters across the time series).
- Checking of internal documentation and archiving.

3.2.17.8.2 Responsibilities in CDV

The sectoral guarantor of QA/QC procedures for mobile sources:

- is responsible for the sectoral QA/QC plan and the compliance of all QA/QC procedures,
- provides plan for the QC procedure and is responsible for its implementation.

Inventory compiler of inventory from mobile sources:

- performs the emission calculations from transport in the emission model,
- provides for data import in the CRT table,
- is responsible for storing of documents,
- carries out auto-control and control of data consistency,
- performs the uncertainty calculation,
- introduces improvements.

The third person check (Jiri Dufek, MOTRAN RESEARCH, s. r. o.)

- detailed control of timeliness, completeness, consistency, comparability and transparency.

The sectoral guarantor of QA/QC procedures for Agricultural and Forestry non-road mobile sources:

- Martin Dědina (Research Institute of Agricultural Technology)

3.2.17.8.3 QA/QC procedure in CDV

During every submission, in the beginning of summer, the inventory compiler first receives preliminary activity data from CzSO and makes first calculations which are compared with previous years regarding to a trend in data from last years. If there are some discrepancies, activity data will be consulted with CzSO and inaccuracies will be corrected. During autumn, CzSO provides final activity data. Then final calculations are made. Also, the QC is made by the inventory compiler, afterwards by a person responsible for

compilation of Transport yearbook in CDV and Jiri Dufek from MOTRAN RESEARCH. Every error is described, documented and saved. The next quality control is made by an expert in CHMI. Last step of QC are European reviews. The QA is made on activity data by comparing it with databases like Eurostat and IEA. Main discrepancies are consulted with CzSO and explained during reviews. Emission estimates are prepared for a submission until 5 February and send to an inventory coordinator. The Stage 1 review questions are processed during the second half of March. The Stage 2 review questions are processed during May and June.

3.2.17.9 Category-specific recalculations

All recalculations and improvements are described in chapter 10.1.1.1. In this chapter, there are only mentioned changes due to review process and improvement plan and also improvements planned in the future.

3.2.17.9.1 Source-specific recalculations, including changes made in response to the review process and impact on emission trend

NA

3.2.17.9.2 Source-specific planned improvements, including tracking of those identified in the review process

No major updates planned currently.

3.2.18 Other Sectors – Commercial/Institutional (1.A.4.a)

3.2.18.1 Category description (CRT 1.A.4.a)

The structure of fuels, their consumption, used emission factors and emissions of individual greenhouse gases are shown in the following outline.

1.A.4.a, 2024								
Structure of Fuels	Activity	CO_2			CH_4		N_2O	
	data	EF	OxF	Emission	EF	Emission	EF	Emission
	[TJ]	[t CO_2/TJ]		[kt]	[kg CH_4/TJ]	[kt]	[kg N_2O/TJ]	[kt]
LPG	459.45	65.86*)	1	30.26	5	0.00230	0.1	0.00005
Other kerosene	85.60	71.90	1	6.15	10	0.00086	0.6	0.00005
Heating and Other Gasoil	42.60	77.40	1	3.16	10	0.00043	0.6	0.00003
Fuel Oil - Low Sulphur	39.50	77.40	1	3.06	10	0.00040	0.6	0.00002
Fuel Oil - High Sulphur	197.50	77.40	1	15.29	10	0.00198	0.6	0.00012
Other Bituminous Coal	16.39	94.06*)	0.9707*)	1.50	10	0.00016	1.5	0.00002
Brown Coal + Lignite	351.29	97.95*)	0.9846*)	33.88	10	0.00351	1.5	0.00053
Coke	6.61	107.00	1	0.71	10	0.00007	1.5	0.00001
Brown Coal Briquets	38.81	97.50	0.9846*)	3.73	10	0.00039	1.5	0.00006
Natural Gas	38 617.11	56.08*)	1	2 165.84	5	0.19309	0.1	0.00386
Wood/Wood Waste	424.69	112.00	1	47.57	300	0.12741	4	0.00170
Gaseous Biomass	862.08	54.60	1	47.07	5	0.00431	0.1	0.00009
Total year 2024	**39 854.86**			**2 263.56**		**0.33488**		**0.00653**
Total year 2023	36 079.81			2 049.43		0.32407		0.00635
Index 2024/2023	1.10			1.10		1.03		1.03
Total year 1990	119 864.09			9 907.15		1.00085		0.10113
Index 2024/1990	0.33			0.23		0.33		0.06

*) *Country specific data*

The origin of the data, the emission factors used and the method of calculating the level of emissions for the individual gases are shown in details in the following outline.

2024							
Structure of Fuels	Source of Activity data	Emission factors			Method used		
		CO_2	CH_4	N_2O	CO_2	CH_4	N_2O
LPG	CzSO	CS	D	D	Tier 2	Tier 1	Tier 1
Other kerosene	CzSO	D	D	D	Tier 1	Tier 1	Tier 1
Heating anf Other Gasoil	CzSO	D	D	D	Tier 1	Tier 1	Tier 1
Fuel Oil - Low Sulphur	CzSO	D	D	D	Tier 1	Tier 1	Tier 1
Fuel Oil - High Sulphur	CzSO	D	D	D	Tier 1	Tier 1	Tier 1
Other Bituminous Coal	CzSO	CS	D	D	Tier 2	Tier 1	Tier 1
Brown Coal + Lignite	CzSO	CS	D	D	Tier 2	Tier 1	Tier 1
Coke	CzSO	D	D	D	Tier 1	Tier 1	Tier 1
Brown Coal Briquets	CzSO	D	D	D	Tier 1	Tier 1	Tier 1
Natural Gas	CzSO	CS	D	D	Tier 2	Tier 1	Tier 1
Wood/Wood waste	CzSO	D	D	D	Tier 1	Tier 1	Tier 1
Gaseous Biomass	CzSO	D	D	D	Tier 1	Tier 1	Tier 1

The whole category 1.A.4 includes emissions which are not included in the 1.A.1 and 1.A.2 categories. They can be generally defined as heat production processes for internal consumption.



Fig. 3-33 Development of CO_2 emissions in source category 1.A.4.a

The main driving force for CO_2 emissions in category 1.A.4 is energy consumption for purposes of space heating. The fluctuations in consumption then can be ascribed to differences in cold winter periods. The trend of decreasing CO_2 emissions is a result of higher standards for new buildings and of successful execution of energy-efficiency-oriented modernisations of existing buildings. The trend has also been supported by shifting to fuels with lower CO_2 emissions (emission factors). The importance of Solid Fuels at the beginning of the period constantly decreases in time. On the other hand, the consumption of Natural Gas increased during the period as well as Biomass consumption. Liquid Fuels play a minor role in this category.

CO_2 emissions produced in category 1.A.4.a represent in 2024 27% of whole 1.A.4, which is 3% of CO_2 emissions from the Energy sector 1.A.

The 1.A.4.a subcategory includes all combustion sources that utilize heat combustion for heating production halls and operational buildings in institutions, commercial facilities, services and trade.

In the CzSO Questionnaire (CzSO, 2025), the consumption of the individual kinds of fuels in this sector is reported in capture Other sectors under the item:

- Commercial and Public Services
- Non-specified (Other)

Last point is included under 1.A.4.a Commercial/Institutional on the basis of an agreement with CzSO. There are embodied the fuels of economic part according to NACE Rev. 2 Commercial/Institutional: NACE Divisions 35 excluding 1.A.1.a and 1.A.3.e, 36 – 39, 45 – 99 excluding 1.A.3.e and 1.A.5.a.

Fig. 3-33 shows that at the beginning of the period in the subsector 1.A.4.a predominated the consumption of fossil fuels, which was coupled with liquid fuels, and gradually substituted primarily with natural gas. The share of biofuels in this subsector is a minority. The overall decrease in fuel consumption is about 66%, which resulted in a decrease in CO_2 emissions by about 77%. Higher decrease in emissions than the one in the fuel consumption is determined by the changes in the structure of fuels in favour of natural gas. Estimates of CO_2, CH_4 and N_2O emissions from gaseous fuels for 1992–1994 in the subcategory 1.A.4.a were revised using interpolation as is described in 2006 IPCC Guidelines (vol. 1, chap. 5, section 5.3.3).

3.2.18.2 Methodological issues (CRT 1.A.4.a)

During processing data for the subsector 1.A.4.a among the used fuels are also included fuels, which are in the questionnaires of CzSO, listed in section "Transport sector". The amount of these fossil fuels is given in Tab. 3-40 in TJ.

Tab. 3-40 Quantities of fuels used in the sector transport in stationary sources

Year	2005	2006	2007	2008	2009	2010	2011	2012
TJ/year	12.7	35.2	33.7	35.9	12.4	12.5	12.1	12.2
Year	2013	2014	2015	2016	2017	2018	2019	2020
TJ/year	12.0	40.2	38.9	36.9	38.7	27.5	13.2	8.3
Year	2021	2022	2023	2024				
TJ/year	11.0	13.2	10.7	13.3				

According to the communication to CzSO, this is a fuel for heating the buildings of the state-owned company Czech Railways and that is why its combustion was situated in the subsector 1.A.4.a. This is the consumption of bituminous coal and lignite worth 1-2 kt per year. The amount of these fuels in the total balance of 1.A.4.a virtually has no effect.

No other sector-specific methodological issues are applied, the general issues are given in chapter 3.2.4.

3.2.18.3 Uncertainties and time-series consistency (CRT 1.A.4.a)

See chapter 3.2.5.

3.2.18.4 Category-specific QA/QC and verification (CRT 1.A.4.a)

See chapter 3.2.6.

3.2.18.5 Category-specific recalculations (CRT 1.A.4.a)

Due to the minor changes in GCV of Natural Gas (CzSO, 2025), Gaseous fuels were recalculated for the years 2010-2023. The highest difference was -0.11 % in CO_2 emission in 2016; all other changes were at the second decinal place or smaller, therefore these changes are not shown in specific table.

3.2.18.6 Category-specific planned improvements (CRT 1.A.4.a)

Currently there are no planned improvements in this category.

3.2.19 Other Sectors – Residential (1.A.4.b)

3.2.19.1 Category description (CRT 1.A.4.b)

The structure of fuels, their consumption, used emission factors and emissions of individual greenhouse gases are shown in the following outline.

1.A.4.b, 2024								
Structure of Fuels	Activity	CO_2			CH_4		N_2O	
	data	EF	OxF	Emission	EF	Emission	EF	Emission
	[TJ]	[t CO_2/TJ]		[kt]	[kg CH_4/TJ]	[kt]	[kg N_2O/TJ]	[kt]
LPG	2 389.17	65.86*)	1	157.34	5	0.0119	0.1	0.0002
Other Bituminous Coal	1 592.96	94.06*)	0.9707*)	145.49	300	0.4779	1.5	0.0024
Brown Coal + Lignite	12 281.11	97.95*)	0.9846*)	1165.78	300	3.6843	1.5	0.0184
Coke	169.00	107.00	1	18.08	300	0.0507	1.5	0.0003
Brown Coal Briquets	1 640.38	97.50	0.9846*)	157.47	300	0.4921	1.5	0.0025
Natural Gas	61 328.04	56.08*)	1	3439.58	5	0.3066	0.1	0.0061
Wood/Wood Waste	75 505.56	112.00	1	8456.62	300	22.6517	4	0.3020
Charcoal	402.56	112.00	1	45.09	200	0.0805	1	0.0004
Total year 2024	**79 400.65**			**5 083.75**		**27.7558**		**0.3323**
Total year 2023	85 395.51			5 602.71		30.7503		0.3598
Index 2024/2023	0.93			0.91		0.9026		0.92
Total year 1990	208 699.35			18 374.86		60.6196		0.4149
Index 2024/1990	0.38			0.28		0.4579		0.80

*) *Country specific data*

The origin of the data, the emission factors used and the method of calculating the level of emissions for the individual gases are shown in details in the following outline.

2024							
Structure of Fuels	Source for	Emission factors			Method used		
	Activity data	CO_2	CH_4	N_2O	CO_2	CH_4	N_2O
LPG	CzSO	CS	D	D	Tier 2	Tier 1	Tier 1
Other Bituminous Coal	CzSO	CS	D	D	Tier 2	Tier 1	Tier 1
Brown Coal + Lignite	CzSO	CS	D	D	Tier 2	Tier 1	Tier 1
Coke	CzSO	D	D	D	Tier 1	Tier 1	Tier 1
Brown Coal Briquets	CzSO	D	D	D	Tier 1	Tier 1	Tier 1
Natural Gas	CzSO	CS	D	D	Tier 2	Tier 1	Tier 1
Wood/Wood Waste	CzSO	D	D	D	Tier 1	Tier 1	Tier 1
Charcoal	FAOSTAT	D	D	D	Tier 1	Tier 1	Tier 1

Fuel consumption in households is determined on the basis of the results of the statistical study “Energy consumption in households”, published in 1997 and 2004 by the Czech Statistical Office according to the PHARE/EUROSTAT method.

In the CzSO Questionnaire (CzSO, 2025), the consumption of the individual kinds of fuels in this sector is reported in capture Other Sector under the item: Residential

The fraction of CO_2 emissions in subsector 1.A.4.b in CO_2 emissions in sector 1.A.4 equalled 60% in 2023. It contributed 7% to CO_2 emissions in the whole Energy sector 1.A.



Fig. 3-34 Development of CO_2 emissions in source category 1.A.4.b

At the beginning of the period, a majority of households in the Czech Republic used coal as a heating fuel (mainly brown coal + lignite). This habit has changed over time and Natural Gas began to be used more than Solid Fuels. However, since 2022, Natural Gas consumption has declined due to the market changes. The same trend appears in the institutional sphere. The number of households using biomass for heating (biomass boilers) in the Czech Republic has increased in the last few years, this trend has slowed down after 2021, see the Fig. 3-34.

The graph shows that at the beginning of the period in the subsector 1.A.4.b dominated consumption of fossil fuels, which have been gradually substituted primarily by natural gas, but also biofuels (in the case of households, it is mainly firewood). The share of liquid fuels (LPG) is negligible. Small annual fluctuations in fuel consumption are to be attributed to the average annual temperatures. Throughout the sector Residential, a slight decrease can be observed in fuel consumption, which was affected by the replacement of old boilers with more modern with higher efficiency and most importantly building insulations, which is controlled by the national programs "Green Savings". Increasing share of biomass has a positive effect on reducing CO_2 emissions, which are included in total greenhouse gas emissions. The total fuel consumption declines in this subsector about 38%, CO_2 emissions from the combustion of fossil fuels decreased by about 72%.

3.2.19.2 Methodological issues (CRT 1.A.4.b)

No specific methodological approaches were applied - general approaches are given in section 3.2.4.

3.2.19.3 Uncertainties and time-series consistency (CRT 1.A.4.b)

See chapter 3.2.5.

3.2.19.4 Category-specific QA/QC and verification (CRT 1.A.4.b)

See chapter 3.2.6.

3.2.19.5 Category-specific recalculations (CRT 1.A.4.b)

Based on changes of activity data in CzSO, 2025, fuel consumptions of Biomass for the years 2023 were recalculated. See the differences in the Tab. 3-41. Due to the minor changes in GCV of Natural Gas (CzSO, 2025), Gaseous fuels were recalculated for the years 2010-2023. The highest difference was -0.11 % in CO_2 emission in 2016; all other changes were on the second decimal places or smaller, therefore these changes are not shown in specific table.

Tab. 3-41 Changes after recalculation in 1.A.4.b for Biomass

Fuel consumption		2023	CH_4 emission		2023
Submission 2025	TJ	80 916.59	Submission 2025	kt	24.2330
Submission 2026	TJ	80 918.72	Submission 2026	kt	24.2334
Difference	TJ	2.1312	Difference	kt	0.0004
Submission 2026	%	0.0026	Submission 2026	%	0.0018

CO_2 emission		2023	N_2O emission		2023
Submission 2025	kt	9 062.6577	Submission 2025	kt	0.3224
Submission 2026	kt	9 062.8964	Submission 2026	kt	0.3224
Difference	kt	0.2387	Difference	kt	0.0000
Submission 2026	%	0.0026	Submission 2026	%	0.0007

3.2.19.6Category-specific planned improvements (CRT 1.A.4.b)

Currently there are no planned improvements in this category.

3.2.20 Other Sectors – Agriculture/Forestry/Fishing (1.A.4.c)

The subsector is further divided into:

- Stationary sources – 1.A.4.c.i
- Off-road Vehicles and Other Machinery – 1.A.4.c.ii

The structure of the fuels throughout the subsector 1.A.4.c, their consumption, used emission factors and emissions of individual greenhouse gases are shown in the following outline.

1.A.4.c, 2024								
Structure of Fuels	Activity	CO_2			CH_4		N_2O	
	data	EF	OxF	Emission	EF	Emission	EF	Emission
	[TJ]	[t CO_2/TJ]		[kt]	[kg CH_4/TJ]	[kt]	[kg N_2O/TJ]	[kt]
LPG	367.56	65.86*)	1	24.21	5	0.00184	0.10	0.00004
Gasoline	670.77	59.95*)	1	40.21	14.17*)	0.00950	0.77*)	0.00052
Diesel Oil	13 555.71	73.12*)	1	991.13	0.44*)	0.00598	10.55*)	0.14301
Fuel Oil - Low Sulphur	39.50	77.40	1	3.06	10	0.00040	0.60	0.00002
Fuel Oil - High Sulphur	197.50	77.40	1	15.29	10	0.00198	0.60	0.00012
Other Bituminous Coal	18.74	94.06*)	0.9707*)	1.71	300	0.00562	1.50	0.00003
Brown Coal + Lignite	188.08	97.95*)	0.9846*)	18.14	300	0.05643	1.50	0.00028
Coke	6.06	107.00	1	0.65	300	0.00182	1.50	0.00001
Brown Coal Briquets	2.37	97.50	0.9846*)	0.23	300	0.00071	1.50	0.00000
Natural Gas	1 753.06	56.08*)	1	98.32	5	0.00877	0.10	0.00018
Wood/Wood Waste	376.94	112.00	1	42.22	300	0.11308	4.00	0.00151
Gaseous Biomass	5 210.81	54.60	1	284.51	5	0.02605	0.10	0.00052
Total year 2024	**16 799.36**			**1 192.94**		**0.23217**		**0.14624**
Total year 2023	16 382.54			1 166.57		0.23578		0.14772
Index 2024/2023	1.03			1.02		0.98		0.99
Total year 1990	46 022.87			3 671.66		5.47293		0.07847
Index 2024/1990	0.37			0.32		0.04		1.86

*) *Country specific data*

The high emission of CH_4 in 1990 is mainly due to the high consumption of other bituminous coal and lignite in the early periods that have high emission factors (300 kg CH_4/TJ) compared to other fuels. At the end of the period there was a significant decrease in the consumption of solid fossil fuels.

The origin of the data, the emission factors used and the method of calculating the level of emissions for each gas is detailed in the following outline.

2024							
Structure of Fuels	Source for	Emission factors			Method used		
	Activity data	CO_2	CH_4	N_2O	CO_2	CH_4	N_2O
LPG	CzSO	CS	D	D	Tier 2	Tier 1	Tier 1
Gasoline	CzSO	CS	CS	CS	Tier 2	Tier 2	Tier 2
Diesel Oil	CzSO	CS	CS	CS	Tier 2	Tier 2	Tier 2

Fuel Oil - Low Sulphur	CzSO	D	D	D	Tier 1	Tier 1	Tier 1
Fuel Oil - High Sulphur	CzSO	D	D	D	Tier 1	Tier 1	Tier 1
Other Bituminous Coal	CzSO	CS	D	D	Tier 2	Tier 1	Tier 1
Brown Coal + Lignite	CzSO	CS	D	D	Tier 2	Tier 1	Tier 1
Coke	CzSO	D	D	D	Tier 1	Tier 1	Tier 1
Brown Coal Briquets	CzSO	D	D	D	Tier 1	Tier 1	Tier 1
Natural Gas	CzSO	CS	D	D	Tier 2	Tier 1	Tier 1
Wood/Wood Waste	CzSO	D	D	D	Tier 1	Tier 1	Tier 1
Gaseous Biomass	CzSO	D	D	D	Tier 1	Tier 1	Tier 1

This subcategory includes both combustion at stationary sources for heating buildings, breeding and cultivation halls and other operational facilities. These are areas from the agriculture (crop and livestock production), forest and fishing. In rural areas is also about the very energy-intensive operations, such as greenhouses, drying grain and hops.

In accordance with the IPCC 2006 Gl., data on fuel consumption and emission data are divided into two subcategories, as mentioned above. In rural areas is mainly about fuel consumption for land cultivation and harvesting mechanisms, in forestry are mainly mining mechanisms. The fishing area has minor importance in the Czech Republic and is concentrated almost exclusively on fish farming.

In the CzSO Questionnaire (CzSO, 2025), the consumption of the individual kinds of fuels in this sector is reported in capture Industry Sector under the item:



Fig. 3-35 Development of CO_2 emissions in source category 1.A.4.c

- Agriculture/Forestry
- Fishing

The distribution of fuels is done according to their nature - motor fuels are allocated to the subcategory 1.A.4.c.ii, all other fuels -into subcategory 1.A.4.c.i. This division is subsequently agreed annually with the CzSO during mutual consultation.

There are embodied the fuels of economic part according to NACE Rev. 2 Agriculture/Forestry/Fisheries: NACE Divisions 01 – 03.



Fig. 3-36 Development of CO_2 emissions in source category 1.A.4.c.i

The fraction of CO_2 emissions in subsector 1.A.4.c in CO_2 emissions in sector 1.A.4 equalled 14% in 2024. It contributed 2% to CO_2 emissions in the whole Energy sector.

Development of fuel consumption and the corresponding CO_2 emissions throughout the subcategory 1.A.4.c are visible on Fig. 3-35.

From the graph on Fig. 3-35 is evident, that the stake in the entire subsector and in the overall period is for the liquid fuel (as it will be shown later, it is mainly about propellant fuel). At the beginning of the period a significant share is for the fossil fuels, but

their consumption during the entire period declines due to the cancelation of the inefficient ways of heating of buildings and process plants. Biofuels are increasingly used until the end of the period.



Fig. 3-37 Development of CO_2 emissions in source category 1.A.4.c.ii

In chart on Fig. 3-36 is shown the fuel consumption and the corresponding CO_2 emissions of only stationary sources and in the following graph (Fig. 3-37) are represented the consumption of fuels and the corresponding CO_2 emissions in off-road transportation and other mechanisms in the agriculture, forestry and fisheries.

In the stationary sources decreased decisively consumption of fossil solid and liquid fuels. The role of natural gas throughout the period was virtually stable and at the end of the period is evident an increased use of biofuels, especially biogas, produced in the biogas stations, built on individual agricultural farms.

To the mobile sources and other mechanisms are to a large extent attributed the consumption of diesel fuels, motor gasoline has minor importance, other fuels are virtually absent. During the period, a noticeable decrease in fuel consumption roughly in the first half of the period is observed, which was caused by higher technical level of engines and especially a decline in demand in all subsectors for agricultural products.

3.2.20.1 Methodological issues (CRT 1.A.4.c)

The basic requirement for processing fuel consumption from mobile sources is their division between subsectors 1.A.3 Transport, 1.A.4.c.ii Off-road vehicles and other machinery and 1.A.5 Other. This distribution is done in coordination with CDV. The aim is that no fuel is included in the balance twice, nor that any fuel is omitted. Therefore, the following distribution is performed:

Motor fuels, which are consumed in the subsector 1.A.4.c.ii are used only for off-road vehicles and other mechanisms.

Motor fuels, which are consumed in the subsector 1.A.5 are allocated to 1.A.3. This is the fuel consumption of the army (transport on and off road, kerosene jet fuel consumption for air transport), and consumption in the fields of construction, extraction of fuels and minerals, industry (only areal transport). Furthermore, the consumption of motor fuels for mobile sources in the public sector (ambulance, fire brigade, etc.), both on and off roads as well as the consumption of aviation fuel are included here.

Based on our improvements CO_2, CH_4 and N_2O emission for the categories 1.A.4.c.ii were recalculated. This need arised because the emission factors have not been updated for many years, resulting in inaccurate emission reporting. The aim was to unify the emission factors with those applied in category 1.A.3 for the same type of fuels. Therefore, the emission factors were taken over from 1.A.3 and use in 1.A.4.c.ii subcategory. More details for emission factors are described in chapter 1.A.3.

3.2.20.2 Uncertainties and time-series consistency (CRT 1.A.4.c)

See chapter 3.2.5.

3.2.20.3 Category-specific QA/QC and verification (CRT 1.A.4.c)

QA/QC procedures in this subsector must be coordinated with CDV. KONEKO, as the company responsible for processing the entire sector 1.A, performs before each submission distribution of motor fuels between the various subsectors 1.A.3, 1.A.5 and 1.A.4.c.ii. Simultaneously, after processing the data part of the submission, checks whether the predetermined distribution of fuel was properly applied and if it is necessary proposes corrections in order to avoid double counting of fuels, or their omission.

Other QA/QC and verification - see section 3.2.6.

3.2.20.4 Category-specific recalculations (CRT 1.A.4.c)

Based on changes of emission factors CO_2, CH_4, N_2O, emissions of Gasoline were recalculated for the years 2010–2023, see the Tab. 3-42. Due to the changes of emission factors CO_2, CH_4, N_2O, emissions of Diessel Oil were recalculated for the years 2010–2023, see the Tab. 3-43. Due to the minor changes in GCV of Natural Gas (CzSO, 2025), Gaseous fuels were recalculated for the years 2010-2023. The highest difference was -0.11 % in CO_2 emission in 2016; all other changes were on the second decimal places or smaller, therefore these changes are not shown in specific table.

Tab. 3-42 Changes after recalculation in 1.A.4.c.ii for Gasoline

CO_2 emissions		2010	2011	2012	2013	2014	2015	2016	2017	2018	2019	2020	2021	2022	2023
Submission 2025	kt	18.634	18.605	18.590	18.591	21.667	18.567	19.614	17.897	18.547	24.662	21.329	21.546	21.656	21.587
Submission 2026	kt	18.619	18.597	18.571	18.576	21.625	18.512	19.536	17.805	18.433	24.580	21.207	21.199	21.017	20.958
Difference	kt	-0.015	-0.008	-0.019	-0.015	-0.043	-0.055	-0.079	-0.091	-0.114	-0.082	-0.122	-0.348	-0.640	-0.629
Submission 2026	%	-0.083	-0.044	-0.101	-0.083	-0.197	-0.296	-0.401	-0.511	-0.614	-0.331	-0.573	-1.614	-2.953	-2.913
CH_4 emissions		2010	2011	2012	2013	2014	2015	2016	2017	2018	2019	2020	2021	2022	2023
Submission 2025	kt	0.004	0.004	0.004	0.004	0.005	0.004	0.004	0.004	0.004	0.005	0.005	0.005	0.005	0.005
Submission 2026	kt	0.004	0.004	0.004	0.004	0.005	0.004	0.004	0.004	0.004	0.005	0.005	0.005	0.005	0.005
Difference	kt	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000
Submission 2026	%	-0.083	-0.044	-0.101	-0.083	-0.197	-0.296	-0.401	-0.511	-0.614	-0.331	-0.573	-1.614	-2.955	-2.915
N_2O emissions		2010	2011	2012	2013	2014	2015	2016	2017	2018	2019	2020	2021	2022	2023
Submission 2025	kt	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000
Submission 2026	kt	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000
Difference	kt	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000
Submission 2026	%	-0.083	-0.044	-0.101	-0.083	-0.197	-0.296	-0.401	-0.511	-0.614	-0.331	-0.573	-1.614	-2.955	-3.385

Tab. 3-43 Changes after recalculation in 1.A.4.c.ii for Diesel Oil

CO_2 emissions		2010	2011	2012	2013	2014	2015	2016	2017	2018	2019	2020	2021	2022	2023
Submission 2025	kt	998.17	1 006.52	1 015.44	1 015.53	1 019.40	1 005.54	1 003.74	994.36	1 014.89	1 028.15	1 010.93	1 002.39	1 007.77	997.45
Submission 2026	kt	984.84	994.28	1 003.71	1 003.71	1 006.86	994.28	992.18	983.09	1 003.71	1 016.30	997.42	984.84	991.13	981.69
Difference	kt	-13.33	-12.24	-11.72	-11.82	-12.54	-11.26	-11.56	-11.27	-11.18	-11.85	-13.50	-17.56	-16.64	-15.77
Submission 2026	%	-1.34	-1.22	-1.15	-1.16	-1.23	-1.12	-1.15	-1.13	-1.10	-1.15	-1.34	-1.75	-1.65	-1.58
CH_4 emissions		2010	2011	2012	2013	2014	2015	2016	2017	2018	2019	2020	2021	2022	2023
Submission 2025	kt	0.06	0.05	0.04	0.04	0.03	0.02	0.02	0.02	0.02	0.02	0.02	0.01	0.01	0.01
Submission 2026	kt	0.04	0.04	0.03	0.03	0.02	0.02	0.02	0.01	0.01	0.01	0.01	0.01	0.01	0.01
Difference	kt	-0.01	-0.01	-0.01	-0.01	-0.01	-0.01	-0.01	-0.01	-0.01	-0.01	-0.01	-0.01	-0.01	-0.01
Submission 2026	%	-23.22	-18.89	-18.33	-16.05	-21.13	-23.43	-25.41	-35.56	-43.29	-36.13	-35.19	-38.94	-44.01	-52.28
N_2O emissions		2010	2011	2012	2013	2014	2015	2016	2017	2018	2019	2020	2021	2022	2023
Submission 2025	kt	0.02	0.03	0.03	0.03	0.04	0.04	0.04	0.04	0.04	0.04	0.05	0.05	0.05	0.05
Submission 2026	kt	0.02	0.03	0.03	0.03	0.07	0.09	0.12	0.13	0.14	0.14	0.15	0.15	0.15	0.14
Difference	kt	0.00	0.00	0.00	0.00	0.04	0.06	0.08	0.09	0.10	0.10	0.10	0.10	0.10	0.10
Submission 2026	%	4.63	7.20	5.54	4.25	99.21	158.81	220.51	248.91	245.31	228.99	221.27	214.30	206.51	203.17

3.2.20.5Category-specific planned improvements (CRT 1.A.4.c)

Currently there are no planned improvements in this category.

3.2.21 Other (1.A.5)

The subsector is further divided into:

- Stationary sources – 1.A.5.a (Non specified stationary; Emissions from fuel combustion in stationary sources that are not specified elsewhere)
- Mobile sources – 1.A.5.b (Non specified mobile; Mobile Emissions from vehicles and other machinery, marine and aviation (not included in 1.A.4.c.ii or elsewhere). Includes emissions from fuel delivered for aviation and water-borne navigation to the country's military as well as fuel delivered within that country but used by the militaries of other countries that are not engaged in.)

The structure of fuels throughout the subsector 1.A.5. their consumption, used emission factors and emissions of individual greenhouse gases are shown in the following outline.

1.A.5.b, 2024								
Structure of Fuels	**Activity data**	**CO_2**			**CH_4**		**N_2O**	
		EF	**OxF**	**Emission**	**EF**	**Emission**	**EF**	**Emission**
	[TJ]	**[t CO_2/TJ]**		**[kt]**	**[kg CH_4/TJ]**	**[kt]**	**[kg N_2O TJ]**	**[kt]**
Kerosene Jet Fuel	736.10	72.75*)	1	44.03	0.50*)	0.00030	1.98*)	0.00120
Diesel Oil	2 711.14	73.12*)	1	198.23	0.44*)	0.00120	10.55*)	0.02860
Total year 2024	**3 447.24**			**242.25**		**0.00150**		**0.02980**
Total year 2023	2588.64			263.99		0.00166		0.02906
Index 2024/2023	1.33			0.92		0.90		1.03
Total year 1990	2 591.59			192.04		0.02274		0.00658
Index 2024/1990	1.33			1.26		0.07		4.53

*) *Country specific data*

The origin of the data, the emission factors used and the method of calculating the level of emissions for each gas is detailed in the following outline.

2024							
Structure of Fuels	**Source of**	**Emission factors**			**Method used**		
	Activity data	**CO_2**	**CH_4**	**N_2O**	**CO_2**	**CH_4**	**N_2O**
Kerosene Jet Fuel	CzSO	CS	CS	CS	Tier 2	Tier 2	Tier 2
Diesel Oil	CzSO	CS	CS	CS	Tier 2	Tier 2	Tier 2

Given that all stationary sources have been reported in subsectors 1.A.1., 1.A.2. and 1.A.4., in this subsector (starting with last submission) will be reported only mobile sources, which were not disclosed in the subsectors 1.A.3. and 1.A.4.c.

In accordance with the IPCC 2006 Gl., the subsector 1.A.5.b. is subdivided into:

- 1.A.5.b.i – Mobile (aviation component)
- 1.A.5.b.iii – Mobile (other)

In the subsector 1.A.5.b.i is reported fuel consumption and corresponding emissions of greenhouse gases from aviation, besides the public air transport. This is primarily the consumption of aviation fuels in the army, in state institutions (aerial vehicles from Integrated Rescue System) or private air transport.



Fig. 3-38 Development of CO_2 emissions in source category 1.A.5.b.

Subsector 1.A.5.b.ii is not exploited in the submission of the Czech Republic, especially as it relates to maritime transport which is not present in the Czech Republic.

Subsector 1.A.5.b.iii is used for the reporting of all remaining fuels (and greenhouse gases) that have not been reported elsewhere; it is mainly the consumption of motor fuels for ground vehicles in the military and in governmental institutions (Integrated Rescue System). Furthermore, it includes the consumption in the fields of construction, mining of fuels and minerals, industry (only areal transport).

The fraction of CO_2 emissions in subsector 1.A.5 in 2024 contributed 0.3% to CO_2 emissions in the whole Energy sector 1.A.

Development of fuel consumption and the corresponding CO_2 emissions throughout the subcategory 1.A.5.b. are seen in Fig. 3-38. Data of Kerosene Jet Fuel and Gasoline before 1998 are not available in sufficient details. Shares of fuels and corresponding emissions before 1998 are reported in the sector 1.A.3. Transport.

The graph on Fig. 3-38 shows that a decisive proportion has diesel oil, another significant share is appertained to kerosene jet fuel (mainly army), the proportion of gasoline is minor.

3.2.21.1Methodological issues (CRT 1.A.5.b)

The basic requirement for processing fuel consumption by mobile sources is their division between subsectors 1.A.3 Transport and 1.A.4.c.ii and 1.A.5. This distribution is carried out in coordination with CDV. The aim is to ensure that no fuel is included in the balance twice and that no fuel is omitted. Therefore, the following distribution was performed:

Motor fuels which are consumed in subsector 1.A.4.c.ii are used only for off-road vehicles and other mechanisms in the agricultural sector, forestry and fisheries.

Subsector 1.A.5.b.i reports fuels from aviation, which have been reallocated from consumption in 1.A.3 since 1998. This corresponds to the consumption of kerosene jet fuel by the army and aviation in state organizations (aerial rescue equipment). Subsector 1.A.5.b.iii reports motor fuels for ground transport systems, which have been reallocated from consumption in 1.A.3 since 1990. This corresponds to the consumption of motor fuels for mobile sources by the army and the public sector (ambulance, fire brigade, etc.), both on and off road.

Based on our improvements CO_2, CH_4 and N_2O emission for the categories 1.A.4.c.ii were recalculated. This need arised because the emission factors have not been updated for many years, resulting in inaccurate emission reporting. The aim was to unify the emission factors with those applied in category 1.A.3 for the same type of fuels. Therefore, the emission factors were taken over from 1.A.3 and use in 1.A.4.c.ii subcategory. More details for emission factors are described in chapter 1.A.3.

3.2.21.2 Uncertainties and time-series consistency (CRT 1.A.5.b)

See chapter 3.2.5.

3.2.21.3 Category-specific QA/QC and verification (CRT 1.A.5.b)

QA/QC procedures in this subsector must be coordinated with CDV. KONEKO, as the company responsible for processing the entire sector 1.A, evaluates the distribution of motor fuels among the various subsectors 1.A.3, 1.A.5 and 1.A.4.c.ii before each submission. Simultaneously, after processing the data portion of the submission, it checks whether the predetermined distribution of fuels was properly applied and, if necessary, proposes corrections in order to avoid double counting of fuels or their omission.

Other QA/QC and verification - see section 3.2.6.

3.2.21.4 Category-specific recalculations (CRT 1.A.5.b)

Due to update of Activity data of Gasoline, Liquid fuels were corrected for the year 2023, see the Tab. 3-44. Based on changes of emission factors CO_2, CH_4, N_2O, emissions of Liquid fuels in 1.A.5. were recalculated for the years 2010–2023, see the Tab. 3-45.

Tab. 3-44 Changes after recalculation of fuel consumption in 1.A.5.b Liquid fuels

Fuel consumption		2023
Submission 2025	TJ	2 899.47
Submission 2026	TJ	2 588.64
Difference	TJ	-310.83
Submission 2026	%	-10.72

Tab. 3-45 Changes after recalculation in 1.A.5.b

CO_2 emissions		2010	2011	2012	2013	2014	2015	2016	2017	2018	2019	2020	2021	2022	2023
Submission 2025	kt	254.577	263.981	251.379	251.380	257.599	267.084	274.427	283.198	235.596	229.244	197.629	219.772	213.589	210.144
Submission 2026	kt	254.559	263.972	251.357	251.362	257.550	267.020	274.336	283.090	235.463	229.172	197.525	219.424	212.949	188.786
Difference	kt	-0.018	-0.010	-0.022	-0.018	-0.049	-0.064	-0.091	-0.107	-0.133	-0.071	-0.105	-0.348	-0.640	-21.357
Submission 2026	%	-0.007	-0.004	-0.009	-0.007	-0.019	-0.024	-0.033	-0.038	-0.056	-0.031	-0.053	-0.158	-0.299	-10.163
CH_4 emissions		2010	2011	2012	2013	2014	2015	2016	2017	2018	2019	2020	2021	2022	2023
Submission 2025	kt	0.019	0.017	0.015	0.013	0.013	0.011	0.010	0.010	0.009	0.008	0.007	0.008	0.008	0.008
Submission 2026	kt	0.016	0.015	0.013	0.012	0.012	0.010	0.009	0.008	0.007	0.007	0.006	0.007	0.007	0.001
Difference	kt	-0.003	-0.002	-0.002	-0.001	-0.002	-0.001	-0.001	-0.002	-0.002	-0.001	-0.001	-0.001	-0.001	-0.007
Submission 2026	%	-16.874	-13.110	-11.925	-9.938	-11.770	-13.254	-13.117	-19.907	-20.864	-15.014	-14.475	-15.436	-17.422	-83.131
N_2O emissions		2010	2011	2012	2013	2014	2015	2016	2017	2018	2019	2020	2021	2022	2023
Submission 2025	kt	0.006	0.007	0.007	0.008	0.009	0.009	0.010	0.010	0.009	0.009	0.009	0.010	0.010	0.009
Submission 2026	kt	0.006	0.007	0.008	0.008	0.017	0.023	0.031	0.035	0.030	0.028	0.027	0.030	0.029	0.028
Difference	kt	0.000	0.000	0.000	0.000	0.008	0.014	0.021	0.025	0.021	0.020	0.019	0.020	0.019	0.018
Submission 2026	%	4.398	6.891	5.316	4.094	95.644	154.141	214.316	242.758	238.029	222.196	215.267	208.202	200.456	194.184

3.2.21.5Category-specific planned improvements (CRT 1.A.5.b)

Currently there are no planned improvements in this category.

3.3 Fugitive emissions from solid fuels and oil and natural gas and other emissions from energy production (CRT 1.B)

Mining, treatment and all handling of fossil fuels are sources of fugitive emissions. In the Czech Republic, CH_4 emissions from underground mining of Hard Coal are significant, while emissions from surface mining of Brown Coal, Oil and Gas production, transmission, storage and distribution are less important.

The current inventory includes CH_4 emissions for the following categories:

- 1.B.1 Solid fuels
- 1.B.2 Oil and Natural Gas



Fig. 3-39 GHG emissions trends from Fugitive emissions from fuels [kt/year]

In 1.B Fugitive Emissions from Fuels category, especially 1.B.1.a Coal Mining and Handling was evaluated as a key category (Tab. 3-1). Category 1.B.2 also was identified as a key category by the latest assessment, but only in one from the four tests (LA). Moreover, identifiers placed this category just over the borderline between key and non-key categories.

Development of individual emissions of greenhouse gases in sector 1.B is shown on the graphs in Fig. 3-39. N_2O emissions for category 1.B.1 are NA, NO and for the category 1.B.2 the difference is visible on the fourth decimal number. Therefore, graph showing this trend was not added because it would be unclear. Development of N_2O emission can be described with the increasing values till 2005 (maximum emissions was between 2003–2005) and then decreasing trend can be observed. Sector 1.B is dominated by methane emissions from subcategory 1.B.1. - Solid fuels, while emissions from sector 1.B.2. - Oil and Natural gas represent on average 20% of the total emissions. CO_2 emissions arise primarily in subcategory 1.B.1 - Solid fuels. N_2O emissions originate only from the subsector 1.B.2.a - Oil and there are insignificant.

The importance of individual greenhouse gases from the total emissions, expressed as CO_2 equivalent, is visible from Fig. 3-40.



Fig. 3-40 The share of individual GHG emissions from the total emissions, expressed as CO_2 eq. (1.B.)

From the graphs on Fig. 3-39 and Fig. 3-40 is also clear that during the period occurred a significant decrease in GHG emissions across category 1.B. As it is shown below, the decrease was mainly due to a decrease in subcategory 1.B.1. - Solid fuels, in which vital source of emissions is underground mining of hard coal. For in 1.B., the decrease of total GHG emissions is 92% compared to the 1990 level.

Fugitive methane emissions are related to Regulation (EU) 2024/1787 on the reduction of methane emissions in the energy sector. Pursuant to this regulation, companies are, inter alia, required to quantify and report their methane emissions. However, as the Czech implementing legislation has not yet been adopted, companies did not submit emission reports in 2025 and they cannot be subject to sanctions for non-compliance.

For inventory purposes, all companies operating within the territory of the Czech Republic whose emissions fall under category 1.B were contacted and requested to provide data on their fugitive methane emissions; however, not all companies provided the requested data on this voluntary basis. The data obtained were critically evaluated by the national experts and, where considered sufficiently reliable, were incorporated into the national inventory. Further details on the use of these data are described below in specific chapters.

3.3.1 Solid Fuels (CRT 1.B.1)

The category is further divided into the following subcategories according to IPCC 2006 Gl.:

- 1.B.1.a Coal mining and handling
  - 1.B.1.a.1 Underground mines
    - 1.B.1.a.i.1 Mining
    - 1.B.1.a.i.2 Post-mining seam gas emissions
    - 1.B.1.a.i.3 Abandoned underground mines
  - 1.B.1.a.2 Surface mines
    - 1.B.1.a.ii.1 Mining
    - 1.B.1.a.ii.2 Post-mining seam gas emissions
- 1.B.1.b Solid fuel transformation
- 1.B.1.c Other

3.3.1.1 Category description (CRT 1.B.1)

The structure of the sector, corresponding activity data, used emission factors and emissions of individual greenhouse gases are shown in the following outline.

1.B.1, 2024								
Structure of sector		Activity data	CH_4		CO_2		N_2O	
			EF	Emission	EF	Emission	EF	Emission
		[Gg]	[kg CH_4/t]	[kt]	[kg CO_2/t]	[kt]	[kg N_2O/t]	[kt]
1.B.1.a	Coal mining/handl.	25.21		16.95	22.7	60.98		NO
1.B.1.a.i.	Underground mines	1.52		14.05	22.7	34.54		NA
1.B.1.a.i.1	Mining		6.750	10.28	22.7	34.54	NA	NA
1.B.1.a.i.2	Post-mining activ.		0.452	0.65	NA	NE	NA	NA
1.B.1.a.i.3	Abandoned mines	+)		3.12	NA	NE	NA	NO
1.B.1.a.ii.	Surface mines	23.68		2.90		NE		NA
1.B.1.a.ii.1	Mining		0.056	1.32	1.12	26.43	NA	NA
1.B.1.a.ii.2	Post-mining activ.		0.067	1.59	NA	NE	NA	NA
1.B.1.b	Solid fuel transformation	0.01	30	0.12	NA	NE	NA	NA
Total year 2024				**17.07**		**60.98**		**NA**
Total year 2023				17.55		65.84		NA
Index 2024/2023				0.97		0.93		NA
Total year 1990				307.91		542.38		NA
Index 2024/1990				0.06		0.11		NA

+) Methodology and emission factors are explained in 3.3.1.2.

The origin of the data, the emission factors used and the method of calculating the level of emissions for each gas is shown in detail in the following outline.

2024								
Structure of sector		Source of Activity data	Emission factors			Method used		
			CH_4	CO_2	N_2O	CH_4	CO_2	N_2O
1.B.1.a	Coal mining/handl.	CzSO				Tier 1-2	Tier 1-2	-
1.B.1.a.i.	Underground mines	CzSO				Tier 1-2	Tier 1-2	-
1.B.1.a.i.1	Mining	CzSO	CS	CS	NA	Tier 2	Tier 2	-
1.B.1.a.i.2	Post-mining aktivity	CzSO	D	D	NA	Tier 1	Tier 1	-
1.B.1.a.i.3	Abandoned mines	various+)	D	D	NA	Tier 1	Tier 1	-
1.B.1.a.ii.	Surface mines	CzSO				Tier 1	Tier 1	-
1.B.1.a.ii.1	Mining	CzSO	CS	CS	NA	Tier 2	Tier 2	-
1.B.1.a.ii.2	Post-mining aktivity	CzSO	D	D	NA	Tier 1	Tier 1	-
1.B.1.b	Solid fuel transformation	FAOSTAT	D	D	NA	Tier 1	Tier 1	-

+) Methodology and emission factors are explained in 3.3.1.2.

The source category 1.B.1 Solid Fuels consists of three sub – source categories: source category 1B.1.a Coal mining and Handling, source category 1.B.1.b Coal transformation and source category 1.B.1.c Other.

The main process coal mining and handling emits 99% of methane emissions from the category 1.B.1 Solid Fuels category is underground mining of Hard Coal in the Ostrava-Karviná area. A lesser source consists in Brown Coal mining by surface methods and post-mining treatment of Hard and Brown Coal. Coal mining (especially Hard Coal mining) is accompanied by an occurrence of methane. Methane, as a product of the coal-formation process, is physically bonded to the coal mass or is present as the free gas in pores and cracks in the coal and in the surrounding rocks.



Fig. 3-41 The trend of GHG emissions and the relationship between emissions of CO_2 and CH_4 (1.B.1)

Besides methane, during mining of coal mass a certain amount of carbon dioxide is released, that accompanies methane in the firedamp. CO_2 is reported only for the underground mining of hard coal, for surface mining of lignite emission factor is not available.

The proportion of subcategory 1.B.2 - Solid fuel transformation in the total emissions of greenhouse gases is quite minor. Subcategory 1.B.1.c - Other is not used, because for reporting the previous subcategories are used.

The graph on Fig. 3-41 shows the time trend of total emissions of greenhouse gases in the entire subsector 1.B.1. The chart also demonstrates the share of CO_2 emissions in the total GHG emissions, which on average makes about 4%. The contribution of the individual subsectors to the total emissions of CH_4, depending on the volume of mining from underground mines (hard coal) and surface mines (lignite) in category 1.B.1 is shown on the graph in Fig. 3-42.

The Czech Republic has historically mined and is still mining large volumes of lignite, primarily for energy purposes. Hard coal is used for energy purposes, as well as for the production of metallurgical coke.

Hard coal mining, although its volume is about 6% of the total volume, is accompanied by considerably more significant CH_4 emissions than mining of lignite.

3.3.1.1.1 Coal Mining and Handling (CRT 1.B.1.a)

In the Czech Republic, mainly Hard Coal is mined in underground mines (i.e. Hard Coal: Coking Coal and Bituminous Coal). Currently, underground mines are in operation in the Ostrava-Karviná coalmining area. In the end of year 2016, the part of Ostrava-Karvinná coalmining area was closed, which results in decreasing of amount of mined Hard Coal and emissions. In the past, Hard Coal was also mined in the vicinity of the city of Kladno. These mines were closed in 2003. Brown Coal was mined in only one underground mine in the Northern Bohemia. This mine was closed in 2016. Emissions from this mine used to be reported together with surface mining of Brown Coal – Lignite in subcategory 1.B.1.a.ii. Surface mines until the last submission. However, a recalculation was made and the data from underground mining of brown coal in the Northern Bohemia were added to the 1.B.1.a.i. Underground Mines. The amount of CH_4



Fig. 3-42 The ratio of methane emissions from Underground mines and Surface mines and the corresponding development of mining of Hard Coal and Lignite (1.B.1)

emissions from brown coal underground mine in the Northern Bohemia contributed about 6% of average to the CH_4 emissions of hard coal underground mines.

Data for mining of various types of coal are taken from the CzSO report for the IEA/EUROSTAT (the report CZECH_COAL.xls).

Underground Mines (ETF 1.B.1.a.i.)

In underground Hard Coal mining, CH_4 is released from the coal mass and from the surrounding rocks into the mine air and must be removed to the surface to prevent formation of dangerous concentrations in the mine.

Underground Mining Activities (1.B.1.a.i.1.)

Hard-coal mining is the principal source of fugitive emissions of CH_4. The mine ventilation must be regulated according to the amounts of gas released to keep its concentration on safe level. At the end of 1950's mine gas removal systems were introduced in opening new mines and levels in the Ostrava – Karviná coal-mining area, which permitted separate exhaustion of partial methane released in the mining activity in the mixture containing the mine air. The total amount of methane emitted can be balanced quite accurately from the methane concentrations in the mine air and their total annual volume.

Post-Mining Activities (1.B.1.a.i.2)

The activity data are the same as in category 1.B.1.a.i.1 Mining Activities. It is assumed that the entire mined volume undergoes manipulation during which residual methane is released.

Abandoned underground mines (1.B.1.a.i.3.)

Abandoned underground mines in the Czech Republic are located in Kladno Basin (near Kladno, 30 km northwest of Prague), in the Ostrava-Karvina coalfield - OKR (North Moravia) and mine Koh-i-noor (Centrum) close to Dolní Jiříkov in North Bohemia (closed 2016). In terms of methane emissions are relevant only abandoned mines in OKR. Coal mining in the Kladno Basin was terminated in 2002. In these mines methane was absent, so the methane emissions estimate is made only from OKR mines.

To get more information about abandoned mines in Kladno basin, the head of Kladenské doly was contacted. Based on our request we received an official answer about this issue. Mining of coal was shut down in 2002 and within the mining period the mines were liquidated. Currently the major of all abandoned underground mines is disposed of in accordance with mining legislation. Basically, it means that mines were filled with backfill material and the mine is closed by a special mining cover. This method reliably eliminates CO_2 and CH_4 emissions, which is also controlled by portable detection device. More information are stated in the official letter, which can be provided upon request.

In the Ostrava-Karvina coalfield coal has been extracted for more than two hundred years. Crucial decline of mining in this area started in 1991, but the closure of mines occurred in the 20s of the 20th centuries.

Ostrava mines have always been significant sources of coal seam gas and in terms of mine safety regulations they were categorized under the mines with greatest threat of occurrence of methane. Methane is observed more than 100 years and reached its peak in the sixties when was the maximum in mining in Ostrava. At that time, exceeded the daily amount of gas is 500 thousand. m^3 CH_4. The gas was discharged from the mines using ventilation with 17 air pits and mine degassing. Amount on the gas in abandoned mines today, after the destruction of almost all pits, is stabilized at around 40 thousand. m^3 CH_4 per day. Based on the amount of methane escaped in recent years and using the international

experience, can be forecasted that the gas will continue to be released from the underground spaces in Ostrava for a number of years.

Parts of abandoned mines have CH_4 recovery systems. There is company, which has established mining areas for mining of fire-damp in Ostrava-Karviná area. In the abandoned mines there are automatic suction devices and firedamp stations. Firedamp arises from abandoned mining pits and surface boreholes into abandoned areas. Mined firedamp is used at the place of mining in autonomous cogeneration units (aggregate for electricity energy production with an ignition combustion engine) (www.dpb.cz).

Surface Mines (CRT ***1.B.1.a.ii.)***

Surface Mining Activities (1.B.1.a.ii.1)

Lignite (Brown Coal) is mined in surface mines in the Czech Republic. Lignite is mined primarily in the Northern Bohemia area. Small parts of very young Lignite mines are located in Southern Moravia.

Prior to the commencement of surface mining in northern Bohemia, where today a decisive amount of lignite in the Czech Republic is mined, there were underground mines. The abundance of methane in these mines has never been a problem. If there was an explosion in the mines, it was caused by swirling of coal dust. Surface mining began in the 50s of the 20th century and in the period after 1990 the underground mines were already not in use.

Post-Mining Activities (1.B.1.a.ii..2)

The activity data are the same as in category 1.B.1.a.ii.1 Mining Activities. It is assumed that the entire mined volume undergoes treatment during which residual methane is released.

3.3.1.1.2 Solid Fuel Transformation (CRT 1.B.1.b)

Production of Coke from Coking Coal

Fugitive methane emissions from coal treatment prior to the actual coking process are listed under 1.B.1.a.i.2 Post-Mining Activities. Emissions from the actual production of Coke are given under 2. Industry.

Production of briquettes from Brown Coal

Fugitive methane emissions from coal treatment prior to the actual briquetting process are listed under 1.B.1.a.i.2 Post-Mining Activities. CO_2 emissions from the actual production of briquettes are included in subcategory 1.A.2.g.

Production of charcoal

CH_4 emissions from charcoal production were estimated by using EF provided by the Revised 1996 Guidelines (IPCC, 1997); the value of 1 000 kg CH_4/TJ of charcoal produced was used. Since there are no available official activity data about charcoal production in the Czech Republic, the un-official data from FAOSTAT statistics were used. The missing data were extrapolated. The default net calorific value 30 MJ/kg (Table 1-13 in Revised 1996 Guidelines) was used to convert activity data to the energy units. Resulting CH_4 emissions please see in the Tab. 3-46. Unfortunately, IPCC 2006 Gl. (IPCC, 2006) do not provide default emissions factors for fugitive emissions from charcoal production. From this reason the emission factor provided in Revised 1996 Guidelines (IPCC, 1997) is still used. Since these emissions are very low national inventory team consider this approach to be relevant in this case.

Tab. 3-46 CH_4 emissions from charcoal production

	1.B.1.b Solid Fuel Transformation		
	Production [kt/year]	Production [TJ/year]	CH_4 emissions [kt/year]
1990	1.00	30.00	0.03
1991	1.00	30.00	0.03
1992	1.00	30.00	0.03
1993	1.00	30.00	0.03
1994	1.00	30.00	0.03
1995	1.00	30.00	0.03
1996	1.00	30.00	0.03
1997	1.00	30.00	0.03
1998	1.80	54.00	0.05
1999	2.60	78.00	0.08
2000	3.40	102.00	0.10
2001	4.20	126.00	0.13
2002	5.00	150.00	0.15
2003	6.00	180.00	0.18
2004	6.00	180.00	0.18
2005	6.00	180.00	0.18
2006	6.00	180.00	0.18
2007	6.00	180.00	0.18
2008	6.00	180.00	0.18
2009	6.00	180.00	0.18
2010	6.60	198.00	0.20
2011	6.40	192.00	0.19
2012	6.00	180.00	0.18
2013	6.00	180.00	0.18
2014	6.00	180.00	0.18
2015	6.00	180.00	0.18
2016	6.00	180.00	0.18
2017	7.98	239.49	0.24
2018	5.60	168.03	0.17
2019	6.07	182.13	0.18
2020	6.07	182.13	0.18
2021	6.12	183.45	0.18
2022	5.56	166.68	0.17
2023	5.56	166.68	0.17
2024	4.00	120.00	0.12

Fugitive CO_2 emissions are not estimated or are negligible and no known method is available for their determination in this category (notation key NE). Fugitive N_2O emissions are not estimated because, according to the current state of knowledge, these emissions cannot occur (notation key NA) and also IPCC 2006 Gl. (IPCC, 2006) does not provide default emission factor.

3.3.1.1.3 Other (CRT 1.B.1.c)

No other subcategory of fugitive methane emissions is known in the Czech Republic.

3.3.1.2 Methodological issues

Underground Mines (CRT 1.B.1.a.i.)

Underground Mining Activities (1.B.1.a.i.1.)

Country specific emission factors were determined for calculation of fugitive methane emissions in underground mines in the second half of the 1990's: the ratio between mining and the volume of methane emissions is given in Tab. 3-47, see (Takla and Nováček, 1997).

Tab. 3-47 Coal mining and CH_4 emissions in the Ostrava - Karvina coal-mining area

	Coal mining	CH_4 emissions	Emission factors
	[mil. t/year]	[mil. m³/year]	[m³/t]
1960	20.90	348.9	16.7
1970	23.80	589.5	24.7
1975	24.11	523.8	21.7
1980	24.69	505.3	20.5
1985	22.95	479.9	20.9
1990	20.60	381.1	19.0
1995	15.60	270.7	17.4
1996	15.10	276.0	18.3
Total	**167.31**	**3 375.3**	**20.2**
1990 till 1996	50.76	927.8	18.3

Only the values for 1990, 1995 and 1996 were used from this table to determine the emission factors.

The average value of the emission factor of 18.3 m^3/t was recalculated to 12.261 kg/t using a density of methane of 0.7 m^3/kg. This emission factor is used for coal mined in the Ostrava-Karviná coalmining area for years 1990–1999. The emission factor set by estimation at 50% of this value was used for the remaining Hard Coal from underground mines in other areas. This is valid for coal with minimum coal gas capacity (coal from the Kladno area to 2002 and coal from the Žacléř area from 1998).

For the period after 2000 were determined new, revised emission factors CH_4/t mined coal.

The management of OKD, a.s. (Ostrava-Karviná mines, joint share company) was contacted since this company monitors in very detail the issues about methane production. In response to a request from the reporting team, the company provided a document in which the total amount of gas released by OKD mines was determined, together with the amount of methane withdrawn by degassing, the amounts of methane used for industrial purposes, venting of methane from degassing and the total amount of methane released into the atmosphere. A summary of the information provided is given in Tab. 3-48.

Tab. 3-48 Methane production from gas absorption of mines and its use

	mil.m^3 CH_4 * $year^{-1}$				
Year	**Total amount of gas**	**Pumped out by gas absorption**	**Industrial use**	**Venting from gas absorption into the atmosphere**	**Released into the atmosphere - total**
2000	236.7	84.1	77.9	6.2	158.8
2001	210.7	73.9	71.1	4.0	140.8
2002	210.0	81.0	70.3	1.3	130.3
2003	200.6	74.8	72.8	2.0	127.8
2004	194.6	77.1	73.4	3.2	120.7
2005	207.7	73.9	70.3	3.6	137.4
2006	221.1	76.9	75.9	0.8	145.0
2007	194.7	71.5	71.0	0.5	123.7
2008	199.5	68.8	68.5	0.3	131.0

This data was used to calculate the emission factors and to determine the average emission factor, which is used for the period after 2000–2008.

The emission factors given in Tab. 3-49 are used for 2000–2008. After 2008, the emission factor calculated as the average value from the values for 2000–2008, i.e. 8.12 t/kt, is used. Research with aim to develop this emission factor was performed in 2011.

Tab. 3-49 Calculation of emission factors from OKD mines for period 2000 onwards

Year	OKD mining	CH_4 emissions	EF
	[kt/year]	[t/year]	[t CH_4/kt]
2000	11 514	106 396	9.24
2001	11 844	94 336	7.96
2002	12 049	87 301	7.25
2003	11 301	85 626	7.58
2004	10 901	80 869	7.42
2005	10 822	92 058	8.51
2006	11 656	97 150	8.33
2007	10 153	82 879	8.16
2008	10 030	87 770	8.75
2000–2008	100 270	814 385	8.12

Tab. 3-47 shows the average emission factor used for the years 1990–1999 for calculation of CH_4 emissions from OKD mines. For the time period 2000 to 2008 were used emission factors determined from the mining and emissions given by OKD mines (see Tab. 3-49). Based on these values an average emission factor, from the period 2000–2008 was set up, which was 8.12 tCH_4/kt. This average value has been used since 2009 (Takla and Nováček, 1997). Based on data provided by OKD this year, the emission factor was updated and is equally to 6.75 tCH_4/kt for years 2010-2024.

This emission factor can be considered as emissions factor on the level Tier II – it is country-specific emission factor, which is applicable for Ostrava-Karviná area.

For other mines in the Czech Republic where hard coal was also mined, the value of 6.7 t/kt was used – the same as in previous submissions. However, it is necessary to remind that underground mining in the mines of other areas than OKD is really minor and at the end of the first decade of 21st century was completely stopped.

Country specific emission factors were determined for calculation of fugitive carbon dioxide emissions. An extra study was performed to determine the CO_2 emission factor for underground hard coal mining. Monthly data on the concentrations and amounts of CO_2 were processed for all the exhaust air shafts in the OKD area for 2009, 2010 and for part of 2011. These data yielded an average value of the emission factor, which is related to the volume of mining. The emission factor is equal to 22.75 t CO_2/kt of mined coal and this emission factor is country specific – Tier II level. This value is valid for the OKD area. The author of the study recommended that the determined emission factor for 1990–2009 be used. He determined an emission factor 22.68 t CO_2/kt of mined coal for 2010 and it was recommended that this value also be used for the subsequent years. These emission factors were used to extend the data for CO_2 emissions for underground hard coal mining; the values are given in the Tab. 3-50.

Tab. 3-50 Emission factors and emissions from underground mining of hard coal

Year	Production OKD	Emission factor	Emission of CO_2
	[kt/year]	[t CO_2/kt]	[kt CO_2/year]
1990	22 415	22.75	456.24
1991	20 201	22.75	395.10
1992	18 637	22.75	392.83
1993	18 355	22.75	373.45

Year	Production OKD	Emission factor	Emission of CO_2
1994	17 376	22.75	362.60
1995	17 738	22.75	356.21
1996	17 453	22.75	343.65
1997	16 570	22.75	349.18
1998	16 112	22.75	332.53
1999	14 343	22.75	306.33
2000	14 855	22.75	315.13
2001	15 138	22.75	324.03
2002	14 467	22.75	322.98
2003	13 645	22.75	309.65
2004	15 579	22.75	301.87
2005	13 254	22.75	300.85
2006	13 385	22.75	324.80
2007	12 894	22.75	293.09
2008	12 663	22.75	288.00
2009	11 001	22.75	250.22
2010	11 593	22.68	262.88
2011	11 441	22.68	259.44
2012	11 652	22.68	264.22
2013	8 746	22.68	198.32
2014	8 900	22.68	201.82
2015	8 426	22.68	191.07
2016	7 015	22.68	159.07
2017	5 601	22.68	127.00
2018	4 562	22.68	103.45
2019	3 540	22.68	80.28
2020	2 200	22.68	49.89
2021	2 260	22.68	51.25
2022	1 734	22.68	39.32
2023	1 493	22.68	33.85
2024	1 523	22.68	34.54

*Post-Mining Activities (*CRT *1.B.1.a.i.2.)*

Methane emissions in the subcategory of Post-Mining Activities were calculated using a uniform emission factor based on the default value of 1.68 kg CH_4/t coal; the activity data are employed at the same level as in subcategory 1.B.1.a.i.1. Mining Activities. Based on data provided by OKD this year, the emission factor was updated and is equally to 0.426 tCH_4/kt for years 1990-2023.

Tab. 3-51 Used emissions factors and calculation of CH_4 emissions from underground coal mining – post mines operations in period 1990–2024

Year	Production OKD [kt/year]	Emission factor [t CH_4/kt]	Emission of CH_4 [kt CH_4/year]
1990	22 415	0.425	11.95
1991	20 201	0.425	11.46
1992	18 637	0.425	9.82
1993	18 355	0.425	11.82
1994	17 376	0.425	10.92
1995	17 738	0.425	10.58
1996	17 453	0.425	10.53
1997	16 570	0.425	10.04
1998	16 112	0.425	9.77
1999	14 343	0.425	8.46
2000	14 855	0.425	8.16

Year	Production OKD [kt/year]	Emission factor [t CH_4/kt]	Emission of CH_4 [kt CH_4/year]
2001	15 138	0.425	7.11
2002	14 467	0.425	7.65
2003	13 645	0.425	7.05
2004	15 579	0.425	6.87
2005	13 254	0.425	6.91
2006	13 385	0.425	7.32
2007	12 894	0.425	6.69
2008	12 663	0.425	6.33
2009	11 001	0.425	5.47
2010	11 593	0.425	5.48
2011	11 441	0.425	5.35
2012	11 652	0.425	5.38
2013	8 746	0.425	4.19
2014	8 900	0.425	4.41
2015	8 426	0.425	4.20
2016	7 015	0.425	3.25
2017	5 601	0.425	2.63
2018	4 562	0.425	2.34
2019	3 540	0.425	1.81
2020	2 200	0.425	1.02
2021	2 260	0.425	0.96
2022	1 734	0.425	0.74
2023	1 493	0.425	0.63
2024	1 523	0.425	0.65

The amount of brown coal mined from underground mine Kohinoor between 2002–2016 was added to the total amount of extracted hard coal. As the EF default value was used 18 m^3/t. To converted to t CH_4/kt, it was necessary to use conversion factor 0.67 kg/m^3. See the Tab. 3-52.

Tab. 3-52 Used emissions factors and calculation of CH_4 emissions from underground coal mining – in period 2002–2016.

Year	Production Kohinoor [kt/year]	Emission factor [t CH_4/kt]	Emission of CH_4 [kt CH_4/year]
2002	380	0.012	4.58
2003	460	0.012	5.55
2004	458	0.012	5.52
2005	464	0.012	5.60
2006	466	0.012	5.62
2007	467	0.012	5.63
2008	298	0.012	3.59
2009	350	0.012	4.22
2010	425	0.012	5.13
2011	430	0.012	5.19
2012	455	0.012	5.49
2013	356	0.012	4.29
2014	480	0.012	5.79
2015	408	0.012	4.92
2016	55	0.012	0.66

*Abandoned underground mines (*CRT *1.B.1.a.2)*

Calculation of methane emissions from abandoned mines has been carried out in accordance with the methodology IPCC 2006 Gl. at the level Tier 1. For the purposes of this calculation, the number of closed mines in the Ostrava-Karvina coalfield was determined in prescribed intervals (intervals years 1901–1925,

1926–1950, 1951–1975, 1976–2000, 2001 to the present). Given that in the Ostrava-Karvina coalfield occur only mines with high amount of the gas, were used values for the percentage of coal mines that are gassy from the column High (IPCC 2006 Gl. (IPCC 2006): Tab. 4.1.5: TIER 1 – ABANDONED UNDERGROUND MINES, DEFAULT VALUES - PERCENTAGE OF COAL MINES THAT ARE GASSY, page 4.24.), the following:

1901–1925: 10%
1926–1950: 50%
1951–1975: 75%
1976–2023: 100%

Emission factors from Table 4.1.6, p. 4.25 were used for calculating the emissions (TABLE 4.1.6: TIER 1 - Abandoned UNDERGROUND MINES - EMISSION FACTOR, MILLION M^3 methane/MINE).

Since 2005, total emissions of methane from abandoned mines have gradually decreased in the context of increased degassing of abandoned mines by the Green Gas company (electricity generation at cogeneration units, stationed for on-site extraction of methane). The overall data and the calculation procedure are shown in Tab. 3-53.

Tab. 3-53 Emission of CH_4 on abandoned mines

Year	CH_4 emission in period [kt/year]				Calculated	Use of CH_4	Total
	1926–1950	1951–1975	1976–2000	2001–2023	emission	[%]	emissions
1990	0.46	2.40	0.00		2.86		2.86
1991	0.46	2.36	1.79		4.60		4.60
1992	0.45	2.32	3.96		6.73		6.73
1993	0.45	2.28	7.18		9.90		9.90
1994	0.44	2.24	9.27		11.95		11.95
1995	0.44	2.21	10.49		13.13		13.13
1996	0.43	2.17	10.43		13.04		13.04
1997	0.43	2.14	9.87		12.43		12.43
1998	0.43	2.11	9.38		11.92		11.92
1999	0.42	2.08	9.46		11.96		11.96
2000	0.42	2.05	9.55		12.03		12.03
2001	0.42	2.02	9.19	0.00	11.63		11.63
2002	0.41	1.99	8.86	0.00	11.27		11.27
2003	0.41	1.97	8.56	1.18	12.12		12.12
2004	0.41	1.94	8.31	0.97	11.63		11.63
2005	0.40	1.92	8.05	0.85	11.22	5.00	10.66
2006	0.40	1.90	7.84	0.76	10.90	7.50	10.08
2007	0.40	1.87	7.62	0.69	10.59	20.00	8.47
2008	0.40	1.85	7.44	0.64	10.33	25.00	7.75
2009	0.39	1.83	7.26	1.80	11.29	50.00	5.65
2010	0.39	1.81	7.09	1.70	10.99	60.00	4.40
2011	0.39	1.79	6.94	1.61	10.73	70.00	3.22
2012	0.38	1.77	6.79	1.53	10.48	70.00	3.15
2013	0.38	1.76	6.65	1.47	10.25	70.00	3.08
2014	0.38	1.74	6.53	1.41	10.05	70.00	3.02
2015	0.38	1.72	6.41	1.36	9.86	70.00	2.96
2016	0.37	1.71	6.28	1.75	10.11	70.00	3.03
2017	0.37	1.69	5.88	2.51	10.45	70.00	3.14
2018	0.37	1.67	5.79	2.43	10.26	70.00	3.08
2019	0.37	1.66	5.70	2.36	10.07	70.00	3.02
2020	0.36	1.64	5.61	3.05	10.67	70.00	3.20
2021	0.36	1.63	5.53	2.97	10.50	70.00	3.15
2022	0.36	1.62	5.47	3.27	10.71	70.00	3.21
2023	0.36	1.60	5.39	3.19	10.54	70.00	3.16
2024	0.36	1.58	5.32	3.12	10.58	70.00	3.17

Surface Mines (CRT 1.B.1.a.ii)

Total emissions, used activity data and emission factors for proper extraction of lignite (Brown Coal) from surface mines and post-mining related adjustments are presented in the Tab. 3-54.

Tab. 3-54 Used activity data, emissions factors and calculation of CH_4 emissions from surface coal mining and post mines operations in period 1990-2024

Year	Brown Coal production [kt/year]	Emission factors for activities mines [t CH_4/kt]	Emission factors for activities post-mines [t CH_4/kt]	Emission of CH_4 [kt CH_4/year]
1990	77 169	0.06	0.067	9.46
1991	74 516	0.06	0.067	9.14
1992	66 665	0.06	0.067	8.17
1993	63 878	0.06	0.067	7.83
1994	56 929	0.06	0.067	6.98
1995	54 893	0.06	0.067	6.73
1996	57 365	0.06	0.067	7.03
1997	55 206	0.06	0.067	6.77
1998	49 151	0.06	0.067	6.03
1999	43 047	0.06	0.067	5.28
2000	48 925	0.06	0.067	6.00
2001	50 461	0.06	0.067	6.19
2002	47 766	0.06	0.067	5.86
2003	49 326	0.06	0.067	6.05
2004	47 583	0.06	0.067	5.83
2005	47 816	0.06	0.067	5.86
2006	48 589	0.06	0.067	5.96
2007	48 824	0.06	0.067	5.99
2008	46 828	0.06	0.067	5.74
2009	44 824	0.06	0.067	5.50
2010	43 357	0.06	0.067	5.32
2011	46 273	0.06	0.067	5.67
2012	43 210	0.06	0.067	5.30
2013	40 027	0.06	0.067	4.91
2014	37 704	0.06	0.067	4.62
2015	37 643	0.06	0.067	4.62
2016	38 328	0.06	0.067	4.70
2017	39 121	0.06	0.067	4.80
2018	38 904	0.06	0.067	4.77
2019	37 261	0.06	0.067	4.57
2020	29 371	0.06	0.067	3.60
2021	29 279	0.06	0.067	3.59
2022	33 388	0.06	0.067	4.09
2023	28 663	0.06	0.067	3.51
2024	23 681	0.06	0.067	2.90

Determination of activity data and emission factors for mining and post-mining treatment is given in the description of the individual activities on surface mines.

Surface Mining Activities (1.B.1.a.ii.1.)

Data from the source part of the questionnaire completed in the CzSO Questionnaire (CzSO, 2025), was employed to determine activity data on extraction of Brown Coal and Lignite.

During surface mining, escaping methane is not related to specific flow of air and thus it is far more difficult to monitor the amount of methane escaping into the air. Consequently, default IPCC emission factors are

employed to calculate methane emissions from surface mining and from post-mining treatment (IPCC 2006).

The emission factor for surface mining activities was used following due to the recommendation E.19 from FCCC/ARR/2016/CZE. The description of recommendation E.19 from FCCC/ARR/2016/CZE (2016 Centralised UNFCCC Review of Czech Republic), states that the upper limit of the proposed range of the Tier 1 EF from the 2006 IPCC GLs is applied by the Czech Republic because the average overburden depths of the surface mines vary from 120 to 200 m. In our study (2023–2024), we conducted literature research on the causes of mining accidents in the North Bohemian Coal Basin (the only Surface Coal Basin in the Czech Republic). Results of literature research and consultation with the Podkrušnohorské technické muzeum (technical museum in the Ore Mountains) confirmed that probably none of the mining accidents in the past were caused by the presence of methane (explosions were mainly caused by CO and coal dust). This implies that methane in the mines was present only in small or no quantities. This indicates that the emission factor for calculating methane emissions must also be lower than 1.34 kg CH_4/t.

In the North Bohemia Coal Basin, insufficient gas formation during low carbonization of brown coals is, thus the available specific literature data is very limited – such deposits are not usually studied as sources of CH_4. The only research conducted in the North Bohemia Coal Basin is reaserach of the Czech Geological Survey (Buzek et al. 2022). The research of Mr. Buzek's team took place in the territory of several brown coal mines and determined the methane content in the pores of the mined coal and, based on this data, also the emission factor 0.0556 kg CH_4/t.

These results were also consulted with the Czech Mining Authority, which send us the officially statement. The Czech Mining Authority considers data determined by the Czech Geological Survey as an appropriate document for determination emission factor of methane emissions in surface mines.

From the submission 2025, the emission factor 0.0556 kg CH_4/t for Surface minig was applied and the entire time series was recalculated, see the Recalculation section. New emission factor and CH_4 emission were compared with emission factor and CH_4 emission of Germany and Poland, as they lie on the same Coal Basion as the Czech Republic, and no significant deviations were found.

In the same research was also studied CO_2 content in the pores of the mined coal (Buzek et al. 2022), based on this data, the emission factor 1.116 kg CO_2/t was established. Established emission factor falls within the range in the 2019 IPCC Refinement default emissin factor. From the submission 2026, this emission factor was applied.

Post-Mining Activities (1.B.1.a.ii.2)

3.3.1.2.1 Solid Fuel Transformation (CRT 1.B.1.b)

Emission calculation was performed for the production of wood charcoal at Tier I, using default emission factors - see chapter 3.3.1.1.2.

CH_4 emissions from charcoal production were estimated by using EF provided by the Revised 1996 Guidelines (IPCC 1997); the value of 1 000 kg CH_4/TJ of charcoal produced was used. Since there are no available official activity data about charcoal production in the Czech Republic, the un-official data from FAOSTAT statistics were used. The missing data were extrapolated. The default net calorific value 30 MJ/kg (Table 1-13 in Revised 1996 Guidelines) was used to convert activity data to the energy units. Unfortunately, IPCC 2006 Gl. (IPCC 2006) do not provide default emissions factors for fugitive emissions from charcoal production. From this reason the emission factor provided in Revised 1996 Guidelines (IPCC 1997) is still used. Since these emissions are very low the team consider this approach to be relevant in this case.

3.3.1.3 Uncertainties and time-series consistency

The inventory methods used in this inventory were consistently employed across the whole reporting period from the base year of 1990 to 2019.

In 2020 was carried out an extensive study aiming to update the uncertainties in the sector 1.B.1. From the study follows that in this category higher uncertainties should be expected than in 1.A. The uncertainties in the activity data result primarily from inaccuracies in weighing of extracted coal. Conversely, imports and exports of raw materials are sensitive economic data and low uncertainties should be expected.

Uncertainties in calculating methane emissions further follow from the emission factors employed. The emission factors for determining emissions from underground mining of hard coal are based on measurement of the methane concentrations in the air ventilated from underground mines in the second half of the 1990's. The uncertainty in the emission factors should be quite low, while the uncertainty in the CO_2 emission factor should be expected higher.

The determination of uncertainties was carried out according the same methodology as in case of category 1.A, i.e. three independent experts estimate of 'basic' uncertainties, which were averaged (see chapter 3.2.5. or for details Veselá et al. 2020).

For specific uncertainties used for introduction into the trend in total national emissions see Annex 2.

3.3.1.4 Category-specific QA/QC and verification

General quality control and source-specific quality control (Tier 1 and Tier 2), in conformance with the requirements of the QSE handbook and its associated applicable documents, have been performed to the full extent.

QC activities at the level of Tier 1 were performed according to the QA/QC plan by the sector compiler. Routine control was performed in the framework of the following activities:

- activity data employed,
- emission factors employed,
- calculation procedures employed,
- transfer of numerical data from the working set to the ETF Reporting Tool.

In control of the emission factors employed, the emission factors used in the Czech Republic methodology were compared with the emission factors of the Slovak Republic, Poland and Germany in the context with the default emission factors. It was found that the emission factors employed for calculation of emissions in the Czech Republic methodology correspond, in their range, to the emission factors employed in the other countries.

Furthermore, the correct usage of the methodology at Tier I level for the calculation of CH_4 emissions from abandoned mines and the performance of own calculations were checked. The calculation procedure was consulted with an independent expert from the VSB (Technical University of Ostrava). It was concluded that the input data and the method of calculation are in line with the methodology.

Control that the transfer of numerical data from the working set to the ETF Reporting Tool does not reveal any differences. The final working set in EXCEL format is locked to prevent intentional rewriting of values and archived at the coordination workplace. The protocols on the performed QA/QC procedures are stored too.

3.3.1.5 Category-specific recalculations

Based on more accurate data was updated the emission factor for CH_4 in 1.B.1.a.i.1. Underground mines, Mining activity and 1.B.1.a.i.2. Underground mines, Post - mining Activities, see the Tab. 3-55 and Tab. 3-56 The emission factor for CO_2 in 1.B.1.a.1.ii Surface mines, Mining Activities was updated based on our improvement plan, see the Tab. 3-57.

Tab. 3-55 Changes after recalculation in CH_4 emissions 1.B.1.a.i.1. Underground mines, Mining activity

CH_4 emissions		2010	2011	2012	2013	2014	2015	2016	2017	2018
Submission 2025	kt	99.19	97.34	98.53	75.35	77.99	74.01	59.39	47.72	40.67
Submission 2026	kt	83.28	81.64	82.55	63.35	65.78	62.45	49.76	40.04	34.41
Difference	kt	-15.90	-15.70	-15.99	-12.00	-12.21	-11.56	-9.62	-7.68	-6.26
Submission 2026	%	-16.04	-16.13	-16.22	-15.92	-15.66	-15.62	-16.21	-16.10	-15.39
CH_4 emissions		2019	2020	2021	2022	2023				
Submission 2025	kt	31.47	18.62	18.36	14.08	12.12				
Submission 2026	kt	26.61	15.60	15.26	11.70	10.07				
Difference	kt	-4.86	-3.02	-3.10	-2.38	-2.05				
Submission 2026	%	-15.43	-16.21	-16.89	-16.89	-16.89				

Tab. 3-56 Changes after recalculation in CH_4 emissions in 1.B.1.a.i.2. Underground mines, Post - mining Activities

CH_4 emissions		1990	1991	1992	1993	1994	1995	1996	1997	1998	1999	2000	2001	2002	2003
Submission 2025	kt	39.98	36.71	33.12	34.77	32.64	32.75	32.35	30.76	29.61	26.49	26.73	26.04	25.74	24.10
Submission 2026	kt	11.95	11.46	9.82	11.82	10.92	10.58	10.53	10.04	9.77	8.46	8.16	7.11	7.65	7.05
Difference	kt	-28.02	-25.26	-23.30	-22.95	-21.72	-22.18	-21.82	-20.72	-19.83	-18.03	-18.57	-18.93	-18.09	-17.06
Submission 2026	%	-70.10	-68.79	-70.36	-66.00	-66.56	-67.71	-67.45	-67.36	-66.99	-68.06	-69.47	-72.70	-70.28	-70.76
CH_4 emissions		2004	2005	2006	2007	2008	2009	2010	2011	2012	2013	2014	2015	2016	2017
Submission 2025	kt	23.51	23.48	25.18	22.82	22.16	19.22	19.98	19.65	19.95	15.13	15.54	14.73	12.02	9.63
Submission 2026	kt	6.87	6.91	7.32	6.69	6.33	5.47	5.48	5.35	5.38	4.19	4.41	4.20	3.25	2.63
Difference	kt	-16.63	-16.57	-17.87	-16.12	-15.83	-13.75	-14.49	-14.30	-14.57	-10.93	-11.13	-10.53	-8.77	-7.00
Submission 2026	%	-70.75	-70.57	-70.95	-70.66	-71.44	-71.56	-72.56	-72.78	-73.02	-72.28	-71.60	-71.51	-72.98	-72.72
CH_4 emissions		2018	2019	2020	2021	2022	2023								
Submission 2025	kt	8.04	6.23	3.77	3.79	2.90	2.50								
Submission 2026	kt	2.34	1.81	1.02	0.96	0.74	0.63								
Difference	kt	-5.70	-4.43	-2.75	-2.83	-2.17	-1.87								
Submission 2026	%	-70.91	-71.03	-72.99	-74.64	-74.64	-74.64								

Tab. 3-57 Changes after recalculation in CO_2 emissions in 1.B.1.a.i.2. Surface mines, Mining Activities

CH_4 emissions		1990	1991	1992	1993	1994	1995	1996	1997	1998	1999	2000	2001	2002	2003
Submission 2025	kt	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
Submission 2026	kt	86.14	83.18	74.41	71.30	63.55	61.27	64.03	61.62	54.86	48.05	54.61	56.33	53.32	55.06
Difference	kt	86.14	83.18	74.41	71.30	63.55	61.27	64.03	61.62	54.86	48.05	54.61	56.33	53.32	55.06
Submission 2026	%	100	100	100	100	100	100	100	100	100	100	100	100	100	100
CH_4 emissions		2004	2005	2006	2007	2008	2009	2010	2011	2012	2013	2014	2015	2016	2017
Submission 2025	kt	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA

Submission 2026	kt	53.11	53.37	54.24	54.50	52.27	50.03	48.40	51.65	48.23	44.68	42.09	42.02	42.78	43.67
Difference	kt	53.11	53.37	54.24	54.50	52.27	50.03	48.40	51.65	48.23	44.68	42.09	42.02	42.78	43.67
Submission 2026	%	100	100	100	100	100	100	100	100	100	100	100	100	100	100

CH_4 emissions		**2018**	**2019**	**2020**	**2021**	**2022**	**2023**
Submission 2025	kt	NA	NA	NA	NA	NA	NA
Submission 2026	kt	43.41	41.58	32.78	32.68	37.27	31.99
Difference	kt	43.41	41.58	32.78	32.68	37.27	31.99
Submission 2026	%	100	100	100	100	100	100

3.3.1.6 Category-specific planned improvements

Given that the issue of emissions from abandoned mines was included in the same time as the transition to new methodology 2006 IPCC Gl., Tier 1 approach was used. Planned improvements assume a change to a higher level, at least Tier II. In terms of the planned improvements, was ensured cooperation with the specialist on the issue of leakage of methane from abandoned mines in the Ostrava-Karvina coalfield and with experts from the Czech Geological Survey.

In the other sub-sectors no improvements are planned at the present.

3.3.2 Oil and Natural Gas (CRT 1.B.2)

The category is divided according to IPCC 2006 Gl. and ETF Reporting Tool into subcategories:

- 1.B.2.a Oil
  - 1.B.2.a.i. Exploration
  - 1.B.2.a.ii. Production
  - 1.B.2.a.iii. Transport
  - 1.B.2.a.iv. Refining/Storage
  - 1.B.2.a.v. Distribution of Oil Products
  - 1.B.2.a.vi. Other
- 1.B.2.b Natural Gas
  - 1.B.2.b.i. Exploration
  - 1.B.2.b.ii. Production
  - 1.B.2.b.iii. Processing
  - 1.B.2.b.iv. Transmission and Storage
  - 1.B.2.b.v. Distribution
  - 1.B.2.b.vi. Other
- 1.B.2.c Venting and Flaring
  - 1.B.2.c.i. Venting
  - 1.B.2.c.ii. Flaring

3.3.2.1 Category description (CRT 1.B.2)

The structure of the sector, the corresponding activity data, the used emission factors and emissions of individual greenhouse gases can be seen on the following outline.

1.B.2, 2024								
		Activity	CH_4		CO_2		N_2O	
Structure of sector		data	EF	Emission	EF	Emission	EF	Emission
		[PJ]	[t CH_4/PJ]	[kt]	[t CO_2/PJ]	[kt]	[kg N_2O/PJ]	[kt]
1.B.2.a.i.	Exploration	NE						
1.B.2.a.ii.	Production and Upgr.	2.93	4.735	0.014	7.576	0.0222	NA	-
1.B.2.a.iii.	Transport	279.18	0.146	0.041	0.013	0.0037	NA	-
1.B.2.a.iv.	Refining	279.18	0.315	0.088	NA	-	NA	-
1.B.2.a.v.	Distrib. of Oil Prod.	279.18	NA	-	NA	-	NA	-
1.B.2.a.vi.	Other	NO						
1.B.2.b.i.	Exploration	NE						
1.B.2.b.ii.	Production	6.26	37.59	0.235	+)	0.0001	NA	-
1.B.2.b.iii.	Processing	NO						
1.B.2.b.iv.	Transmission and	211.64	11.01	2.331	+)	0.0093	NA	-
	Storage	132.29	2.50	0.331	+)	0.0013	NA	-
1.B.2.b.v.	Distribution	101.37	94.95	9.625	+)	0.0383	NA	-
1.B.2.b.vi.	Other	I.E.						
1.B.2.c.i.	Venting - Oil	2.93	235.4	0.690	48.7	0.1428	NA	-
1.B.2.c.ii.	Flaring - Oil	2.93	0.568	0.002	919.9	2.6976	0.015	0.00004
Total year 2024				**13.357**		**2.915**		**0.00004**
Total year 2023				13.197		2.915		0.00004
Index 2024/2023				1.01		1.00		1.00
Total year 1990				42.695		2.202		0.00003
Index 2024/1990				0.31		1.32		1.43

+) As emission factor is used the average annual CO_2 content in natural gas

The origin of the data, the emission factors used and the method of calculating the level of emissions for each gas is shown in details in the following outline.

2024								
Structure of sector		Source of Activity data	Emission factors			Method used		
			CH_4	CO_2	N_2O	CH_4	CO_2	N_2O
1.B.2.a.i.	Exploration	NE						
1.B.2.a.ii.	Production and Upgrading	CzSO	CS	D	NA	Tier 2	Tier 1	-
1.B.2.a.iii.	Transport	CzSO	D	D	NA	Tier 1	Tier 1	-
1.B.2.a.iv.	Refining	CzSO	CS	NA	NA	Tier 3	-	-
1.B.2.a.v.	Distribution of Oil Products	NA						
1.B.2.a.vi.	Other	NO						
1.B.2.b.i.	Exploration	NO						
1.B.2.b.ii.	Production	CzSO	CS	CS	NA	Tier 2	Tier 2	-
1.B.2.b.iii.	Processing	NO						
1.B.2.b.iv.	Transmission and	CzSO	CS	CS	NA	Tier 2	Tier 2	-
	Storage	ERU	CS	CS	NA	Tier 2	Tier 2	-
1.B.2.b.v.	Distribution	ERU	CS	CS	NA	Tier 2	Tier 2	-
1.B.2.b.vi.	Other	NO						
1.B.2.c.i.	Venting - Oil	CzSO	D	D	NA	Tier 1	Tier 1	-
1.B.2.c.ii.	Flaring - Oil	CzSO	D	D	D	Tier 1	Tier 1	Tier 1

Approximately 96% of fugitive emissions are formed in the Czech Republic from gas industry in extraction, storage, transport and distribution of Natural Gas and in its final use. Crude Oil extraction and refining processes are very less important.

Determination of methane emissions from the processes of refining of Crude Oil is based on the recommended (default) emission factors according to the IPCC 2006 Gl. (IPCC 2006). For years prior to 2000, the maximum values of CH_4 EFs published in the Revised 1996 IPPC Guidelines (Workbook, table 1-6) were selected, this conservative approach attempts to replicate the poor condition of refineries during the 1990s. From 2002 to 2012, the maximum value of the EF CH_4 for developed countries was selected in the IPCC 2006 Guidelines (vol.2 chap.4, table 4.2.4). From 2013 to 2020, the average value of the EF CH_4 for developed countries was selected in the 2006 IPCC Guidelines was used, reflecting recent improvements in the fuel refining process taking place in the Czech Republic.

Methane emissions from the gas industry were determined using national emission factors based on the specific emission factors for the individual parts of the gas industry system.

The graph in Fig. 3-44 gives an overview of the trend in emissions in this category in the time series since 1990.

The graph on Fig. 3-44 shows that the proportion of total CO_2 emissions from the total GHG emissions is negligible (approximately 0.1%).

The contribution of the individual subsectors (Oil and Natural Gas) to the total CH_4 emissions throughout the period in the category 1.B.2 is shown on Fig. 3-44b.

As shown on Fig. 3-44 for the amount of CH_4 emissions in sector 1.B.2. Oil and Natural Gas are therefore



Fig. 3-44 The trend of GHG emissions and the relationship between CO_2 and CH_4 emissions (1.B.2)



Fig. 3-44b The ratio of methane emissions from subsector Oil (1.B.2.a) and Natural Gas (1.B.2.b)

crucial the emissions, produced in the gas industry.

3.3.2.1.1 Oil (CRT 1.B.2.a)

In subcategory Oil are reported emissions from mining, processing of domestic crude oil and emissions from refining of imported crude oil. The share of domestic crude oil is very small - about 1% (from 0.4 to 4.9%). The time profile of domestic production and imports of crude oil in the Czech Republic is shown on Fig. 3-45.

GHG emissions from Crude Oil transport and refining and from Crude Oil production, which is performed in the Czech Republic in combination with mining of Natural Gas, are reported in this category. CO_2 emissions from the refinery resulting from combustion processes (including flaring) are included in 1.A.1.b Crude Oil Refining.



Fig. 3-45 Crude Oil production and import in the CZ in 1990–2024

Exploration (1.B.2.a.i.)

Emissions from this subcategory are not estimated, since activity data are not available, which means that in CRT table notation key "NE" is used. Exploration is not regularly performed in the Czech Republic. The statement of MND a.s. (only company with licence for exploration in the Czech Republic) is that they perform exploration but only very random and this activity do not release emissions at all.

Level of emissions in accordance with paragraph 37(b) of the UNFCCC Annex I inventory reporting guidelines:

"Emissions should only be considered insignificant if the probable level of emissions is less than 0.05% of total national greenhouse gas emissions and does not exceed 500 kt CO_2 equivalent. The total national estimated emissions for all gases and categories considered insignificant must remain below 0.1% of total national greenhouse gas emissions."

The total greenhouse gas emissions of the Czech Republic are: 136.39 million tons of CO_2eq.

Emissions from domestic oil production in the Czech Republic is 0.051 kt CO_2eq.

If the survey represented a whole tenth of mining (exaggerated assumption), then there would be an emission of about 0.0051 kt, which is 0.00003% of the total annual emissions of the Czech Republic - that is 1 300 times lower than the recommended limit. These values are example from the inventory year 2021–2023.



Fig. 3-46 Crude Oil production in the CZ in 1990–2024

Production and Upgrading (1.B.2.a.ii.)

Crude Oil is mined in the Czech Republic in Southern Moravia. The Fig. 3-46 gives the amount of mined Crude Oil in the territory of the Czech Republic.

The quantity of crude oil extracted in each year depends on the amount of recoverable reserves. From Fig. 3-44b is visible that the maximum extraction was in the period from 2003 to 2006. It is expected that the decline in production after 2023 will continue.



Fig. 3-47 Natural Gas production and import in the CZ in 1990–2024

Transport (1.B.2.a.iii.)

Transport of Crude Oil in the territory of the Czech Republic is performed only in closed systems (pipeline transport – Oil pipeline Družba from Russia and Ingolstat from Germany). Default emission factors were used to calculate fugitive CH_4 and CO_2 emissions in this subsector.

Refining (1.B.2.a.iv.)

Crude Oil is processed in the territory of the Czech Republic in two main refinery facilities. The total volume of Crude Oil processed in the Czech Republic is presented in Fig. 3-45.

Distribution of Oil Products (1.B.2.a.v.)

The final products after processing Crude Oil no longer contain dissolved methane or carbon dioxide and thus fugitive emissions are not considered in this subcategory. For completeness, activity data corresponding to the volume of processed Crude Oil in the individual years were recorded in ETF.

Other (1.B.2.a.vi.)

No other operations are considered.

3.3.2.1.2 Natural Gas (CRT 1.B.2.b)

In the subcategory Natural Gas are reported GHG emissions from domestic natural gas production and emissions related to the operation of individual parts of the gas system (import, transit, storage and distribution to end users). The share of the domestic natural gas production is very small - about 2.7% (from 1.7 to 4.9%). The time profile of domestic production and import of natural gas in the Czech Republic is shown on Fig. 3-47.

Exploration (1.B.2.b.i.)

Emissions formed in exploratory boreholes are not reported in this subcategory. This activity is not performed in the Czech Republic, or only completely random.

Production (1.B.2.b.ii.)

Natural Gas is extracted in the Czech Republic in the area of Southern Moravia, accompanying extraction of Crude Oil, and in Northern Moravia, where it is derived from degassing of hard coal deposits. The Fig. 3-48 gives the amount of production Natural Gas in the territory of the Czech Republic.

The development of domestic extraction is relatively stable over time. Fluctuations in individual years are due to technical and geological conditions of mining and market demand.



Fig. 3-48 Natural Gas production in the area of CZ in 1990 – 2024

Processing (1.B.2.b.iii.)

Gas treatments, except for drying, are not performed in the Czech Republic. The drying process is not a source of GHG emissions.

Transmission and Storage (1.B.2.b.iv.)

The calculation of GHG emissions in this subcategory is carried out in two steps; independently. In the first step is carried out an estimation of the emissions for the transit system and high-pressure gas pipelines. This estimate is based on calculation of a pipeline length and the corresponding emission factors. The second step emissions from underground gas storage facilities are taken directly from the operational records of company which provides natural gas storage in the Czech Republic.

A transit gas pipeline runs through the territory of the Czech Republic with a length of 4 058 km. Since 2022 this pipeline is gradually used for domestic Natural Gas transport. Before the war, our network was primarily focused on transit. However, this has shifted due to geopolitical and safety measures in the energy and natural gas markets, as EU countries aim to reduce dependency on Russian fossil fuels. Consequently, there has been a significant shift in the primary direction of gas flow within our country. Those steps led to significant decrease in the final consumption in pipeline transport. Until the conflict in Ukraine is resolved, emissions from this pipeline will be reported in 1.B.2.b.iii.2. In addition to this central gas pipeline, a system of high-pressure gas pipelines is in operation in the territory of the Czech Republic, providing supplies of Natural Gas from the transit gas pipeline and underground gas storage areas to centres of consumption. In 2024, the high-pressure gas pipelines had an overall length of 12 690 km.

This subcategory also includes all the technical equipment on high-pressure gas pipelines. On the transit gas pipeline, this consists primarily of compressor stations and transfer stations, while measuring and regulation stations are located on domestic long-distance gas pipelines.

Methane emissions formed during controlled technical discharge of Natural Gas at compressor stations, during inspections and repairs to pipelines and emissions from pipeline accidents are estimated. These emissions are recorded by the gas companies. In addition, escapes of Natural Gas from leaks in the entire pipeline system, including technical equipment, are also evaluated. The control of calculated data are performed according to the Czech public database IRZ (E-PRTR), where methane emissions are reported on each compression stations (from the reporting treshold 100 t/emissions site).

Emissions from storage (injection and mining) of Natural Gas in the territory of the Czech Republic are reported in this subcategory. The total turnover (injection and mining) of Natural Gas in underground storage areas corresponded to 3 885 mil. m^3 in 2024.

Distribution (1.B.2.b.v.)

Emissions from distribution gas pipelines, with an overall length in 2024 of 74 150 km, and during consumption at the end consumer are reported in this category. The distribution networks are being continuously lengthened and the number of customers is increasing. The large fluctuations in AD in the period 1990–2011 are because for that period AD were collected from individual gas companies. This data collection led to inaccuracies, which were addressed following the availability of updated official statistics from Energy Regulatory Office since 2012. In the beginning of the monitoring period (after 1990), it was necessary to increase technological level of gas facilities. Emissions were calculated from EF, which arise from the length of pipeline, number of customers and regulation stations, to the consumed amount of natural gas in individual years (from the CzSO questionnaire). For the year 2023 the number of gas pressure station control was 4 500 and number of gas use in household and small customers 2 727 457, medium and large costumers 7 807. These data are taken from the yearbook of Energy Regulatory Office.

Other (1.B.2.b.vi.)

No additional emissions are reported.

3.3.2.1.3 Venting and Flaring (CRT 1.B.2.c)

In the Czech Republic there is only one deposit, which is in South Moravia. Crude oil extraction takes place there, along with natural gas production.

Tab. 3-58 gives the CH_4 and CO_2 emissions from Venting for domestic production (mining) of Crude Oil; N_2O emissions are not included in this subcategory since no emission factor is available for their calculation. Tab. 3-58 further contains values of emissions CH_4, CO_2 and N_2O from Flaring in domestic production of Crude Oil. From the table it is clear that this is a minor proportion from the total emissions in whole subcategory Oil and Gas (1.B.2.a).

Tab. 3-58 Emissions of CH_4, CO_2 and N_2O from Venting and Flaring in 1990–2024

	Venting - emissions [t/year]		Flaring - emissions [t/year]		
	CH_4	CO_2	CH_4	CO_2	N_2O
1990	0.49	0.10	0.001	1.92	0.00003
1991	0.68	0.14	0.002	2.64	0.00004
1992	0.80	0.17	0.002	3.14	0.00005
1993	1.09	0.23	0.003	4.25	0.00007
1994	1.25	0.26	0.003	4.90	0.00008
1995	1.43	0.30	0.003	5.59	0.00009
1996	1.49	0.31	0.004	5.82	0.00009
1997	1.60	0.33	0.004	6.24	0.00010
1998	1.75	0.36	0.004	6.85	0.00011
1999	1.81	0.37	0.004	7.06	0.00011
2000	1.73	0.36	0.004	6.76	0.00011
2001	1.81	0.37	0.004	7.06	0.00011
2002	2.62	0.54	0.006	10.24	0.00016
2003	3.13	0.65	0.008	12.23	0.00019
2004	3.02	0.62	0.007	11.78	0.00019
2005	3.08	0.64	0.007	12.05	0.00019
2006	2.62	0.54	0.006	10.23	0.00016
2007	2.44	0.50	0.006	9.52	0.00015
2008	2.39	0.50	0.006	9.35	0.00015
2009	2.19	0.45	0.005	8.58	0.00014
2010	1.76	0.36	0.004	6.86	0.00011
2011	1.65	0.34	0.004	6.44	0.00010
2012	1.56	0.32	0.004	6.08	0.00010

	Venting - emissions [t/year]		Flaring - emissions [t/year]		
	CH_4	CO_2	CH_4	CO_2	N_2O
2013	1.54	0.32	0.004	6.01	0.00010
2014	1.50	0.31	0.004	5.85	0.00009
2015	1.28	0.26	0.003	4.99	0.00008
2016	1.17	0.24	0.003	4.56	0.00007
2017	1.08	0.22	0.003	4.21	0.00007
2018	1.11	0.23	0.003	4.33	0.00007
2019	0.81	0.17	0.002	3.17	0.00005
2020	0.92	0.19	0.002	3.60	0.00006
2021	0.84	0.17	0.002	3.28	0.00005
2022	0.76	0.16	0.002	2.97	0.00005
2023	0.69	0.14	0.002	2.70	0.00004
2024	0.69	0.14	0.002	2.70	0.00004

3.3.2.2 Methodological issues

During the 1990's, Czech refineries have undergone a quite extensive process of innovation and reconstruction, to decrease technical losses of raw materials and final products. Comprehensive verification has been carried out of the seals of the individual fittings, pumps and all the technical equipment. This entire process, which was carried out mainly for economic reasons, also led to a decrease in overall emissions, especially of NMVOCs. Consequently, the emission factors taken from the IPCC GI. (IPCC, 2006) can be considered to correspond to the current technical condition of refineries in this country. In this connection, it should be pointed out that fugitive emissions from refinery technology could not be determined by direct measurements, as they are not connected with specific air outlets or chimneys. Thus, they can be determined only on the basis of professional estimates from balance losses or using emission factors. The resultant emissions of the individual substances were compared with the data in the national emission database and are of the same order of magnitude.

In general, it can be stated that fugitive greenhouse gas emissions occur in this subcategory only in operations in which Crude Oil saturated in carbon dioxide and methane is in contact with the atmosphere. All operations involving Crude Oil in the Czech Republic are hermetically sealed. Thus, fugitive emissions are formed only through leaks in the technical equipment. Following thermal treatment of Crude Oil, the resultant products no longer contain any dissolved gases and no fugitive emissions need be considered in subsequent operations.

3.3.2.2.1 Oil (CRT 1.B.2.a)

CH_4 emissions from Crude Oil transport and refining and from Crude Oil mining, which is performed in the Czech Republic in combination with mining of Natural Gas, are reported in this category. CO_2 emissions from the refinery resulting from combustion processes (including flaring) are included in 1.A.1.b Crude Oil Refining.

Exploration (1.B.2.a.i.)

Exploration is not systematically performed in the Czech Republic. For this reason, there are no known procedures for the determination of emissions in this subsector.

Activity data: number of mined boreholes – notation key NE, default emission factors have not been published for CO_2 and CH_4 – notation key NE. N_2O emissions: notation key NA: N_2O emissions are practically not formed in exploratory work.

Production and Upgrading (1.B.2.a.ii.)

Activity data for determining CH_4 and CO_2 emissions are taken from the CzSO – IEA questionnaires.

CH_4 emissions are determined as the product of annual Crude Oil mining and the emission factor. The emission factor has a value of 0.1771 kg CH_4/m^3 and was determined on the basis of published data in (Zanat et al., 1997). The emission factor was determined as the sum of the individual emission factors from pumping of raw Crude Oil and from storage of raw Crude Oil. These data were obtained by direct measurement. The resultant emission factor, which is used for the calculation of CH_4 emissions is based also on the net calorific values and density of crude oil.

CO_2 emissions are estimated based on the default emission factor (IPCC 2006 Gl. (IPCC 2006), Table 4.2.4, Tier 1 Emission factors for fugitive emissions from Oil and Gas operation in developed countries, page 4.52).

EF CO_2: 2.8E-04 Gg per 10^3 m^3 total oil production = 7 576 kg/PJ

For the estimation of N_2O emissions, no emission factor was available.

Transport (1.B.2.a.iii.)

In this case, the activity data correspond to the total amount of petroleum transported through the territory of the Czech Republic by the pipeline system in the individual years. This amount corresponds to the Total Crude Oil input to refineries. The default emission factors from IPCC 2006 Gl. (IPCC 2006), Table 4.2.4, Tier 1 Emission factors for fugitive emissions from Oil and Gas operation in developed countries, page 4.52 are employed to calculate the CH_4 and CO_2 emissions.

EF CH_4: 5.4E-06 Gg per 10^3 m^3 oil transported by pipeline = 146 kg/PJ

EF CO_2: 4.9E-07 Gg per 10^3 m^3 oil transported by pipeline = 13 kg/PJ

These emission factors were used to calculate fugitive emissions for the years since 1990.

For the estimation of N_2O emissions, no emission factor was available.

Refining (1.B.2.a.iv.)

Methane emissions from refining are calculated using IPCC Tier 1 methodology (Table 4.2.4 in IPCC 2006 Gl. (IPCC 2006)). Emissions are calculated by multiplying the amount of Crude Oil input to refinery by the emission factor. The emission factor value used was 585 kg/PJ.

This emission factor is based on the data from IPCC 2006 Gl. (IPCC 2006), Table 4.2.4, Tier 1 Emission factors for fugitive emissions from Oil and Gas operation in developed countries, page 4.52

EF CH_4: $2.6x10^{-6}$ to $41.0x10^{-6}$ Gg per 10^3 m^3 oil refined = 585 kg/PJ (average)

The value decreased during years and it was due to the improvements in technology of refining. For example, for storage of crude oil, Czech companies use modern technologies contain double floating roof and the bottom of the tank is double with a vacuum gap divided into four separate sections with separate pressure sensors that constantly monitor the tightness. Also during refining processes, they follow BAT document for refining mineral oils.

Based on ERT recommendation (2022CZEQA28) recalculation of emission factor was done for the submission 2021–2023. For the period 1990–1999 the highest emission factor from Guidelines 2006 IPCC (1 148, respectively 1 150 kg/PJ) was used. This conservative approach attempts to replicate the poor

condition of refineries during the 1990s. For 2002–2012, the maximum value of the CH_4 EF for developed countries was taken from the 2006 IPCC Guidelines (vol.2 chap.4, table 4.2.4), which was a linear transition to an average value was applied and since 2013 the average value is used (585 kg/PJ). This average value comes from the minimum and maximum of default emission factor stated in Guidelines 2006 IPCC and reflecting recent improvements in the fuel refining process in the Czech Republic.This recalculation was held in response to the ERT recommendation (2022CZEQA28) and eventhough the emissions are higher, they are still under the threshold of significance for the Czech Republic.

Based on our request the Czech refinery company provide their CH_4 emission data from all their company plant and equipment for years 2023-2024. This is the only company managing refineries in the Czech Republic. After critically assessed by the national expert, these emission data were applied in the national inventory.

The decrease in the iEF is based on the assumption that that there is ongoing "ecologization" of the refineries and oil storage facilities, whereby oil companies invest a significant amount of money to upgrade their equipment to minimize environmental damage. In the past, these investments were mainly aimed to reduce the usual pollutants, including non-methane volatile organic compounds (NMVOCs). The equipment upgrades aimed to reduce NMVOCs also led to a decrease in CH_4 emissions from 1.B.2.iv (refining/storage). The operators in the Czech Republic are legally required to estimate and report NMVOC emissions in the integrated central system, which uses these data for national environmental policy decisions as well as for international reporting (e.g under European Monitoring and Evaluation Programme). For better expression of the situation a graph, which demonstrated the correlation between the EF for CH_4 emission from 1.B.2.iv (refining/storage) and that for NMVOCs, is shown in Fig. 3-49. The graph clearly showed that the decrease in EF for NMVOC, which is based on direct reporting by operators (i.e. tier 3), is even more significant than the decrease in CH_4 emission factor used for the GHG inventory.



Fig. 3-49 Correlation between EF for NMVOC and CH_4 emissions.

The IPCC method does not give any EF for CO_2 or N_2O. Consequently, the notation key NA is used in ETF.

Distribution of Oil Products (1.B.2.a.iii.5)

The available IPCC methodology does not provide any EF for CO_2, CH_4 or N_2O – notation key – NA. The products which originate during oil processing cannot contain CO_2 or CH_4. There is not known process by which could arise fugitive CO_2 or CH_4 emissions during the distribution of oil products.

Other (1.B.2.a.vi.)

Activity data: notation key: NO; CH_4, CO_2 and N_2O emissions – notation key NO.

3.3.2.2.2 Natural Gas (CRT 1.B.2.b)

Leakages in the distribution network and household distribution pipes can be considered to constitute the most serious source of emissions. In the 1990's, the distribution network was newly constructed almost entirely from welded plastics and the old pipeline was reconstructed to a major degree in the same manner. Household distribution pipes are subject to strict standards and any poor seals can be identified by the characteristic smell. In addition to safety aspects, all leakages also have an economic impact both for the distribution company and for the end user, so this aspect is carefully monitored and, as soon as

possible, immediately remedied. As a whole, the gas distribution in the CZ is at a high technical level and it can be stated that all leakages are carefully sought out and eliminated.

As a method was developed in the last few years for determining methane emissions in the gas industry using specific emission factors, this sophisticated method of calculation continues to be used, although, from the standpoint of ref. (IPCC 2006), calculation using default values would probably suffice. Qualified estimation of methane emissions is thus carried out using specific emission factors for the individual parts of the gas industry system (Table 4.2.8. Classification of Gas losses as low, medium or high at selected types of Natural gas facilities, IPCC 2006 Gl. (IPCC 2006), page 4.71). Emission factors were determined by the International Gas Union (IGU) in 1998 in Study Group 8.1 Methane Emissions (Gas and the Environment, 2000). These EF were corrected on the basis of consultation with Czech Gas experts to the Czech conditions (technical conditions of the individual parts of the gas supply system).

Companies from the gas industry are preparing on the fulfilling demands from Regulation of the European parliament and the council on methane emissions reduction in the energy sector and amending Regulation (EU) 2019/942. Partial results could already be used in the submission 2023/2025, as it can be seen from the Tab. 3-60. The total emissions are summarized in the Tab. 3-61.

The total emission value given corresponds to about 0.17% of the total consumption of Natural Gas in the Czech Republic. The detailed calculation given corresponds to Tier 2.

In general, it can be stated that the determined methane emissions in category 1.B.2 Gas are basically formed in several ways:

- through poor seals in the flanges and joints, fittings, probes in mining and storage fields and other parts of the pipeline system,
- through pipeline perforation,
- through technical discharge of gas into the air,
- through accidents.

Exploration (1.B.2.b.i.)

Exploration of Natural gas is not carried out in the Czech Republic regularly, but only very randomly. Therefore, notation key NE was used in CRT Report tables for the emissions and activity data. The statement of MND a.s. (only company with licence for exploration in the Czech Republic) is that they perform exploration but only very random and this activity do not release emissions at all, see chapter *Exploration (1.B.2.a.i.)* for more explanation.

Production (1.B.2.b.iii.)

There are three companies holding licences for natural gas mining in the Czech Republic. All three companies were contacted with a request to provide emission data and/or emission factors. All companies provided data for the year 2024, which were applied in the 2026 submission. The resulting calculation corresponds to a Tier 3 approach.

Transmission and Storage (1.B.2.b.iv.)

This subcategory is composed of transit gas pipelines, very high-pressure and high-pressure pipelines and compression stations. Before the war in Ukraine, our network was primarily focused on transit. However, this has shifted due to geopolitical and safety measures in the energy and natural gas markets, as EU countries aim to reduce dependency on Russian fossil fuels. Consequently, there has been a significant shift in the primary direction of gas flow within our country and the activity data has been reduced in that time.

The emission factors were taken from the 2006 IPCC Guidelines Table 4.2.8. In this Table, values are following: low = 200 m^3/km/yr, medium = 2000 m^3/km/yr, high = 20 000 m^3/km/yr for Transmission Pipeline System. The difference between low EF and medium EF seems to us to high, thus we used middle value 600 m^3/km/yr for very high-pressure and high-pressure pipelines in previous inventory years. Due to reduction of natural gas transported by pipelines and thus reducing the emissions, we use EF 200 m^3/km/yr for the year 2023, 2024. Thanks to this, the consistent emission factors are used for all activity data in Trasmission subcategory. Detailed information is described in Tab. 3-59.

Tab. 3-59 Emission factors and CH_4 emissions for transmission

Year	EF CH_4 Transit gas pipelin [m^3/km/year]	CH_4 Emission Transit gas pipelin [t/year]	EF CH_4 Very high and high presure pipelin [m^3/km/year]	CH_4 Emission Very high and high presure pipelin [t/year]	CH_4 Emission Compression station (IRZ) [t/year]	CH_4 Emission Transmission Sum [kt/year]
2020	200	500.55	600	5 057.83	556.65	6.12
2021	200	500.55	600	5 044.48	632.15	6.18
2022	200	534.11	600	5 024.62	512.76	6.07
2023	200	534.10	200	1 670.68	219.29	2.42
2024	200	534.09	200	1 670.01	127.10	2.33

There is only one company operating in the Czech Republic in the Transmission subcategory. The company was contacted with a request to provide emission data and/or emission factors repeatedly in years 2023, 2024, and 2025. However, the requested information was not made available. The data enforceability based on Regulation (EU) 2024/1718 can not be applied because the Czech implementing legislation has not yet been adopted, companies did not submit emission reports in 2025.

From the submission 2025 the activity data and emission from Storage are reported in this subcategory.

Distribution (1.B.2.b.v.)

In the Czech Republic, three main companies operate in the natural gas Distribution subcategory, with the largest company GasNet s.r.o. supplying natural gas to approximately 81% of customers. GasNet s.r.o. has been publishing its Sustainability Report since 2020, which includes information on its fugitive methane emissions. These data were fully incorporated into the national inventory in the 2026 submission. To avoid double counting, emission estimates calculated by GasNet s.r.o. were used as the basis, and emissions corresponding to the remaining approximately 19% of the market were added proportionally. GasNet s.r.o. applied the Marcogaz (2019) methodology for the quantification of its emissions.

The reduction observed in 2022 and the slight increase in 2023 are attributable to higher technological leakages reported by GasNet s.r.o. in 2023, resulting from the initiation of reconstruction works on the distribution system. These measures are expected to lead to a decrease in fugitive emissions in the future.

Other (1.B.2.b.vi.)

1.B.2.b.vi. is reserved for "others". Until the submission 2025 we have used this "empty" category only to report the volume of stored gas, since separately stored gas cannot be reported anywhere else. Gas storage is reported according to the IPCC methodology in subcategory 1.B.2.b.iv. (transit and storage) together with emissions from transit transport. The data in 1.B.2.vi. should only be taken as additional information. From the submission 2025, the new ETF system did not allow us to fill 1.B.2.b.vi. subcategory anyway. It was decided to moved activity data from 1.B.2.b.vi to the subcategry 1.B.2.b.iv. which already contains emissions for Storage Based on this change recalculation has to be done for the whole time series.

Fugitive methane emissions are calculated in these subcategories using an internal calculation model based on the methodology proposed in 1997 in IGU (Alfeld, 1998). Calculations of emissions are supplemented by data from the national Integrated Pollution Register (IPR) and investigations at individual distribution companies on registered units of Natural Gas and in this submission also from direct data on methane emissions from some gas companies.

Tab. 3-60 Model calculation of CH_4 emissions in the Natural Gas sector (2024)

	EF		Activity data		Losses of NG	Only methane*)
	value	units	value	units	[mil.m³/year]	
Production	0.2	% vol.	179.2	mil. m³	0.36	0.337
Total production						0.337
High pressure pipelines	200	m³/km.year	12 690	km	2.538	2.386
Transmission pipelines	200	m³/km.year	4 058	km	0.812	0.763
Compressors **)						0.182
Storage ***)						0.472
Total Transmission and storage						3.80
CNG filling to cars	0.47	% vol.	92.286	mil. m³	0.430	0.404
Technological leaks***)						0.548
Fugitive leaks***)						9.625
Regulation stations and measurement	1 000	m³/pc.year	940.5	pc	0.941	0.884
Distribution networks	300	m³/km.year	3 456	km	1.037	0.975
Number of customers	2	m³/consumer	585 346	pc	1.171	1.100
Total distribution						13.54
Total 1.B.2.b - Gas			12.37	12.37	12.37	17.68
Emissions in Gg (0.7 kg/m³)						**12.37**

*) *conversion to methane content in natural gas x 0.94*
**) *data from IRZ (Integrated Pollution Register of CZ version of E-PRTR)*
***) *data from operating register of leakage Natural Gas - Czech Gas Companies*

Emissions calculated in this model are then transformed to the structure of the sectors and subsectors according to the IPCC methodology.

Tab. 3-61 Recapitulation of methane emissions in 1.B.2.b – Gas.

Total production	0.235
Total Transmission and storage	2.662
Total Distribution	9.625
Total 1.B.2.b - Gas	**12.522**

3.3.2.2.3 Venting and Flaring (CRT 1.B.2.c)

The estimations of CO_2, CH_4 and N_2O emissions from venting and flaring in the course of oil production were obtained by using the default EFs provided by the IPCC 2006 Gl. (IPCC 2006) (see table 4.2.4, pages 4.48 – 4.54). In this case the following EFs were taken:

Venting (Default Weighted Total)

CH_4: 8.7E-03 Gg per 10^3 m^3 total oil production

CO_2: 1.8E-03 Gg per 10^3 m^3 total oil production

N_2O: NA

Flaring (Default Weighted Total)

CH_4: 2.1E-05 Gg per 10^3 m^3 total oil production

CO_2: 3.4E-02 Gg per 10^3 m^3 total oil production

N_2O: 5.4E-07 Gg per 10^3 m^3 total oil production

Owing to the fact that activity data are required in kg/PJ, the value was converted to kg/PJ by using the typical value of density for crude oil of 880 kg/t and value NCV was taken from CzSO questionnaires IAE as a simple average for domestic oil (42 MJ/kg):

Venting

CH_4: 235 390 kg/PJ

CO_2: 48 701 kg/PJ

Flaring

CH_4: 568.2 kg/PJ

CO_2: 919 913 kg/PJ

N_2O: 14.61 kg/PJ

3.3.2.3 Uncertainties and time-series consistency

The inventory methods used in this inventory were consistently employed across the whole reporting period from the base year of 1990 to 2024.

In 2020 was carried out an extensive study aiming to update the uncertainties in the sector 1.B.2. From the study follows that in this category higher uncertainties should be expected than in 1.A. During fuel mining/production is expected relatively high uncertainties due to used measuring instruments (for large quantities - millions of tonnes have relatively low accuracy) as well as the overall difficult operating conditions. Conversely, imports and exports of raw materials are sensitive economic data and low uncertainties should be expected. Venting and flaring is minor subcategory in inventories of the Czech Republic, but this subcategory is less explored than others and thus the uncertainties are quite high.

The emission factors for determining emissions in extraction of Natural Gas and Crude Oil are based on specific measurements. Emission factors used to determine emissions in transport and distribution of Natural Gas are based on isolated measurements and estimates by experts in the gas industry. Determination of gas leaks in technical operations, starting-up of compressors and accidents, as appropriate, are evaluated on the basis of calculations with knowledge of the necessary technical parameters, such as the gas pressure, pipeline volume, etc. The uncertainties then correspond to knowledge of these technical parameters.

The determination of uncertainties was carried out according the same methodology as in case of category 1.A i.e. three independent experts estimate of 'basic' uncertainties, which were averaged (see chapter 3.2.5 or for details Veselá et al., 2020).

For specific uncertainties used for introduction into the trend in total national emissions see Annex 2.

3.3.2.4 Category-specific QA/QC and verification

General quality control and source-specific quality control (Tier 1 and Tier 2), in conformance with the requirements of the QSE handbook and its associated applicable documents, have been performed to the full extent.

QC activities at the level of Tier 1 were performed according to the QA/QC plan by the sector compiler. Routine control was performed in the framework of the following activities:

- activity data employed,
- emission factors employed,
- calculation procedures employed,
- transfer of numerical data from the working set to the ETF Reporting Tool.

In control of the emission factors employed, the emission factors used in the Czech Republic methodology were compared with the emission factors of Slovakia, Poland and Germany in the context with the default emission factors. It was found that the emission factors employed for calculation of emissions in the Czech Republic methodology correspond, in their range, to the emission factors employed in the other countries. Comparison of the emission factors used in the Czech Republic with the emission factors of the surrounding countries corresponds to the level of Tier 2.

Control of the transfer of numerical data from the working set to the ETF Reporting Tool did not reveal any differences.

The final working set in EXCEL format was locked to prevent intentional rewriting of values and archived at the coordination workplace.

The protocols on the performed QA/QC procedures are stored in the archive of the sector compiler.

3.3.2.5 Category-specific recalculations

The new obtain data was used for subcategory 1.B.2.a.iv. Oil – Refining/Storage and CH_4 emission was updated for the year 2023, see the Tab. 3-62. Based on the recommendation from EU review CZ-1B2b-2025- 0001 was recalculated emissions in 1.B.2.b.v. Distribution in 2021. The main Czech distribution company made update in their emission data; therefore, the emissions was corrected in 2020 and 2022, 2023, see the Tab. 3-63.

Tab. 3-62 Changes after recalculation in CH_4 emissions in 1.B.2.a.iv. Oil – Refining/Storage

Fuel consumption		2023
Submission 2025	TJ	0.19
Submission 2026	TJ	0.08
Difference	TJ	-0.11
Submission 2026	%	-58.62

Tab. 3-63 Changes after recalculation in CO_2 and CH_4 emissions in 1.B.2.b.v. Distribution

Fuel consumption		2020	2021	2022	2023
Submission 2025	TJ	125.99	132.61	110.05	98.51
Submission 2026	TJ	125.99	132.61	110.05	98.51
Difference	TJ	0.00	0.00	0.00	0.00
Submission 2026	%	0.00	0.00	0.00	0.00
CO_2 emissions		2020	2021	2022	2023
Submission 2025	kt	0.065	0.065	0.043	0.045
Submission 2026	kt	0.036	0.046	0.036	0.037
Difference	kt	-0.029	-0.019	-0.007	-0.008
Submission 2026	%	-45.220	-29.303	-15.371	-17.501

CH_4 emissions		2020	2021	2022	2023
Submission 2025	kt	16.290	16.294	10.699	11.362
Submission 2026	kt	8.924	11.519	9.055	9.374
Difference	kt	-7.366	-4.775	-1.645	-1.989
Submission 2026	%	-45.220	-29.303	-15.371	-17.501

3.3.2.6 Category-specific planned improvements

When the Czech implementing legislation related to Regulation (EU) 2024/1787 on the reduction of methane emissions will be adopted, is planned to switch to data from individual company reports.

3.4 CO_2 transport and storage (CRT 1.C)

Not performed in the Czech Republic.

4 Industrial processes and product use (CRT Sector 2)

The sector of industrial processes of GHG emission inventory includes emissions from technological processes and not from fuel combustion used to supply energy for carrying out these processes. Consistent emphasis is put on the distinction between the emissions from fuel combustion in the Energy sector and the emissions from technological processes and production.

For example, in the production of cement, consideration is given only to emissions derived from the thermal decomposition of mineral raw materials (specifically CO_2 emissions from the decomposition of limestone) and not from fuel used to heat the rotary kiln (considered in category 1.A.2.f). However, the situation in iron and steel production is more complicated. Evaluation of the CO_2 emissions is based on consumption of metallurgical coke in blast furnaces, where coke is used dominantly as a reducing agent (iron is reduced from iron ores), even though the resulting blast furnace gas is also used for energy production, mainly in metallurgical plants.

In 2024, the total aggregate GHG emissions from industrial processes were 11 102.40 kt of CO_2 equivalents, which represents a decrease of 12.58% compared to the previous year. The decline was driven by several factors across different subcategories, in particular high interest rates, expensive energy and raw materials. Emissions decreased by 35.13% compared to the reference year 1990.

The Czech Republic declines any responsibility for errors caused by the UNFCCC ETF reporting tool, the latest version 1.30.5 of the ETF tool from the 9th of December 2026 was used for creating the submission. CRT table cells, which do not affect the national total, may still have an empty cell instead of NA or NO and have Tier and method parameters missing in the automated summary sheets due to bugs in the ETF reporting tool; even sector background table white cells have been successfully filled by the sector expert. For more information on completeness and the ETF bugs, please see Annex 5.6.

4.1 Overview of sector

4.1.1 General description and key categories identification

The major share of CO_2 emissions in this sector comes from sub-source categories 2.C.1 Iron and Steel Production, 2.F.1 Refrigeration and Air Conditioning and 2.A.1 Cement production; these three subcategories cover almost 8% of total emissions (excl. LULUCF). N_2O emissions coming from 2.B Chemical Industry are less significant. Tab. 4-1 gives a summary of the main sources of direct greenhouse gases in this sector, shows the share of national emissions in 2024 and lists the type of key category analysis for key categories.

Tab. 4-1 Overview of key categories in sector Industrial Processes (2024)

Category	Gas	KC A1	KC A2	KC A1[1]	KC A1[2]	KC A2[1]	KC A2[2]	% of total GHG[1]	% of total GHG [2]
2.F.1 Refrigeration and Air conditioning	F-gases	LA, TA	LA, TA	Yes	Yes	Yes	Yes	3.76	3.58
2.C.1 Iron and Steel Production	CO_2	LA, TA	LA, TA	Yes	Yes	Yes	Yes	3.30	3.14
2.A.1 Cement Production	CO_2	LA		Yes	Yes			1.58	1.51
2.B.8 Petrochemical and Carbon Black Production	CO_2	LA, TA	LA, TA	Yes	Yes	Yes	Yes	1.01	0.96
2.A.4 Other Process Uses of Carbonates	CO_2	LA, TA		Yes	Yes			0.54	0.52

2.B.1 Ammonia Production	CO_2	LA		Yes	Yes		0.47	0.45
2.A.2 Lime Production	CO_2	LA		Yes	Yes		0.43	0.41
2.B.2 Nitric Acid Production	N_2O	TA	TA	Yes	Yes	Yes	0.10	0.09

KC: key category
[1] including LULUCF
[2] excluding LULUCF

4.1.1 Emissions trends



Fig. 4-1 Trend of emissions from IPPU [kt CO_2 eq.]

This chapter describes the emissions of greenhouse gases in a more disaggregated way than chapter 2: Trends in Greenhouse Gas Emissions.

GHG emissions in this category are driven mainly by economic development, supply and demand of products, where abatement technology is used only in specific cases (e.g. nitric acid production), or the driving force is different (e.g. substitutes to ozone depleting substances). GHG emission trend from Industrial Processes and Product Use from base year 1990 to 2024 is depicted in Fig. 4-1. CO_2 eq. emissions have shown a stable trend since 2010 with slightly increasing fluctuations. In category 2.C Metal production, emissions fell sharply due to the bankruptcy and final closure of one of the two largest steel producers in the Czech Republic. In category 2.A Mineral industry, ongoing reduced demand in the construction sector led to lower production of cement and lime, resulting in decreased process emissions. For category 2.F Use of fluorinated gases, the continued impact of EU regulation on F-gases contributed to reduced consumption of high-GWP gases and lower emissions. Overall, these developments reflect both structural changes in the Czech industry and short-term market conditions, leading to a significant year-on-year reduction in emissions from industrial processes.



Fig. 4-2 Emissions from principal subcategories of IPPU [kt CO_2 eq.]

GHG emission trends for the principal categories of IPPU are depicted in Fig. 4-2 for the years 1990, 1995, 2000, 2005, 2010, 2015, 2020 and 2024. Emissions in 2009 and 2010 were rather influenced by the economic crisis, and in 2019 and 2020 by the Covid-19 pandemic. Emissions from category 2.A decreased by 39% compared to 1990. A decreasing trend of emissions is observed also for categories 2.B and 2.C. Emissions decreased by 41% for 2.B and by 69% for 2.C compared to 1990. It can be seen that the emissions of fluorinated greenhouse gases from category 2.F have been increasing since 1995, peaked around 2019, and are now showing a decreasing

trend. A brief description of the relevant category trends is provided for all the categories in the following chapters. Tab. 4-2 lists all categories under the IPPU sector with the indicated type of emissions.

Tab. 4-2 Overview of categories in sector Industrial Processes and Product Use (2024)

IPCC Category	Emissions							
	CO_2	CH_4	N_2O	HFCs	PFCs	SF_6	NF_3	HFOs[1]
2.A Mineral Industry	x							
2.B Chemical Industry	x	x	x					
2.C Metal Industry	x	x						
2.D Non Energy Products from Fuels and Solvent Use	x							
2.E Electronics Industry				x	x	x	x	
2.F Product Uses as Substitutes for ODS				x	x			
2.G Other Product Manufacture and Use			x			x		
2.H Other	x							x

[1] *Hydrofluoroolefins (HFO-1234yf and HFO-1234ze)*

4.2 Mineral Industry (CRT 2.A)



Fig. 4-3 Trend of emissions from 2.A Mineral Industry and share of specific subcategories [kt CO_2]

This category describes GHG emissions from the non-combustion processes from the following categories: 2.A.1 Cement Production, 2.A.2 Lime Production, 2.A.3 Glass Production, 2.A.4 Other Process Uses of Carbonates.

Emission trend for category 2.A Mineral Industry is depicted in Fig. 4-3. The major share 59% belongs to 2.A.1 Cement Production, 16% belongs to 2.A.2 Lime Production, 5% belongs to 2.A.3 Glass Production and 20% to 2.A.4 Other Process Uses of Carbonates. Tab. 4-3 lists the CO_2 emissions in the individual subcategories in 2.A Mineral Products in 2024.

Tab. 4-3 CO_2 emissions in individual subcategories in 2.A Mineral Products category in 1990–2024

	Category 2.A - CO_2 emissions [kt]					
	2.A.1 Cement Production	2.A.2 Lime Production	2.A.3 Glass Production	2.A.4.a Ceramics	2.A.4.b Other use of Soda Ash	2.A.4.d Other
1990	2 489.18	1 336.65	142.75	113.86	NO	NE,NO
1991	2 308.92	844.66	122.40	89.98	NO	NE,NO
1992	2 468.42	831.46	120.77	85.36	NO	NE,NO
1993	2 194.55	778.67	117.14	105.49	NO	NE,NO
1994	2 208.38	806.53	126.65	108.31	NO	NE,NO
1995	2 005.01	817.53	96.05	100.49	NO	NE,NO
1996	2 116.49	830.73	101.01	123.10	NO	76.00
1997	2 083.36	852.73	111.98	146.87	NO	240.63
1998	2 067.65	797.00	116.83	200.61	NO	417.31
1999	1 962.91	787.47	120.29	145.88	NO	536.94

2000	1 936.86	828.53	138.18	177.02	NO	552.77
2001	1 628.84	827.06	138.88	156.33	0.10	571.20
2002	1 403.48	815.33	155.73	113.01	0.21	576.40
2003	1 484.85	808.00	163.47	119.83	0.33	589.07
2004	1 626.76	808.73	191.86	118.51	0.44	584.10
2005	1 624.53	762.82	190.94	141.15	0.47	625.84
2006	1 748.45	758.02	202.02	109.05	0.35	627.62
2007	2 043.08	794.07	194.87	135.06	0.50	659.02
2008	1 996.15	742.01	175.38	112.43	0.56	648.19
2009	1 566.08	625.43	153.46	90.78	0.41	639.40
2010	1 469.00	655.77	127.78	100.43	0.86	694.57
2011	1 664.53	676.44	113.84	100.31	1.06	800.61
2012	1 517.15	597.44	128.09	108.31	1.09	740.32
2013	1 331.79	612.99	126.25	116.73	1.03	723.73
2014	1 482.73	630.90	135.23	89.94	1.11	710.00
2015	1 558.16	611.54	151.96	68.64	1.01	692.93
2016	1 697.60	639.82	138.06	70.26	1.01	673.52
2017	1 728.27	673.53	155.01	79.03	1.15	661.44
2018	1 867.54	749.37	147.68	90.41	0.75	649.40
2019	1 977.24	680.95	143.60	110.04	0.79	529.87
2020	1 891.03	650.80	138.83	104.32	0.81	432.66
2021	1 957.87	667.02	143.92	91.17	1.00	582.98
2022	1 846.97	555.89	145.87	100.01	0.99	629.70
2023	1 483.05	416.56	132.50	46.87	0.79	516.08
2024	1 449.97	397.91	131.66	43.59	0.68	451.79

Tab. 4-4 gives an overview of the emission factors and methodology used for computations of emissions in category 2.A Mineral Products in 2024.

Tab. 4-4 CO_2 emission factors and methodology used for computations of 2024 emissions and removals in category 2.A

IPCC Category	Emission factor CO_2	Unit	Source or type of EF	Methodology
2.A.1 Cement Production	0.52	t CO_2/t sinter	EU ETS	Tier 3
2.A.2 Lime Production	0.77	t CO_2/t CaO	CS	Tier 3
2.A.3 Glass Production	0.11	t CO_2/t Glass	EU ETS	Tier 3
2.A.4.a Ceramics	0.13	t CO_2/tiles thousand m^2	CS (EU ETS)	Tier 3
	0.04	t CO_2/brick unit	CS (EU ETS)	Tier 3
	C	t CO_2/roofing tiles	CS (EU ETS)	Tier 3
2.A.4.b Other Uses of Soda Ash	C	t CO_2/t soda ash	PS	Tier 3
2.A.4.d Other Flue-gas desulfurisation	0.44	t CO_2/t desulfurated flue-gas	CS (EU ETS)	Tier 3
Mineral wool production	0.25	t CO_2/t mineral wool	Default (IPCC 2006)	Tier 1
Denitrification	0.73	t CO_2/t urea	CS (EU ETS)	Tier 3

The column source or type of EF indicates the way how the certain emission factor determined was. Detailed information for each emission factor is given in the relevant chapters.

4.2.1 Cement Production (CRT 2.A.1)

CO_2 emissions from cement production have decreased since 1990 by 42%. Total CO_2 emissions equal to 1 449.97 kt in 2024. The decrease in the emissions during the 1990's was caused by the transition from a planned economy to a market economy. This led to a decline in industrial production and consequently to a decrease in emissions. Since 2003, the cement production has begun to recover and production has increased. The decrease in emissions since 2008 was caused by the economic crisis and related construction constraints. A decline in demand for cement and building materials due to the economic slowdown, lower investment in the construction sector and a reduction in new construction projects led

to a lower need for cement production in 2024. Cement production was identified as a key category in this year's submission.

4.2.1.1 Source category description

Cement production is one of the traditional anthropogenic sources of carbon dioxide included in inventories; however, its importance is incomparably smaller than the total combustion of fossil fuels. Approx. 60% of the CO_2 is emitted during the transformation of raw materials (mainly decarbonisation of limestone). Process-related CO_2 is emitted during the production of clinker (calcination process) when calcium carbonate ($CaCO_3$) is heated in a cement kiln up to temperatures of about 1 500 °C. During this process, calcium carbonate is converted into lime (CaO - calcium oxide) and carbon dioxide. CO_2 emissions from combustion processes taking place in the cement industry (especially heating of rotary kilns) have been reported in IPCC category 1.A.2.f Limestone (and dolomite). This category also contains a small amount of magnesium carbonate ($MgCO_3$) and fossil carbon (C), which will also calcinate or oxidize in the process, causing CO_2 emissions.

4.2.1.2 Methodological issues

CO_2 emissions from 2.A.1 Cement Production are calculated according to the Tier 3 methodology described in IPCC 2006 Gl. (IPCC 2006). This methodology describes an approach based on direct data from individual operators of cement kilns.

Four cement plants operate in the Czech Republic. Information submitted directly by the cement kiln operators is available for the years 1990, 1996, 1998–2002 and 2005–2024. For these years, the emission factor value was derived from CCA (Czech Cement Association) data (activity data about production of clinker) and individual installation data about emissions. For the years 1991–1995, 1999–2001 EFs were interpolated. Since 2010, CO_2 emissions has been based on data submitted by the cement kiln operators in the EU ETS system. The EU ETS system covers all cement kiln operators in the Czech Republic. The content of calcium/magnesium oxide (CaO/MgO) and the composition of the limestone and dolomite are measured and independently verified. These parameters are used for the calculation of the CO_2 emissions and, therefore, substantial attention is devoted to their determination.

The methodology used for CO_2 emissions must be in accordance with national legislation (Zákon 383/ 2012 o podmínkách obchodování s povolenkami na emise skleníkových plynů/Act No. 383/2012 Coll., the Greenhouse Gas Emission Allowance Trading Act) and the EU legislation (Commission Decision of 18 July 2007 establishing guidelines for the monitoring and reporting of greenhouse gas emissions pursuant to Directive 2003/87/EC of the European Parliament and of the Council).

All operating cement plants in the Czech Republic are equipped with dust control technology and the dust is then recycled to the kiln. Use of dolomite or the amount of magnesium carbonate in the raw material, as well as fossil carbon (C) content is known; all above mentioned variables are used for emission estimates in the EU ETS system.

Data on cement clinker production is published yearly by the Czech Cement Association (CCA), which associates all Czech cement producers. Clinker production data, together with interpolated EFs, were used for years without direct data from cement kiln operators (1991–1995, 1999–2001). IEF, which is calculated based on CO_2 emissions and clinker production, varies during the whole time series from 0.518 to 0.553 t CO_2/t clinker.

Tab. 4-5 introduces the activity data for clinker production, emission factor and CO_2 emissions for the whole time series.

Tab. 4-5 Activity data, CO_2 emission factor and CO_2 emissions in 2.A.1 Cement Production category in 1990–2024

	Unit	1990	1991	1992	1993	1994	1995	1996	1997	1998	1999
Clinker production	[kt]	4 726.0	4 368.0	4 653.0	4 122.0	4 134.0	3 740.0	3 934.0	3 829.0	3 758.0	3 547.0
EF CO_2	[t CO_2/ t clinker]	0.527	0.529	0.531	0.532	0.534	0.536	0.538	0.544	0.550	0.553
CO_2 emissions	[kt]	2 489.2	2 308.9	2 468.4	2 194.6	2 208.4	2 005.0	2 116.5	2 083.4	2 067.7	1 962.9
	Unit	**2000**	**2001**	**2002**	**2003**	**2004**	**2005**	**2006**	**2007**	**2008**	**2009**
Clinker production	[kt]	3537.0	2954.0	2549.0	2725.0	3017.0	3045.1	3287.7	3837.0	3758.7	2923.2
EF CO_2	[t CO_2/ t clinker]	0.548	0.551	0.551	0.545	0.539	0.533	0.532	0.532	0.531	0.536
CO_2 emissions	[kt]	1936.9	1628.8	1403.5	1484.9	1626.8	1624.5	1748.5	2043.1	1996.1	1566.1
	Unit	**2010**	**2011**	**2012**	**2013**	**2014**	**2015**	**2016**	**2017**	**2018**	**2019**
Clinker production	[kt]	2748.5	3132.3	2837.6	2472.2	2792.1	2919.2	3188.1	3236.0	3514.3	3722.2
EF CO_2	[t CO_2/ t clinker]	0.534	0.531	0.535	0.539	0.531	0.534	0.532	0.534	0.531	0.531
CO_2 emissions	[kt]	1469.0	1664.5	1517.1	1331.8	1482.7	1558.2	1697.6	1728.3	1867.5	1977.2
	Unit	**2020**	**2021**	**2022**	**2023**	**2024**					
Clinker production	[kt]	3556.0	3673.0	3497.0	2814.3	2796.9					
EF CO_2	[t CO_2/ t clinker]	0.532	0.533	0.528	0.527	0.518					
CO_2 emissions	[kt]	1891.0	1957.9	1847.0	1483.1	1450.0					

4.2.1.3 Uncertainties and time-series consistency

In 2012, research was conducted in order to develop new uncertainty estimates. The uncertainties for this category are based on the IPCC 2006 Gl. (IPCC 2006). Since the Tier 3 method is used for determining emissions in this category, the uncertainties were estimated at the level of 2% both for activity data and emission factors. Overall uncertainty data are given in Chapter 1.6.

Time series consistency is ensured as the inventory approaches concerned are employed identically across the whole reporting period from the base year 1990 to 2024.

4.2.1.4 Source-specific QA/QC and verification

The input information and calculations are archived by the sectoral expert and the coordinator of NIS.

Verification is provided by comparison of the activity data obtained from CCA, CzSO, ISPOP and EU ETS. The cement clinker production data provided by CCA, which are used as input activity data for the submission, are compared with data provided by CzSO, ISPOP and data obtained from EU ETS forms. The percentage differences between cement production data for 2024 obtained from CCA and other sources are as follows:

- Difference between the data from CCA and CzSO: 0.001%
- Difference between the data from CCA and ISPOP: 0.001%
- Difference between the data from CCA and EU ETS: 0.003%

In addition to verification of the input data, the inter-annual changes in the implied emission factors are analysed. The EU ETS reports, which have been used for emission estimates since 2010, have been substantiated by independent verifiers.

The quality control was held by fulfilling the QA/QC form presented in A 4.1.

4.2.1.5 Source-specific recalculations, including changes made in response to the review process and impact on emission trend

This year, no recalculations were performed in this sector.

4.2.1.6 Source-specific planned improvements, including tracking of those identified in the review process

Since the Tier 3 method is used for emission calculations in this category, no significant improvements are planned.

4.2.2 Lime Production (CRT 2.A.2)

CO_2 emissions from lime production have decreased considerably since 1990 by 70%. The decrease in emissions between 1990 and 1991 was caused by the transition from a planned economy to a market economy and the closing of lime kilns, together with a decrease in industrial production. Since then, lime production has varied slightly around 1 100 kt/year. In 2012, the production of lime dropped to a longterm minimum of 758.07 kt. In 2024, production of lime decreased by 26.35 kt compared to the previous year to a new minimum of 518.93 kt. The production of lime in 2024 was impacted by a decline in demand in the construction sector, rising energy prices and a slowdown in industrial sectors, leading to an overall decrease in output. Local lime production is still identified as a key category in this year's submission though.

4.2.2.1 Souce category description

From a chemical point of view, lime is calcium oxide. CO_2 is released during calcination. During the production of lime, the limestone is heated up, which leads to decomposition (i.e. calcination) of $CaCO_3$/$MgCO_3$ to the lime (CaO, CaO·MgO), and CO_2 is released into the atmosphere.

4.2.2.2 Methodological issues

Five lime producers operate in the Czech Republic. CO_2 emissions from 2.A.2 Lime Production are calculated according to the Tier 3 methodology described in IPCC 2006 Gl. (IPCC 2006) since 2010.

CO_2 emissions are based on data submitted by the lime producers in the EU ETS system. The ETS data are available for the time period 2010–2024 for each process. This data is at the Tier 3 level. Data in the EU ETS takes into account the actual carbonates present, impurities in the raw material and LKD (LKD is included in the data and thus emission estimates also include LKD). IEF is not constant because emissions reported in EU ETS forms are calculated separately as pure CaO and additional carbonate additives. The ratio of their composition varies, and therefore IEF fluctuates between 0.788 and 0.758 t CO_2/t $CaCO_3$ since 2010.

EU ETS data are also available for the time period 2005–2009, but only in the form of total emissions for each plant (including emissions which are reported in the Energy sector), and this is not sufficient for their

use for this reporting. Only CO_2 emissions generated in the process of the calcination step of lime treatment are considered in this category. CO_2 emissions from combustion processes (heating of kilns and furnaces) are reported under category 1.A.2.f.



Fig. 4-4 Final emission values [kt CO_2] with applied EF 0.7332 and 0.7884 [t CO_2/t lime] compared to EU ETS data

For the time period 1990–2009, the activity data is based on the data from CLA (the Czech Lime Association) and emissions were calculated by using the Tier 1 method. These data were considered to be more accurate than the data provided by CzSO, which do not differentiate between lime and hydrated lime (the data from CLA differentiate between lime and hydrated lime). This period's calculation is based on Vácha's research, which states: "According to provided information by CLA, the content of calcium oxide (CaO) in manufactured lime is 93%. Particle 0.93 is added to the computation formula in order to recalculate lime to pure 100% CaO. „The national EF, used for the time period 1990–2009, reflects the production of lime and quick lime (0.7884 t CO_2/t lime) (Vácha, 2004). The calculation in the period 1990–2009 is based on the following formula.

$$Emissions(CO_2) = Amount\ of\ Lime\ Produced * 0.7884\ t\ \ CO_2/t\ CaO * 0.93$$

The combination of the average purity (93%) and the national EF resulting emission factor is 0.733 t CO_2/t lime. The reason for the lower IEF for the time period 1990–2009 than the IEF for the time period 2010–2018 is due to different sources of activity data for each time series. In Fig. 4-4 is depicted that emissions would be overestimated if just the national EF (without considering purity) was used.

In 2015, research was carried out related to the country-specific emission factor from lime production (Beck, 2015). This research clarified the very small fluctuation of the emission factor (depending on the composition of the limestone) and further successfully defended the connection between Tier 1 data for the 1990–2009 period and Tier 3 data for the 2010 –2014 period. Detailed information about the research is provided in Annex 3.

Tab. 4-6 lists activity data for lime production, emission factors and CO_2 emissions for the whole time series.

Tab. 4-6 Activity data, CO_2 emission factor and CO_2 emissions in 2.A.2 Lime Production category in 1990–2024

	Unit	1990	1991	1992	1993	1994	1995	1996	1997	1998	1999
Lime production	[kt]	1 823.0	1 152.0	1 134.0	1 062.0	1 100.0	1 115.0	1 133.0	1 163.0	1 087.0	1 074.0
EF CO_2	[t CO_2/ t lime]	0.733	0.733	0.733	0.733	0.733	0.733	0.733	0.733	0.733	0.733
CO_2 emissions	[kt]	1 336.6	844.7	831.5	778.7	806.5	817.5	830.7	852.7	797.0	787.5
	Unit	**2000**	**2001**	**2002**	**2003**	**2004**	**2005**	**2006**	**2007**	**2008**	**2009**
Lime production	[kt]	1 130.0	1 128.0	1 112.0	1 102.0	1 103.0	1 040.4	1 033.8	1 083.0	1 012.0	853.0
EF CO_2	[t CO_2/ t lime]	0.733	0.733	0.733	0.733	0.733	0.733	0.733	0.733	0.733	0.733
CO_2 emissions	[kt]	828.5	827.1	815.3	808.0	808.7	762.8	758.0	794.1	742.0	625.4

	Unit	2010	2011	2012	2013	2014	2015	2016	2017	2018	2019
Lime production	[kt]	831.7	858.1	758.1	778.0	816.2	800.2	835.8	888.0	985.6	897.9
EF CO_2	[t CO_2/ t lime]	0.788	0.788	0.788	0.788	0.773	0.764	0.766	0.758	0.760	0.758
CO_2 emissions	[kt]	655.8	676.4	597.4	613.0	630.9	611.5	639.8	673.5	749.4	680.9

	Unit	2020	2021	2022	2023	2024
Lime production	[kt]	855.7	878.0	728.4	545.3	518.9
EF CO_2	[t CO_2/ t lime]	0.761	0.760	0.763	0.764	0.767
CO_2 emissions	[kt]	650.8	667.0	555.9	416.6	397.9

4.2.2.3 Uncertainties and time-series consistency

The uncertainties for this category are in line with the IPCC 2006 GI. (IPCC 2006). Since activity data are based on the EU ETS for the time period 2010–2024, which include all the lime producers in the Czech Republic, the uncertainty in the activity data was estimated at the level of 2%.

For the time period 1990–2009, the country-specific emission factor is used, and the uncertainty was estimated to be at the same level as that for the activity data, i.e. 2%. The overall uncertainty data are given in Chapter 1.6.

Time series consistency is ensured as the inventory approaches concerned are employed identically across the whole reporting period from the base year 1990 to 2024.

4.2.2.4 Source-specific QA/QC and verification

The input information and calculations are archived by the sectoral expert and the coordinator of NIS.

Verification is provided by comparison of the activity data obtained from CLA, CzSO and EU ETS. The lime production data obtained from EU ETS forms (input activity data for the submission) are compared with the data provided by CLA and CzSO. The percentage differences between the lime production data for 2024 obtained from the EU ETS and other sources are as follows:

- Difference between the data from EU ETS and CLA: 10.4%
- Difference between the data from EU ETS and CzSO: 1.97%

In addition to verification of the input data, the inter-annual changes in the implied emission factors are analysed. The EU ETS reports, which have been used for emission estimates since 2010, are substantiated by independent verifiers. The emission estimates are compared with the sum of the emissions from technological processes reported by the individual kiln operators. The country-specific emission factor used for emission estimates for 1990–2009 was compared with the emission factors used for the calculation by individual operators.

The quality control was held by fulfilling the QA/QC form presented in Annex 5.

4.2.2.5 Source-specific recalculations, including changes made in response to the review process and impact on emission trend

This year, no recalculations were performed in this sector.

4.2.2.6 Source-specific planned improvements, including tracking of those identified in the review process

Since the Tier 3 method is used for emission calculations in this category, no significant improvements are planned.

4.2.3 Glass Production (CRT 2.A.3)

Since 1990, glass production has decreased by 4%. It reached its peak at 1,750.00 kt in 2006 and then since 2015, the annual production has been approximately 1,200 kt, with 1,190 kt produced in 2024. Emissions from glass production have decreased by 8% since 1990 and amounted to 131.66 kt CO_2 in 2024.

4.2.3.1 Source category description

CO_2 emissions from Glass Production (2.A.3) are derived particularly from the decomposition of alkaline carbonates added to glass-making sand.

4.2.3.2 Methodological issues

CO_2 emissions from 2.A.3 Glass Production were calculated according to the Tier 3 methodology described in the IPCC 2006 Gl. (IPCC 2006) since 2010.

Since 2010, CO_2 emissions have been based on data submitted by the glass producers in the EU ETS. The ETS data are available for the time period 2010–2024 for each process. These data are at the Tier 3 level. The activity data for total glass production were obtained from CzSO.

Emissions for 1990–2009 were calculated according to the Tier 1 methodology with the country specific emission factor. The country specific emission factor was calculated as the average emission factor from data submitted directly by the manufacturers in the EU ETS for 2010–2024. The country specific emission factor used for emission estimates in 1990–2009 equals 0.115 t CO_2/t glass, which indicates that the country specific emission factor is slightly higher than the default emission factor multiplied by the cullet ratio 50%, which equals 0.10 t CO_2/t glass. The activity data for the emission estimates were obtained from the Association of the Glass and Ceramic Industry for 1990–2009.

Tab. 4-7 lists activity data for glass production, emission factors and CO_2 emissions for the whole time series.

Tab. 4-7 Activity data, CO_2 emission factor and CO_2 emissions in 2.A.3 Glass Production category in 1990–2024

	Unit	1990	1991	1992	1993	1994	1995	1996	1997	1998	1999
Glass production	[kt]	1 236.6	1 060.2	1 046.1	1 014.7	1 097.1	832.0	875.0	970.0	1 012.0	1 042.0
EF CO_2	[t CO_2/ t glass]	0.115	0.115	0.115	0.115	0.115	0.115	0.115	0.115	0.115	0.115
CO_2 emissions	[kt]	142.8	122.4	120.8	117.1	126.7	96.0	101.0	112.0	116.8	120.3
	Unit	**2000**	**2001**	**2002**	**2003**	**2004**	**2005**	**2006**	**2007**	**2008**	**2009**
Glass production	[kt]	1 197.0	1 203.0	1 349.0	1 416.0	1 662.0	1 654.0	1 750.0	1 688.0	1 519.2	1 329.3
EF CO_2	[t CO_2/ t glass]	0.115	0.115	0.115	0.115	0.115	0.115	0.115	0.115	0.115	0.115
CO_2 emissions	[kt]	138.2	138.9	155.7	163.5	191.9	190.9	202.0	194.9	175.4	153.5
	Unit	**2010**	**2011**	**2012**	**2013**	**2014**	**2015**	**2016**	**2017**	**2018**	**2019**

Glass production	[kt]	1 022.5	1 055.5	1 088.4	1 157.6	1 119.3	1 254.7	1 295.3	1 194.5	1 219.4	1 179.0
EF CO_2	[t CO_2/ t glass]	0.125	0.108	0.118	0.109	0.121	0.121	0.107	0.130	0.121	0.122
CO_2 emissions	[kt]	127.8	113.8	128.1	126.2	135.2	152.0	138.1	155.0	147.7	143.6

	Unit	2020	2021	2022	2023	2024
Glass production	[kt]	1 151.7	1 200.5	1 298.8	1 182.3	1 190.3
EF CO_2	[t CO_2/ t glass]	0.121	0.120	0.112	0.112	0.111
CO_2 emissions	[kt]	138.8	143.9	145.9	132.5	131.7

4.2.3.3 Uncertainties and time-series consistency

Since activity data are based on the EU ETS for the time period 2010–2024, the uncertainty in the activity data was estimated at the level of 2%.

Time series consistency is ensured as the inventory approaches concerned are employed identically across the whole reporting period from the base year 1990 to 2024.

4.2.3.4 Source-specific QA/QC and verification

The input information and calculations are archived by the sectoral expert and the coordinator of NIS.

Activity data on glass production provided by CzSO were discussed with a representative of the Association of the Glass and Ceramic Industry, who confirmed their reliability. In addition to verification of the input data, the inter-annual changes of the implied emission factors are analysed. The EU ETS reports, which are used for emission estimates since 2010, are proved by independent verifiers.

The quality control was held by fulfilling the QA/QC form presented in A 4.1.

4.2.3.5 Source-specific recalculations, including changes made in response to the review process and impact on emission trend

This year, no recalculations were performed in this category.

4.2.3.6 Source-specific planned improvements, including tracking of those identified in the review process

Since the Tier 3 method is used for emission calculations in this category, no significant improvements are planned.

4.2.4 Other Process Uses of Carbonates (CRT 2.A.4)

The 2.A.4 category Other Process Uses of Carbonates summarizes, in the Czech Republic, CO_2 emissions from 2.A.4.a Ceramics, 2.A.4.b Other uses of Soda Ash and from 2.A.4.d Other. CO_2 emissions from 2.A.4 Other Process Uses of Carbonates have increased since 1990 by 335%.

CO_2 emissions from 2.A.4.a Ceramics equalled to 43.59 kt in 2024. The decrease in emissions from 2015 was caused by changes in the methodology of laboratory analysis for emission estimates used by one of the ceramics manufacturers in the EU ETS. The sharp decline compared to last year is due to lower

production of bricks and tiles as a result of a reduced demand in the construction sector. CO_2 emissions from 2.A.4.b Other Uses of Soda Ash amounted to 0.68 kt CO_2 in 2024. CO_2 emissions from the subsector 2.A.4.d Other amounted to 451.79 kt CO_2 in 2024.

4.2.4.1 Source category description

CO_2 emissions from 2.A.4.a Ceramics are derived particularly from the decomposition of alkaline carbonates, fossil and biogenic carbon-based substances included in the raw materials.

CO_2 emissions from 2.A.4.b Other Uses of Soda Ash category come from soda ash use for the Glass production category; soda ash is used in only one other installation. CO_2 emissions from this category are small and insignificant (varied between 0.10 and 1.15 kt CO_2) compared to the other categories.

CO_2 emissions from the 2.A.4.d Other category include emissions from mineral wool production, flue-gas desulphurisation and denitrification. The ETF Reporting Tool does not allow separation of these four categories by adding new nodes under 2.A.4.d Other category. Consequently, these four categories are reported collectively.

4.2.4.2 Methodological issues

2.A.4.a Ceramics

CO_2 emissions from 2.A.4.a Ceramics have been calculated according to the Tier 3 methodology described in the IPCC 2006 Gl. (IPCC 2006) since 2010.

The activity data and emissions are taken directly from EU ETS forms for 2010–2024. Emissions for 1990–2009 were calculated according to the Tier 1 methodology with the country specific emission factor, which was derived as the average emission factor calculated from EU ETS data for 2010–2013. The activity data for production were obtained from CzSO. The calculation is based on the total production of ceramic products (fine ceramics, tiles, roofing tiles, and bricks) and the emission factor value.

2.A.4.b. Other Uses of Soda Ash

In category 2.A.4.b Other Uses of Soda Ash is considered, that for each mole of soda ash used, one mole of CO_2 is emitted, so that the mass of CO_2 emitted from the use of soda ash can be estimated from a consideration of the consumption data and the stoichiometry of the chemical process. The data, considering the amount and purity of the soda ash used, were obtained directly from the installation operator. The activity data for soda ash use and IEF have been reported as C since 2013 because only one manufacturer uses soda ash, and thus these data are confidential.

2.A.4.d Other

CO_2 emissions from the 2.A.4.d Other category include emissions from mineral wool production, flue-gas desulphurisation, denitrification by using urea and removals from $CaCO_3$ production.

Emissions from mineral wool production are estimated according to Tier 1 methodology, using the default EF. Activity data about mineral wool production are obtained by CzSO. Activity data are available for the time period 2000–2002 and 2007–2024. CO_2 emissions for time the period 2003–2006 were interpolated. Data before 2000 are not available but, according to a representative of the mineral wool industry, a small amount of production took place before 2000. The total amount of CO_2 emissions before 2000 would be lower than the total amount of emissions in 2000. The total amount of emissions in 2000 is under the threshold of significance, and thus emissions before 2000 are reported as NE.

Emissions from flue-gas desulphurization are obtained from EU ETS forms, which correspond to Tier 3 methodology with CS EF. CO_2 emissions from sulphur removal were calculated from coal consumption for electricity production, the sulphur content and the effectiveness of sulphur removal units between 1996, when the first sulphur removal units came into operation, and 2005. In 2005, these data were verified by comparison with data from the individual operators, which were collected for the EU ETS preparation and cover the years 1999–2005. The EU ETS data forms have been used since 2006. The methodology used for the estimation of the CO_2 emissions must be in accordance with the national legislation (Zákon č. 383/2012 Sb. Zákon o podmínkách obchodování s povolenkami na emise skleníkových plynů /Act No. 383/2012 Coll. The Act on conditions for trading in greenhouse gas emission allowances) and the EU legislation (Commission Decision of 18 July 2007 establishing guidelines for the monitoring and reporting of greenhouse gas emissions pursuant to Directive 2003/87/EC of the European Parliament and of the Council).

For the period 1996–2005, CO_2 emissions from flue-gas desulphurisation were estimated using the amount of limestone and dolomite consumed in FGD units and the corresponding CO_2 emission factor, in line with the material-balance approach of the 2006 IPCC Guidelines. Information on sulphur content and the performance of desulphurisation units was available from national air-pollution reporting (REZZO/SPE) and from technical documentation of FGD installations, which typically achieved removal efficiencies of approximately 95–97%. These parameters were used to support the consistency of the historical estimates prior to the introduction of the EU ETS data.

Denitrification by using urea appeared in the EU ETS for the first time in year 2017, at the same time when this technology was introduced in the Czech Republic, following new legislation based on the EU Industrial Emissions Directive 2010/75/EU. Data for the year 2016 were due to the transitional period negligible and thus reported as "NE". Prior to 2016, urea was not used for denitrification, so emissions from this source were reported using the notation key "NO". The main purpose of denitrification by using urea is to reduce NO_x emissions which are produced during combustion processes. As a reducing agent in the denitrification process is used aqueous urea solution ($CO(NH_2)_2$). The denitrification process can be described using the following equation:

$$CO(NH_2)_2 + 2NO + {}^1/_2\, O_2 \rightarrow 2N_2 + CO_2 + 2H_2O$$

It is obvious that as a side effect of this process, CO_2 emissions are emitted. In 2024, 26 facilities (power plants, heating plants and chemical plants) reported CO_2 emissions from denitrification processes. Data (activity data, emission factors and CO_2 emissions) are obtained directly from users of this process, and thus the methodology used for emission estimates is Tier 3. CO_2 emissions from denitrification amounted to 5.51 kt in 2024; emissions are under the threshold of significance. The denitrification process is closely linked to heat and electricity production, and for clarity and consistency with the EU ETS, it is reported in this category together with desulphurization.

Previously, the production of $CaCO_3$ in one paper mill in the Czech Republic was included. During this process, CO_2 reacts with hydrated lime, forming $CaCO_3$. For each mole of $CaCO_3$ produced, one mole of CO_2 is absorbed, so the mass of CO_2 removal can be estimated from the produced amount of $CaCO_3$ and the stoichiometry of the chemical process. In reality, when lime and cement products are used in construction, the same reaction occurs, and these processes are not included in estimations. Therefore, it was decided to remove the absorption of CO_2 in $CaCO_3$ production from the inventory.

These three categories (mineral wool production, flue-gas desulphurization and denitrification) are reported collectively in the ETF Reporting Tool. Activity data for this category are reported as C (NK). It is not possible to add up activity data for mineral wool production, flue-gas desulphurization, denitrification and $CaCO_3$ production because activity data describe completely different types of inputs.

Tab. 4-8 lists the CO_2 emissions and removals in the individual subcategories in 2.A.4 Other Process Uses of Carbonates for the time period 1990–2024.

Tab. 4-8 CO_2 emissions and removals in individual subcategories in 2.A.4 Other Process Uses of Carbonates category in 1990–2024

	Category 2.A.4 - CO_2 emissions [kt]				
	2.A.4.a Ceramics	2.A.4.b Other uses of Soda Ash	2.A.4.d Mineral wool production	2.A.4.d Flue-gas desulphurization	2.A.4.d Denitrification
1990	113.86	NO	NE	NO	NO
1991	89.98	NO	NE	NO	NO
1992	85.36	NO	NE	NO	NO
1993	105.49	NO	NE	NO	NO
1994	108.31	NO	NE	NO	NO
1995	100.49	NO	NE	NO	NO
1996	123.10	NO	NE	76.00	NO
1997	146.87	NO	NE	240.63	NO
1998	200.61	NO	NE	417.31	NO
1999	145.88	NO	NE	536.94	NO
2000	177.02	NO	13.08	539.69	NO
2001	156.33	0.10	19.82	551.38	NO
2002	113.01	0.21	25.02	551.38	NO
2003	119.83	0.33	29.03	560.04	NO
2004	118.51	0.44	33.04	551.06	NO
2005	141.15	0.47	37.06	588.79	NO
2006	109.05	0.35	41.07	586.55	NO
2007	135.06	0.50	45.08	613.93	NO
2008	112.43	0.56	41.19	607.00	NO
2009	90.78	0.41	39.40	600.00	NO
2010	100.43	0.86	43.57	651.00	NO
2011	100.31	1.06	61.31	739.31	NO
2012	108.31	1.09	41.63	698.70	NO
2013	116.73	1.03	42.83	680.90	NO
2014	89.94	1.11	46.89	663.11	NO
2015	68.64	1.01	47.62	645.31	NO
2016	70.26	1.01	46.00	627.52	NE
2017	79.03	1.15	48.99	609.72	2.72
2018	90.41	0.75	49.78	591.93	7.69
2019	110.04	0.79	46.63	478.63	4.62
2020	104.32	0.81	47.32	380.60	4.74
2021	91.17	1.00	47.60	529.07	6.30
2022	100.01	0.99	38.81	583.90	6.99
2023	46.87	0.79	41.95	465.22	8.92
2024	43.59	0.68	40.33	405.94	5.51

4.2.4.3 Uncertainties and time-series consistency

The uncertainties for this category are in line with the IPCC 2006 Gl. (IPCC 2006), i.e. at the level of 5% for the activity data and 10% for the CO_2 emission factor. Overall uncertainty data are given in Chapter 1.6.

For 2.A.4.a Ceramics, the time series consistency is ensured as the inventory approaches concerned are employed identically across the whole reporting period from the base year 1990 to 2024.

For 2.A.4.b Other uses of Soda Ash, the time series consistency is ensured as the inventory approaches concerned are employed identically across the whole reporting period from 2001, when the use of soda started, to 2024.

For 2.A.4.d Other the time series consistency is ensured as the inventory approaches concerned are employed identically across the whole reporting period for mineral wool production from 2000 to 2024 and for flue-gas desulphurization from 1996 to 2024.

4.2.4.4 Source-specific QA/QC and verification

The input information and calculations are archived by the sectoral expert and the coordinator of NIS.

Data for the emission estimates, except for category 2.A.4.d Mineral wool production, are obtained from EU ETS forms. The EU ETS forms are proved by independent verifiers. In addition to verification of the input data, the inter-annual changes of the implied emission factors are analysed.

The quality control was held by fulfilling the QA/QC form presented in A 4.1.

4.2.4.5 Source-specific recalculations, including changes made in response to the review process and impact on emission trend

2.A.4.d Other

This year, no recalculations were performed in this category.

4.2.4.6 Source-specific planned improvements, including tracking of those identified in the review process

The search for AD for mineral wool production is scheduled for the period 1990–1999. Since the Tier 3 method is used for emission calculations in this category (except for mineral wool production), no other significant improvements are planned.

4.3 Chemical Industry (CRT 2.B)



Fig. 4-5 Trend of emissions from 2.B Chemical Industry and share of specific subcategories [kt CO_2 eq.]

From the categories of sources classified under the Chemical industry (2.B), categories Ammonia Production (2.B.1), Nitric Acid Production (2.B.2), Caprolactam (2.B.4.a), Titanium Dioxide Production (2.B.6), Petrochemical and Carbon Black Production (2.B.8) are relevant for the Czech Republic, while Adipic Acid Production (2.B.3), Glyoxal (2.B.4.b), Glyoxylic Acid (2.B.4.c), Carbide Production (2.B.5), Soda Ash Production (2.B.7) and Fluorochemical Production (2.B.9) are not occurring. The subcategory 2.B.10 Other (please specify) includes two subcategories: Other non-energy use in chemical industry and Non selective catalytic reduction.

The major share 58.33% belongs to 2.B.8 Petrochemical and Carbon Black Production, 26.02% belongs to 2.B.1 Ammonia Production, 8.78% to 2.B.10 Other, 5.28% to 2.B.2 Nitric Acid Production and 1.6% to 2.B.4.a Caprolactam Production. The emission trend for the category 2.B Chemical Industry is depicted in Fig. 4-5.

Tab. 4-9 lists the exact amount of CO_2 eq. emissions from the individual subcategories in 2.B Chemical Industry for the time period 1990–2024.

Tab. 4-9 CO_2 eq. emissions in individual subcategories in 2.B Chemical industry category in 1990–2024

	Category 2.B - CO_2 eq. emissions [kt]				
	2.B.1 Ammonia Production	2.B.2 Nitric Acid Production	2.B.4.a Caprolactam Production	2.B.8 Petrochemical and Carbon Black Production	2.B.10 Other
1990	990.80	932.80	68.82	832.97	IE
1991	933.44	598.90	66.58	631.83	IE
1992	989.89	760.55	59.02	710.28	IE
1993	933.98	572.40	62.58	728.02	IE
1994	1055.82	749.95	53.71	907.97	IE
1995	903.19	863.90	65.88	861.78	IE
1996	989.20	829.45	63.67	906.57	IE
1997	931.15	855.95	64.24	924.33	IE
1998	886.50	922.20	55.85	1020.63	IE
1999	788.90	752.60	65.65	1060.52	IE
2000	936.02	861.25	67.68	959.32	IE
2001	761.75	850.65	63.90	1010.01	IE
2002	638.58	731.40	39.13	939.99	IE
2003	850.60	728.75	58.55	921.98	IE
2004	843.43	837.40	63.55	1148.32	IE
2005	721.70	789.70	71.10	1114.98	IE

	Category 2.B - CO_2 eq. emissions [kt]				
	2.B.1 Ammonia Production	2.B.2 Nitric Acid Production	2.B.4.a Caprolactam Production	2.B.8 Petrochemical and Carbon Black Production	2.B.10 Other
2006	683.27	702.25	71.64	1069.28	IE
2007	617.11	575.05	71.87	962.46	IE
2008	700.21	535.30	56.79	1075.15	222.76
2009	744.18	402.80	58.65	976.52	136.47
2010	705.45	288.85	65.66	1051.73	210.17
2011	628.05	328.60	70.13	960.82	220.22
2012	653.79	336.55	68.21	1022.08	224.54
2013	601.13	188.61	57.57	988.73	214.76
2014	689.05	255.52	61.42	1130.17	219.50
2015	741.66	280.18	65.60	749.01	223.06
2016	685.72	216.44	59.18	318.88	233.58
2017	743.75	134.32	61.44	1053.75	206.53
2018	585.60	112.24	64.36	1065.60	207.40
2019	582.93	91.88	58.08	1043.61	226.18
2020	381.79	72.10	60.47	878.32	221.53
2021	701.31	121.11	64.35	1062.05	191.45
2022	682.45	104.49	55.44	1063.53	144.43
2023	544.85	82.41	33.42	931.49	123.60
2024	430.96	87.45	26.50	966.04	145.35

Tab. 4-10 gives an overview of the emission factors used for computations of emissions in category 2.B Chemical Industry for year 2024.

Tab. 4-10 Emission factors used for computations of 2024 emissions in category 2.B

IPCC Category	Emission factor	Unit	Source or type of EF	Methodology
2.B.1 Ammonia Production	3.27	kt CO_2/kt NH_3	CS	Tier 2
2.B.2 Nitric Acid Production	0.65	kg N_2O /t HNO_3	PS	Tier 3
2.B.4 Caprolactam, Glyoxal and Glyoxilic Acid Production	C	kg N_2O/t caprolactam	CS	Tier 1
2.B.8 Petrochemical and Carbon Black production	1.90	t CO_2/t ethylene	Default (IPCC 2006)	Tier 1
	3.00	kg CH_4/t ethylene	Default (IPCC 2006)	Tier 1
	0.29	t CO_2/t VCM	Default (IPCC 2006)	Tier 1
	0.02	t CH_4/t VCM	Default (IPCC 2006)	Tier 1
	C	t CO_2/t carbon black	PS	Tier 3
	0.06	kg CH_4/t carbon black	Default (IPCC 2006)	Tier 1
	C	t CO_2/t styrene	PS	Tier 1
	0.004	t CH_4/t styrene	Default (IPCC 2006)	Tier 1
2.B.10 Other	2.69	t CO_2/t Other	IEF	Tier 1

The column source or type of EF indicates the way how was the certain emission factor determined. Detailed information for each emission factor is given in the relevant chapters.

The following table (Tab. 4-11) contains information about chemical production in the Czech Republic and the number of manufacturers. It can be seen that, except for nitric acid production, only one manufacturer for each product operates in the Czech Republic, and thus, due to confidentiality reasons, it is very difficult to obtain direct information about production and emissions related to the production from manufacturers. Each manufacturer (in the case of the Czech Republic – chemical plants) reports their

emissions in the EU ETS but only as bulk emissions, which is not sufficient for emission estimates because emissions are related to the total emissions from all processes carried out in a plant (other production, combustion processes, etc.). For those reasons, Tier 1 methodology is used for emission estimates, except for N_2O emissions from nitric acid production, CO_2 emissions from ammonia production and CO_2 emissions from carbon black production.

Tab. 4-11 Chemical production in the Czech Republic with number of manufacturers

IPCC Category	Number of manufactures
2.B.1 Ammonia Production	1
2.B.2 Nitric Acid Production	3 (4 installation units)
2.B.4 Caprolactam	1
2.B.8.b Ethylene	1
2.B.8.c Ethylene Dichloride and Vinyl Chloride Monomer	1
2.B.8.f Carbon Black	1
2.B.8.g Styrene	1

4.3.1 Ammonia Production (CRT 2.B.1)

The production of ammonia constitutes an important source of CO_2 derived from non-energy use of fuels in the chemical industry. CO_2 emissions from ammonia production in 2024 equalled to 430.96 kt of CO_2, emissions decreased by 53.83% compared to 1990 (990.80 kt of CO_2 eq.). Emissions in the period 2005–2024 fluctuate slightly every year, with a minimum in 2020 and a maximum in 2009. The sharp decrease of emissions in 2020 was probably due to the Covid-19 pandemic and lockdown, and their impact on the production. The increase of emissions from 2014 was mainly caused by the end of urea production, which has not been produced since 2014. Emission in 2024 decreased by 21% compared to emissions in 2023 as the production of ammonia in the last year also decreased also by 21%. The reason for the decrease in production was caused by two events: 1. A two-month shutdown due to revitalization of the plant; 2. A two-weeks shutdown due to the discovery of an aerial bomb from World War II in August. Category 2.B.1 was identified as a key source.

4.3.1.1 Source category description

Industrial ammonia production is based on the catalytic reaction between nitrogen and hydrogen:

$$N_2 + 3H_2 \rightarrow 2NH_3$$

Nitrogen is obtained by cryogenic rectification of air, and hydrogen is prepared using starting materials containing bonded carbon (such as, e.g., Natural Gas, Residual Oil, Heating Oil, etc.). Carbon dioxide is generated in the preparation of these starting materials. In the Czech Republic, hydrogen for ammonia production is derived from residual oil from petroleum refining, which undergoes partial oxidation in the presence of water vapour. In order to increase the hydrogen production, the second step involves the conversion of carbon monoxide, which is formed by partial oxidation, in addition to carbon dioxide and hydrogen. The final products of this two-step process are hydrogen and carbon dioxide. The production technology has practically not changed since 1990.

4.3.1.2 Methodological issues

The Tier 2 approach is used to estimate the emissions from ammonia production. As there is only one producer for ammonia in the Czech Republic, all provided data (process type, fuel type, ammonia production data, CO_2 recovered for urea production data) are plant specific.

The equation used for the calculation of emissions differs from the equations in the IPCC 2006 Gl., Volume 3, Chapter 3, but is still consistent with the Tier 2 methodology in the 2006 IPCC guidelines. Emissions are calculated from the corresponding amount of ammonia produced, using the default emission factor provided in IPCC 2006 Gl. 3.273 kt CO_2/kt NH_3 (IPCC 2006). This emission factor was obtained from IPCC 2006 Gl., Volume 3, Chapter 3, Table 3.1, corresponding to the total fuel requirement, which is 42.5 GJ (NCV)/t NH_3 (IPCC 2006). Total CO_2 emissions from ammonia production were lowered by the CO_2 used in urea production, and thus, the emissions were calculated using the following equation:

$$CO_2\ Emissions = (NH_3\ production * EF) - (CO_2\ consumed\ in\ urea\ production * stochiometric\ coefficient)$$

Urea production decreased to 1.1 kt in 2013. Untill 2013 the urea-related emissions were allocated under the agriculture sector (please see chapter 5.8 for details, CRT 3.H). Since 2014, urea has not been produced in the Czech Republic, and emissions are calculated without the subtraction of CO_2 consumed in urea production. A potential uncertainty in the emission factor for ammonia would not influence the total sum of CO_2 emissions, because a corresponding amount of oil is not considered in the energy sector. The relevant activity data and corresponding emissions are given in Tab. 4-12. Related CO_2 emissions from ammonia production are reported in Table 1.A(d) under Other Oil, which is the feedstock used, as well (please see chapter 3.2.3. for details).

Tab. 4-12 Activity data and CO_2 emissions from ammonia production in 1990–2024

	Unit	1990	1991	1992	1993	1994	1995	1996	1997	1998	1999
Residual fuel oil used for NH_3 product	[TJ]	14 997	14 534	14 985	14 012	15 644	13 812	14 865	13 623	14 044	11 963
Ammonia produced	[kt]	335.86	325.51	335.59	313.8	350.35	309.32	332.91	305.1	314.52	267.91
CO_2 from 2.B.1	[kt]	990.80	933.44	989.89	933.98	1055.82	903.19	989.20	931.15	886.50	788.9
CO_2 consumed in urea production	[kt]	108.48	131.94	108.48	93.09	90.89	109.22	100.42	67.44	142.94	87.96
	Unit	2000	2001	2002	2003	2004	2005	2006	2007	2008	2009
Residual fuel oil used for NH_3 product	[TJ]	13 690	11 522	10 052	13 084	12 987	11 326	10 802	10 119	11 453	11 793
Ammonia produced	[kt]	306.59	258.04	225.12	293.03	290.84	253.65	241.91	226.62	256.49	264.10
CO_2 from 2.B.1	[kt]	936.02	761.75	638.58	850.60	843.43	721.70	683.27	617.11	700.21	744.18
CO_2 consumed in urea production	[kt]	67.44	82.83	98.22	108.48	108.48	108.48	108.48	124.61	139.27	120.21
	Unit	2010	2011	2012	2013	2014	2015	2016	2017	2018	2019
Residual fuel oil used for NH_3 product	[TJ]	11 484	10 278	10 659	8 212	9 400	10 118	9 355	10 146	7 989	7 953
Ammonia produced	[kt]	257.19	230.18	238.72	183.91	210.53	226.60	209.51	227.24	178.92	178.10
CO_2 from 2.B.1	[kt]	705.45	628.05	653.79	601.13	689.05	741.66	685.72	743.75	585.60	582.93
CO_2 consumed in urea production	[kt]	136.34	125.34	127.54	0.81	NO	NO	NO	NO	NO	NO
	Unit	2020	2021	2022	2023	2024					
Residual fuel oil used for NH_3 product	[TJ]	5 209	9 568	9 310	7 433	5 879					
Ammonia produced	[kt]	116.65	214.27	208.51	166.47	131.67					
CO_2 from 2.B.1	[kt]	381.79	701.31	682.45	544.85	430.96					
CO_2 consumed in urea production	[kt]	NO	NO	NO	NO	NO					

4.3.1.3 Uncertainties and time consistency

In 2014, estimates of the uncertainty parameters were verified in the study (Bernauer and Markvart, 2015) which, in addition to an expert opinion, also takes into account data given in the IPCC 2006 Gl. (IPCC 2006). The uncertainty in the activity data remains unchanged at 5% and the uncertainty in the emission factor (CO_2 EF) was also left at a value of 7%.

Time series consistency is ensured as the above mentioned methodology is employed identically across the whole reporting period from the base year 1990 to 2024.

4.3.1.4 Source-specific QA/QC and verification

The input information and calculations are archived by the sectoral expert and the coordinator of NIS.

During verification, attention is focused on identifying gaps. Attention is also focused on checking sources from inter-sector boundaries (Energy, Industry) that they are neither omitted nor counted twice. Therefore, CO_2 emissions from residual oil used for ammonia production are not taken into account in the Energy sector. This part of the QA/QC procedure is carried out in cooperation with KONEKO marketing, Ltd. (see Chapter 3.6).

The quality control was held by fulfilling the QA/QC form presented in Annex 5.

4.3.1.5 Source-specific recalculations, including changes made in response to the review process and impact on emission trend

In this year, no recalculations were performed in this category.

4.3.1.6 Source-specific planned improvements, including tracking of those identified in the review process

In this year, no source-specific improvements are planned.

4.3.2 Nitric Acid Production (CRT 2.B.2)

The production of nitric acid constitutes one of the most important sources of N_2O in the chemical industry. N_2O emissions from the production of nitric acid in 2024 equalled to 0.33 kt N_2O; emissions have decreased by 85.4% compared to 1990. The substantial decrease in recent years has been a consequence of the gradual introduction of mitigation technology and improving its effectiveness.

4.3.2.1 Source category description

The production of nitric acid is one of the traditional chemical processes in the Czech Republic. It is carried out in three factories, where one of them manufactures more than 60% of the total amount. Nitric acid is produced using the classical method, high-temperature catalytic oxidation of ammonia (Ostwald process) and subsequent absorption of nitrogen oxides in water. Nitrous (dinitrogen) oxide is formed at the ammonia oxidation reactor as an unwanted side product. Nitric acid production can be described using the following stoichiometric equations:

a) Ammonia oxidation in the gas phase

$$4NH_3 + 5O_2 \rightarrow 4NO + 6H_2O$$

b) NO oxidation in the gas phase

$$2NO + O_2 \leftrightarrow 2NO_2$$

c) NO_2 absorption in water

$$3NO_2 + H_2O \leftrightarrow 2HNO_3 + NO$$

The nitric acid is manufactured at three pressure levels (at atmospheric pressure (A – atmospheric pressure), slightly elevated pressure (MP – medium pressure) (approx. 0.4 MPa) and at elevated pressure (HP – high pressure) (0.7 - 0.8 MPa)). While production processes prior to 2003 mostly progressed at atmospheric pressure and only to a lesser degree at medium elevated pressure, the process at elevated pressure had predominated since 2004. Since 2004, the technology to reduce N_2O emissions, based on catalytic decomposition of this oxide, has been gradually introduced at units working at elevated pressure. It has been possible to substantially improve the effectiveness of this process in recent years.

All the nitric acid production processes in the Czech Republic are equipped with technologies for the removal of nitrogen oxides (NO_X), based on selective (SCR) or non-selective catalytic reduction (NSCR). Non-selective catalytic reduction (NSCR) also makes a substantial contribution to the removal of N_2O. Following Tab. 4-13 shows more detailed information about the technology used for nitric acid production and the technologies used for the removal of NO_x by units.

Tab. 4-13 Pressure level and removal technology used by unit in the Czech Republic

Unit	Pressure level	Removal technology
1	MP	NSCR
2	HP	SCR
3	MP	NSCR
4	MP	SCR
5	A	SCR

4.3.2.2 Methodological issues

Nitrous oxide emissions from 2.B.2 Nitric Acid Production are generated as a by-product in the catalytic process of oxidation of ammonia. It follows from domestic studies (Markvart and Bernauer, 1999, 2000, 2003), describing conditions prior to 2004, that the resulting emission factor depends on the technology employed: higher emission factor values are usually given for processes carried out at normal pressure, while lower values are usually given for medium-pressure processes. Two types of processes were carried out in this country before 2004, at pressures of 0.1 MPa and 0.4 MPa. The amount of nitrous oxide in the exit gases is also affected by the type of process employed to remove nitrogen oxides, NO_X (i.e. NO and NO_2). In this country, the process of Selective Catalytic Reduction (SCR) is mostly used, which slightly increases the amount of N_2O, and also to a certain degree Non-Selective Catalytic Reduction (NSCR), which also removes N_2O to a considerable degree.

Studies (Markvart and Bernauer, 2000, 2003) recommend the following emission factors for various types of production technology and removal processes that are given in Tab. 4-14. The emission factors for the basic process (without $DENO_X$ technology) are in accordance with the principles given in IPPC 2006 Gl. (IPCC 2006). The effect of the NO_X removal technology on the emission factor for N_2O was evaluated on the basis of the balance calculations presented in studies (Markvart and Bernauer, 2000, 2003).

Tab. 4-14 Emission factors for N_2O recommended by (Markvart and Bernauer, 2000. 2003) for 1990–2003

Pressure in HNO_3 production	**0.1 MPa**			**0.4 MPa**		
Technology $DENO_X$	--	SCR	NSCR	--	SCR	NSCR
Emission factors N_2O [kg N_2O/t HNO_3]	9.05	9.20	1.80	5.43	5.58	1.09

During 2003, conditions changed substantially as a result of the installation of new technologies operating under a higher pressure of 0.7 MPa. At the same time, some older units operating under an atmospheric pressure of 0.1 MPa were phased out. These changes in technology were monitored in the study of Markvart and Bernauer (Markvart and Bernauer, 2005). This study presents a slightly modified table of N_2O emission factors, while those for new technologies were obtained from a set of continuous emission measurements lasting several months. Other values are based on several discrete measurements. A table of these technology-specific emission factors is given below.

Tab. 4-15 Emission factors for N_2O recommended by Markvart and Bernauer, for 2004 and thereafter

Pressure in HNO_3 production	0.1 MPa	0.4 MPa	0.4 MPa	0.7 MPa
Technology $DENO_X$	SCR	SCR	NSCR	SCR
Emission factors N_2O [kg N_2O/t HNO_3]	9.05	4.9	1.09	7.8 [a)]

[a)] EF without N_2O mitigation.

In the last quarter of 2005, a new N_2O mitigation unit based on catalytic decomposition of N_2O was experimentally installed for 0.7 MPa technology, and became the most important such unit in the Czech Republic. As a consequence of this technology, the relevant EF decreased from 7.8 to 4.68 kg N_2O/t HNO_3 (100%). Therefore, the mean value in 2005 for the 0.7 MPa technology was equal to 7.02 kg N_2O/t HNO_3 (100%) (Markvart and Bernauer, 2006).

In 2006–2024, the mitigation unit described above was utilized in a more effective way. The decrease in the emission factor for 0.7 MPa technology as a result of the installation of the N_2O mitigation unit and gradual improvement of the effectiveness is given in Tab. 4-16.

Tab. 4-16 Decrease in the emission factor for 0.7 MPa technology due to installation of the N_2O mitigation unit

	2004 [a)]	2005	2006	2007	2008	2009	2010	2011	2012
EF [kg N_2O/t HNO_3 (100%)]	7.8	7.02	5.94	4.37	4.82	2.85	1.29	1.30	1.45
Effectiveness of mitigation [%]	-	10.00	23.85	43.97	38.21	63.46	83.46	83.33	81.41
	2013	2014	2015	2016	2017	2018	2019	2020	2021
EF [kg N_2O/t HNO_3 (100%)]	1.86	2.81	3.07	2.00	1.52	0.93	0.64	0.68	0.96
Effectiveness of mitigation [%]	76.18	64.02	60.60	74.31	80.56	88.02	91.78	91.25	87.73
	2022	2023	2024						
EF [kg N_2O/t HNO_3 (100%)]	0.83	0.70	0.71						
Effectiveness of mitigation [%]	89.33	90.97	90.93						

[a)] EF without N_2O mitigation.

The Tier 1 approach was used for emission estimates in the years 1990 to 2012. AD for these years were taken from CzSO. N_2O emissions for the years 1990–2012 were based on a mean value of the nitric acid production capacity with NSCR technology and compared with measured values of the outlet gas mixture. Since 2013, activity data and emissions have been taken directly from the EU ETS form and thus Tier 3 is the methodology for emission estimates. Tab. 4-17 gives the N_2O emissions from the production of nitric acid, including the production values.

Tab. 4-17 Emission trends for HNO_3 production and N_2O emissions in 1990–2024

	Production of HNO_3, [kt HNO_3 (100%)]	Emissions of N_2O from HNO_3 production [kt N_2O]	Implied Emission Factor IEF [kg N_2O/kt HNO_3]
1990	530.00	3.52	6.64
1991	349.56	2.26	6.46

	Production of HNO_3, [kt HNO_3 (100%)]	Emissions of N_2O from HNO_3 production [kt N_2O]	Implied Emission Factor IEF [kg N_2O/kt HNO_3]
1992	439.39	2.87	6.53
1993	335.95	2.16	6.43
1994	439.79	2.83	6.43
1995	505.32	3.26	6.45
1996	484.80	3.13	6.46
1997	483.10	3.23	6.69
1998	532.50	3.48	6.54
1999	455.00	2.84	6.24
2000	505.00	3.25	6.44
2001	505.08	3.21	6.36
2002	437.14	2.76	6.31
2003	500.58	2.75	5.49
2004	533.73	3.16	5.92
2005	532.21	2.98	5.60
2006	543.11	2.65	4.88
2007	554.22	2.17	3.92
2008	506.96	2.02	3.98
2009	505.17	1.52	3.01
2010	441.70	1.09	2.47
2011	561.82	1.24	2.21
2012	550.46	1.27	2.31
2013	514.94	0.71	1.38
2014	546.77	0.96	1.76
2015	532.15	1.06	1.99
2016	562.66	0.82	1.45
2017	533.95	0.51	0.95
2018	579.34	0.42	0.73
2019	566.99	0.35	0.61
2020	466.52	0.27	0.58
2021	601.57	0.46	0.76
2022	579.16	0.39	0.68
2023	514.16	0.31	0.60
2024	525.89	0.33	0.62

While the slight fluctuations in IEF to 2004 were caused by slow changes in the relative contributions of the individual technologies with various technologically specific emission factors, since 2005, the reduction in IEF has been caused mainly by the gradual increase in the effectiveness of the mitigation units employed for the dominant technology (see Tab. 4-17) to 2010. A further reduction in IEF in 2011 was then caused by an increasing contribution of this dominant technology (0.7 MPa) to 56% of the annual production of HNO_3.

The Institute of Physical Chemistry of the Czech Academy of Science, together with the University of Chemistry and Technology Prague are studying the high temperature decomposition of N_2O from HNO_3 production by using a structured catalyst with a focus on the possible use of the technology on an industrial scale. It follows that the development of technologies used in nitric acid production is still ongoing, and possible improvements could be introduced in the future.

4.3.2.3 Uncertainties and time-series consistency

In 2014, the estimates of the uncertainty parameters were refined on the basis of the study (Markvart and Bernauer, 2013), which takes into account the data in IPCC 2006 Gl. (IPCC 2006). The uncertainty in the

activity data following adjustment was equall to 4%, and the uncertainty in the average emission factor (N_2O EF) was reduced to 15% in relation to the increasing number of direct measurements.

Time series consistency is ensured as inventory approaches concerned are employed identically across the whole reporting period from the base year of 1990 to 2024.

4.3.2.4 Source-specific QA/QC and verification

The input information and calculations are archived by the sectoral expert and the coordinator of NIS.

Verification is provided by comparison of the activity data obtained from CzSO, EU ETS and ISPOP. The nitric acid production data provided by CzSO are compared with data provided by EU ETS and ISPOP. The percentage differences between nitric acid production data for 2024 obtained from the EU ETS and other sources are as follows:

- Difference between the data from ISPOP and CzSO: 3.74%
- Difference between the data from EU ETS and ISPOP: 0.00%

In addition to verification of the input data, the inter-annual changes of the implied emission factors are analysed. The EU ETS reports, which are used for emission estimates since 2013, have been proved by independent verifiers. The quality control was held by fulfilling the QA/QC form presented in A 4.1.

4.3.2.5 Source-specific recalculations, including changes made in response to the review process and impact on emissions trend

In this year, no recalculations were performed in this category.

4.3.2.6 Source-specific planned improvements, including tracking of those identified in the review process

No improvement is planned for the next submission.

4.3.3 Adipic Acid Production (CRT 2.B.3)

Adipic Acid production is not occurring in the Czech Republic.

4.3.4 Caprolactam, Glyoxal and Glyoxylic Acid Production (CRT 2.B.4)

4.3.4.1 Source category description

There is only one facility for the production of caprolactam in the Czech Republic. Glyoxal and Glyoxylic Acid are not produced in the Czech Republic. Information provided in this chapter is related to caprolactam production.

Caprolactam is prepared by traditional technology from cyclohexanone and hydroxylamine sulphate, which is prepared by the Rasching process. Cyclohexanone reacts with hydroxylamine sulphate yielding cyclohexanonoxime, from which caprolactam is produced by the Beckmann rearrangement. Then caprolactam is isolated from the reaction mixture by neutralisation with ammonium hydroxide.

4.3.4.2 Methodological issues

There is only one facility for caprolactam production in the Czech Republic. Emission estimates for caprolactam production are based on a series of studies (Markvart and Bernauer, 2004–2013; Bernauer and Markvart, 2014–2016). The facility for caprolactam production provided data on the consumption of ammonia (1177 kg NH_3/hour) and the production capacity (5.4 t caprolactam/hour). Assuming that the conversion of NH_3 to N_2O is routinely 2%, the used emission factor for caprolactam was established from the mass balance. The production unit in the facility works at atmospheric pressure and thus the emission factor should be compared with the emission factor for atmospheric burning of ammonia and not with high-pressure burning of ammonia.

The emissions of N_2O were estimated using the Tier 1 approach, equation 3.9 from IPCC 2006 Gl., Volume 3, Chapter 3. The activity data for the time series 1990–2024 were provided by the producer. The plant-specific emission factor was used for calculation. At the beginning of 2025 producer announced that it would cease production of caprolactam as a result of a company restructuring. It is therefore likely that it has already started to reduce production in previous years.

4.3.4.3 Uncertainties and time-series consistency

In relation to the relatively insignificant greenhouse gas emissions from category 2.B.4, uncertainties derived from the sources included in this category have no great impact on the overall uncertainty in the determination of GHG emissions in the Czech Republic. Thus, it does not matter greatly that the uncertainty in emissions from these sources was determined by an expert estimate.

4.3.4.4 Category-specific QA/QC and verification

The input information and calculations are archived by the sectoral expert and the coordinator of NIS.

In relation to the relatively unimportant greenhouse gas emissions from category 2.B.4, only QC, Tier 1 procedures were used, in accordance with the QA/QC plan.

4.3.4.5 Category-specific recalculations, including changes made in response to the review process and impact on emission trend

In this year, no recalculations were performed in this category.

4.3.4.6 Category-specific planned improvements, including tracking of those identified in the review process

No improvement is planned for the next submission. Emissions are estimated according to a series of studies (Markvart and Bernauer, 2004–2013; Bernauer and Markvart, 2014–2016) and activity data provided by the producer.

4.3.5 Carbide Production (CRT 2.B.5)

Carbides are not produced in the Czech Republic.

4.3.6 Titanium Dioxide Production (CRT 2.B.6)

In the Czech Republic titanium dioxide is produced using sulphate route process and as it is stated in the IPCC 2006 Gl., volume 3, chapter 3.7 this process does not give rise to process greenhouse gas emissions that are of significance.

This conclusion is supported by EU ETS data, where the only sources of emissions originate from neutralization process and from natural gas usage in the pigment thermal process. Those emissions are reported elsewhere. Emissions from neutralization process are reported in NID chapter 4.2.4 (CRT 2.A.4). Emission from natural gas usage in thermal processes are reported in NID chapter 3.2.12 (CRT 1.A.2c).

4.3.7 Soda Ash Production (CRT 2.B.7)

A factory for soda ash production in the Czech Republic was founded in 1905 and the first production of soda ash started in 1907. The factory constituted a monopolist manufacturer of soda in the Czech Republic and Czechoslovakia. Soda was produced by the traditional Solvay process and the product was usually distributed to glass manufacturers. The factory was closed in 1991. Since then, soda has not been produced in the Czech Republic.

4.3.8 Petrochemical and Carbon Black Production (CRT 2.B.8)

This category includes carbon dioxide and methane emissions from the production of ethylene, ethylene dichloride, carbon black and styrene. Total emissions from category 2.B.8 Petrochemical and Carbon Black Production equalled to 974.74 kt CO_2 eq. in year 2024, emissions have increased by 15.98% compared to 1990.

Sharp decrease of emissions for 2015 and 2016 was caused by an accident in the refinery plant with ethylene unit in August of 2015. The accident resulted in an unplanned shutdown of the petrochemical part of the production plant. The ethylene unit was reconstructed and the production capacity returned to its normal value as before the accident.

Category 2.B.8 was identified as a key source.

4.3.8.1 Source category description

Ethylene in the Czech Republic is produced by pyrolysis of petroleum fractions, composed of a very wide range from fractions of C3-C4 (propane) to the higher boiling fractions. The ethylene unit contains several pyrolysis furnaces that process raw gas (LPG, ethane and propane) and liquids (HCVD - hydrocracked vacuum distillate, naphtha, and in very limited quantities of diesel fuel). Basically, a thermal, non-catalytic fission in the presence of steam is performed and its major products are ethylene, propylene, benzene and C4 fraction.

1,2-dichloroethane known, also as ethylene dichloride, is produced in the Czech Republic at the same integrated facility as vinyl chloride monomer (VCM), which is subsequently used for PVC production (Bernauer and Markvart, 2016). 1,2-dichloroethane is prepared by oxychlorination of ethylene and is then used as source material for vinyl chloride monomer (VCM) production.

In the Czech Republic, carbon black is produced in one facility by the furnace black process. The input materials for the production are heavy aromatic hydrocarbons.

Styrene is produced in one facility by catalytic alkylation of benzene over ethylbenzene followed by ethylbenzene dehydrogenation. The internal ethylbenzene dehydrogenation operates in a system of 2 reactors in the presence of catalysers (Fe_2O_3-Cr_2O_3-K_2O).

4.3.8.2 Methodological issues

Default emission factors from the IPCC 2006 Gl. (IPCC 2006) are employed to determine carbon dioxide and methane emissions from the production of carbon black, ethylene, ethylene dichloride and styrene. Related CO_2 emissions from Petrochemical and Carbon Black Production are reported in Table1.A(d) under Naphtha, which is the major feedstock used, as well (please see chapter 3.2.3. for details).

CO_2 and CH_4 emissions from the production of ethylene

Reliable data for the production of ethylene are available from CzSO. The IPCC 2006 Gl. provides a value of 1.73 t CO_2/t ethylene produced (with correction factor 110% for countries of Eastern Europe) and 3 kg CH_4/t ethylene produced as default emission factors (IPCC 2006). In the period 1990–2024, CO_2 emissions varied between 184.41 (due to the accident) to 958.85 kt CO_2 and methane emissions varied between 0.29 and 1.51 kt CH_4, detailed values for each year are available in Tab. 4-18.

Tab. 4-18 Emission trends from CO_2 and CH_4 emissions from production of ethylene in 1990–2024

	Ethylene Production [kt]	CO_2 Emissions [kt]	CH_4 Emissions [kt]
1990	388.02	738.40	1.16
1991	286.45	545.12	0.86
1992	325.37	619.17	0.98
1993	332.68	633.10	1.00
1994	389.53	741.28	1.17
1995	373.34	710.47	1.12
1996	390.80	743.69	1.17
1997	399.09	759.46	1.20
1998	448.94	854.34	1.35
1999	466.32	887.40	1.40
2000	411.66	783.39	1.23
2001	439.16	835.72	1.32
2002	412.12	784.26	1.24
2003	396.88	755.27	1.19
2004	503.86	958.85	1.51
2005	485.14	923.22	1.46
2006	462.14	879.46	1.39
2007	408.55	777.47	1.23
2008	464.73	884.38	1.39
2009	416.10	791.83	1.25
2010	454.97	865.80	1.36
2011	412.07	784.17	1.24
2012	441.08	839.37	1.32
2013	425.62	809.95	1.28
2014	491.50	935.32	1.47
2015	308.44	586.96	0.93
2016	96.91	184.41	0.29
2017	456.10	867.96	1.37
2018	451.55	859.29	1.35
2019	448.57	853.63	1.35
2020	375.13	713.87	1.13
2021	464.16	883.29	1.39
2022	464.28	883.52	1.39

	Ethylene Production [kt]	CO_2 Emissions [kt]	CH_4 Emissions [kt]
2023	414.54	788.87	1.24
2024	419.71	798.71	1.26

CO_2 and CH_4 emissions from the production of ethylene dichloride and vinyl chloride monomer

The data on production of PVC are obtained from CzSO. While CzSO does not publish information on the amount of VCM, it does give data on the amount of PVC produced, which are practically the same as VCM data. The IPCC 2006 Gl. methodology provides a value of emissions of carbon dioxide 0.294 t CO_2/t VCM produced and for methane 0.0226 kg CH_4/t VMC produced as default emission factors (IPCC 2006). Carbon dioxide emissions varied in the period 1990–2024 between 8.77 kt CO_2 and 40.29 kt CO_2. Due to the low emission factors' value, the values of methane emissions varied in the period 1990–2024 between 0.001 and 0.003 kt CH_4, which is considered as insignificant value. In 2024, emissions of carbon dioxide equalled to 11.36 kt and methane emissions equalled to 0.00087 kt, which is the lowest value in the entire time series. At the beginning of 2025 producer announced that it will cease production of caprolactam and ethylene dichloride as a result of a company restructuring. It is therefore likely that it has already started to reduce production in previous years.

CO_2 and CH_4 emissions from the production of carbon black

Exact information on activity data related to carbon black production is available since 2013; thus, the data for other years were taken from the study (Bernauer and Markvart, 2016). Since 2013, the activity data and CO_2 emissions have been based on data from the EU ETS. In the Czech Republic, only one facility is involved in carbon black production and thus the activity data and emissions are reported as confidential C (NK) in the ETF Reporting Tool. Data are available for review experts in calculation sheets upon a request. The emission factor taken from the IPCC 2006 Gl. equals to 0.06 kg CH_4/t carbon black produced and 2.62 t CO_2 /t carbon black produced (IPCC 2006).

CO_2 and CH_4 emissions from the production of styrene

Because of the growing consumption of polystyrene, the production of styrene has gradually increased since 1990. CzSO also does not publish any information on the production of styrene. Thus, the necessary activity data were estimated on the basis of production capacities for years 1990–2011:

1990–1998	70 kt styrene p.a.
1999	80 kt styrene p.a.
2000–2003	110 kt styrene p.a.
2004	140 kt styrene p.a.
2005–2010	150 kt styrene p.a.
from 2011	exact production from EU ETS forms and from the producer

These estimates on the amount of styrene produced were based on the data given in the article (Dvořák and Novák, 2010). The emission factor taken from the IPCC 2006 Gl. equals to 0.004 kt CH_4/kt styrene (IPCC 2006). The emission factor for CO_2 emissions is 0.27 kt CO_2/kt styrene (Bernauer and Markvart, 2015) (IPCC 2006). Since 2011, activity data are based on data from the EU ETS and data from producer. In the Czech Republic, only one facility is involved in production of styrene, thus the activity data and emissions are reported as confidential C (NK) in ETF reporting tool. Data are available for review experts in calculation sheets upon a request. In 2024, emissions of carbon dioxide equalled to 39.87 kt and methane emissions equalled to 0.59 kt.

4.3.8.3 Uncertainties and time-series consistency

The uncertainties for this category are in line with the IPCC 2006 Gl. (IPCC 2006), i.e. at the level of 5% for the activity data and 40% for the CO_2 and CH_4 emission factors. Overall uncertainty data are given in Chapter 1.6.

Time series consistency is ensured as inventory approaches concerned are employed identically across the whole reporting period for each subcategory.

4.3.8.4 Source-specific QA/QC and verification

The input information and calculations are archived by the sectoral expert and the coordinator of NIS.

The quality control was held by fulfilling the QA/QC form presented in A 4.1.

4.3.8.5 Source-specific recalculations, including changes made in response to the review process and impact on emission trend

In this year, no recalculations were performed in this category.

4.3.8.6 Source-specific planned improvements, including tracking of those identified in the review process

No improvements are planned.

4.3.9 Fluorochemical Production (2.B.9)

Fluorinates are not produced in the Czech Republic.

4.3.10 Other (2.B.10)

CO_2 emissions from category 2.B.10, which includes other non-energy use in chemical industry and non-selective catalytic reduction equalled to 145.353 kt CO_2 in 2024.

4.3.10.1 Source category description

Subcategory 2.B.10 Other is divided into two subcategories. The first sub-category includes CO_2 emissions from non-selective catalytic reduction (NSCR) of output gases from nitric acid production; the second one includes emissions for hydrogen production by steam reforming in the petrochemical and chemical industry (excluding hydrogen used for NH_3 production, which is based on other feedstock than NG, see section 4.3.1). Emissions from NSCR are not very significant (about 10-16 kt of CO_2). Emissions from steam reforming of NG are somewhat more significant (about 130-220 kt of CO_2)).

4.3.10.2 Methodological issues

Thanks to intensive consultation with experts at CzSO and the University of Chemistry and Technology in Prague (VSCHT), it is now possible to reliably specify emissions from non-energy use, and thus, reallocate activity data, which are reported under 1.A.2.c in accordance with IPCC 2006 Gl. (IPCC 2006).

The production of nitric acid in installations with NSCR is obtained from EU ETS forms. Currently, two installation units with NSCR are operating in the Czech Republic. Emissions of CO_2 are calculated by simple Tier 1 methodology, where the production data are multiplied by the emission factor. The emission factor is based on a series of studies (Markvart and Bernauer, 2004–2013) and (Bernauer and Markvart, 2014–2016). Reduction of oxygen, which is the main source of CO_2 emissions in the NSCR process, can be described by the following reaction

$$CH_4 + 2O_2 \rightarrow CO_2 + 2H_2O$$

The emission factor 103 kg CO_2/1 t HNO_3 was derived for the reaction and was used for emission estimates.

Emissions for hydrogen production by steam reforming in the petrochemical and chemical industry (excluding hydrogen used for NH_3 production) are calculated using the following equation

$$Emissions = (Net\ calorific\ value\ of\ NG * EF\ for\ NG) - emissions\ of\ NSCR$$

The net calorific value of natural gas consumed for non-energy use in the chemical industry is obtained from the Energy Questionnaire - Natural Gas provided by AIE - Eurostat – UNECE. EF for natural gas is calculated on the basis of the NET4GAS Ltd. correlation (see Annex A 5.1).

Tab. 4-19 gives an overview of the CO_2 emissions from category 2.B.10 Other. Related CO_2 emissions from 2.B.10 are reported in Table 1.A(d) under Natural Gas as well (please see chapter 3.2.3 for details).

Tab. 4-19 Emission trends for category 2.B.10 Other in 2008–2024

	Unit	2008	2009	2010	2011	2012	2013	2014
Other non-energy use in chemical industry	CO_2 emissions [kt]	208.34	123.08	195.74	206.72	210.01	201.33	204.76
Non selective catalytic reduction	CO_2 emissions [kt]	14.42	13.39	14.42	13.49	14.52	13.43	14.77
	Unit	**2015**	**2016**	**2017**	**2018**	**2019**	**2020**	**2021**
Other non-energy use in chemical industry	CO_2 emissions [kt]	208.02	220.49	190.15	191.76	211.09	205.56	176.81
Non selective catalytic reduction	CO_2 emissions [kt]	15.04	13.09	16.37	15.64	15.10	15.96	14.64
	Unit	**2022**	2023	2024				
Other non-energy use in chemical industry	CO_2 emissions [kt]	134.45	117.13	136.47				
Non selective catalytic reduction	CO_2 emissions [kt]	9.98	6.47	8.88				

4.3.10.3 Uncertainties and time consistency

The uncertainty of the activity data and emission factors used for computations of emissions from category 2.B.10 correspond to the uncertainty estimates from the Energy sector, category 1.A.2 Manufacturing industries and construction. The uncertainties are for this category in line with IPCC 2006 GI. (IPCC 2006), i.e. at the level of 3% for the activity data and 2.5% for the emission factor.

Time series consistency is ensured as the inventory approaches concerned are employed identically across the whole reporting period from 2008 to 2024.

4.3.10.4 Source-specific QA/QC and verification

The input information and calculations are archived by the sectoral expert and the coordinator of NIS.

The quality control was held by fulfilling the QA/QC form presented in A 4.1.

4.3.10.5 Source-specific recalculations, including changes made in response to the review process and impact on emission trend

In this year, no recalculations were performed in this category.

4.3.10.6 Source-specific planned improvements, including tracking of those identified in the review process

In further submissions it is planned to investigate the possibility of disaggregating data for non-energy and energy use of NG for the 1990–2007 period. CO_2 emissions from NG in the chemical industry were reported for this period under 1.A.2.c.

4.4 Metal Industry (CRT 2.C)

This category includes mainly CO_2 emissions from 2.C.1 Iron and Steel Production; 99.5% of CO_2 emissions arise from 2.C.1. CO_2 emissions from iron and steel are identified as a key category (by both level and trend assessments). A small amount of CH_4 is also emitted.

Ferro-alloys were manufactured in limited amounts in a small production unit in the Czech Republic; this process could constitute an unsubstantial source of CO_2 emissions. Specific data were obtained straight from the operator – there is only one producer of ferrovanadium.

For the production of Lead and Zinc data are also obtained straight from the operators, however there is only one producer of secondary lead and one producer of zinc.

Investigation revealed one smaller production plant, which reported that aluminium was used as a reducing agent; this did not lead to CO_2 emissions. In 2009 this production was stopped.

4.4.1 Iron and Steel Production (CRT 2.C.1)

4.4.1.1 Category description

Iron has been produced in the Czech Republic in two major metallurgical facilities located in the cities of Ostrava and Třinec in the Moravian-Silesian Region, in the north-eastern part of the Czech Republic. Both these metallurgical works employ blast furnaces and also lines for the production of steel, coking furnaces and other supplementary technical units. The closure of the Ostrava company's primary steel production in 2023 has a significant impact on the steel industry in the Czech Republic which affected the activity data and therefore also emissions in the last few years. The situation further deteriorated in 2024, when Liberty Ostrava entered insolvency after prolonged financial difficulties linked to unpaid energy supplies, failed restructuring efforts and the collapse of its external financing, which also led to the insolvency of its neighbouring coke and energy producer. Another large steel plant is located immediately next to the metallurgical works in Ostrava, taking raw iron (in the liquid state) from the nearby blast furnaces. Several small companies produce specialized steel products. Their emissions account for less than 1% of overall emissions.

The sub-category 2.C.1 has been identified as a key category in this submission based on the assessment of levels and trends by both the KC Approach 1 and KC Approach 2 analyses.

4.4.1.2 Methodological issues

The CO_2 emissions from iron and steel production were calculated using the national approach which can be considered as Tier 2. However, Tier 2 emission estimations based in IPCC 2006 Gl. (IPCC 2006) include recommendations to also include emissions arising from combustion of Blast Furnace and Oxygen Steel Furnace Gas in other than metallurgical complexes (for instance in Energy category 1.A.1.a). However, it is expected in the Czech Republic that all Blast Furnace and Oxygen Steel Furnace Gases are combusted directly in the metallurgical complexes. This means that the national approach to emission estimations contains a few aspects from Tier 1, as some parts of the equation are available for the computation. An important aspect of the computation is the amount of carbon in the reducing agent (i.e. in metallurgical coke), and thus also the amount of carbon in scrap and in steel. Further, small amount of Bituminous Coal in 2014–2024 was also used as reducing agent in the blast furnace, as well as Coal Tar in years 2007 till 2013 and then in 2018–2020. Thus, the approach used is considered to be as close to Tier 2 based on IPCC 2006 Gl. (IPCC 2006) as possible. Details of the amount of reducing agents are given in Tab. 4-20. In the carbon balance the amount of carbon in coke, bituminous coal (in 2014–2024) and coal tar (in 2007–2013, 2018–2020) that is used in blast furnaces. Further amount of carbon in sinter, pig iron and steel is part of the emission estimation. The total amount of total carbon produced in the process is following equation



Fig. 4-6 Trend of CO_2 emissions in 2.C.1, 1990–2024 [kt CO_2]

$$C_{total} = \left(C_{coke} + C_{bituminous\ coal} + C_{coal\ tar} + C_{scrap} + C_{electrodes}\right) - C_{steel}$$

Coke Oven Gas is not in the official CzSO data reported in transformation processes, so it is used only for warming up, so the emissions are reported under 1.A.2.a. Blast Furnace Gas is used for warming the air for the blast furnace.

99% of produced pig iron is used immediately in the facility for steel production. Iron ore charge for blast furnaces is ensured from three quarters by sintering of sinter fines in our own Sinter Plant and the remaining portion of iron ore charge is formed by pellets, lump ores and secondary materials. There is only one integrated steelwork in the EU which includes a pelletisation plant (in the Netherlands) and five standalone pelletisation plants in EU. Therefore, all pellets are imported to the Czechia and the notation key is “NO”. Blast furnace coke is supplied from the neighboring Coke Oven Plant, part of blast furnace coke and liquid fuel is purchased from external sources. Produced hot metal and sinter is used for internal consumption only. Steel is here homogenised, additionally alloyed to the exact chemical composition, heated to the appropriate casting temperature and desulphurized, and modification of inclusions is performed using filled profiles. After this out-of-furnace processing molten steel is sequentially cast on three continuous casters into billets, slabs or small slabs. Finishing lines represents two section-rolling mills and a wire-rod mill, which provide a wide assortment of profiles and wire rod. In the total production of

the iron and steel in the Czech Republic, the electric furnaces cover less than 5%. This percentage is calculated using the total volume of iron and steel produced in the country and the volume produced by electric furnaces. The data are provided by CzSO. The rest of the iron and steel is made in blast furnaces and oxygen converters. In the EU ETS forms we can see that from the total amount of CO_2 emissions about 6% is recycled in the process via either following usage of the waste gas, the production of the gray cast iron or with the formation of slug that is subsequently used in the construction industry.

Some of the activity data, particularly for scrap, electrodes and steel, were provided to the Czech Hydrometeorological Institute by the Czech Statistical Office under a confidentiality agreement. For this reason, these data cannot be published in the NID or in any other publicly accessible documents.

The calculation in IPCC 2006 Gl. (IPCC 2006) also includes CO_2 emissions from limestone and dolomite used in iron and steel metallurgy. Since the 2015 submission, these emissions have been reported under 2.C.1. Data reported under the EU ETS were used for these emissions, i.e. Tier 3. The data for limestone and dolomite are since 2011 available in the EU ETS data. Since no reliable data for limestone and dolomite used before that year is available in the stastics, the overlap method (Guidelines: Chapter 5: Time Series Consistency, page 5.9) was applied for the time series 1990–2010 based on the data available for 2011–2020. The calculation is based on a strong correlation relationship between the desired values of dolomite and limestone mass and the mass of coke utilized in furnaces.

Related CO_2 emissions from 2.C.1 are reported in Table 1.A(d). For more information, please see chapter 3.2.3.

The amounts of blast furnace coke consumed, and corresponding emissions are given in Tab. 4-20.

Tab. 4-20 The activity data and CO_2 emissions in 1990–2024

	Coke consumed in blast furnaces [kt]	Other Bituminous Coal [kt]	Coal Tar [kt]	Use of limestone and dolomite [kt]	CO_2 from 2.C.1 [kt]
1990	3211	NO	NO	1380	9782.03
1991	2559	NO	NO	1100	7768.24
1992	2624	NO	NO	1147	8087.05
1993	2426	NO	NO	1060	7479.57
1994	2663	NO	NO	1164	8188.93
1995	2587	NO	NO	1130	7961.45
1996	2701	NO	NO	1180	8309.70
1997	2846	NO	NO	1279	9003.33
1998	2750	NO	NO	1236	8702.15
1999	1941	NO	NO	892	6273.65
2000	2327	NO	NO	1055	7416.03
2001	2175	NO	NO	995	6987.88
2002	2252	NO	NO	1030	7237.87
2003	2459	NO	NO	1124	7875.94
2004	2628	NO	NO	1171	8221.49
2005	2260	NO	NO	1004	7059.99
2006	2480	NO	NO	1137	7993.16
2007	2570	NO	35	1164	8288.67
2008	2366	NO	59	1073	7730.34
2009	1801	NO	56	822	5947.47
2010	2082	NO	33	923	6590.18
2011	2086	NO	26	870	6541.83
2012	2007	NO	23	859	6374.51
2013	2057	NO	7	924	6562.69
2014	1886	276	NO	885	6745.33
2015	1780	300	NO	789	6471.40
2016	1842	319	NO	866	6734.22
2017	1605	278	NO	779	5988.78
2018	1735	285	30	832	6439.45
2019	1566	267	27	720	5813.09

	Coke consumed in blast furnaces [kt]	Other Bituminous Coal [kt]	Coal Tar [kt]	Use of limestone and dolomite [kt]	CO_2 from 2.C.1 [kt]
2020	1568	275	NO	781	5923.49
2021	1777	256	NO	846	6347.92
2022	1586	235	NO	799	5580.52
2023	1194	240	NO	590	4334.44
2024	798	227	NO	390	3097.77

Estimation of CH_4 from metal production is based on the IPCC 2006 Gl. Tier 1 methodology. Default emission factors 0.1 g CH_4 per tonne of coke produced and 0.07 kg CH_4 per tonne of sinter produced were used. In this case, the relevant activity data correspond to the amount of coke produced from the Energy Balances of the CR are given in CRT Tables and official statics data of sinter produced.

Emission estimates of precursors for the relevant subcategories have been transferred from NFR to CRT, as described in previous chapters and in Chapter 9.

1.1.1.1 Uncertainties and time consistency

The uncertainty estimates have so far been based on expert judgment. Their improvement is ongoing, and some uncertainty estimates for Iron and steel production have been revised in previous submissions (CHMI, 2012). The new estimate of EF (CO_2) is now 10%, which is in accordance with the 2006 Gl. (IPCC 2006) and is slightly higher than the former value (5%). The estimate for AD (7%) remained unchanged, because this value is in good agreement with the recommendation in the Regulation of Commission (EU) No. 601/2012 (EU, 2012). Further improvement of uncertainty estimates is planned for the next submission.

Consistency of the time series is ensured as the inventory approaches concerned are employed identically across the whole reporting period from the base year of 1990 to 2024.

1.1.1.2 Source-specific QA/QC and verification

The sector-specific QA/QC plan follows from the overall plan described in Chapter 1. The greatest attention was focused on identifying gaps and imperfections by observing trends in figures and by checking IEFs. Attention was also focused on checking sources from inter-sector boundaries (Energy, Industry) that they are neither omitted nor counted twice. CO_2 emissions from coke used in blast furnaces are not considered in Energy sector (see Chapter 3.2).

Activity data available in the official CzSO materials in relation to QA/QC were independently determined by experts from CHMI and KONEKO and were mutually compared. Experts at CHMI additionally checked most of the calculations carried out by experts at KONEKO and vice versa. For another QA, especially QA of computational approach, is also used former coordinator of National Inventory System.

The quality control was held by fulfilling the QA/QC form presented in A 4.1.

1.1.1.3 Source-specific recalculations, including changes made in response to the review process and impact on emission trend

Activity data for Coal Tar and few other categories were updated from the questionnaire for the year 2023 which resulted in the slight correction of total emission of CO_2 in CRT data.

1.1.1.4 Source-specific planned improvements, including tracking of those identified in the review process

In future submissions is planned to investigate data relevant for potential implementation of Tier 3 methodology in this category. The EU ETS data were studied and compared with current CzSO source. However, the issue needs further investigation to asure the correct transition to the Tier 3 method. The transition process will be discussed with relevant representatives.

4.4.2 Ferroalloys Production (CRT 2.C.2)

4.4.2.1 Source category description

Ferroalloys Production is production of concentrated alloys of iron and or more metals such as silicon, manganese, chromium, molybdenum, vanadium and tungsten. In the Czech Republic is only one producer of ferrovanadium. Therefore, activity data are reported as confidential.

4.4.2.2 Methodological issues

The activity data were obtained straight from the operator, where ferrovanadium is produced. IPCC 2006 Gl. (IPCC 2006) does not provide emission factors of this type of ferroalloy. However, IPCC 2006 Gl. provides emission factors based on specific share of Si in the ferroalloy. Chemical composition of the ferrovanadium produced in the Czech Republic is known. Using the simple proportion rule, emission factors were calculated for CO_2, as well as for CH_4. This can be considered as conservative approach.

The emissions are under the threshold of significance and can be considered negligible.

Tab. 4-21 Evaluation of emission factors used for 2.C.2 emission estimates

Composition of ferrovanadium		IPCC 2006 Gls. EF		EF CO_2 (1.5% of Si)	EF CH_4 (1.5% of Si)
Vanadium	75-85%	FeSi 45% Si	2.5	0.083333*)	
Aluminum	1.5% max	FeSIi 65% Si	3.6	0.083077	0.023077*)
Silicon	1.5% max	FeSi 75%Si	4	0.08	0.02
Carbon	0.25% max.	FeSi90%Si	4.8	0.08	0.018333
Phosphorus	0.08% max.				
Sulfur	0.08% max.				

**) emission factors used for computation*

4.4.2.3 Uncertainties and time consistency

Since default emission factors were used for emission computations, the uncertainty of emission factors was considered default, i.e. provided in table 4.9 in IPCC 2006 Gl. (IPCC 2006) as 25%. The uncertainty of activity data is estimated on the level of 5%.

4.4.2.4 Source-specific QA/QC and verification

The sector-specific QA/QC plan follows from the overall plan described in Chapter 1. General QC procedures were applied in this sector. The activity data and composition of ferroalloys were discussed with representative of The Steel Federation, Inc.

4.4.2.5 Source-specific recalculations, including changes made in response to the review process and impact on emission trend

No recalculation was performed in this category in current submission.

4.4.2.6 Source-specific planned improvements, including tracking of those identified in the review process

Since the emissions are negligible, no improvement is planned.

4.4.3 Aluminium Production (2.C.3)

Investigation revealed one smaller production plant, which reported that aluminium was used as a reducing agent; this did not lead to CO_2 emissions. In 2009 this production was stopped. Recently, there is only secondary production of aluminium in the Czech Republic. From this reason no greenhouse gases are reported in this category. There is recycling of aluminium. To avoid using of F-gases is used cover salts method. The recommendation from FCCC/ARR/2016/CZE, I.13 is not in line with IPCC 2006 Gl. and further not comparable to the reporting of other Annex I Parties. The recommendation is requesting to report CO_2 and PFC emissions from secondary aluminium production in the correct category (2.C.7 Other). There is no guidance for this kind of processes for reporting under 2.C.7. Further, no Annex I Party is reporting such emissions. The inventory team believes that no greenhouse gases are arising from the processes mentioned.

4.4.4 Lead Production (2.C.5)

4.4.4.1 Source category description

In the Czech Republic there is no primary production of lead, however secondary production and recycling is happening. There is one installation specialised for this production.

4.4.4.2 Methodological issues

Research was performed on potential Lead producers in the Czech Republic. The data were obtained straight from the operator; the data has to be displayed as confidential since there is only one producer of lead in the Czech Republic. The CO_2 emissions were estimated at the level of Tier 1 methodology based on the IPCC 2006 Gl. (IPCC 2006) using the default CO_2 emission factor 0.2 t CO_2/t of lead. CO_2 emissions in 2024 equalled to 10.30 kt.

The emissions are under the threshold of significance for the Czech Republic.

4.4.4.3 Uncertainties and time consistency

Since default emission factors were used for emission computations, the uncertainties were based in IPCC 2006 Gl. recommendation, i.e. 10% for activity data and 50% for emission factor.

4.4.4.4 Source-specific QA/QC and verification

The sector-specific QA/QC plan follows from the overall plan described in Chapter 1. General QC procedures were applied in this sector. The activity data and composition of ferroalloys were discussed with representative of The Steel Federation, Inc.

4.4.4.5 Source-specific recalculations, including changes made in response to the review process and impact on emission trend

No recalculation was performed in this category in current submission.

4.4.4.6 Source-specific planned improvements, including tracking of those identified in the review process

Since the emissions are negligible, no improvement is planned.

4.4.5 Zinc Production (2.C.6)

4.4.5.1 Source category description

There is no primary production of Zinc in the Czech Republic, however secondary production is occurring. The reported emissions are all from secondary production, there is one producer of zinc, which is operating since 1998. In 1990–1999 were in the Czech Republic one more operator existing, the data are also included in the emission estimates.

4.4.5.2 Methodological issues

The research of potential Zinc producers in the Czech Republic was performed. Detailed data were obtained straight from the operator, so the data has to be displayed as confidential. The CO_2 emissions were estimated on the level Tier 1 methodology based on IPCC 2006 Gl. (IPCC 2006) using default CO_2 emission factor 1.72 t CO_2/t of zinc. CO_2 emissions in 2024 equalled 0.25 kt, which presents negligible share in the whole inventory.

4.4.5.3 Uncertainties and time consistency

Since default emission factors were used for emission computations, the uncertainties were based in IPCC 2006 Gl. recommendation, i.e. 10% for activity data and 50% for emission factor.

4.4.5.4 Source-specific QA/QC and verification

The sector-specific QA/QC plan follows from the overall plan described in Chapter 1. General QC procedures were applied in this sector.

4.4.5.5 Source-specific recalculations, including changes made in response to the review process and impact on emission trend

No recalculation in this category was performed in this submission.

4.4.5.6 Source-specific planned improvements, including tracking of those identified in the review process

Since the emissions are negligible, no improvement is planned.

4.5 Non-energy products from fuels and solvent use (CRT 2.D)

This subcategory includes the emissions from the first use of fossil fuels as products, where their primary use is other than combustion for energy production or use as a reducing agent in industrial processes.

Products reported in this subcategory include Lubricants, Paraffins, Asphalts and Solvents. Emissions from other (secondary) use or disposal of these products are included in the relevant sectors (e.g. Energy, Waste).

Fig. 4-7 shows the share of individual subcategories in 2.D in 2024. 71% of 2.D CO_2 emissions are produced from Lubricant Use, followed by Urea used as catalysts (22%) and the use of Paraffin Wax (7%).



Fig. 4-7 The share of individual subcategories for CO_2 emissions in 2.D in 2024 [kt CO_2 eq.]

4.5.1 Lubricant Use (2.D.1)

4.5.1.1 Source category description

Lubricants are produced from refining of crude oil in petrochemical installations. There can be distinguished between engine oils and industrial oil or grease.

4.5.1.2 Methodological issues

The activity data are provided by CzSO in the official Energy balance of the Czech Republic. The non-energy use of fuels is also included. The amount of lubricants used for other than energy production is included in this category as activity data.

The Tier 1 methodology from the IPCC 2006 Gl. was used for CO_2 emission estimations. The default emission factor 20 kg C/GJ was used; the Oxidised During Use (ODU) factor was used as a default value equal to 0.2. CO_2 emissions from this category in 2024 were equal to 84.3 kt CO_2. Related CO_2 emissions from 2.D.1 are reported in Table1.A(d) under Lubricants as well (please see chapter 3.2.3 for details).

4.5.1.3 Uncertainties and time consistency

Since the activity data used are from official statics, the suggested 5% uncertainty (IPCC 2006) was applied for this category. Since default ODU factor was used, suggested 50% uncertainty from IPCC 2006 Gl. was applied for emission factor uncertainty.

4.5.1.4 Source-specific QA/QC and verification

Standard QA/QC procedures were applied for this subcategory. Special attention was paid to cross-sectoral issues (Energy x IPPU), so no emissions are omitted, nor counted twice.

4.5.1.5 Source-specific recalculations, including changes made in response to the review process and impact on emission trend

No recalculation performed in this submission.

4.5.1.6 Source-specific planned improvements, including tracking of those identified in the review process

No improvements are planned in this subcategory.

4.5.2 Paraffin Wax Use (2.D.2)

4.5.2.1 Source category description

This category includes use of products separated from fossil fuels called paraffins, waxes or vaseline. From chemical point of view they are mixtures of solid paraffinated hydrocarbons obtained from crude oils. Different types are characterised by point of solidification and amount of oil contained.

4.5.2.2 Methodological issues

Activity data reported in official Energy balance of CzSO as non-energy use are used for emission estimation in this category. Tier 1 methodology from IPCC 2006 Gl. (IPCC 2006) was used for CO_2 emission estimation. Default emission factor 20 kg C/GJ was used, Oxidised During Use (ODU) factor was used default equal to 0.2. CO_2 emissions in 2024 from this category were equal to 8.25 kt CO_2.

4.5.2.3 Uncertainties and time consistency

Since the activity data used are from official statics, the suggested 5% uncertainty (IPCC 2006) was applied for this category. Since default ODU factor was used, suggested 50% uncertainty from IPCC 2006 Gl. (IPCC 2006) was applied for emission factor uncertainty.

4.5.2.4 Source-specific QA/QC and verification

Standard QA/QC procedures were applied for this subcategory. Special attention was paid to cross-sectoral issues (Energy x IPPU), so no emissions are omitted, nor counted twice.

4.5.2.5 Source-specific recalculations, including changes made in response to the review process and impact on emission trend

No recalculation performed in this submission.

4.5.2.6 Source-specific planned improvements, including tracking of those identified in the review process

No improvements are planned in this subcategory.

4.5.3 Other (2.D.3)

4.5.3.1 Source category description

Solvent Use

This category includes particularly emissions of NMVOC (ozone precursor) from the use of solvents, which based in IPCC 2006 Gl. (IPCC 2006) are not considered to be a source of direct CO_2 emissions.

Road Paving With Asphalt

This category includes particularly emissions of ozone precursors in 1990–2005 time - series. Based on the IPCC 2006 Gl. (IPCC 2006), only NMVOC emission should be reported. Data in reporting for the UNECE/CLRTAP inventory in NFR are used. Emissions from Road Paving with Asphalt are not considered to be a source of CO_2 emissions (IPCC 2006).

Urea used as catalyst

IPCC 2006 Gl. (IPCC 2006) incorporate this category as source of CO_2 emissions. However, based on methodology emissions from this process should be included in Energy sector, 1.A.3. Since the emissions does not arise from fuel combustion, the emissions are covered under IPPU sector.

4.5.3.2 Methodological issues

Solvent Use

The IPCC Gl. (IPCC 2006) uses the CORINAIR methodology (EMEP/CORINAIR Guidelines, 1999) for processing NMVOC emissions in this category. This manual also gives the following conversions for the relevant activities, which can be used in conversion of data from the CORINAIR (i.e. SNAP) structure to the IPCC classification.

The inventory of NMVOC is elaborated annually for the UNECE/CLRTAP inventory in NFR and is also adopted for the National GHG inventory.

Solvent Use activity data are based on the following sources of information:

- statistical information on producers and imports from the Czech Statistical Office,
- REZZO data,
- annual reports of the Association of Coatings Producers and Association of Industrial Distilleries,
- information from the Customs Administration,
- regular monitoring of economic activities and economic developments in the CR, knowledge and monitoring of important operations in the sphere of surface treatments, especially in the area of application of coatings, degreasing and cleaning,

- regular monitoring of investment activities is performed in the CR for technical branches affecting the consumption of solvents and for overall developmental technical trends of all branches of industry,
- monitoring of implementation of BAT in the individual technical branches,
- technical analysis of consumption of solvents in households; NMVOC emissions from households are entirely fugitive and according to qualified estimates, contribute approximately 16.5% to total NMVOC emissions.

The activity data for Solvent Use were extracted from the official Energy balance. From the whole amount of non-energy use of Other oil products were extracted the Oil needed for NH_3 production. Sum of the rest of Other Oil and non-energy use of White spirit was considered as the best available data for Solvent Use. This approach was approved with relevant experts from CzSO.

Road Paving With Asphalt

The activity data from last submission were used. Emissions are used from UNECE/CLRTAP inventories.

Urea used as catalyst

The emissions from urea as a catalyst are calculated in COPERT programme version 5.9.2 (updated from 5.8.1 to 5.9.2). Tier 2 Approach is used. Diesel consumption for each vehicle category is used as activity data and emission is calculated using Eq. 3.2.2 in IPCC 2006 Gl. (IPCC 2006). The program takes into account country specific H:C and O:C ratio in the fuels and also different values of the urea consumption factor according to the vehicle categories (the activity level is from 2% to 6% of diesel consumption by the vehicle). Purity of AdBlue used in the vehicles is 32.5% of urea in 67.5% of deionized water which is reflected in the final amount of CO_2 emissions (Audiowell 2020). The emission is estimated for 2006–2024 times series. Since 2006, the urea as a catalyst was used in buses and heavy duty vehicles, and since 2014 in light duty vehicles and passengers cars.

CO_2 emissions in 2024 from this category were equal to 26 kt CO_2.

4.5.3.3 Uncertainties and time consistency

Solvent Use

The uncertainty of NMVOC emissions is considered to be quite large, based on IPCC 2006 Gl. (IPCC 2006) it is considered as 50%. The uncertainty of activity data is considered based on expert judgement as 25%.

Time series consistency is ensured as the inventory approaches concerned are employed identically across the whole reporting period from the base year 1990 to 2024.

Road Paving With Asphalt

Since no CO_2, CH_4 or N_2O emissions were estimated in this category, no uncertainties were considered in this category.

Urea used as catalyst

Suggested default range for uncertainty was applied for 2.D.3 category, i.e. 5% for activity data and 5% for emission factor uncertainty. However, even though the emissions are reported under 2.D.3, the range was applied based on IPCC 2006 Gl. Vol. 2 Energy (IPCC 2006), where the methodology for emission estimation from urea used as a catalyst is provided.

4.5.3.4 Source-specific QA/QC and verification

Solvent Use

The emission data in this section were taken from the UNECE/CLRTAP inventories in NFR. Annual reports are available on the method of calculation for the individual years since 1998. Following transfer of the emission data to the new ETF Reporting tool, it was apparent that trends in the emissions did not exhibit any significant deviations.

Road Paving With Asphalt

No specific QA/QC or verification procedures are applied.

Urea used as catalyst

Standard QA/QC procedures were applied for this subcategory. Activity data estimate was discussed with the expert for transport.

4.5.3.5 Source-specific recalculations, including changes made in response to the review process and impact on emission trend

Solvent Use

No recalculations performed in this submission.

Road Paving With Asphalt

No recalculations performed in this submission.

Urea used as catalyst

The whole time series was 2006–2023 were recalculated. The main reason was the upgrade of Coppert Program from version 5.8.1 to 5.9.2. Moreover, Activity data for the last four years were updated, and years 2020–2024 were consequently recalculated. This is given by the methodology of obtaining traffic performance data (for more details, please see chapter 3.2.16.3 in NID). For a detailed explanation of those changes, see chapter 1.A.3.b – Road transport.



Fig. 4-8 Impact of the recalculations of urea used as a catalyst.

The recalculation is under Treshold of significance.

4.5.3.6 Source-specific planned improvements, including tracking of those identified in the review process

Solvent Use

No improvements are planned in this category.

Road Paving With Asphalt

No improvements are planned in this category.

Urea used as catalyst

No improvements are planned in this category.

4.6 Electronics Industry (CRT 2.E)



Fig. 4-9 Trend of emissions from 2.E Electronics Industry [kt CO_2 eq.]

Of the categories of sources classified under the Electronics Industry (2.E), only the Integrated Circuit or Semiconductor (2.E.1) category is relevant for the Czech Republic. This category includes the gases HFC-23, CF_4, C_2F_6, SF_6 and NF_3. According to information obtained from manufactures, SF_6 or other fluorine compounds are not used in category 2.E.3 Photovoltaics.

The emission trend for the category 2.E Electronics Industry, which also represents the emission trend of subcategory 2.E.1 is depicted in Fig. 4-9 from year 1997, when the use of CF_4 began, to 2024. Emissions of F-gases equalled to 41.51 kt CO_2 eq. in 2024. Tab. 4-22 lists the exact amount of CO_2 eq. emissions from category 2.E.

Tab. 4-22 Emissions from category 2.E. Electronics Industry in the time period 1997–2024

		1997	1998	1999	2000	2001	2002	2003	2004	2005	2006
Emissions	**[kt CO_2 eq.]**	1.02	1.02	8.69	11.16	20.87	19.31	4.79	3.99	6.17	19.99
		2007	**2008**	**2009**	**2010**	**2011**	**2012**	**2013**	**2014**	**2015**	**2016**
Emissions	**[kt CO_2 eq.]**	17.81	26.30	32.26	38.28	6.27	3.98	3.88	4.04	5.20	6.32
		2017	**2018**	**2019**	**2020**	**2021**	**2022**	**2023**	**2024**		
Emissions	**[kt CO_2 eq.]**	6.95	6.47	5.35	4.51	35.08	53.55	70.56	41.51		

Tab. 4-23 gives an overview of the emission factors and methodology used for computations of emissions in category 2.E. Electronics Industry in 2024.

Tab. 4-23 Type of CO_2 emissions factors used for computations of 2024 emissions in category 2.E Electronics Industry

	F-gas reported	Source or type EF	Methodology
2.E.1 Integrated Circuit or Semiconductor	HFC-23, CF_4, C_2F_6, SF_6, NF_3	Default (IPCC 2006)	Tier 2a

4.6.1 Integrated Circuit or Semiconductor (CRT 2.E.1)

4.6.1.1 Source category description

This category includes the gases C_2F_6, CF_4, SF_6, CHF_3 (HFC-23) and NF_3 used by semiconductor manufacturers. These gases are used in the plasma chemical thin layer etching process. The process is based on the reaction between atomic fluorine and the material of the layer. Atomic fluorine is derived from the fluorinated gases mentioned above in the presence of capacity-induced plasma.

In 2024, gases C_2F_6, CF_4, SF_6, CHF_3 (HFC-23) and NF_3 were used for semiconductor manufacturing, while in year 2020 only gases SF_6 and NF_3 were used. The change in reported gases is due to the change of company product portfolio. According to the main manufacturer, the fluctuating trend in emissions is linked with the fluctuating consumption of gases for semiconductor manufacturing. The consumption of gases in the current year depends on the planned capacity of production, type of manufactured products and types of etching processes.

4.6.2 Methodological issues

Gases C_2F_6, CF_4, SF_6, CHF_3 (HFC-23) and NF_3 are reported for category 2.E.1 Integrated Circuit or Semiconductor. Activity data about consumption of F-gases are available since 1997.

Emissions from this category are calculated using Tier 2a methodology described in IPCC 2006 Gl., Equation 6.2 without using fractions a_i and d_i, which are considered by expert judgement to be negligible and further using Equation 6.3 for estimation of by-product emissions of CF_4 (IPCC 2006). By-product emissions of CF_4 are reported together with regular CF_4 emissions.

The manufacturers of electrical equipment maintain very eco-friendly policies (involving treatment, training of staff, certificate etc.). Operational leakages are not measured (legislation does not force operators to do so) but can be estimated based on stock change. After a consultation with the main operator in the country the leakages are virtually non-existent and depend solely on accidents. Leakages represent less than 100 kg/year in total. Such a low amount of SF_6 is not required to be reported from the operator into national database "Integrated system of reporting obligations" (*Integrovaný systém plnění ohlašovacích povinností* - ISPOP).

The emission factors employed are summarized in Tab. 4-24. The default emission factors for the gases HFC-23, CF_4, C_2F_6, SF_6 and NF_3 were chosen from IPCC 2006 Gl., Volume 3, Table 6.3 (IPCC 2006).

Tab. 4-24 Emissions factors used for computations of 2024 emissions from 2.E.1 Integrated Circuit or Semiconductor

F-gas	IPCC 2006 Gl. (IPCC 2006)			
	(1-Ui)	B_{CF4}	B_{C2F6}	B_{C3F8}
HFC-23 (CHF_3)	0.4	0.07	NA	NA
CF_4	0.9	NA	NA	NA
C_2F_6	0.6	0.2	NA	NA
SF_6	0.2	NA	NA	NA
NF_3	0.2	0.09	NA	NA

4.6.3 Uncertainties and time-series consistency

The uncertainty estimates were based on expert judgment (see IPCC 2006 Gl., Volume 1, Chapter 3 Uncertainties). Improvement of uncertainty estimation is in progress.

Time series consistency is ensured as the inventory approaches concerned are employed identically across the whole reporting period from 1997 (when the use of CF_4 began) to 2024.

4.6.4 Source -specific QA/QC and verification

The input information and calculations are archived by the sectoral expert and the coordinator of NIS.

Validation was performed by comparing the data obtained directly from manufacturer with data obtained from Customs Office of the Czech Republic, ISPOP and Ministry of the Environment.

The quality control was held by fulfilling the QA/QC form presented in A 4.1.

4.6.5 Source -specific recalculations, including changes made in response to the review process and impact on emission trend

In this year, no recalculations were performed in this category.

4.6.6 Source -specific planned improvements, including tracking of those identified in the review process

Although the current survey considered factors ai and di in Tier 2a methodology as negligible, it is planned to explore this technology further in more detail in future submissions, no later than the introduction of F-gases in the EU ETS trading. Improvement of uncertainty estimation is in progress.

4.7 Product Uses as Substitutes for Ozone Depleting Substances (ODS) (CRT 2.F)

This category describes emissions of F-gases from the following categories: 2.F.1 Refrigeration and Air Conditioning, 2.F.2 Foam Blowing Agents, 2.F.3 Fire Protection, 2.F.4 Aerosols and 2.F.5 Solvents. The base year of using F-gases in the Czech Republic is 1995. The determination of the base year was based on the information from possible emission sources and on fact, that the same base year is determined in neighboring countries with similar composition.

The emission trend for category 2.F is depicted in Fig. 4-10. The major share of 99% in the range of actual emissions for the year 2024 corresponds to category 2.F.1. Actual emissions from other categories under 2.F are insignificant compared to category 2.F.1. Actual emissions of F-gases increased from 86.90 kt CO_2 eq. in 1995 to 3 491.55 kt CO_2 eq. in 2024. This significant leap forward by orders of magnitude has been driven mainly by substantial increase in the use of HFCs in refrigeration. Due to legislative restrictions on F-gases, there has been a decline since 2019.



Fig. 4-10 Trend of emissions from 2.F Product Uses as Substitutes for Ozone Depleting Substances and share of specific subcategories [kt CO_2 eq.]

Detailed information about actual emissions is given in Tab. 4-25 and in the CRT Tables. The higher level of emissions during the last decade could be explained by the growth of large users, such as the automotive industry and the manufacturing of stationary air-conditioning. The vast majority of F-gases remain from the production of refrigerators and air conditioners.

Tab. 4-25 Actual emissions of HFCs and PFCs in 1995–2024 [kt CO_2 eq.]

	Category 2.F - emissions of PFCs and HFCs [kt CO_2 eq.]		
	Emissions of PFCs and HFCs	Emissions of HFCs	Emissions of PFCs
1995	86.90	86.89	0.01
1996	216.17	215.49	0.68
1997	389.62	389.02	0.60
1998	530.01	529.49	0.52
1999	636.76	635.87	0.89
2000	802.15	800.04	2.11
2001	1 001.69	998.32	3.38
2002	1 102.27	1 098.75	3.52
2003	1 218.89	1 212.19	6.69
2004	1 351.78	1 343.12	8.65
2005	1 357.33	1 347.96	9.37
2006	1 610.64	1 600.80	9.84
2007	1 968.06	1 957.64	10.42
2008	2 228.87	2 217.19	11.68
2009	2 244.56	2 233.98	10.58
2010	2 458.45	2 450.62	7.82
2011	2 665.40	2 659.54	5.86
2012	2 769.14	2 764.27	4.88
2013	2 897.49	2 893.55	3.94
2014	3 076.25	3 073.55	2.70
2015	3 326.21	3 324.47	1.74
2016	3 544.33	3 542.93	1.40
2017	3 751.21	3 749.82	1.39
2018	3 816.80	3 815.27	1.53
2019	3 839.59	3 838.46	1.13
2020	3 747.82	3 747.23	0.59
2021	3 737.85	3 737.54	0.31
2022	3 609.06	3 608.90	0.16
2023	3 570.31	3 570.22	0.09

2024	3 491.55	3 491.49	0.06

Tab. 4-26 gives an overview of the emission factors and methodology used for computations of emissions in category 2.F Product Uses as Substitutes for Ozone Depleting Substances in 2024.

Tab. 4-26 Type of emissions factors used for computations of 2024 emissions in category 2.F

	Reported emissions	Source or type EF	Methodology
2.F.1 Refrigeration and Air Conditioning	HFCs, PFCs	CS and Default (IPCC 2006)	Tier 2a
2.F.2 Foam Blowing Agents	HFCs	Default (IPCC 2006)	Tier 1a
2.F.3 Fire protection	HFCs, PFCs	Default (IPCC 2006)	Tier 1a
2.F.4 Aerosols	HFCs	Default (IPCC 2006)	Tier 1a
2.F.5 Solvents	HFCs	Default (IPCC 2006)	Tier 1a

Emissions of F-gases (HFCs, PFCs, SF_6, NF_3) in the Czech Republic are at relatively low level due to the absence of large industrial sources. Furthermore all of the F-gases in the Czech Republic are imported; therefore there are no fugitive emissions from manufacturing. Additionally, there is no production of other fluorinated gases (CFCs, HCFCs, etc.) that could lead to by-product F-gases emissions and there is no primary aluminium and magnesium industry in the Czech Republic.

Currently, the national F-gas inventory is based on the method of actual emissions, according to the IPCC 2006 Gl. (IPCC 2006). Data about direct import/export, use and destruction for subcategories under 2.F are obtained from following sources:

- ISPOP ("Integrated system of reporting obligations"),
- The F-gas register (Questionnaire on production, import, export, feedstock use and destruction of the substances listed in Annexes I or II of the F-gas regulation),
- The database of Cross-border movements of goods (Customs data).

Collecting of data and preparation of input data for emission estimates is described in more detail in Annex 0.

In 2024, the structure of customs data provided for import and export of F-gases changed. It will be necessary to verify further whether the current dataset covers the same scope of information as in previous years. By 11th March 2024, Regulation EU/2024/573 introduces restrictions on the production and placing on the market of products using fluorinated greenhouse gases, in particular those with a high global warming potential (GWP). At the same time, it sets targets for a gradual reduction of the amount of these gases on the market through a quota system and bans the use of specific types of gases in certain applications such as refrigeration, air conditioning and foam insulation. The regulation is reflected in the first fill emissions of relevant F-gases throughout all 2.F categories. The implementation of this regulation may also contribute to improvements in the structure and availability of data in future reporting years.

Only two companies in the Czech Republic are dealing with regeneration of HFC coolants. Appliances containing HFCs are still being disposed in lower amounts, considering their 6–30 year life cycle (IPCC 2006 GL, Volume 3, Chapter 7, Table 7.9), which depends on the type of device. In recent years, the online platform Retradeables briefly operated as a marketplace for recovered F-gases, but it was discontinued due to limited interest. According to the ISPOP database and the F-gas register, 6.47 t of F-gases were disposed of in 2024 in the Czech Republic.

4.7.1 Refrigeration and Air Conditioning (CRT 2.F.1)

4.7.1.1 Source category description

This category describes emissions of F-gases from the following subcategories: 2.F.1.a Commercial Refrigeration, 2.F.1.b Domestic Refrigeration, 2.F.1.c Industrial Refrigeration, 2.F.1.d Transport Refrigeration, 2.F.1.e Mobile Air Conditioning and 2.F.1.f Stationary Air Conditioning.

The major share 36.4% in the range of actual emissions for the year 2024 belongs to the subcategory 2.F.1.e, share 29.2% belongs to the subcategory 2.F.1.a, share 21.8% belongs to the subcategory 2.F.1.f, share 9.9% belongs to the 2.F.1.c, share 2.7% belongs to the 2.F.1.d and share 0.02% belongs to the 2.F.1.b. Trend of emissions from 2.F.1 is depicted on Fig. 4-11. Category 2.F.1 was identified as a key category in this submission.

A large number of blends are being used in refrigeration and air conditioning systems. Many blends contain HFCs and/or a limited amount of PFCs in various proportions. The main type of blend used in the Czech Republic for stationary air conditioning/refrigeration is R 410A, a mixture of HFC-32 and HFC-125 in a ratio of 50:50. Blends R-407C and R-507A are used in smaller amounts. R-407C is a mixture of HFC-32, HFC-125 and HFC-134a in a ratio of 23:25:52. R-407C is used mainly in stationary air conditioning. R-507A is a mixture of HFC-125 and HFC-143a in a ratio of 50:50. A consumption of blend R-404A has been decreasing since 2018. The blend contains HFC-125, HFC-143a and HFC-134a gases in a ratio of 44:52:4. The decreasing consumption is consequence of fact that manufacturers are preparing for limitation of this blend according to EU legislative. Blends containing HFO-1234yf and HFO-1234ze have been used in the Czech Republic since 2016. Emissions from these gases are reported separately in category 2.H.3 Other (see chapter 4.9.2 for more information).

An overview of reported gases under a specific subcategory is presented in Tab. 4-27. PFCs have not been used in the Czech Republic for many years, but emissions from previous use of PFCs still occur.



Fig. 4-11 Trend of emissions from 2.F.1 Refrigeration and Air conditioning and share of specific subcategories [kt CO_2 eq.]

Tab. 4-27 An overview of the F-gases reported under subcategory 2.F.1

Source category	Reported F-gases
2.F.1.a Commercial Refrigeration	HFC-125, HFC-143a, HFC-23, HFC-134a, HFC-227ea, HFC-32, HFC-152a, C_6F_{14}, C_3F_8, C_2F_6
2.F.1.b Domestic Refrigeration	HFC-134a
2.F.1.c Industrial Refrigeration	HFC-32, HFC-125, HFC-134a, HFC-143a
2.F.1.d Transport Refrigeration	HFC-32, HFC-125, HFC-134a, HFC-143a
2.F.1.e Mobile Air Conditioning	HFC-134a
2.F.1.f Stationary Air Conditioning	HFC-32, HFC-125, HFC-134a, HFC-143a

4.7.1.2 Methodological issues

Emissions from all subcategories under 2.F.1, except subcategory 2.F.1.e, are calculated by the Phoenix calculation model. Tier 2a methodology was used for emission estimates in all the subcategories under 2.F.1; the emission factors used for the estimation are in the default ranges proposed by IPCC 2006 Gl. (IPCC 2006).

2.F.1.a, 2.F.1.b, 2.F.1.c, 2.F.1.d, 2.F.1.f

Emissions from categories 2.F.1.a, 2.F.1.b, 2.F.1.c, 2.F.1.d, 2.F.1.f are calculated by calculation model Phoenix, which was introduced for the first time for submission 2017–2015 (Ondrusova, Krtkova 2018).

The calculation model can be divided to four main parts: *input, divider, emission estimates and output*. For input, it is important to update the data on the consumption of F-gases, emission factors and legislative changes. The divider separates the input activity data into sub-applications, where division into the sub-applications is based on expert judgement. The emission estimates are fully automatic and calculate the emissions of refrigerant due to the charging process of new equipment, emissions during lifetime and emissions at the end of lifetime. The output provides information about total emissions under the sub-applications and overall emission trends for category 2.F.1.

INPUT

Input of the model consists of three parts, which are manually updated - activity data, emission factors and legislative measures. Data about direct import/export and destruction are obtained from three different sources. Moreover, AD from these sources are then verified to avoid double counting via possible duplicities across the data sources. For more information about data sources and the sorting system please Annexes 0.

The data sources cover trade between the Czech Republic and both EU and non-EU countries, ensuring global market coverage. In the AD sources, importers, exporters and users of F-gases may also voluntarily report amounts of consumed F-gases below the threshold. With the implementation of Regulation (EU) 2024/573, smaller F-gas flows are increasingly captured in reporting.

Addition to the stock of specific F-gas, net consumption in the current year is calculated as import minus export and destruction. The calculation of an addition to the stock of F-gas takes into account the total amount of chemical banked in the previous year, new additions to the stock and subtraction of emissions.

Selection of emission factors should be based on the national information provided by manufacturers, service providers, disposal companies and other organizations. Collecting of such detailed information is very difficult under the current state of administration in the Czech Republic, and thus, the emission factors are based on the expert judgement and the emission factors are in the default ranges proposed by IPCC 2006 Gl., Table 7.9 (IPCC 2006). Emission factors used for emissions estimates are shown in Tab. 4-28.

Tab. 4-28 Parameters used for emission calculations for category 2.F.1 in calculation model

Source category	Lifetimes [years]	Emission Factors [% of initial charge/year]		End-of-Life emissions [%]	
Factor in equation	(d)	(k)	(x)	($\eta_{rec,d}$)	(p)
		Initial Emissions	Operation Emissions	Recovery Efficiency	Initial Charge Remaining
2.F.1.a Commercial Refrigeration	10.50	3.00	13.00	55.00	70.00
2.F.1.b Domestic Refrigeration	13.50	0.50	0.35	55.00	70.00
2.F.1.c Industrial Refrigeration	17.00	3.00	13.00	55.00	70.00

2.F.1.d Transport Refrigeration	8.50	0.50	20.00	55.00	30.00
2.F.1.f Stationary Air Conditioning	13.50	0.50	6.50	55.00	70.00

DIVIDER

Unfortunately, there is a lack of information about the specific use of gas obtained from the above sources, and thus, the calculation model must divide input data into sub-applications by a divider. The divider is shown in Tab. 4-29. The percentage share of each gas in the relevant sub-application is currently based on sectoral expert judgement, which is supported by the data obtained from Association of refrigeration and air conditioning.

The calculation model takes into account the phasing out or the phasing down of F-gases depending on the Montreal Protocol and national and regional regulation schedules, e.g. according to Regulation EU No 573/2024, the F-gas HFC-134a cannot be longer used in domestic refrigeration since 2015, which means that the relative share of HFC-134a has been considered to be 0% since 2015.

Tab. 4-29 Distribution of HFCs and PFCs use by application area used for emission calculations in 2024

Reported F-gases	2.F.1.a Commercial Refrigeration	2.F.1.b Domestic Refrigeration	2.F.1.c Industrial Refrigeration	2.F.1.d Transport Refrigeration	2.F.1.f Stationary Air Conditioning
HFC-125	40%	x	15%	5%	40%
HFC-143a	60%	x	15%	5%	20%
HFC-23	100%	x	x	x	x
HFC-134a	60%	0%	15%	5%	20%
HFC-227ea	100%	x	x	x	x
HFC-32	40%	x	15%	5%	40%

EMISSION ESTIMATES

Total emissions for individual F-gas are calculated as the sum of emissions from filling of new equipment E_{charge}, emissions during the equipment lifetime $E_{lifetime}$ and emissions at the system end of life $E_{end\ of\ life}$ in accordance with Equation 7.10 described in IPCC 2006 Gl. (IPCC 2006). Emissions from subcategories under 2.F.1 are calculated using Tier 2a Method (emission-factor approach) described in IPCC 2006 Gl. (IPCC 2006). The parameters used for emission estimates were established by an expert judgement and Table 7.9 in the input of the calculation model (IPCC 2006). Equations for emission calculation are in accordance with the equations described in the IPCC 2006 Gl. (Equation 7.12, Equation 7.13, and Equation 7.14). Emissions from decommissioning are calculated using Gaussian distribution model with mean at lifetime expectancy. The model takes into account different approach for serviced equipment and newly filled equipment, assuming only half life-expectancy for the serviced equipment, resp. the amount of service-filled gas.

OUTPUT

The output of the model represents an overview of F-gas emissions in sub-applications for the individual gases from 1995 to the latest year of the national inventory reporting and a total overview of emissions from category 2.F.1 (except 2.F.1.e). Tab. 4-30 depicts emissions of F-gases for the individual sub-applications in 2024 and comparison with levels of emissions in 2023 and in the base year.

Tab. 4-30 Emissions of HFCs and PFCs from subcategories under 2.F.1 in 2024 – comparison to levels of emissions in 2024 and 1995

Source sub-application	Emissions of HFCs and PFCs 2024	Difference 2024 and 2023	Difference 2024 and 1995

	[kt CO_2 eq.]	[%]	[%]
2.F.1.a Commercial Refrigeration	1007.36	-6.94%	99.98%
2.F.1.b Domestic Refrigeration	0.64	-9.50%	99.98%
2.F.1.c Industrial Refrigeration	340.50	-0.95%	99.99%
2.F.1.d Transport Refrigeration	93.82	-6.92%	99.98%
2.F.1.f Stationary Air Conditioning	1256.66	1.31%	100.00%

In some years notation key NE is used under 2.F.1 for the amount remaining in products at decommissioning and the emissions from the disposal and recovery of HFC-134a and HFC-32 gases. Notation key NE is used in accordance with decision 24/CP.19. Emissions are considered to be insignificant. The level of emissions is below 0.05% of the national total GHG emissions and the ETF Reporting Tool does not allow report values lower than 1.0E-14. A number lower than 1.0E-14 is rounded off to 0.00 by the ETF Reporting Tool. Specific subcategories with notation key NE and the related year are shown in Tab. 4-31.

Tab. 4-31 Subcategories in which is used notation key NE for gases HFC-134a and HFC-32 with related year

Source category	Reported F-gas	Year
2.F.1.a Commercial Refrigeration	HFC-134a	1996
	HFC-32	1998, 1999
2.F.1.b Domestic Refrigeration	HFC-134a	1996
2.F.1.c Industrial Refrigeration	HFC-32	1998, 1999
	HFC-134a	1996
2.F.1.d Transport Refrigeration	HFC-32	1998
	HFC-134a	1996
2.F.1.f Stationary Air Conditioning	HFC-32	1998, 1999
	HFC-134a	1996

2.F.1.e

Emissions from subcategory 2.F.1.e are calculated separately from other subcategories under category 2.F.1. The main reason for this separation is the different approach to collecting activity data for the emission estimates. Emissions of HFC-134a from filling new equipment E_{charge}, emissions during the equipment lifetime $E_{lifetime}$, and emissions at the end of life of the system $E_{end\ of\ life}$, are calculated separately. Total emissions are calculated as a sum of emissions from filling new equipment E_{charge}, emissions during lifetime $E_{lifetime}$ and emissions at the end of life of the equipment $E_{end\ of\ life}$. Emission factors used for emission estimates for 2.F.1.e are shown in Tab. 4-32.

Tab. 4-32 Parameters used for emission calculations for subcategory 2.F.1.e

Source category	Lifetimes [years]	Emission Factors [% of initial charge/year]		End-of-Life emissions [%]	
Factor in equation	(d)	(k) Initial Emissions	(x) Operation Emissions	($\eta_{rec,d}$) Recovery Efficiency	(p) Initial Charge Remaining
2.F.1.e Mobile air conditioning	Passenger cars 15 Light duty vehicles 13 Heavy duty vehicles 16 Buses 14	0.50	20.00	10.00	30.00

Since 2016, car producers started to use HFO-1234yf as a substitute for HFC-134a in accordance with the Directive 2006/40/EC, and thus, also emissions of HFO-1234yf were calculated. Since ETF Reporting Tool

does not allow creating node for alternative refrigerant under 2.F.1.e category, emissions of HFO-1234yf are reported under category 2.H.3 Other and then emissions are accounted in national inventory.

Emissions from filling new equipment

Data for emission estimates are obtained from the Automotive Industry Association. These data contain the production figures for the Czech automobile industry since 1995. Three car producers (ŠKODA AUTO Inc., Hyundai Motor Czech Ltd. and Toyota Motor Manufacturing Ltd.), bus producers (SOR Libchavy Ltd., Iveco Czech Republic Inc. and other) and one truck producer (TATRA TRUCKS Inc.) are currently operating in the Czech Republic. Approximately 62% of all new passenger cars are produced by a single manufacturer.

Emissions from filling of new cars are calculated by following steps:

- Data about total production for each producer are obtained directly from each producer and checked with data provided by the Automotive Industry Association. For the the year 2024, the amount of cars produced in the CR are listed in the Tab. 4-33 bellow.

Tab. 4-33 Number of vehicles produced in the Czech Republic in the year 2024

Car producer	Number of vehicles produced in 2024
ŠKODA AUTO Inc.	896 933
Hyundai Motor Czech Ltd.	330 890
Toyota Motor Manufacturing Ltd.	225 058

- The initial charge of HFC-134a filled into new equipment is estimated for each car type of each producer. Therefore the initial charge is not constant through the time series, neither for all producers. The initial charge varies between 390 g and 865 g per unit.
- The percentage share of cars equipped with air conditioning through the time series is based on data from the main Czech car bazaar and expert judgement. The percentage share of cars equipped with air conditioning is calculated for each producer separately.
- In 2016, producers started to use HFO-1234yf as a substitute for HFC-134a in accordance with the preparation of Phase 3 of Directive 2006/40/EC. HFC-134a is filled into cars which are intended for the non-EU market. The share of cars that were intended for the non-EU market was calculated on the basis of data from the producers' yearbooks and these data have been used for emission estimates since 2016.
- The amount of HFC-134a filled into new cars of each type in the given year is calculated as:
  $Amount\ of\ HFC\text{-}134a_{\ t} = Production_{\ t} * Average\ initial\ charge_{\ t} * Average\ percentage\ share\ of\ cars\ with\ AC_{\ t}$.
  Since 2016, the calculation has also taken into account transition to the use of alternative refrigerant. The total amount of HFC-134a filled into new cars produced in the Czech Republic is calculated as the sum of the amounts used for each car type by each producer.
- The emissions are calculated according Equation 7.12 described in IPCC 2006 GI. The emission factors are in the default ranges proposed in Table 7.9 IPCC 2006 GI. (IPCC 2006).

Emissions from filling of new buses and trucks are calculated by the following steps:

- Data about the total production for each producer are obtained from the Automotive Industry Association.
- The initial charge of HFC-134a filled into new equipment is considered to be 10 kg per bus and 1.2 kg per truck.
- The percentage share of new buses and trucks equipped with AC is linearly interpolated from 50% in 1995 to 100% in 2014; since 2014, it has been assumed that all buses and trucks are manufactured with air conditioning. Unfortunately, there is a lack of detailed information from

producers and thus the percentage share is based on expert judgement, which is based on emission estimates in neighbouring countries and the conditions in the Czech Republic.

- The amount of HFC-134a filled into new buses and trucks in a given year is calculated separately as: *Amount of HFC-134a $_t$ = Production $_t$ * Initial charge $_t$ * Percentage share of buses/trucks with AC $_t$*. The total amount of HFC-134a filled into new buses and trucks produced in the Czech Republic is calculated as the sum of the amounts used for filling new buses and trucks.
- Emissions are calculated according Equation 7.12 described in IPCC 2006 GI. The emission factors are in the default ranges proposed in Table 7.9 IPCC 2006 GI. (IPCC 2006).

Emissions during the equipment lifetime

Detailed data about vehicles stock in the Czech Republic are obtained from COPERT (software and methodology developed by EMISIA S.A.) for 1995–2024. Data from COPERT were provided by the Transport Research Centre (CDV). Data contain information about the numbers of passenger cars, light duty vehicles, heavy duty trucks and buses divided by the fuel type, segment and EURO standard as it is summarized in Tab. 4-34.

Tab. 4-34 Information about vehicles fleet of the Czech Republic obtained from COPERT

Type	Fuel	Segment	Euro standard
Passenger Cars	Petrol Diesel LPG Bifuel CNG Bifuel Battery electric	Mini Small Medium 2-Stroke Large SUV	Conventional ECE 15/00-01 ECE 15/02 ECE 15/03 ECE 15/04 Euro 1 Euro 2 Euro 3 Euro 4 Euro 5 Euro 6 a/b/c Euro 6 d/e Euro 6 d-temp Euro 7 Improved Conventional Open Loop PRE ECE
Light Commercial vehicles	Battery electric Petrol Diesel	N1-I N1-II N1-III	Conventional Euro 1 Euro 2 Euro 3 Euro 4 Euro 5 Euro 6 a/b/c Euro 6 d/e Euro 6 d-temp Euro 7
Heavy duty trucks	CNG Petrol LNG Diesel	Articulated (divided according weight) Rigid (divided according weight)	Conventional Euro I Euro II Euro III Euro IV Euro V Euro VI A/B/C Euro VI D/E Euro VII
Buses	Battery electric Biodiesel CNG	Coaches articulated > 18t Coaches standard <= 18t Urban biodiesel buses	Conventional EEV Euro I

Type	Fuel	Segment	Euro standard
	Diesel	Urban buses articulated > 18t	Euro II
	Diesel Hybrid	Urban buses midi <= 15t	Euro III
		Urban buses standard 15-18t	Euro IV
		Urban CNG buses	Euro V
		Urban CNG Buses <=15 t	Euro VI A/B/C
		Urban CNG Buses >18 t	Euro VI D/E
		Urban CNG Buses 15 - 18 t	Euro VII

Information obtained from COPERT and depicted in the table above is too detailed for the emission estimates of HFC-134a, and thus, as important input for emission estimates is only taken the type of vehicle (passenger car, light duty vehicle, heavy duty truck and bus) in adequate euro standard (in the case of buses and heavy duty trucks euro standard it's not taken into account).

Operational emissions for cars and light duty vehicles are calculated as follows:

- Number of cars or light duty vehicles in adequate euro standard is obtained from COPERT (e.g. 1 244 472 passenger cars (Euro standard 4) were registered in the Czech Republic in 2024).
- Percentage shares of cars or light duty vehicles equipment with AC in each Euro standard group are based on data from COPERT and expert judgement as it is in following table. Since 2017, cars placed on EU market cannot contain refrigerant HFC-134a. Therefore it is considered that new models are equipped with HFO-1234yf.

Tab. 4-35 AC shares and type of refrigerant in Euro standard

Type	AC Share	Refrigerant
Conventional	10%	HFC-134a
ECE 15/00-01	10%	HFC-134a
ECE 15/02	10%	HFC-134a
ECE 15/03	10%	HFC-134a
ECE 15/04	10%	HFC-134a
Euro 1	20%	HFC-134a
Euro 2	60%	HFC-134a
Euro 3	85%	HFC-134a
Euro 4	95%	HFC-134a
Euro 5	95%	HFC-134a
Euro 6 2017–2019	95%	HFO-1234yf
Euro 6 2018–2020	95%	HFO-1234yf
Euro 6 up to 2016	95%	HFC-134a
Euro 6 up to 2017	95%	HFO-1234yf
PRE ECE	10%	HFC-134a

- The number of cars equipped with air conditioning is calculated as total number of cars or light duty vehicles in euro standard multiplied by appropriate percentage share as in Tab. 4-35. Newer types containing HFO-1234yf are excluded from calculation.
- The specific charge for the year is estimated as 0.7 kg per unit for 1995–2005, 0.65 kg per unit for 2006–2008 and, since 2009, 0.6 kg per unit. The lower charges are a result of transformation of the car fleet.
- The refrigerant stocks are calculated for cars and light duty vehicles as follows: *HFC-134 stock* $_t$ = *Number of cars or light duty vehicles equipped with air conditioning (HFC-134a)* $_t$ * *charge* $_t$.
- Emissions are calculated according Equation 7.13 described in IPCC 2006 Gl. The emission factors are in the default ranges proposed in Table 7.9 IPCC 2006 Gl. (IPCC 2006).

Operation emissions for heavy duty trucks and buses are calculated by the following steps:

- The number of heavy duty trucks and buses for 1995–2024 are obtained from COPERT.
- The percentage share of buses equipment with air conditioning is linearly interpolated from 10% in 1995 to 79% in 2024; the percentage share of trucks equipped with air conditioning is linearly interpolated from 50% in 1995 to 100% in 2024. There is a lack of detailed information about percentage shares of heavy duty trucks and buses with air conditioning, and thus, the percentage share is based on expert judgement, which is based on the emission estimates of neighbouring countries and the conditions in the Czech Republic.
- The specific charge of HFC-134a filled into the equipment is estimated as 10 kg per bus and 1.2 kg per truck.
- The refrigerant stocks are calculated separately for buses and trucks as: *HFC-134 stock $_t$ = Number of buses or trucks with air conditioning $_t$ * specific charge $_t$.*
- The emissions are calculated according Equation 7.13 described in IPCC 2006 Gl. The emission factors are in the default ranges proposed in Table 7.9 IPCC 2006 Gl. (IPCC 2006).

Emissions at the system end of life

Emissions at the system end of life are calculated by the following steps:

- The number of disposed vehicles (passenger cars, light duty vehicles, heavy duty vehicles and buses) is obtained from the Car Importers Association.
- The average vehicle lifetime is estimated as to 15 years for passenger cars, 13 years for light duty vehicles, 16 years for heavy duty vehicles and 14 years for buses. The estimations are based on information from the Car Importers Association, the Automotive Industry Association and the Ministry of Transport.
- The percentage time series of vehicles with air conditioning are based on data from the main Czech car bazaar and expert judgement and are the same as for the estimation of operational emissions (percentage share for passenger cars and light duty vehicles is simplified in comparing with the approach used for the estimation of operational emissions mainly due to the fact that data about disposed vehicles are not sorted to Euro standard).
- The specific charge of refrigerant is the same as for the estimation of operational emissions (please see paragraphs above).
- The amount of disposed refrigerant is calculated as: *HFC-134a disposed $_t$ = Number of disposed vehicles $_t$ * percentage share of cars with air conditioning $_{t-average\ lifetime}$ * charge $_{t-average\ lifetime}$*
- The emissions are calculated according Equation 7.14 described in IPCC 2006 Gl. The emission factors are in the default ranges proposed in Table 7.9 IPCC 2006 Gl. (IPCC 2006).

Tab. 4-36 gives the emissions of F-gases from mobile air conditioning units in 2024 and comparison with emission levels in 2023 and in the base year for HFC-134a.

Tab. 4-36 Emissions of HFCs and PFCs from 2.F.1.e in 2024 – comparison to emission levels in 2023 and 1995

Source sub-application	Emissions of HFCs and PFCs 2024 [kt CO_2 eq.]	Difference 2024 and 2023 [%]	Difference 2024 and 1995 [%]
2.F.1.e Mobile air conditioning	1256.66	1.31%	1351.05%

4.7.2 Foam Blowing Agents (CRT 2.F.2)

This category includes only emissions from subcategory 2.F.2.a Closed cells. Emissions from following gases are occurring from this category in the Czech Republic: HFC-134a (from stocks, from disposal), HFC-227ea (from stocks), HFC-245fa (from stocks). F-gases were used in the Czech Republic only for producing hard

foam. Solely HFC-143a was used regularly for foam blowing. HFC-227ea and HFC-245fa were used occasionally in previous years for testing purposes. Due to high costs, HFCs are being replaced by other hydrocarbons. Total emissions from 2.F.2 amounted to 3.89 kt CO_2 eq. in 2024. Use of HFC for foam blowing was not reported in 2024.

Increased amount of emissions from category 2.F.2 in 2016, 2017 and 2018 was driven by emissions from disposal of HFC-134a. Default product lifetime is 20 years which means that emissions from disposal started to be accounted in inventory since 2015. In 1995, small amount of HFC-134a was used in category 2.F.2, and thus, emissions from disposal in 2015 were not so significant. The amount of HFC-134a used in 1996 was approximately 77 times higher than in 1995, and thus, emissions from disposal in 2016 are higher comparing to 2015. A similar situation can be observed for emissions from disposal for the years 2017 and 2018.

4.7.2.1 Methodological issues

Emissions from this category are calculated by default methodology and EF described in IPCC 2006 Gl., Equation 7.7 for foam blowing (IPCC 2006).

4.7.3 Fire Protection (CRT 2.F.3)

Emissions from following gases are occurring in category 2.F.3 Fire protection: HFC-227ea, HFC-236fa, C_3F_8 (only from stocks and disposal). Total emissions from 2.F.3 amounted to 33.79 kt CO_2 eq. in 2024.

4.7.3.1 Methodological issues

Emissions from this category are calculated on the basis of IPCC 2006 Gl., Equation 7.17 (IPCC 2006). Calculations are based on data concerning production of new equipment and servicing the old equipment. It was revealed in consultations with servicing companies that first-fill leakages are very low and remain below 2% of the total emissions. Operational leakages are virtually non-existent and depend solely upon activation of fire alarms.

In the equipment servicing process, the original halons are sucked out and usually re-used again. The halons are recycled either with simple filtration or distillation. Re-use of original media without any treatment may also occur. Old types of halons (prohibited in the years before 2000) can no longer be manufactured but some of the mixtures can be reused after regeneration. A major part of new equipment employs HFC-227ea, while some installations are filled with HFC-236fa. Due to reuse of regenerated old halon mixtures, HFCs are being introduced rather slowly.

4.7.4 Aerosols (Propellants) (CRT 2.F.4)

This category include emission estimates from metered dose inhalers used in medical applications (2.F.4.a), and from general-purpose aerosols (2.F.4.b). Total emissions from 2.F.4 amounted to 2.91 kt CO_2 eq. in 2024.

Metered dose inhalers (MDIs) containing F-gases first appeared on the Czech market in 1995. In these MDIs, HFC-134a was used as a propellant. One year later, MDIs with HFC-227ea started to be sold as well. The number of sold MDIs containing HFC-134a has been increasing with minor fluctuations since 1995. The number of sold MDIs containing HFC-227ea reached its peak in 1999 and since then it has been gradually decreasing. Currently, approximately 90% of the sold MDIs contain HFC-134a.

HFC-134a was used in general-purpose aerosols from 1996 to 2015, and thus, emissions from 2.F.4.b are not occurring in 2024. F-gases were replaced by cheaper propellants, specifically dimethyl ether and other hydrocarbons (butane, isobutane and propane).

4.7.4.1 Methodological issues

Emissions from this category are based on IPCC 2006 Gl., Equation 7.6; EF equals to 50% (default) (IPCC 2006).

Information about MDIs supply between 1995 and 2024 is obtained from the State Institute for Drug Control. Amount of propellant is estimated separately for each product. The share of propellant in products varies between 88% and 99%.

Data about consumption of HFC-134a in general-purpose aerosols were obtained from ISPOP, the F-gas register, Database of Cross-border movements of goods (for more details see chapter 4.7.1), and questionnaire survey provided by sectoral expert.

4.7.5 Solvents (Non-Aerosol) (CRT 2.F.5)

Emissions from the use of HFC-245fa are not occurring in 2024 in category 2.F.5; emissions of other gases such as HFC-134a, HFC-152a are not occurring from 2014 and 2007 specifically. Emissions from 2.F.5 are not occurring in 2025.

4.7.5.1 Methodological issues

Emissions from this category are based on IPCC 2006 Gl., equation 7.5; EF equals to 50% (default) (IPCC 2006).

4.7.6 Uncertainties and time-series consistency

The uncertainty estimates were based on expert judgment (see IPCC 2006 Gl., Volume 1, Chapter 3 Uncertainties). The uncertainties for the activity data are at level 37% and 23% for the emission factors. Improvement of uncertainty estimation is in progress.

Time series consistency is ensured as the above mentioned methodologies for all categories under 2.F. are employed identically across the whole reporting period.

4.7.7 Source-specific QA/QC and verification

The input information and calculations are archived by the sectoral experts and the coordinator of NIS.

QA/QC and verification are provided for the activity data, emission factors and emission estimates:

- The activity data for all the subcategories under 2.F, except subcategory 2.F.1.e, are obtained from ISPOP, the F-gas register and the Database of Cross-border movements of goods. Verification of the activity data is conducted by comparison of the data received from the mentioned sources to ensure that no double counting occurs. Verification of the activity data for subcategory 2.F.1.e is ensured by comparison of the data obtained from COPERT, the Automotive Industry Association and the Car Importers Association. Estimated inputs of HFC-134a used in mobile air conditioning are compared with the data obtained from the latest NIDs for neighbouring countries with similar

transportation status. All inputs for emission estimates are checked by external QA/QC staff members.

- Selection of the emission factors for emission estimates is currently based on expert judgement. All the emission factors are default or in the default ranges proposed by IPPC 2006 Gl. For category 2.F.1, the emission factors are verified by comparison with the emission factors for neighbouring countries and for countries with a similar climate and status of refrigeration and air conditioning use.

Quality control was performed by completion of the QA/QC form in A 4.1 by a responsible compiler (autocontrol) and then by QA/QC staff members.

4.7.8 Source-specific recalculations, including changes made in response to the review process and impact on emission trend

Recalculation in subcategory 2.F.1.e

Subcategory 2.F.1.e Mobile Air Conditioning was recalculated following changes in data from COPERT model, activity data for calculating HFC-134a emissions from stocks were updated as well. Furthermore, the calculation of the number of vehicles containing HFC-134a was modified. Newer car types containing HFO-1234yf were excluded from the calculation (see Tab. 4-35)**.** The activity data for operation emission estimates are obtained from the COPERT since 2017 submission.

No other recalculation has been made in submission 2026.

4.7.9 Source-specific planned improvements, including tracking of those identified in the review process

The TERT recommended that the Party collect data and information on the reuse of recovered F gases in refrigeration, air conditioning and other subcategories. We acknowledge this recommendation. At present, the available information does not allow us to quantify the impact of reused HFCs in the inventory beyond the amounts listed in the existing registers. In line with the TERT's advice, we will continue working to identify relevant data sources and collect information on F gas reuse across different applications.

In parallel, future submissions will include an investigation of the emission factors used under category 2.F.1. Current emission factors are based on sectoral expert judgement, the opinion of a sectoral expert from another European country, and Table 7.9 of the IPCC 2006 Guidelines, Volume 3. We plan to examine country specific conditions and document the rationale for the chosen approach in order to improve transparency. The new dataset provided by the Customs Administration will also be assessed for its suitability for inventory use. In line with Regulation (EU) 2024/573, the inventory is planned to be made more accurate as improved input data become available.

4.8 Other Product Manufacture and Use (CRT 2.G)

This category describes GHG emissions from the following categories: 2.G.1 Electrical Equipment, 2.G.2 SF_6 and PFCs from Other Product Use, 2.G.3 N_2O from Product Uses and Category and 2.G.4 Other. Under the 2.G category are reported SF_6 and N_2O emissions.



Fig. 4-12 Trend of emissions from 2.G Other Product Manufacture and Use and share of specific subcategories [kt CO_2 eq.]

The emission trend for category 2.G is depicted in Fig. 4-12. The major share of 75% of GHG emissions for the year 2024 belongs to category 2.G.3, the share 20% belongs to category 2.G.1 and the share 5% belongs to category 2.G.2. Total GHG emissions from 2.G were 264.03 kt CO_2 eq. in 2024.

Tab. 4-37 lists the exact amount of CO_2 emissions from the individual subcategories in 2.G. Other Product Manufacture and Use for the 1990 to 2024 period.

Tab. 4-37 CO_2 eq. emissions in individual subcategories in 2.G Other Product Manufacture and Use category in 1990–2024

	Category 2.G - emissions [kt CO_2 eq.]			
	2.G.1 Electrical Equipment	2.G.2 SF_6 and PFCs from Other Product Use	2.G.3 N_2O from Product Uses	2.G.4 Other
1990	86.68	0.14	183.38	NO
1991	86.52	0.14	183.38	NO
1992	87.84	0.19	183.38	NO
1993	89.06	0.16	183.38	NO
1994	90.17	0.19	183.38	NO
1995	91.19	0.21	183.38	NO
1996	91.76	9.56	183.38	NO
1997	90.83	8.23	183.38	NO
1998	89.37	8.52	183.38	NO
1999	84.27	6.35	183.38	NO
2000	82.55	20.34	183.38	NO
2001	82.94	3.82	183.38	NO
2002	89.39	27.95	183.38	NO
2003	94.40	51.61	183.38	NO
2004	93.14	29.00	183.38	1.95
2005	87.05	16.89	183.38	10.18
2006	87.18	12.13	183.38	8.23
2007	86.54	9.66	183.38	NO
2008	83.39	7.07	198.75	NO
2009	85.53	5.56	198.75	NO
2010	79.20	4.48	198.75	NO
2011	84.55	4.49	198.75	NO
2012	88.96	4.46	198.75	NO
2013	78.84	4.42	198.75	NO
2014	76.56	4.39	198.75	NO
2015	73.27	4.59	198.75	NO
2016	72.57	4.54	198.75	NO
2017	68.52	4.53	198.75	NO
2018	65.28	4.42	198.75	NO
2019	63.07	4.46	198.75	NO
2020	60.60	4.43	198.75	NO
2021	58.43	19.09	198.75	NO
2022	56.33	16.66	198.75	NO
2023	54.30	16.63	198.75	NO

	Category 2.G - emissions [kt CO_2 eq.]			
	2.G.1 Electrical Equipment	2.G.2 SF_6 and PFCs from Other Product Use	2.G.3 N_2O from Product Uses	2.G.4 Other
2024	52.35	12.92	198.75	NO

Tab. 4-38 gives an overview of the emission factors and methodology used for computations of emissions in category 2.G for the year 2024.

Tab. 4-38 Type of emissions factors used for computations of 2024 emissions in category 2.G Other Product Manufacture and Use

	Reported emissions	Source or type EF	Methodology
2.G.1 Electrical Equipment	SF_6	Default (IPCC 2006)	T1
2.G.2 SF_6 and PFCs from Other Product Use	SF_6	Default (IPCC 2006)	D
2.G.3 N_2O from Product Uses	N_2O	Default (IPCC 2006)	D

4.8.1 Electrical Equipment (2.G.1)

4.8.1.1 Source category description

This subcategory is divided into Medium Voltage (MV) Electrical equipment (< 52 kV) and High Voltage (HV) Electrical Equipment (> 52 kV) containing SF_6. The division into the two groups was based on data from two large and one smaller facility for energy transmission and distribution. According to the data almost 98.4% of the electrical equipment in this country is attributed to HV Electrical Equipment and 1.6% to MV Electrical equipment.

Data about consumption of SF_6 in electrical equipment are obtained from ISPOP, the F-gas register and Database of Cross-border movements of goods (for more details see chapter 4.7.1). SF_6 for use in electrical equipment is mainly imported as part of the equipment, which is filled below operational amount. First servicing could be then considered as “first fill”. Bulk imports are mostly being transferred for the purpose of operational stock-in-trade.

4.8.1.2 Methodological issues

Emissions from this category are calculated in line with IPCC 2006 Gl., specifically Equation 8.1, which is called the Tier 1 method. Emissions for MV Electrical equipment and HV Electrical Equipment were estimated separately using default emission factors (Table 8.2, IPCC 2006 Gl., Volume 3 for MV Switchgear and Table 8.3, IPCC 2006 Gl., Volume 3 for HV Switchgear). The ETF Reporting Tool does not allow separation of the subcategory 2.G.1 Electrical equipment into two groups. Emissions of SF_6 from MV Electrical equipment and HV Electrical Equipment are reported collectively.

Operational leakage is not measured (legislation does not force operators to do so) but operators usually distinguish between amount of SF_6 used for servicing or filling to new equipment. According to consultations with the main operator in the country, the leakage is virtually non-existent and depends solely on accidents; leakage usually remains below 100 kg p.a. in total. Such a low amount of SF_6 does not even require the operator to report SF_6 usage in ISPOP.

SF_6 for use in electrical equipment is mainly imported as the part of the equipment which is filled below the operational amount. First servicing is then considered as “first fill”. Bulk imports are mostly imported for the purpose of operational stock-in-trade. In the year 2024, there is no new SF_6 filled into the new equipment thus zero emissions from manufacturing are occurring for the year 2024.

4.8.1.3 Uncertainties and time-series consistency

The uncertainty estimates were based on expert judgment (see IPCC 2006 Gl., Volume 1,Chapter 3 Uncertainties). Improvement of uncertainty estimation is in progress.

Time series consistency is ensured as the inventory approaches concerned are employed identically across the whole reporting period from the base year 1990 to 2024.

4.8.1.4 Source -specific QA/QC and verification

The input information and calculations are archived by the sectoral expert and the coordinator of NIS.

Verification of the activity data for subcategory 2.G.1 is performed by comparison of the data obtained from ISPOP, from the F-gas register and from Database of Cross-border movements of goods.

The quality control was held by fulfilling the QA/QC form presented in A 4.1.

4.8.1.5 Source -specific recalculations, including changes made in response to the review process and impact on emission trend

In this year, there was an activity data update of 2022 which resulted in minor emission changes.

4.8.1.6 Source -specific planned improvements, including tracking of those identified in the review process

In further submissions it is planned to contact other facilities for energy transmission and distribution to verify the current division of activity data into MV and HV electrical equipment or update this division to more accurate version.

4.8.2 SF_6 and PFCs from Other Product Use (CRT 2.G.2)

4.8.2.1 Source category description

This category includes emission estimates from double-glazed sound-proof window (2.G.2.c) and from accelerators use (2.G.2.b).

SF_6 was used for manufacturing sound-proof windows in the Czech Republic during 1996–2009. The use of SF_6 for sound-proof windows manufacturing reached a maximum during 2002–2004, with the highest consumption in 2003. Higher consumption of SF_6 during these years led to an increase in emissions from manufacturing. Then SF_6 started to be replaced by nitrogen and argon. The lifetime of windows filled with SF_6 is assumed to be 25 years, which means that emissions are occurring from stocks and since 2021 also from the disposal.

The survey of other uses of SF_6 was undertaken for submission 2018–2016. Category 2.G.2.b Accelerators has been added to the submission. In the Czech Republic, accelerators are used in radiotherapy centres and one accelerator containing SF_6 is used in a research institute (UJV Řež, Tandetron). Data about the total number of accelerators used for radiotherapy treatment is obtained from the Institute of Health Information and Statistics of the Czech Republic. In 2024, there were 56 accelerators in use.

The main shoe producers were contacted to obtain information about the amount of SF_6 used in the production of shoe soles. According the data, SF_6 is not used by shoe manufacturers in the Czech Republic.

4.8.2.2 Methodological issues

SF_6 emissions from soundproof windows

Emissions from this category (Sound-proof glazing) are calculated in line with IPCC 2006 Gl., specifically Equation 8.20 for the assembly, 8.21 for the use and 8.22 for the disposal (IPCC 2006). The calculation of disposal was corrected this year within the Capacity building in F-gasses field activity.

SF_6 emissions from accelerators

Total SF_6 emissions reported in 2.G.2.b Accelerators are calculated as the sum of emissions from medical accelerators and the Tandetron research accelerator. Data about the total number of accelerators used in radiotherapy treatment have been obtained from the Institute of Health Information and Statistics of the Czech Republic since 1990. Unfortunately, the data do not differentiate accelerators using SF_6. To avoid underestimation of emissions, we used a conservative estimate and assume that every medical accelerator uses SF_6. Emissions are calculated according to Tier 1 methodology, Equation 8.18 with default charge factor 0.5 kg and emission factor 2 kg/kg SF_6 (IPCC 2006).

Tandetron is a research particle accelerator. Detailed information about SF_6 was obtained directly from the research institute. According to the research institute, leakages of SF_6 were negligible during the 12 years of operation. During the year, SF_6 can leak into the atmosphere only during regular checks of the installation and this leak is estimated at 6.17 g SF_6 per year.

4.8.2.3 Uncertainties and time-series consistency

The uncertainty estimates were based on expert judgment (see IPCC 2006 Gl.,Volume 1,Chapter 3 Uncertainties). Improvement of uncertainty estimation is in progress.

Time series consistency is ensured as the inventory approaches concerned are employed identically across the whole reporting period from the base year 1990 to 2024.

4.8.2.4 Source-specific QA/QC and verification

The input information and calculations are archived by the sectoral expert and the coordinator of NIS. The quality control was held by fulfilling the QA/QC form presented in Annex 5.

4.8.2.5 Source-specific recalculations, including changes made in response to the review process

Thanks to the Capacity building in the F-gasses field activity the disposal of the emissions of the sound-proof windows has been corrected. This was an issue CZ-2G-2024-0001. The emissions of disposal are now reported from 2021 on.

4.8.2.6 Source-specific planned improvements, including those in response to the review process

The survey of other uses of SF_6 will continue. For future submissions, it is planned to investigate the use of SF_6 in accelerators in more detail. Unfortunately, due to the current state of data confidentiality in the military sector, it is assumed that data about the consumption of SF_6 in military applications will not be provided to the sectoral expert for emission estimates, but effort will be exerted in the survey.

4.8.3 N_2O from Product Uses (CRT 2.G.3)

4.8.3.1 Source category description

This category (2.G.3) includes N_2O emissions from the use of this substance in the food industry (aerosol cans) and in health care (anaesthesia).

4.8.3.2 Methodological issues

The calculation of emissions from this category, are based on IPCC 2006 Gl., Volume 3, Chapter 8, Equation 8.24 (IPCC 2006). These not very significant emissions corresponding to 0.75 kt N_2O were derived from production in the Czech Republic (0.6 kt N_2O) and from import of N_2O (0.15 kt N_2O), see (Markvart and Bernauer, 2010–2013 and Bernauer and Markvart 2014–2016).

So far, in the Czech Republic, no relevant data have been available to distinguish between N_2O used in anaesthesia and for aerosol cans. Therefore, the existing split (80% for anaesthesia) was based only on a rough estimate.

Data from Customs Office were obtained as an attempt to improve emission estimates from this category. Customs data contain detailed information about imported/exported amount of oxides of nitrogen to/from the Czech Republic by a single importer/exporter for a year 2016 and summary data about import/export for 1993–2016. Customs code is related to oxides of nitrogen not only N_2O. According to the data, oxides of nitrogen were imported to the Czech Republic by 26 importers (mainly by companies trading with industrial gases not by end consumer) and exported by 15 companies in 2016. Export of oxides of nitrogen is multiple times higher than import every year. Total stock of nitrogen oxides in 2016 for 1993–2016 time series is calculated to -20 kt of oxides of nitrogen. It was concluded that customs data are not suitable for emission estimates of N_2O in category 2.G.3. Firstly, customs data are related to import/export of oxides of nitrogen not only N_2O. Secondly, oxides of nitrogen are imported by companies trading with industrial gases. These companies sell their products to the end users, and thus, information about possible use is missing. And at the end, the amount of exported oxides of nitrogen is every year higher than the amount of imported oxides of nitrogen, and thus, total stock is calculated in negative values.

4.8.3.3 Uncertainties and time-series consistency

The uncertainty estimates were based on expert judgment (see IPCC 2006 Gl., Volume 1, Chapter 3 Uncertainties). Improvement of uncertainty estimation is in progress.

Uncertainties for activity data in this category at the level of 50% were estimated. No uncertainty was determined for the emission factor since we assumed that all the gas is emitted (the emission factor is equal 1 t/t N_2O). Overall uncertainty data are given in Chapter 1.7.

Time series consistency is ensured as the inventory approaches concerned are employed identically across the whole reporting period from the base year 1990 to 2024.

4.8.3.4 Source-specific QA/QC and verification

The input information and calculations are archived by the sectoral expert and the coordinator of NIS.

The quality control was held by fulfilling the QA/QC form presented in A 4.1.

4.8.3.5 Source-specific recalculations, including changes made in response to the review process

In this year, no recalculations were performed in this category.

4.8.3.6 Source-specific planned improvements, including those in response to the review process

No improvement is planned in this category.

4.8.4 Other (CRT 2.G.4)

4.8.4.1 Source category description

This category includes estimated emissions from the experimental use of SF_6 under laboratory conditions. The experiment started in 2004 and lasted two years, which means that emissions occurred only in 2004–2006.

4.8.4.2 Methodological issues

The amount of SF_6 used in the experiments is investigated every year in data obtained from ISPOP, the F-gas register and from the Customs Administration of the Czech Republic. In the data set, research institutes are selected and, if the data contains information about an imported amount of SF_6, the research institutes are contacted for more detailed information.

4.8.4.3 Uncertainties and time-series consistency

The uncertainty estimates were based on expert judgment (see IPCC 2006 Gl., Volume 1, Chapter 3 Uncertainties). Improvement of uncertainty estimation is in progress.

4.8.4.4 Source-specific QA/QC and verification

The input information and calculations are archived by the sectoral expert and the coordinator of NIS.

The quality control was held by fulfilling the QA/QC form presented in A 4.1.

4.8.4.5 Source-specific recalculations, including changes made in response to the review process

In this year, no recalculations were performed in this category.

4.8.4.6 Source-specific planned improvements, including those in response to the review process

No improvements are currently planned in this category in next submission.

4.9 Other (CRT 2.H)

This category describes GHG emissions from the subcategories 2.H.1 Pulp and paper production and 2.H.3 Other. Total GHG emissions from 2.H were 0.94 kt CO_2 eq. in 2024.

4.9.1 Pulp and paper (CRT 2.H.1)

In this category, CO_2 emissions from Paper and Pulp industry which do not fall into specific categories (e.g. use of soda ash and urea under category 2.A.4.d) are reported here. The activity data are taken from the EU ETS. One of the paper mills produces its own $CaCO_3$ with a high degree of purity. During this process, CO_2 is reabsorbed. This process was classified as category 2.A.4.d before but it was taken from the inventory after revision (for more information, see chapter 4.2.4.2).

Emissions reported in this category come from application of liquid CO_2. Liquid CO_2 is used for pH adjustment in the delignification process. There is only one company which uses the technology in the Czech Republic. After the process, used liquid CO_2 is sent to the cleaning zone and then to the combustion boiler afterward. The data comes from the EU ETS for the period 2010–2024. Values for years 2006–2010 were obtained directly from the company. Material flow data provided by the company was used to correlate the figures from 1996, when the technology was implemented, to 2006. Since only one manufacturer reports CO_2 emissions from kraft processes, IEF is reported as C (confidential). CO_2 emissions from 2.H.1 amounted to 0.94 kt in 2024.

4.9.2 Other (CRT 2.H.3)

Emissions of HFO-1234yf and HFO-1234ze, which are refrigerants primarily utilized in air conditioning systems, are classified as Other in category 2.H.3. since the ETF system does not allow creating nodes for alternative refrigerants under 2.F.1.e subcategory. HFO-1234yf and HFO-1234ze have recently been widely used due to their low global warming potential (GWP) as both gases' GWP are considered to be one (IPCC 2014).

HFO-1234yf and HFO-1234ze were implemented into calculation model Phoenix which calculates emissions from 2.F.1.a, 2.F.1.b, 2.F.1.c, 2.F.1.d and 2.F.1.f. For more details, please see chapter 4.7.1. Emissions of HFO-1234yf and HFO-1234ze estimated in Phoenix were 0.18 kt CO_2 eq in 2024.

The main field, where HFO-1234yf is used, are mobile air conditioning systems. A calculation process of these emissions estimates is the same as for HFC-134a in category 2.F.1.e. Estimated emissions of HFO-1234yf from mobile air conditioning were 0.173 kt CO_2 eq in 2024.

4.10 Acknowledgement

The authors would like to thank the Czech Ministry of Environment for providing the EU ETS data and data from the F-gas register and to CzSO for providing data about cross-border movements of goods and other statistics used for emission estimates.

The authors would like namely to thank to Mr. Beck and Mr. Bernauer for their contribution during the inventory preparation as consultants and for final QC/QA checks and to Mr. Řeháček and Ms. Ondrušová for their huge contribution to development of F-gases emission estimates in previous years.

The authors would also like to thank representatives of companies that willingly respond to our surveys and therefore help to bring to life these emission estimates.

5 Agriculture (CRT Sector 3)

5.1 Overview of sector

Agricultural land covers 45% and arable land 32% of the area of the country (CzSO 2024). Czech agriculture is affected by the communist history of the country, when small farmers were almost eliminated by the collectivization process after World War II. Unfortunately, the period with cooperative ownership without any small family farms lasted far too long and only very few original farmers started managing their farms again in the 1990s. At present, 74% of farms are smaller than 50 ha and occupy only 7.5% of agricultural land.

The Czech Republic is situated in the cool climate zone (the long term annual average temperature is 8.3 °C for the period 1991–2020, www.chmi.cz). The level of livestock breeding, manure management and agricultural land management is comparable to that in the developed Western European countries.

Temperatures in 2024 were markedly above normal across the entire territory of the Czech Republic compared to the long-term annual average for 1991–2000, with an average annual temperature of 10.3 °C. This value exceeds the long-term average (1991–2020) by 2 °C. Although 2024 was thermally extreme and the warmest year since 1961, it did not rank among dry years from the perspective of the water balance. This was not only due to higher precipitation (annual average total of 776 mm, representing 113% of the 1991–2020 normal), but above all to its distribution. Precipitation in 2024 improved soil moisture and particularly benefited spring crops, forage crops and stands in drier regions. Conversely, prolonged and extreme rainfall in summer and autumn caused lodging of cereals, the spread of diseases, deterioration in grain quality, and complications during harvest. Overall, yields were rather average; however, especially in cereals, both yields and production quality were often below average due to the unfavourable timing of precipitation.

The total harvested area of cereals in the 2024/2025 marketing year amounted to 1,307.6 thousand hectares, representing only a 0.7% decrease compared to the previous year. The largest shares of the total area were traditionally occupied by wheat (59.4%), barley (24.3%), and maize (6.7%). Cereal production harvested in the Czech Republic in the 2024/2025 marketing year was 5.9% lower than in the previous year, mainly due to unfavourably timed precipitation during the harvest period. Compared to the previous year, the cultivated area increased for durum wheat, oats, triticale, grain maize, and buckwheat. In contrast, a year-on-year decrease was recorded for both, spring and winter, wheat, rye, and both, spring and winter, barley. The most significant part of domestic cereal consumption is represented by their use in animal feed and food processing. Within technical uses, cereals are processed into bioethanol, ethanol, and, in some cases, used as an energy crop for biomass production.

The harvested area of oilseed crops decreased year on year by 6.8%. Traditionally oilseed rape had the largest share of oilseed harvested areas in the Czech Republic (78.3%), predominantly winter oilseed rape. Significantly smaller shares were represented by poppy seed (8.4%), soybean (6.5%), sunflower (3.7%), mustard (2.7%), and flax (0.2%).

A significant year-on-year increase in area was recorded for poppy seed (+39.5%) and spring oilseed rape (+33.8%), followed by soybean (+6.9%). Conversely, a year-on-year decrease in area occurred for flax (−32.3%), mustard (−25.6%), sunflower (−17.1%), and winter oilseed rape (−9.7%). Total production declined by 24.6% compared to the previous marketing year's harvest, mainly due to lower production of winter oilseed rape.

The area of sugar beet intended for sugar production increased by 6.8% in 2024/25 compared to the previous year, and sugar production increased by 9.1%, representing a record high over the past 60 years. After a decline in the previous period, the area for non-food uses of sugar increased again, with a year-on-year rise of 155.8%. The harvested area of potatoes increased year on year by 6.4%, and their production increased by 11.5%.

Compared to the previous year, the harvested area of hop gardens decreased by 0.3%, and hop production declined by 7.2%. Total fruit production, including strawberries, was 42% lower than the fruit harvest in 2023.

The results for 2024 indicate a year-on-year improvement in cattle numbers by 2% compared to 2023. Total cow numbers increased by 2.0%, of which the number of suckler cows increased by 4.2%, while the number of dairy cows increased only by 0.7%. Total swine numbers increased by 4.4% year on year; the number of sows increased by 1.7%, gilts by 7.9%, and piglets by 5.8%. Poultry numbers increased by 17.8%. The number of broiler chickens increased by 24.8%, breeding chickens by 35.1%, and laying hens by 8.1%. In contrast, the number of breeding hens decreased by 1.0% and roosters by 0.2%. Among other poultry, the number of ducks increased by 21.1% and geese by 4.2%, while the number of turkeys declined by 47.3%.

In 2024, mineral fertilizer consumption increased compared to 2023, returning to the average level of the years 2019–2022. This represented an increase to 110.2 kg of pure nutrients per hectare of agricultural land in 2024, corresponding to a year-on-year rise of 36%. The total input of pure nutrients from farmyard manure and organic fertilizers increased by 3.99% to 67.8 kg/ha. Total consumption of liming materials increased by 10.6% compared to 2023.

Under the Czech national conditions, agricultural greenhouse gas emissions consist mainly of emissions from enteric fermentation (CH_4 emissions), manure management (CH_4 and N_2O emissions), agricultural soils (N_2O emissions), urea application and liming (CO_2 emissions). The other IPCC subcategories – rice cultivation, prescribed burning of savannas, field burning of agricultural residues and “other” – do not occur in the Czech Republic.

Methane emissions are derived from animal breeding. These emissions originate primarily from enteric fermentation (digestive processes), which is mostly manifested for ungulate animals (mostly cattle in the Czech Republic). Another part of methane emissions is derived from manure management, where methane is formed under anaerobic conditions with simultaneous formation of ammonia, which, however, is not monitored in the framework of greenhouse gas inventories[1].

Nitrous oxide emissions are formed mainly by nitrification and denitrification processes in manure and soils. The anthropogenic contribution that is determined in the national inventory of greenhouse gases is caused by nitrogenous substances derived from inorganic fertilizers with nitrogen content, manure from animal breeding, sewage sludge application to soils, nitrogen contained in parts of agricultural crops that are returned to soils and nitrogen mineralized in soils. In addition, emissions are also being produced from storage facilities and management of manure as a fertilizer and indirect emissions are being derived from atmospheric deposition and nitrogenous substances leached into water courses and reservoirs.

[1] *The reporting of ammonia emissions is coordinated and managed by CHMI under the supervision of the Ministry of the Environment. For the national estimation of ammonia emissions from manure management, the Tier 2 approach is used according to the section 3.B Manure management EMEP/EEA in Emission Inventory Guidebook (EEA 2023). Ammonia emissions from synthetic fertilizers application are estimated according to the the Tier 2 approach described in the section 3.D Crop production and agricultural soils EMEP/EEA in Emission Inventory Guidebook (EEA 2023).*

Carbon dioxide emissions are derived from non-organic fertilization use on agricultural soils based on industrially produced urea and limestone and dolomite applied to soils.

The emission estimates in this submission are affected both by increased nitrogen consumption from synthetic fertilizers and by several technical corrections to the calculation. The most significant methodological change in the estimates was the implementation of the technical correction recommended by TERT within the 2025 Review (ID: CZ-3D-2025-001). Specifically, this involved applying the default Frac Leach value from the 2019 IPCC differently for the share of the territory considered in wet and dry climate zones.

All changes and their consequences for emission estimates are described in the relevant chapters of the NID. Overall, the implemented improvements and updates of the calculation resulted in an average 11% increase in emissions from the sector (Fig. 5-1) in comparison with previous Submission 2025. A detailed description of each category follows below.

All the above-mentioned changes and improvements were consulted and prepared with a team of experts (Dr. Klír, Dr. Wollnerová, Dr. Dedina) from the Czech Agrifood Research Center (CARC – formerly called CRI), which has been involved in the NIS team of the Czech Republic since 2019. Since 2025, Prof. Trnka from Global Change Research Institute CAS (GCRI, CzechGlobe) has also been a member of the team.

The CARC experts are responsible for the implementation of Council Directive 91/676/EEC of 12 December 1991 concerning the protection of waters against pollution caused by nitrates from agricultural sources and for EUROSTAT / OECD statistics of nutrient budgets from the agricultural sector. Since 2022, the cooperating CARC experts are members of the Discussion Group on Nutrients Statistics in the framework of Eurostat.

Prof. Trnka has been working at CzechGlobe since 2010 as the head of the "Impacts of climate change on agrosystems" team, and the head of the scientific section "Modeling and climate analysis". From 2023, he is the scientific coordinator of the research program "Advanced methods of reduction and sequestration of greenhouse gas emissions in agriculture and forest landscapes for climate change mitigation" aimed at scientific solutions for estimations of GHG emissions from agricultural land.

Dr. Martin Dědina (CARC) is resposible for preparation the reports on pollutant emissions from agriculture for CHMI. Thanks to this cooperation, a unified database of input data in the agricultural sector was prepared for nitrogen emission estimates and their budget (Beranova et al. 2022b).

The Czech Republic declines any responsibility of errors caused by the UNFCCC ETF reporting tool, the latest version 1.30.5 of the ETF tool from the 9th of December 2026 was used for creating the submission. CRT table cells, which do not affect the national total, may still have an empty cell instead of NA or NO and have Tier and method parameters missing in the automated summary sheets due to bugs in the ETF reporting tool even sector background table white cells have been sussesfully filled by the sector expert. For more information on completeness and the ETF bugs, please see Annex A 5.6.

5.1.1 Key categories

There are seven categories of sources evaluated by the analyses described in IPCC 2006 Guidelines as the key categories in the agricultural sector. The sources overview, including their contribution to the aggregate emissions, is given in Tab. 5-1 .

Tab. 5-1 Overview of significant source categories in agriculture (Submission 2026), assessed with and without considering LULUCF

Category	Gas	KC A1	KC A2	KC A1[1]	KC A1[2]	KC A2[1]	KC A2[2]	% of total GHG[1]	% of total GHG[2]
3.A Enteric Fermentation	CH_4	LA, TA	LA, TA	Yes	Yes	Yes	Yes	4.03	3.84
3.D.1 Direct N_2O Emissions From Managed Soils	N_2O	LA, TA	LA, TA	Yes	Yes	Yes	Yes	2.27	2.16
3.D.2 Indirect N_2O Emissions From Managed Soils	N_2O	LA, TA	LA, TA	Yes	Yes	Yes	Yes	0.63	0.60
3.B Manure Management	N_2O	LA	LA	Yes	Yes	Yes	Yes	0.43	0.41
3.B Manure Management	CH_4	TA	LA, TA	Yes	Yes		Yes	0.40	0.39
3.H Urea application	CO_2		LA			Yes	Yes	0.21	0.20
3.G Liming	CO_2	TA	TA	Yes	Yes	Yes	Yes	0.14	0.14

KC: key category
[1] including LULUCF
[2] excluding LULUCF

5.1.2 Quantitative overview

Agriculture is the third largest emissions producing sector in the Czech Republic. In 2024, its contribution represented 8% to the total GHG emissions excl. LULUCF and excl. indirect emissions. This equalled to 7 447 kt CO_2 eq.; 50% of sectoral emissions came from enteric fermentation, 36% from managed agricultural soils, and 10% from manure management. Carbon dioxide emissions from liming and urea application on managed soils contributed by 4% to the total agricultural emissions in 2024. The share of emission categories in the total emissions was relatively stable to year 2000 and changed gradually since 2001, when the anaerobic digesters were incorporated into estimating nitrous emissions. While the share of emissions from enteric fermentation is relatively stable, the share of emissions from manure management and from managed soils slowly decrease. The total emissions from agriculture decreased by about 43% during the period 1990–2024. A quantitative overview and emission trends in the reported period are provided in Tab. 5-2.

Tab. 5-2 Emissions from agriculture, sorted by source categories, 1990–2024

Year	TOTAL	Enteric Fermentation (3.A)	Manure Management (3.B)	Agricultural Soils (3.D)	Liming (3.G)	Urea Application (3.H)
			[kt CO_2 eq.]			
1990	13 014	6 523	2 515	2 630	1 237	109
1991	11 704	6 254	2 398	2 592	329	132
1992	9 689	5 596	2 232	1 639	114	109
1993	9 048	4 851	2 052	1 944	108	93
1994	7 980	4 249	1 805	1 727	109	91
1995	8 867	4 231	1 725	2 686	116	109
1996	8 558	4 144	1 721	2 476	118	100
1997	7 858	3 874	1 665	2 156	97	67
1998	7 414	3 614	1 606	1 956	95	143
1999	7 195	3 713	1 625	1 677	91	88
2000	7 444	3 565	1 542	2 102	118	116
2001	8 699	3 565	1 504	3 363	110	157
2002	8 124	3 463	1 437	2 988	104	132
2003	6 118	3 358	1 392	1 165	82	120
2004	7 196	3 230	1 304	2 432	80	151
2005	7 353	3 335	1 285	2 520	67	146

Year	TOTAL	Enteric Fermentation (3.A)	Manure Management (3.B)	Agricultural Soils (3.D)	Liming (3.G)	Urea Application (3.H)
			[kt CO_2 eq.]			
2006	7 246	3 288	1 239	2 481	82	156
2007	7 387	3 323	1 215	2 568	84	197
2008	6 900	3 355	1 162	2 104	100	179
2009	6 880	3 274	1 016	2 376	67	148
2010	7 573	3 256	916	3 175	65	161
2011	6 622	3 265	804	2 263	84	207
2012	6 871	3 239	756	2 549	121	206
2013	7 631	3 292	716	3 283	142	198
2014	7 051	3 371	716	2 675	158	130
2015	6 332	3 424	718	1 751	171	268
2016	7 238	3 368	735	2 670	175	290
2017	7 244	3 452	745	2 656	166	225
2018	6 205	3 529	781	1 546	163	185
2019	6 570	3 542	758	1 928	193	149
2020	7 197	3 520	757	2 599	165	156
2021	7 340	3 565	774	2 680	146	176
2022	6 776	3 658	743	2 029	154	192
2023	6 692	3 614	733	2 075	121	148
2024	7 447	3 698	762	2 664	132	191



Fig. 5-1 Trend of emissions from agricultural sector [kt CO_2 eq.], 1990–2024

The sum of emissions from agriculture in the Czech Republic culminated in 1990 (100%) and the lowest emissions were estimated in 2003 (47% of the total emissions in 1990, a decrease by 53%). The reason for the relatively largest decrease after 1990 was a decrease in the livestock population. Thereafter, the total emissions were relatively stable from 1997 to 2024, fluctuating by 1-42%, 17% on average, with the lowest values in 2003 and maximum in 2001. In 2015 and 2016 the consumption of urea became highest in the reporting period. This negative environmental trend ended in 2017 when the urea consumption decreased. The emissions categories expressed in their relative shares compared to 1990 are shown in Tab. 5-3.

Tab. 5-3 Emission categories expressed in relative shares compared to 1990 (year 1990 is stated as 100%)

Year	TOTAL	Enteric Fermentation (3.A)	Manure Management (3.B)	Agricultural Soils (3.D)	Liming (3.G)	Urea Application (3.H)
			Relative share [%]			
1990	100	100	100	100	100	100
1995	68	65	69	102	9	101
2000	57	55	61	80	10	107
2005	57	51	51	96	5	135
2010	58	50	36	121	5	148
2015	49	52	29	67	14	247
2016	56	52	29	102	14	267
2017	56	53	30	101	13	207
2018	48	54	31	59	13	171
2019	50	54	30	73	16	137
2020	55	54	30	99	13	144
2021	56	55	31	102	12	162
2022	52	56	30	77	12	177
2023	51	55	29	79	10	136
2024	57	57	30	101	11	176

An overview of the latest recalculations is given in Chapter 10. The methodology used is in accordance with the IPCC 2006 Guidelines with respect to some provisions of the IPCC 2019 Guidelines in Enteric fermentation (3.A) category and Agricultural soils category (3.D).

The total emissions estimated for 2024 (current Submission 2026) are by about 11% higher than estimated for 2023. The share of the main categories in the total GHG emissions from the sector remained without significant changes excluding updated category 3.D. The rationale for the increase of the total emissions in recent years is described in the following paragraphs.

5.1.3 General overview of source specific QA/QC and verification

Following the recommendation in the latest in-country review, a sector-specific QA/QC plan was revised, tightly linked to the corresponding QA/QC plan of the National Inventory System, chapter 1.5. The plan describes the key procedures of inventory compilation and provides a table of personal responsibilities and a timetable of sector-specific QA/QC procedures. This plan consolidates the quality assurance procedures and facilitates effective quality control of the inventory in the sector Agriculture. IFER - Institute of Forest Ecosystem Research is the technically responsible institution for preparing emission estimates and reporting for this sector. Since 2019 the experts (Dr. Klír, Dr. Wollnerová) representing the CARC have joined the inventory team and since 2024 prof. Trnka and his colleagues from CzechGlobe have joined the inventory team. All these experts have been also involved in the QA/QC procedures.

Czech Agrifood Research Center, Ministry of Agriculture of the Czech Republic, Czech University of Life Sciences, Institute of Animal Science Prague, Research Institute for Cattle Breeding, Institute of Agricultural Economics and Czech Hydrometeorological Institute are the additional collaborating institutions contributing with relevant information used in inventory of the sector Agriculture. Finally, the NID experts from Slovakia responsible for the agricultural sector (Slovak Hydrometeorological Institute, SHMI) also cooperate closely in the inventory methods and potential improvements.

The identified errors and inconsistencies were documented, and corrections were made where needed. In addition to the official review process, the emission inventory methods were reviewed internally by the

technical experts involved in the emission inventory of the Agriculture and LULUCF sectors. To comply with QA/QC, it is necessary to check e.g., the comparison of the country-specific and the default values:

- The activity data for livestock categories, annual crop production, the number of synthetic fertilizers, sewage sludge, liming and urea applied to managed soils (Czech official statistics, urea production data)
- The consistency of the time-series activity data and emission factors
- The update of the national zoo-technical data
- All the emission factors and parameters/fractions employed.

QA/QC includes checking the activity data, emission factors and methods employed. Additionally, communication and exchange of information on activity data, emissions factors, and methods with the respective Czech experts responsible for other reporting (Convention on Long-Range Transboundary Air Pollution, in-country reporting of the Ministry of Agriculture, etc.) help retain consistency of emission reporting with other relevant reporting protocols.

The inventory compiling procedure is initiated by IFER, where all the necessary data, obtained from the Czech Statistical Office (CzSO), are inserted into the excel spreadsheets and verified by other IFER experts. There are some more specific parameters, which are not available from CzSO, required to estimate the country-specific emission factors for cattle (Tier 2). The zoo-technical national data (esp. cattle breeding) is supplied by the experts from the agricultural institutes (see above). The climatic data is supplied from CzechGlobe. The appropriate values in the calculation spreadsheets are updated at IFER, replacing the older values. The verified data are transferred to ETF Reporting Tool, where the data are technically verified once again. The completeness check of the CRT tables is performed for the final time-series approval.

The responsible person (IFER expert) fills in the QA/QC forms, including information from checking and verifying activity data, ETF data and NID content separately for the reported emission inventory categories. The QA/QC forms are archived in IFER and CHMI (ftp server). All the information used for the inventory document is archived by the author and by the NIS coordinator. Hence, all the background data and calculations are verifiable.

In 2021, Dr. Jana Beranová, responsible for the sector Agriculture, was nominated as a member of the new expert group under the European Commission on methane emissions from agriculture. This group carries consultations on the livestock sector, feed and feed additives.

More precise information about QA/QC procedures is available in relevant subchapters.

5.2 Livestock (CRT 3.1)

The methods for estimating CH_4 and N_2O emissions from enteric fermentation and manure management for livestock require definitions of livestock sub-categories and their annual population data (see Tab. 5-4) and, for the higher Tier 2 methods used for cattle, also a feed intake and other zoo-technical characteristics. The coordinated livestock characterization was used to ensure consistency across the source categories for the whole emission inventory. Statistical Yearbook of the Czech Republic was the source of population data for livestock categories. All the numbers were confirmed by the Ministry of Agriculture.

Tab. 5-4 Trends in livestock populations [1 000 heads], 1990–2024 (CzSO 2025)

	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
Cattle	3 404	1 983	1 539	1 362	1 319	1 366	1 340	1 359	1 390	1 370	1 397
Swine	4 638	3 744	3 571	2 786	1 846	1 555	1 546	1 493	1 329	1 362	1 422
Sheep	430	165	84	140	197	232	204	183	174	174	180
Poultry	31 693	26 448	30 507	25 144	24 073	21 304	22 992	25 788	23 764	21 957	25 875
Horses	27	18	24	21	30	34	39	33	37	37	37
Goats	41	45	32	13	22	27	29	25	25	25	25

Livestock population trends in key categories (cattle, pig and poultry) determine the emission trends in agricultural sector. The population of cattle in 2024 represented only 41% of the population in 1990 and the swine population in 2024 corresponded to only 31% of the initial population in 1990.

For Submission 2026, only data as of December 31 of each year are available for cattle, pigs, and poultry. The data for other animal categories (goats, sheep, horses) are expected to be available every three years. Therefore, for the current submission, the same data as in 2022 and 2023 (Submission 2024, Submission 2025) were used for other animal categories.

Changes in national statistics starting in 2024 are a result of implementation the new regulation on statistics on agricultural inputs and products (SAIO)**.** This regulation is a part of the modernization of the European system of agricultural statistics and, by improving and strengthening statistics on agricultural inputs and products in agriculture, should help to improve knowledge of agricultural practices and production in connection with the Common Agricultural Policy (CAP), the Green Pact for Europe and the "farm to fork" strategy.

5.2.1 Enteric Fermentation (CRT 3.A)

5.2.1.1 Source category description

This chapter describes the estimation of CH_4 emissions from enteric fermentation. In 2024, 91% of agricultural CH_4 emissions, 132.1 kt of CH_4, arose from this source category. This category includes emissions from cattle (dairy and non-dairy), swine, sheep, horses, and goats. Camels, llamas, mules, asses, and buffaloes in the Czech Republic are kept only in several private farms and ZOOs, but the populations of this non-native livestock are very low (hundreds of heads). Their breeding is not very intensive and therefore methane emissions for the non-native livestock were not estimated. Enteric fermentation emissions from poultry were not estimated as the IPCC 2006 Guidelines does not provide any default emission factor for this animal category. The contribution of emissions from livestock other than cattle to the total emissions from enteric fermentation was less than 3.3% (4.37 kt CH_4) of the total CH_4 emissions from the enteric fermentation category.

5.2.1.2 Methodological issues

Emissions from enteric fermentation of domestic livestock were calculated using the Tier 2 (cattle category) and Tier 1 (other livestock) methodologies presented in the IPCC 2006 Guidelines and the last Refinement of IPCC Guidelines from 2019 (IPCC 2019).

5.2.1.2.1 Enteric Fermentation of cattle (Tier 2)

The emission factor for methane from enteric fermentation (EF) in kg/head p.a. is proportional to the daily feed intake and the conversion factor. It thus holds that:

$$EF_i = GE \cdot \frac{365}{55.65} \cdot Y$$

where the gross energy intake (GE) in MJ/head/day, is taken as the main feed ration for the given type of cattle (there are 10 subcategories of cattle) and Y is the methane conversion factor presented for cattle in Table 10.12 (IPCC 2006, updated version in IPCC 2019). Methane conversion factor of zero is assumed for all juveniles consuming milk only (calves' categories, first three months of life) – p. 10.48 IPCC 2019. The coefficient of 55.65 is the energy content of methane with unit of MJ/kg CH_4. This equation should be solved for each cattle subcategory, denoted by index i.

EF is estimated for each cattle category and reported for dairy and non-dairy cattle. The value reported for non-dairy (other) cattle is the weighted average of the results calculated in each non-dairy category separately, including calves. Total emissions are the sum of the two products ($EF_{DairyCattle}$*population of dairy cattle + $EF_{NonDairyCattle}$ *population of non-dairy cattle).

There are 10 cattle subcategories in use which the data are available for in Czech Statistical Yearbooks (CzSO 1990–2025):

- Calves younger than 6 months of age, male
- Calves younger than 6 months of age, female
- Young bulls (6-12 months of age)
- Young heifers (6-12 months of age)
- Bulls and bullocks (1-2 years)
- Bulls and bullocks (over 2 years)
- Heifers (1-2 years)
- Heifers (over 2 years)
- Mature dairy cows
- Mature suckler cows

In the calculation, it is also very important to distinguish between dairy and suckler cows, where the fraction of suckler cows (ratio of suckler/all cows) gradually increased in the 1990–2024 period. The population of suckler cows increased from 2% up to 62% of the dairy cattle population during the reporting period because of changes in agricultural policy after 1990.

Considering that this is a key source of emissions, the Czech Republic uses Tier 2 methods to estimate methane emission factors for cattle. The calculation procedure was prepared in 2004 as a part of the VaV/740/4/02 project funded by the Ministry of the Environment (Kolář et al. 2004). The activity data was then updated repeatedly, most recently in 2016, when the shares of manure management systems were adjusted. IPCC methodology allows, if the daily food intake for each subcategory of cattle is not known directly, to calculate gross energy intake (GE) from national zoo-technical inputs: weight, weight gain (for growing animals), mature weight, daily milk production including the percentage of fat in milk, pregnancy (% of females that give birth in the year), feeding digestibility (% of energy in the feed not extracted) and the feeding situation (stall, pasture).

The original national zoo-technical inputs (noted above) were updated several times during reporting periods by the experts from the Czech University of Life Sciences Prague in 2006 and 2011 and were discussed with the experts from the Mendel University Brno (prof. Zeman 2021) and from Institute of Animal Science in 2022 (Dr. Joch).

For Submission 2023 and following, the methodological update of enteric fermentation estimation of methane emissions was implemented, including changes in activity data entering the calculations. Update and validation were required in review process (Issue A3). Refined country-specific data used in estimates

were the aim of this update, so were the validation and use of methane emission factor calculation based on the data on feeding situation derived from the nutritional standards. Newly we have estimated feed intake using a simplified Tier 2 method according to the procedures updated in IPCC 2019 Guidelines to validate the calculated GE.

The estimation of enteric fermentation was subjected to a rigorous control and validation of activity data entering the estimation of gross energy (GE) intake (digestibility, weight gain, activity coefficient, etc.). The estimation of GE was subsequently compared to the estimation of dry matter intake (DMI) using simplified Tier 2 method (IPCC 2019) and the practice of deriving DMI from the assumed feed rations. In connection with the revision of digestibility data, the Methane Conversion Factor Y_m value was also revised for all subcategories of cattle. The entire procedure is described in detail as an official output (Beranova et al. 2022a) of the aforementioned project and was submitted to a review to prof. Zeman, Mendel University Brno, Czech Republic. The calculation spreadsheet has been accordingly corrected and updated.

Specifically, the following adjustments were implemented:

- Country-specific approach to the activity coefficient (C_a), 1990–2024
- AWMS refinement, technical correction and input data unification, 1990–2024
- Increased pregnancy coefficient ($C_{pregnancy}$) for mature heifers, 1990–2024
- Increased value of milk production for suckler cows, 1990–2024
- Body weight increment refinements in the selected categories, 1990–2024
- The digestibility of feed (DE) value refinements, validation reflecting the dry matter intake (DMI) standards 1990–2024, DMI estimates based on the productivity, 2020–2024
- Revised methane conversion factor (Y_m) values for dairy cows from 2014 (6.4%) to the target value of 6.15% (2018) and adjustments for the methane conversion factor (Y_m) values for non-dairy cattle from 2014.

5.2.1.2.2 Activity data overview

The body weight data in relevant cattle categories is derived from the Czech legislation (Decree 377/2013 Coll.) and it is fully harmonized with nitrogen balance reporting and air pollution reporting (Tab. 5-5), no changes in Submission 2026.

Tab. 5-5 Weight of an individual in cattle categories [kg], 1990–2024

Cattle categories	1990–1994	1995–1998	1999–2004	2005–2009	2010–2015	2016	2017	2018–2024
Dairy cattle	520	540	580	585	590	620	620	650
Suckler cows	520	540	580	585	590	620	620	650
Mature heifers >2 yrs.	485	490	505	510	515	541	541	600
Mature bulls >2 yrs.	750	780	820	840	850	850	850	800
Heifers 1-2 yrs.	380	385	395	395	390	410	410	470
Bulls 1-2 yrs.	490	510	530	540	560	560	560	560
Heifers 6-12 m.*	275	280	285	285	290	299	265*	265
Bulls 6-12 m.*	325	330	335	340	350	368	300*	300
Calves <6 m., F*	128	132	133	135	135	139	115*	115
Calves <6 m., M*	128	132	133	135	135	149	115*	115

** Before 2017, the Czech Statistical Office used age categories different from the national legislation (0-8 months, 8-12 months for young categories) and the relevant body weight of calves, young bulls and heifers were used in the estimates. Since 2017 the input data has been adapted to the Czech legislation (0-6 months, 6-12 months). The time series is consistent – data on weight are relevant to the number of heads in the category.*

The feeding situation is the most important input to the estimation of net energy for activity NE_a (Eq. 10.4, IPCC 2006). One of the components of animal´s energy intake is the energy needed for animals to obtain their food, water and shelter (NE_a, eq. 10.4, IPCC 2019). To calculate this energy, the activity coefficients

are used to multiply the energy for maintenance (NE_m, eq. 10.3, IPCC 2019). The default values of the activity coefficients C_a are listed in IPCC 2019, Table 10.5.

Based on the expert recommendation, the country-specific technology coefficient (Ki) is used for estimating energy requirements (Zeman, 2006). The following table (Tab. 5-6) shows the differences between the activity and technology coefficient values.

Tab. 5-6 Activity coefficient (adjusted in compliance with IPCC 2019 Gl.) and the corresponding values for the production system (Zeman, 2006)

Feeding situation	Description	C_a Activity coefficient [%/100]	Production system	Ki Technology coefficient
Stall	Animals are confined to a small area and expend very little or no energy to acquire feed	0	Binding	0 No increased energy demands
Pasture	Animals are confined in areas with sufficient forage requiring modest energy expense to acquire feed	0.17	Free housing	0.1 Energy demands higher by 10%
Pasture-grazing large areas/Range	Animals graze in open range land and expend significant energy to acquire feed	0.36	Pasture/Range	0.2-0.3 Energy demands higher by 20-30%

The technology coefficient (Ki) allows an improved coverage of changes in cattle breeding, which occurred in cattle breeding in the Czech Republic after 1990. For the individual time series, it makes possible to consider the development of cattle breeding technologies in the period 1990–2024 and cover the gradual transition from binding housing, which prevailed from 70's, to free housing, which, in compliance with a valid legislation, dominates nowadays. Accordingly, the entire time series was recalculated including the above-described development. The original feeding situation was represented as a percentage of time, which cattle spent on a surrounding pasture and moderate energy was spent in acquiring feed. For the rest of the time, it was assumed that cattle spent in stall with a limited possibility to move (Tab. 5-6). Accordingly, the activity coefficient was calculated as the weighted average C_a of the time share in stall and pasture, e.g., in case of 5% of year spent on pasture the activity coefficient value was 0.0085, hence the energy for maintenance value increased by this coefficient.

The following table (Tab. 5-7) shows the activity coefficients updated with the country-specific data. It is obvious that the refinement leads to increasing value of the activity coefficient with an increasing proportion of free housing and pasture.

Tab. 5-7 The update of activity coefficient estimation by using the breeding coefficient; dairy cattle, suckler cows and non-dairy cattle as a summarized category

Dairy cattle: technology proportion	1990–1994	1995–2004	2005–2009	2010–2015	2016–2024
Binding housing, %	85	45	19	0	0
Free housing, %	10	45	70-72	93-98	100
Pasture/range, %	5	10	9-11	2-7	0
C_a, Activity coefficient value	0.020	0.065	0.090-0.092	0.102-0.107	0.100
Suckler cows: technology proportion	**1990–1994**	**1995–2004**	**2005–2009**	**2010–2015**	**2016–2024**
Binding housing, %	60	25	0	0	0
Free housing, %	10	40-45	65	50	50
Pasture/range, %	30	30-35	35	50	50
Ca, Activity coefficient value	0.070	0.105-0.110	0.135	0.150	0.150
Non-dairy cattle (weighted average)	**1990–1994**	**1995–2004**	**2005–2009**	**2010–2015**	**2016–2024**
C_a, Activity coefficient value	0.034-0.035	0.080-0.081	0.116	0.125	0.125-0.129

The daily milk production statistics (Tab. 5-8), in which only milk from dairy cows is considered, increased to 26.96 kg/day/head in 2024 in comparison with data from 2023 (26.34 kg/day), with an average fat

content of 3.83%. The activity data of milk production comes from the official statistics (CzSO) and these are verified in the Yearbook of Cattle Breeding in the Czech Republic (annual report).

Based on information provided by Institute of Animal Science (Beranova 2022a) the milk production of suckler cows increased, namely to 8 kg/day (2 920 kg/yr). Milk production is related to rearing calves. The original value used earlier was from 3.7 kg of milk/day.

Tab. 5-8 Daily milk production of dairy cows and fat content in milk, 1990–2024

Year	Dairy cattle population [1 000 heads]	Daily milk production [kg/day/head]	Fat content [%]
1990	1 198	10.97	4.03
1995	727	11.66	4.02
2000	544	13.93	4.00
2005	430	17.61	3.90
2010	375	19.44	3.86
2015	369	22.53	3.84
2016	367	22.64	3.91
2017	365	23.16	3.89
2018	359	24.01	3.86
2019	361	23.86	3.98
2020	357	25.04	3.89
2021	362	25.11	3.88
2022	357	25.59	3.89
2023	358	26.34	3.84
2024	360	26.96	3.83

Based on the information provided by Institute of Animal Science (Beranova et al. 2022a), **the share of mature embedded heifers** in the calculation increased to 80%. Earlier, this share was not considered.

Weight gain, based on the expert estimate (Beranova et al. 2022a), was adjusted for the entire time period 1990–2024 in category of mature heifers and mature bulls. Earlier, the weight gain in these categories was not considered in the estimation. Based on the expert information, the weight gain was set to 0.12 kg/day up to 0.60 kg/day. Furthermore, the weight gain for growing bulls and calves increased for the period 2010–2024. Development of weight gain in the country is shown in Tab. 5-9.

Tab. 5-9 Weight gain development overview [kg per livestock categories]; dairy and suckler cow weight gains are assumed to be zero and are not listed in the table, 1990–2024 (source: Kolář et al. 2004, Zeman et al. 2021, Beranova et al. 2022a).

Cattle category	1990–1994	1995–1998	1999–2009	2010–2024
	Weight gain [kg/day]			
Dairy cattle	0	0	0	0
Suckler cows	0	0	0	0
Mature heifers >2 yrs.	0.12	0.20	0.30	0.40
Mature bulls >2 yrs.	0.12	0.20	0.40	0.60
Heifers 1-2 yrs.	0.69	0.74	0.80	0.80
Bulls 1-2 yrs.	0.74	0.76	0.84	1.20
Heifers 6-12 m.	0.55	0.63	0.70	0.70
Bulls 6-12 m.	0.82	0.94	1.12	1.20
Calves <6 m., F	0.50	0.56	0.63	1.00
Calves <6 m., M	0.65	0.68	0.72	1.00

The digestibility of feed is one of the essential inputs into the enteric fermentation calculation. In the original CHMI study „Recalculating cattle enteric fermentation methane emission series“ (Kolář et al. 2004), the digestibility of feed value was estimated as 60% for all cattle categories in the period 1990–2002.

In 2010, the entire time series of emission factors calculation had been recalculated with the digestibility values of dairy cows of 67%, suckler cows 62% and other categories 65%. This value, with a missing country-specific data, had been understood as a conservative estimate of the real digestibility of feed, which, according to a literature data, had ranged between 68-70% for dairy cows (CHMI 2022).

To improve accuracy of the digestibility estimates, which, especially in case of dairy cows, did not correspond with the above-average milk production requiring appropriate feed, there was a study prepared by Zeman et al. (2021) which estimated the digestibility from the composition of a representative set of feeding rations. Feeding ratios were designed to reflect the real conditions of the feeding base in the Czech Republic and various levels of milk production and dairy cow maintenance (Zeman et al. 2021).

Tab. 5-10 shows the resulting digestibility (DE) values for time series. For dairy cows, there were two DE values validated (2010 and 2021), based on which the values for the period 1996–2010 were extrapolated. This follows the fact that the increment in DE is a continuous phenomenon.

Tab. 5-10 Digestibility (DE) of dairy and non-dairy cattle: values development in NID (former NIR) of the Czech Republic, 1991–2024 (CHMI 2025, Beranova et al. 2022a)

Time series	DE, Dairy cows [%]	DE, Non-dairy cattle, weighted average [%]	Source
1991–1995	67.0	64.9-65.0	CHMI 2024
1996–2000	68.0	64.8-64.9	Extrapolated values
2001–2005	69.0	64.7-64.8	Extrapolated values
2006–2009	69.5	64.5-64.6	Extrapolated values
2010–2024	70.0	65.1-65.6	Validation on the basis of DMI

In case of non-dairy cattle, the calculation counts with DE values given for individual categories. Until 2010, DE of 62% applied for suckler cows and 65% for other categories, thus the weighted average of all categories was slightly below 65%, according to the suckler cow representation in the population. Since 2011, the digestibility values reflect the breeding technology and fluctuate from 60% for mature heifers to 71% for growing bulls (1-2 years). The digestibility in other cattle categories is, on average, above 65%.

For the emission factor calculation according to eq. 10.21 of IPCC 2006 Guidelines, the methane conversion factor (Y_m) value is fundamental. As a part of the recalculation update, with a support of the refined IPCC 2019 Gl., Y_m values applicable for the country were updated too (Tab. 5-11). This was based on a better specification of Y_m, derived from feeding ratio quality, digestibility and neutral detergent fibre content as published in IPCC 2019 Gl., Table 10.12. The updated Y_m is shown in Tab. 5-11. Y_m values for calves reflect the fact that milk-fed calves do not produce any methane emissions. 3.3 is the value of the weighted average of Y_m reflecting the circumstance of calves being milk-fed up the age of 3 months.

As for the dairy cows, Y_m factor was adjusted according to the expected feed quality. Factor value of 6.15 is the weighted average of values given for high and medium producing dairy cows with average digestibility of feed 70% and neutral detergent fibre content above 35%. Similarly, Y_m applied for mature bulls represented a weighted average considering the bull share consuming feed of lower digestibility (grazing livestock) and higher digestibility (breeding purposes).

Tab. 5-11 Development of methane conversion factor (Y_m) values in 1990–2024 (Beranova et al. 2024)

Cattle category	1990–2010	2014	2015–2017	2018–2024
	Ym, Methane conversion factor [%]			
Dairy cattle	6.5	6.4	6.3	6.15
Suckler cows	6.5	6.5	6.5	6.5
Mature heifers >2 yrs.	6.5	6.5	7.0	7.0
Mature bulls >2 yrs.	6.5	6.5	6.75	6.75
Heifers 1-2 yrs.	6.5	6.5	6.3	6.3
Bulls 1-2 yrs.	6.5	6.5	6.3	6.3
Heifers 6-12 m.	6.5	6.5	6.3	6.3

Cattle category	1990–2010	2014	2015–2017	2018–2024
	Ym, Methane conversion factor [%]			
Bulls 6-12 m.	6.5	6.5	6.3	6.3
Calves <6 m., F	3.25	3.25	3.25	3.3
Calves <6 m., M	3.25	3.25	3.25	3.3

As the official statistics, specifically from CzSO, provide population values for dairy cows and other cattle, the resulting EFs in the ETF tables are defined for the categories of "Dairy cows" and "Non-dairy cattle".

The weighted average of non-dairy cattle feeding situation and pregnancy, in %, were calculated and entered in the ETF tables. The weighted feeding situation is mostly affected by time spent on pasture of suckler cows (50%), as well as by the case of pregnancy (90% of suckler cows are pregnant, 80% of mature heifers, zero of other cattle categories). An overview of the current input data (NID 2024) is presented in Tab. 5-12, and the calculated data are presented in Tab. 5-13.

The sources of input data are as follows:

- CzSO = Statistical Yearbook of the Czech Republic, the Czech Statistical Office
- CS = Country-specific, publicly available data (the Czech legislation, Cattle breeding Yearbook, etc.)
- IPCC 2006 Guidelines, default values, Table 10.4-10.7, 10.12

Tab. 5-12 Activity data and input data used for estimating gross energy intake (GE) and emission factors for all age categories of cattle, actual data for 2024

	Dairy	Suckler	Mature Heifers	Mature Bulls	Heifers 1-2 yrs	Bulls 1-2 yrs	Heifers 6-12 m	Bulls 6-12 m	Calves,F <0.6 m	Calves,M <0.6 m
Population [1 000 heads], CzSO	360	220	69	19	217	92	138	84	119	79
Body weight [kg], CS	650	650	600	800	470	560	265	300	115	115
Mature weight [kg], CS	624	624	624	768	624	768	624	768	624	768
Avg. weight gain [kg/head/day], calc.	0.00	0.00	0.40	0.60	0.80	1.20	0.70	1.20	1.00	1.00
Avg. daily milk production [kg/head/day], CS	26.96	8.00	-	-	-	-	-	-	-	-
Milk fat content [%], CS	3.43	3.43	-	-	-	-	-	-	-	-
Feed digestibility [%], CS	70	64	60	60	66	71	66	66	66	66
Emitting [% of year], CS	100	100	100	100	100	100	100	100	100	100
Number of days with pasture, CS	0	183	183	55	110	73	128	62	18	18
Pregnancy [% of year], CS	90	90	80	-	-	-	-	-	-	-
Protein content in milk [%], CS	3.43	3.43	-	-	-	-	-	-	-	-
Cf_i, net energy for maintenance, T. 10.4	0.386	0.386	0.322	0.370	0.322	0.370	0.322	0.370	0.322	0.370
C_a, activity coef., CS	0.100	0.150	0.150	0.115	0.130	0.120	0.135	0.117	0.105	0.105
$C_{pregnancy}$, net energy for pregnancy, T. 10.7	0.10	0.10	0.10	-	-	-	-	-	-	-
Y_m, methane conv. factor, T. 10.12	0.062	0.065	0.070	0.068	0.063	0.063	0.063	0.063	0.033	0.033
C, net energy for growth, Eq. 10.6	0.8	0.8	0.8	1.2	0.8	1.2	0.8	1.2	1	1

Tab. 5-13 Calculated values used for estimating methane emissions from enteric fermentation for all age categories of cattle, actual data for 2024

	Dairy	Suckler	Mature Heifers	Mature Bulls	Heifers 1-2 yrs	Bulls 1-2 yrs	Heifers 6-12 m	Bulls 6-12 m	Calves,F <0.6 m	Calves,M <0.6 m
NE_m, net energy for maintenance [MJ/head/day]	49.69	49.69	39.04	55.66	32.50	42.59	21.15	26.67	11.31	12.99
NE_a, net energy for activity [MJ/head/day]	4.97	7.45	5.86	6.40	4.23	5.11	2.86	3.12	1.19	1.36
NE_g, net energy for growth [MJ/head/day]	0	0	9.25	11.31	16.48	18.51	9.26	11.59	6.19	5.30
NE_l, net energy for lactation [MJ/head/day]	80.94	24.02	0	0	0	0	0	0	0	0
NE_w, net energy for work [MJ/head/day]	0	0	0	0	0	0	0	0	0	0
NE_p, net energy for pregnancy [MJ/head/day]	4.47	4.47	3.12	0	0	0	0	0	0	0
GE, gross energy intake [MJ/head/day]	378.36	262.17	217.2	276.83	187.18	203.82	115.05	143.26	66.52	67.66
REM, ratio of net energy for maintenance	0.53	0.51	0.50	0.50	0.52	0.53	0.52	0.52	0.52	0.52
REG, ratio of net energy for growth	0.33	0.30	0.28	0.28	0.31	0.34	0.31	0.31	0.31	0.31
EF from enteric fermentation [kg CH_4/head/year]	152.62	111.77	99.72	122.56	77.35	84.22	47.54	59.20	14.40	14.65

Details of the calculation are given in the above-mentioned studies (Kolář, Havlíková and Fott 2004, Beranová et al. 2022) and the results are illustrated in Tab. 5-13. It is obvious that EFs increased slightly from 1990 because of the increasing weight and milk production of cows and because of the increasing weight and weight gain for other cattle. On the other hand, CH_4 emissions from enteric fermentation of cattle dropped during the period 1990–2024 to about one half of the former values due to the rapid decrease in numbers of animals kept (Tab. 5-14).

Tab. 5-14 Activity data and methane emissions from enteric fermentation of dairy and non-dairy cattle, Tier 2, 1990–2024

Year	Dairy cattle population [1 000 heads]	Other cattle population [1 000 heads]	EF Dairy cattle [kg CH_4/hd/yr]	EF Other cattle [kg CH_4/hd/yr]	Emissions Dairy cattle [kt CH_4]	Emissions Other cattle [kt CH_4]	Emissions Cattle, total [kt CH_4]
1990	1 198	2 206	97.59	47.59	116.91	104.99	221.89
1991	1 157	2 106	94.87	48.81	109.81	102.79	212.60
1992	999	1 870	96.71	49.82	96.65	93.16	189.81
1993	896	1 552	97.04	49.61	86.97	77.01	163.98
1994	790	1 319	99.11	49.58	78.32	65.39	143.72
1995	727	1 255	105.23	53.44	76.52	67.08	143.61
1996	708	1 235	104.72	53.77	74.10	66.42	140.52
1997	652	1 172	102.87	54.48	67.05	63.86	130.92
1998	594	1 069	107.44	54.38	63.79	58.15	121.94
1999	579	1 043	112.17	58.11	64.95	60.59	125.53
2000	544	995	114.64	58.62	62.37	58.35	120.72
2001	526	1 022	114.23	59.58	60.06	60.89	120.95
2002	493	995	117.88	59.66	58.10	59.34	117.45
2003	463	955	120.45	60.78	55.77	58.04	113.80
2004	434	925	122.81	60.71	53.28	56.17	109.45
2005	430	932	126.62	63.25	54.40	58.97	113.37
2006	421	922	126.47	63.29	53.26	58.38	111.63
2007	408	952	128.07	63.54	52.19	60.51	112.70

Year	Dairy cattle population [1 000 heads]	Other cattle population [1 000 heads]	EF Dairy cattle [kg CH_4/hd/yr]	EF Other cattle [kg CH_4/hd/yr]	Emissions Dairy cattle [kt CH_4]	Emissions Other cattle [kt CH_4]	Emissions Cattle, total [kt CH_4]
2008	403	967	129.88	64.02	52.31	61.94	114.25
2009	397	936	130.91	64.19	51.94	60.06	112.00
2010	375	944	131.17	65.72	49.24	62.04	111.28
2011	374	965	133.46	64.32	49.92	62.10	112.02
2012	367	954	135.91	63.94	49.89	61.00	110.89
2013	375	957	136.43	64.32	51.20	61.54	112.74
2014	372	1 001	137.01	64.41	51.02	64.46	115.48
2015	369	997	137.08	66.96	50.59	66.78	117.37
2016	367	972	140.36	65.89	51.55	64.06	115.62
2017	365	1 001	141.92	66.57	51.87	66.63	118.50
2018	359	1 007	143.29	69.41	51.38	69.87	121.25
2019	361	1 006	143.41	69.51	51.83	69.90	121.73
2020	357	983	146.99	69.63	52.48	68.45	120.93
2021	362	997	147.12	69.79	53.31	69.59	122.90
2022	357	1 034	148.79	71.01	53.07	73.41	126.48
2023	358	1 012	150.70	70.08	53.90	70.92	124.82
2024	360	1037	152.62	70.14	54.95	72.76	127.70

5.2.1.2.3 Enteric Fermentation of other livestock (sheep, goats, swine, horses)

Compared to cattle, the contribution of other farm animals to the total CH_4 emissions from enteric fermentation is much lower (3.3% in 2024). Therefore, methane emissions from enteric fermentation of other farm animals (other than cattle) are estimated using the Tier 1 approach. Because some of the features of keeping livestock in the Czech Republic are similar to those in the neighbouring countries of Germany and Austria, the default EFs for Tier 1 approaches recommended for Developed countries were employed. The Czech Statistical Office publishes data on the numbers of goats, sheep, swine, horses, and poultry annually in the Statistical Yearbooks (1990–2024). Considering the rather low numbers in these animal categories, the default emission factors (Table 10.10, IPCC 2006 Gl.) were used for estimating methane emissions: 8 kg of CH_4 annually per head for sheep, 5 kg of CH_4 for goats, 1.5 kg of CH_4 for swine and 18 kg of CH_4 for horses. An overview of methane emissions estimated for other livestock in the period 1990–2024 is presented in Tab. 5-15.

Tab. 5-15 Methane emissions from enteric fermentation of other livestock, Tier 1, 1990–2024

Year	Sheep	Swine	Goats	Horses	Total
	CH_4 emissions from enteric fermentation [kt]				
1990	3.44	6.96	0.21	0.49	11.09
1995	1.32	5.62	0.23	0.33	7.49
2000	0.67	5.36	0.16	0.43	6.62
2005	1.12	4.18	0.07	0.37	5.74
2010	1.58	2.77	0.11	0.54	4.99
2015	1.85	2.33	0.13	0.61	4.93
2016	1.75	2.22	0.13	0.58	4.68
2017	1.74	2.30	0.14	0.62	4.80
2018	1.75	2.26	0.15	0.63	4.80
2019	1.70	2.26	0.15	0.66	4.78
2020	1.63	2.32	0.14	0.69	4.78
2021	1.47	2.24	0.13	0.60	4.43
2022	1.39	1.99	0.12	0.67	4.18

Year	Sheep	Swine	Goats	Horses	Total
			CH_4 emissions from enteric fermentation [kt]		
2023	1.43	2.04	0.12	0.67	4.28
2024	1.44	2.13	0.12	0.67	4.37

5.2.1.3 Uncertainty and time-series consistency

Uncertainty estimates are based on the expert judgement. The uncertainty in the activity data equals 5% and the uncertainty in the emission factors equals 20%. The combined uncertainty, calculated according to IPCC Tier 1 methodology, equals 20.6%.

Several methodological updates were made during the reporting period described in the relevant NID text. Time series consistency is always preserved. Recalculations due to the methodological updates were carried out for the whole reported period.

5.2.1.3.1 Historical overview

Initially, calculations were based on historical studies (Dolejš 1994 and Jelínek et al. 1996). It has been suggested in several reviews organized by UNFCCC that an approach based on historical studies was obsolete. Moreover, IEFs (implied emission factors) were mostly found as outliers: especially EFs for enteric fermentation in cattle seemed to be substantially underestimated. Details of the historical approach are given in former NIRs (submitted before 2006).

For submission 2007 the new concept for calculating CH_4 emissions followed the Good Practice Guidelines (IPCC 2000) was implemented. The estimation was based on the following decisions:

1) Methane emissions from enteric fermentation of livestock (a key source) come predominantly from cattle. Therefore Tier 2, as described in Good Practice Guidance (IPCC 2000) is employed only for cattle.
2) Methane emissions from enteric fermentation of other farm animals are estimated by the Tier 1 approach. Because some features of keeping livestock in the Czech Republic are like those in the neighbouring countries such as Germany and Austria, the default EFs for Tier 1 approaches recommended for developed countries were employed.

An increased attention was paid to enteric fermentation. It was stated that cooperation with specialized agricultural experts is crucial for obtaining new consistent and comparable data of suitable quality. The relevant country-specific data for milk production, weight, weight gain for growing animals, type of stabling, etc. were collected by our external experts (Hons et Mudřík 2003). Moreover, the statistical data for sufficiently detailed cattle classification, which is available in the Czech Republic, was also collected at the same time. Calculating the enteric fermentation of cattle using the Tier 2 approach was described in a study (Kolář, Havlíková and Fott 2004) for the whole time series from 1990 using the above-mentioned country-specific data. The necessary QA/QC procedures were performed in cooperation with the experts from IFER. The country-specific data like the weight of individual categories of cattle, weight gains in these categories and recent feeding situations were revised in 2006. The new values were estimated similarly by our external experts (Mudřík and Havránek 2006) for the next period.

The national zoo-technical inputs (mainly weight, weight gain, daily milk production including the percentage content of fat and the feeding situation) were updated several times in cooperation with experts from the Institute of Animal Sciences. These changes in the activity data and input parameters obviously did not result in any changes in emissions for the entire reporting period.

The important revision of cattle weight data (NIR 2018), along with the harmonization of this input data with the national legislation, increased the country-specific emission factors for enteric fermentation as well as increased the total emissions by about 2% in the category of enteric fermentation.

Until 2017, Czech Statistical Office had used age categories different from the national legislation (the age periods had been 0-8 months and 8-12 months for young categories) and the relevant body weight of calves, young bulls and heifers had been used in the estimates. Since 2017, the input data were adapted to the Czech legislation (0-6, 6-12 months). The time series is consistent – the weight data are relevant to the number of heads in the category. This change does not have any significant impact on the livestock emissions.

For the needs of CHMI, based on the knowledge and analysis processed in 2019–2022 during the research project “Development of the methodologies for reporting and projections of greenhouse gas emissions and removals including projections of usual pollutants” funded by The Technological Agency of the Czech Republic (TACR), a specific report "Update of the methodology for estimating emissions from enteric fermentation from cattle, evaluation of the possibilities of using country-specific data for estimating emissions from enteric fermentation" (Beranova et al. 2022a) was prepared. As a part of the presented output, the existing estimation procedures used for methane emissions were examined. The estimates were subsequently adjusted according to the IPCC requirements specified in the refinement of the emission estimation methodology for the national GHG inventory (IPCC 2019). In cooperation with the experts from the Institute of Animal Science and Mendel University Brno, the activity data were updated and the entire time series of methane emission estimates for cattle was recalculated. The aim was to effectively use the country-specific data for emission estimation and validate the methane emission factor based on the data on the assumed nutrition of cattle from the nutritional standards (norms). The calculation spreadsheet has been updated consequently in following submissions.

5.2.1.4 Source-specific QA/QC and verification

Generally, QA/QC includes check on activity data, emission factors and methods employed. All the differences are discussed and, if necessary, also corrected. The procedure of inventory compiling is initiated by IFER, where all the necessary data, obtained from the Czech Statistical Office (CzSO), are inserted into the excel spreadsheets and verified by other IFER experts. There are some more specific parameters, not available from CzSO, required for estimating the country-specific emission factors for cattle (Tier 2). The zoo-technical national data (esp. cattle breeding) are supplied by the experts from agricultural institutes. The appropriate values in the calculation spreadsheets are updated at IFER, replacing the older values. The verified data is transferred to the ETF Reporting Tool, where the data is technically verified again. A completeness check of ETF tables was performed for the final time-series approval.

The country-specific parameter, digestibility (DE, %), for cattle was estimated on the basis of the existing publications. Considering the individual OMD (organic matter digestibility) values for the most common feed (e.g., corn silage, hay and straw, green fodder – alfalfa and clover, etc.), the average digestibility for cattle was estimated. The estimated average digestibility corresponds to approximately 70% (Koukolová and Homolka 2008 and 2010, Tománková and Homolka 2010, Jančík et al. 2010, Petrikovič et al. 2000, Petrikovič and Sommer 2002, Sommer 1994, Zeman et. al. 2006, Třináctý 2010, Čermák et al. 2008). Dr. Pozdíšek (expert from the Research Institute for Cattle Breeding, personal communication) determined the conservative average digestibility values for three basic cattle sub-categories. These digestibility values were updated for the entire reporting period (Tab. 5-10).

The new refinement of DE values (validation) was made by comparing the calculated gross energy (GE) results and dry matter intake (DMI, kg/day) values from feed. Three DMI values were available, obtained from the independent information sources:

1. Direct calculation from GE value: DMI = GE/18.45
2. Derivation from average feeding rations standards available for individual dairy categories (Beranova et al., 2022a)
3. Calculation according to simplified Tier 2 methodology of IPCC Guildelines 2019 (eq. 10.17-10.18B).

The results of the comparison are shown in table (Tab. 5-16).

Tab. 5-16 Comparison of digestibility values derived from the calculation of DMI from GE values, calculation recommended by IPCC Guidelines 2019 (data 2024), DMI values are from Czech feeding ratio standards.

Cattle category	DE [% of energy]	GE [MJ/day]	DMI (GE/18.45) [kg/day]	DMI eq. 10.17-10.18B [kg/day]	DMI Czech feeding standards, avg. [kg/day]	Avg. value of DMI [kg/day]
Dairy cattle	70	378.36	20.51	20.12	19.80	20.14
Suckler cows	64	262.17	14.21	14.30	14.80	14.44
Mature heifers >2 yrs.	60	217.20	11.77	13.20	11.40	12.12
Mature bulls >2 yrs.	60	276.83	15.00	14.81	13.90	14.57
Heifers 1-2 yrs.	66	187.18	10.15	11.74	9.90	10.60
Bulls 1-2 yrs.	71	203.82	11.05	11.52	10.65	11.07
Heifers 6-12 m.	66	115.05	6.24	6.41	6.05	6.23
Bulls 6-12 m.	66	143.26	7.76	7.10	7.60	7.49
Calves <6 m., F	66	66.52	3.61	3.42	3.35	3.46
Calves <6 m., M	66	67.67	3.67	3.42	3.35	3.48

From the comparison of these three DMI values obtained in a different way it is obvious, that the values correspond within the expected uncertainties and, accordingly, they mostly vary by ±5% from the average, in case of heifers and growing heifers by ±10% from the average counted from all the three values.

The updated enteric fermentation emission factors for dairy and other cattle were compared with the default enteric fermentation factors available for the Western Europe region in IPCC 2006 Guidelines (Table 10.11) and IPCC 2019 Guidelines (Table 10.11), Tab. 5-17.

Tab. 5-17 Comparison of emissions factors for methane emissions from enteric fermentation of dairy and non-dairy cattle, factors recommended by IPCC 2006 Gl. for Western Europe, IPCC 2019 Gl. for Western Europe and data calculated for Submission 2026

Cattle category	EF, IPCC 2006 [kg CH_4/head/year]	EF, IPCC 2019 [kg CH_4/head/year]	EF, NID (data 2024) [kg CH_4/head/year]
Dairy cattle	117*	126**	153***
Other cattle	57	52	70

*Average milk production 6 000 kg/head/year

** Average milk production 7 410 kg/head/year

*** Average milk production 9 573 kg/head/year

The current emission factor for dairy cows corresponds to high milk production and highly digestible feed and it is about 21% higher than the current default value. The current emission factor for other cattle is 35% higher than the default value according to IPCC 2019 Guidelines. The value needs to be further refined based on the animal nutrition data.

Tab. 5-18 Comparison of two different estimations of emission factors for methane emissions from enteric fermentation of dairy and non-dairy cattle, input data 2023-2024 (Submission 2025 and 2026)

Cattle category	EF, NID (data 2023), eq. 10.21 [kg CH_4/head/year]	EF, eq. 10.21A [kg CH_4/head/year]

	2023	2024	2023	2024
Dairy cattle	151	153	148	150
Other cattle	70	70	70	70

IPCC 2019 Guidelines methodology makes it possible to estimate the value of the methane emission factor from enteric fermentation from equation 10.21A using the dry matter intake and methane yield value (MY, g CH_4/kg DMI), which is given in Table 10.12 with values corresponding to the quality of the feed rations. Thus, EF can be calculated using different data, which makes it possible to compare the quality of input data. We performed the verification for the data of the last two submissions (NID 2025 and NID 2026, data from 2023 and 2024) for all cattle categories (Tab. 5-18). We adjusted used MY values using the same procedure as for the Y_m if the values given in the IPCC table did not exactly correspond to the situation in Czech Republic.

5.2.1.5 Source-specific recalculations, including changes made in response to the review process and impact of emission trends

A detailed description of the last recalculation related to estimates of emissions from enteric fermentation of cattle is available in the text report of Submission 2023.

5.2.1.6 Source-specific planned improvements, including tracking of those identified in the review process

The relevant research in the Czech Republic should focus on specifying the quality (composition) of the feed rations in terms of dry matter and non-detergent fiber content for individual cattle categories or specifying the composition of the feed rations in grazing and intensive farming. By adjusting the feed rations, a significant reduction in methane emissions from enteric fermentation can be achieved. When the research results are available, the NID team will use them to update the input data.

5.2.2 Manure Management (CRT 3.B)

This chapter describes the estimation of CH_4 (49% contribution to emissions from the manure management category) and direct (25%) and indirect (26%) N_2O emissions from animal manure management. The total emissions from manure management (CH_4 and N_2O) equalled 762 kt CO_2 in 2024. For detailed information, see Tab. 5-2. The extensive decrease, from 2010 to 2024 by about 17%, is caused by methodological update in shares of different animal waste management systems (AWMS) and a transition to country-specific data of nitrogen excretion rate.

Good agricultural practices were developed, based on agricultural policies and structures that support the trends in the animal waste management system allocation after the Velvet Revolution (1989) and mainly after the Czech Republic entered the European Union (2004). These procedures include inexpensive and austerity measures, such as the incorporation of relevant proteins in livestock feed, regular cleaning of stables or proper timing of manure applications to agricultural land in the period when plants absorb the maximum amount of nutrients. These measures may also involve other procedures, such as using low-emission techniques for manure application, storage and suitable livestock housing.

5.2.2.1 Source category description

This emission source covers manure management for domestic livestock. Both nitrous oxide (N_2O) and methane (CH_4) emissions from manure management of livestock (cattle, swine, sheep, horses, goats and poultry) are reported.

Nitrous oxide is produced by the combined nitrification and denitrification processes occurring in the manure. Methane is produced in manure during the decomposition of organic matter by anaerobic and facultative bacteria under anaerobic conditions. Emissions are dependent on the amount of organic matter in manure, climatic conditions and manure management. An overview of the total emissions from manure management is presented in Tab. 5-19.

During the period 1990–2024, the emissions from manure management decreased by about 70%. Decreasing emissions from cattle and swine predominated in this trend. The reduction in the cattle population is partly counterbalanced by an increase in cattle efficiency (increasing gross energy intake and milk production and milk quality).

Tab. 5-19 Overview of emissions from manure management [kt CO_2 eq.], 1990–2024

Year	Total emissions, category 3.B	CH_4 emissions	Direct N_2O emissions	Indirect N_2O emissions
		[kt CO_2 eq.]		
1990	2 515	1 539	543	433
1995	1 725	1 092	351	282
2000	1 542	960	322	259
2005	1 285	782	276	227
2010	916	502	221	194
2015	718	346	186	187
2016	735	360	185	190
2017	745	367	186	192
2018	781	387	195	199
2019	758	376	189	194
2020	757	377	187	193
2021	774	386	191	196
2022	743	362	189	192
2023	733	355	187	192
2024	762	371	193	198

5.2.2.2 Methodological aspects

5.2.2.2.1 Animal waste management systems

The first country specific AWMS system distribution had been based on the expert study of Mudřík and Hons (2004) and was updated several times (last time in 2011) by the expert opinions during the reporting period. The more recent update of AWMS for cattle, swine and poultry categories was based on Klír (2019) and Nesňal et al. (2018) concerned with the 2016–2024 data series. The amount of manure in liquid and solid forms consumed in anaerobic digesters was derived from the statistical survey. AWMS were upgraded based on Klír et al. (2011) for goats, horses, and sheep as well. This upgrade concerned the data series 2014–2024.

For 2024 submission, we ensured that the animal waste management system (AWMS) data was updated and adjusted with respect to the likely development of manure management handling, to remove inconsistencies in individual handling shares. This issue was commented on relevant review report (Issue ID A14). The current form of AWMS respects the gradual onset of anaerobic digestion in full compliance with UN-ECE reporting and OECD/EUROSTAT reporting. It is an important step to complete the harmonization of ammonia and NO_x reporting and nitrous oxide reporting. The overview of the country-specific distribution of AWMS is shown in Tab. 5-21, Tab. 5-22 and Tab. 5-23 and Fig. 5-2).



Fig. 5-2 Animal waste management systems distribution, all livestock, 1990–2024

There are four main manure management systems defined in the Czech Republic (Klír 2011, Klír 2019) according to Table 10.18 (IPCC 2006, IPCC 2019), from the reporting year 2015:

1. Anaerobic digesters
2. Liquid storage
3. Solid storage
4. Pasture/Range/Paddock

The use of manure in anaerobic digesters is relevant for cattle, swine and poultry manure. The operation of anaerobic digesters began in 2001 when two biogas stations started to work. The specific structure of Czech animal breeding (mostly in factory farming) made it possible to build anaerobic digesters close to farms to consume daily manure production very efficiently without the need to store the manure. Consumption of manure in anaerobic digesters in the Czech Republic is limited because the sources of biological input (manure, green biomass etc.) are also limited. The number and capacity of anaerobic digesters remained at their maximum number from 2013 (Tab. 5-20).

Tab. 5-20 Increase in the number of biogas stations, estimation of total digestates production and amount of nitrogen in digestate, 2001–2024 (CARC)

Year	Number of biogas stations	Digestate production [1 000 t/year]	Amount of N in digastate [kg/year]
2001	2	42	210 000
2005	10	210	1 050 000
2010	135	2 835	14 175 000
2011	204	4 284	21 420 000
2012	327	6 867	34 335 000
2013–2024	386	8 106	40 530 000

Animal waste management systems (AWMS) are used for N_2O and CH_4 emission estimations in the same way. The annual update of the AWMS is possible thanks to the cooperation with CARC (Dr. Klír, Dr. Wollnerová) and unification of Nex rate for all categories of farm animals. The result of the intensive cooperation was the unification of input data in all country reports on nitrogen emissions and the nutrition balance from the agricultural sector.

Tab. 5-21 Overview of Czech country-specific AWMS: dairy and non-dairy cattle, fractions of individual manure management systems [%], 1990–2024

Livestock category	Type of AWMS Fraction of manure N per AWMS [%]				
Dairy cattle	Anaerobic digesters	Liquid system	Daily spread	Solid storage	PRP
1990	0	25	2	68	5
1995	0	24	1	65	10
2000	0	25	1	64	10
2005	2	24	1	62	11
2010	15	19	1	58	7
2015	32	11	1	54	2
2020	32.5	10.7	0	56.8	0
2021	32.5	10.7	0	56.8	0
2022	32.5	10.7	0	56.8	0
2023	32.5	10.7	0	56.8	0
2024	32.5	10.7	0	56.8	0
Non-dairy cattle (weighted avg.)					
1990	0	27	1	60	12
1995	0	23	1	59	17
2000	0	18	1	64	17
2005	0	17	1	66	16
2010	2	10	1	63	24
2015	3	6	1	65	25
2020	2.8	6.5	0	62.3	28.4
2021	2.9	6.4	0	62.3	28.4
2022	2.7	6.8	0	62.4	28.1
2023	2.7	6.8	0	62.4	28.1
2024	2.6	6.8	0	62.1	28.5

Tab. 5-22 Overview of the Czech country-specific AWMS: swine and poultry, fractions of individual manure management systems [%], 1990–2024

Livestock category	Type of AWMS Fraction of manure N per AWMS [%]					
Swine	Anaerobic digesters	Liquid system	Daily spread	Solid storage	PRP	Other
1990	0	76	0	23	0	1
1995	0	76	0	23	0	1
2000	0	76	0	23	0	1
2005	2	75	0	23	0	0
2010	19	56	0	25	0	0
2015	47	28	0	25	0	0
2020	44.8	22.7	0	32.4	0	0
2021	45.0	22.5	0	32.5	0	0
2022	48.1	19.4	0	32.5	0	0
2023	49.6	17.9	0	32.5	0	0
2024	48.6	18.9	0	32.5	0	0
Poultry						
1990	0	0	0	84	2	14
1995	0	0	0	84	2	14
2000	0	0	0	84	2	14
2005	2	0	0	84	2	12

2010	3	0	0	84	2	11
2015	6	0	0	84	0	10
2020	8.7	0	0	91.3	0	0
2021	6.8	0	0	93.3	0	0
2022	6.8	0	0	93.2	0	0
2023	6.9	0	0	93.2	0	0
2024	8.4	0	0	91.6	0	0

Tab. 5-23 Overview of the Czech country-specific AWMS systems: sheep, horses and goats, fractions of individual manure management systems [%], 1990–2024

Livestock category	Type of AWMS Fraction of manure N per AWMS [%]				
	Liquid system	Daily spread	Solid storage	PRP	Other
Sheep	0	0	50	50	0
Horses	0	0	50	50	0
Goats	0	0	40	60	0

The animal waste management system (AWMS) has been updated annually based on a long-term statistical survey of agricultural farms in the Czech Republic. This investigation, ongoing since 2005, evaluated crop production and livestock production of the farms. From the point of view of AWMS, data on livestock housing systems are processed annually. These data show the percentage of individual housing and grazing systems for individual categories of animals. A further complementary basis for the uniform calculation of the AWMS was the statistical study of IAEI (Institute of Agricultural Economics and Information), which surveyed farms for manure transferred annually to biogas stations. Based on these data, nitrogen production in livestock manure (Nex rate) was divided according to the percentage of individual housing systems for each livestock category. Subsequently, the amount of nitrogen in the manure transferred to biogas stations was separated. The result was the determination of the percentage share of individual methods of handling manure in agriculture.

Manure management storage and usage are subjected to national Decree No. 377/2013 Coll. This regulation is based on EU regulation No. 91/676/EHS from 1991. The manure storage capacity corresponds to the estimated production for 6 months. This does not apply to the storage of solid manure on agricultural land before use. Solid manure may be stored on agricultural land at suitable places in a field for a maximum period of 24 months outside vulnerable zones and 12 months in vulnerable zones. The company/owner can store the manure for fertilizer again on the same agricultural land four years after soil cultivation of the agricultural land. Liquid manure is to be stored in leak-proof tanks or scrub areas in stables. Reservoirs and tanks or areas in the stables must match the capacity of at least four months estimated production of liquid manure or share at a minimum of three months estimated production of liquid manure and dung, depending on the climatic conditions of the region. In vulnerable zones there must be storage capacity equivalent to six months' production of these fertilisers. The decree No. 377/2013 Coll. includes five annexes with data for calculating the production of manure in a situation where records of the manure management system evidence on individual farm level are not available (e.g. typical animal mass of livestock, nitrogen content in excrements, dry mass of excrements etc.). A farmer can calculate the production and control the use of manure according to the number of heads of livestock.

5.2.2.2.2 Methane emissions CRT 3.B(a)

CH_4 emissions from manure management were identified as a key source by trend and level assessments (TA, TA /see Tab. 5-1). The estimation of methane emissions from manure management for cattle and swine categories is performed according to the Tier 2 method. Methane emissions in other livestock categories are estimated according to the Tier 1 approach.

In relation to the decreasing trend in the animal population (especially cattle and swine), the methane emissions from manure management had rapidly decreased during the period 1990–2012. The trend in methane emissions from manure management is presented in Fig. 5-3. Between 2012–2024, emissions increased slightly, with an average fluctuation by about 10%, with a minimum in 2013 and a maximum in 2018.



Fig. 5-3 Trend in methane emissions from manure management, 1990–2024

Cattle category

The activity data on cattle population distributed by age and gender were obtained from the Statistical Yearbook of the Czech Republic (CzSO), providing a consistent time series of the animal population numbers during the entire reported period (1990–2024). Gross energy (GE) values were estimated based on the national study of Kolář et al. (2004) and IPCC 2006 Gl. and IPCC 2019 Gl. in the special spreadsheet (more information in the Enteric Fermentation chapter). In connection with the refinement of activity data in the calculation of gross energy intake (chapter Enteric Fermentation), the value of volatile solids (VS) was changed. Methane conversion factor (MCF) changed because of the changes in AWMS (Fig. 5-2). Consequently, the methane emission factor from manure management changed significantly in all cattle categories. GE values are reported in ETF as country-specific data for the entire reported period (Tab. 5-24).

Tab. 5-24 Gross energy (GE) for dairy and non-dairy cattle [MJ/head/day], reported period 1990–2024

	1990	1995	2000	2005	2010	2015	2020	2021	2022	2023	2024
Dairy cattle	228.9	246.8	268.9	297.0	307.7	331.8	364.4	364.7	368.9	373.6	378.4
Other cattle	119.8	133.3	144.7	155.0	164.1	167.1	171.1	171.5	174.0	172.0	172.1

EF is calculated for each cattle category and reported for dairy and non-dairy cattle. The value reported for non-dairy (other) cattle is the weighted average of results calculated for each non-dairy category separately. The total emissions are the sum of two products ($EF_{DairyCattle}$*population of dairy cattle + $EF_{NonDairyCattle}$ *population of non-dairy cattle).

The current updated data on the AWMS distribution were employed for the emission estimation. Other specific parameters for estimating the emission factors for cattle (B_o, MCF) were obtained from Dämmgen

et al. (2012). The specific parameters recommended to use by studies in neighbouring countries are the same as the default values of IPCC 2006 Gl. and correspond to the climate zone in the country. The parameters recommended in Dämmgen et al. (2012) were used for the emission estimation (Tab. 5-25). The VS parameters calculated by Dämmgen et al. (2012) based on B_o, ASH and MCF values and EF for estimating the methane emissions are presented in Tab. 5-25 and Tab. 5-26.

Tab. 5-25 Activity data, input data and calculated data used for estimating methane emission factors for manure management for all age cattle categories, current data (2024)

	Dairy	Suckler	Mature Heifers	Mature Bulls	Heifers 1-2 yrs	Bulls 1-2 yrs	Heifers 6-12 m	Bulls 6-12 m	Calves,F <0.6 m	Calves,M <0.6 m
Population [1 000 heads], CzSO	360	220	69	19	217	92	138	85	119	79
Body weight [kg], CS	650	650	600	800	470	560	265	300	115	115
GE, gross energy intake [MJ/head/day]*	378.36	262.17	217.2	276.83	187.18	203.82	115.05	143.26	66.52	67.66
DE, digestibility of feed [%], CS	70	64	60	60	66	71	66	66	66	66
ASH, content of manure as a fraction of dry feed intake, [%]	8	8	8	8	8	8	8	8	8	8
VS, volatile solid excr. per day in dry organic matter *	6.42	5.23	4.77	6.07	3.55	3.35	2.18	2.71	1.26	1.28
Sum of (MCF*AWMS) *	0.0328					0.0263				
B_o, maximum methane producing capacity	0.24	0.18	0.18	0.18	0.18	0.18	0.18	0.18	0.18	0.18
EF from manure management [kg CH_4/head/year]*	12.35	5.18	4.72	8.96	3.83	3.51	2.59	2.87	1.91	1.95

**Calculated value*
CS – country-specific data
CzSO – Statistical Yearbook of the Czech Republic, the Czech Statistical Office
B_o – Table 10A-4, Table 10A-5, IPCC 2006 Gl.
ASH – recommendation p. 10.42 IPCC 2006 Gl.

Tab. 5-26 List of parameters for methane emission factor estimation from manure management in the Czech conditions, MCF values [%]

Cattle, all age categories	MCF values (IPCC 2006 Gl., Table 10.17) [%]
Anaerobic digesters	1
Liquid system	17
Daily spread	0.1
Solid storage	2
Pasture, range and paddock	1

The equations for determining the emission factors and estimating the methane emissions were taken from IPCC 2006 Guidelines:

1. Eq. 10.22 (IPCC 2006 Gl., p. 10.37) was used to estimate the methane emissions:

$$CH_{4\ emissions}\left[\frac{kt}{year}\right] = \sum\left(\frac{EF \cdot cattle\ population}{10^6}\left[\frac{kg}{kt}\right]\right)$$

2. Eq. 10.24 (IPCC 2006 Gl., p. 10.42) was utilized to estimate the VS parameter:

$$VS = GE \cdot \left[\frac{1 - DE}{100} + (UE \cdot GE)\right] \cdot \frac{1 - ASH}{18.45}$$

3. The methane emission factors were estimated using Eq. 10.23 (IPCC 2006 Gl., p. 10.41):

$$EF = VS \cdot 365 \cdot B_o \cdot 0.67 \cdot \sum (MCF \cdot MS)$$

An overview of the daily volatile excreted solids (VS, kg dry matter/animal/day), methane emission factor and methane emissions for dairy cattle and non-dairy cattle is presented in Tab. 5-27.

Tab. 5-27 Overview of VS [kg dry matter/head/day], EF [kg CH_4/head/year] and methane emissions [kt] from manure management, dairy and non-dairy category, 1990–2024

Year	Dairy cattle			Other cattle		
	VS [kg DM/head/day]	EF [kg CH_4/head/yr]	Methane emissions [kt CH_4]	VS [kg DM/head/day]	EF [kg CH_4/head/yr]	Methane emissions [kt CH_4]
1990	4.22	14.03	16.81	2.33	5.49	12.12
1995	4.55	14.65	10.65	2.60	5.70	7.16
2000	4.83	15.95	8.68	2.84	5.44	5.42
2005	5.18	17.56	7.54	3.06	5.54	5.16
2010	5.22	14.12	5.30	3.22	4.30	4.06
2015	5.62	10.86	4.01	3.22	3.40	3.39
2016	5.76	11.26	4.13	3.19	3.37	3.28
2017	5.82	11.38	4.16	3.16	3.33	3.33
2018	6.02	11.77	4.22	3.29	3.65	3.68
2019	6.03	11.74	4.24	3.30	3.66	3.69
2020	6.18	12.04	4.30	3.31	3.67	3.61
2021	6.18	12.05	4.37	3.31	3.68	3.67
2022	6.25	12.04	4.29	3.36	3.67	3.79
2023	6.33	12.19	4.36	3.33	3.64	3.69
2024	6.41	12.35	4.45	3.33	3.63	3.77

Swine

In 2019, ERT from EU noted that the Tier 1 methodology used for CH_4 emissions from manure management of swine, which is one of the key sources, resulted in a potential over-estimate exceeding the threshold of significance. Recalculation based on country-specific zoo-technical data was planned for the Submission 2022 according to the improvement plan. In 2020, ERT noted the requirement of a Tier 2 approach to be used obligatorily in Submission 2021 and proposed a Potential Technical Correction (PTC) that used the default IPCC parameters and Eq. 10.23 (IPCC 2006). The list of parameters recommended is listed in the following Tab. 5-28 and Tab. 5-29. By Submission 2022 this update was implemented in the inventory.

Czech statistical data allows splitting the swine population into two subpopulations: market swine and breeding swine (CzSO). The proportion between subpopulations varies from 9% to 12% (breeding animals/all swine ratio) over a time series. The proportion of 12% was recorded in the years 1990–1995, the lowest proportion of breeding animals was recorded in 2008. There are the default value data of maximum methane producing capacity and volatile solids available in T. 10A-7 (IPCC 2006). Country-specific AWMS allows to calculate methane conversion factor. Results of the current estimation are available in Tab. 5-30.

Tab. 5-28 List of parameters for estimating methane emissions from manure management of swine in the Czech conditions, data 2024

Input data (2024)	Market swine	Breeding swine	Data source
Swine population [1 000 heads]	1 295.91	125.92	CzSO
VS, volatile solid [kg/head/day]	0.3	0.46	IPCC T. 10A-7, T. 10A-8

B_0, maximum methane producing capacity	0.45	0.45	IPCC T. 10A-7, T. 10A-8
MS * MCF, [%]	5.22	5.22	CS, IPCC T. 10.17

Tab. 5-29 List of parameters for estimating methane emissions from manure management of swine in the Czech conditions, MCF values [%], data 2024

Swine, all subcategories	MCF values (IPCC 2006 Gl., Table 10.17, CS) [%]		
AWMS (CS)	Share of MS (2024)	MCF values	MS*MCF
Anaerobic digesters	48.6	2.8*	1.36
Liquid system	18.9	17	3.21
Solid storage	32.5	2	0.65
Other	0	1	0
Sum MS*MCF			5.22

**Recommended value, technical correction, 2021, TERT*

Tab. 5-30 Activity data for estimating methane emissions from manure management of swine in the Czech conditions, 1990–2024*

Year	Market swine		Breeding swine		Weighted avg.	
	VS [kg DM/head/day]	EF [kg CH_4/head/yr]	VS [kg DM/head/day]	EF [kg CH_4/head/yr]	EF [kg CH_4/head/yr]	Total emissions [kt CH_4]
1990	0.3	4.43	0.46	6.79	4.71	21.86
1995	0.3	4.43	0.46	6.79	4.72	17.67
2000	0.3	4.43	0.46	6.79	4.70	16.78
2005	0.3	4.36	0.46	6.69	4.63	12.89
2010	0.3	3.31	0.46	5.07	3.48	6.42
2015	0.3	1.74	0.46	2.66	1.82	2.83
2016	0.3	2.12	0.46	3.24	2.22	3.28
2017	0.3	2.07	0.46	3.17	2.17	3.32
2018	0.3	2.01	0.46	3.09	2.11	3.18
2019	0.3	1.93	0.46	2.96	2.02	3.05
2020	0.3	1.90	0.46	2.92	1.99	3.08
2021	0.3	1.89	0.46	2.90	1.98	2.96
2022	0.3	1.75	0.46	2.68	1.83	2.43
2023	0.3	1.68	0.46	2.57	1.76	2.39
2024	0.3	1.72	0.46	2.64	1.81	2.27

** Implementation of AWMS system update*

This methodological update made for Submission 2022 resulted in decreased estimates of methane emissions from manure management.

Other livestock categories

Methane emissions from other farm animals are estimated by the Tier 1 approach. The default EFs for the developed countries were employed (Tab. 5-31):

Tab. 5-31 Default methane emission factors used for estimating CH_4 emissions from manure management (Table 10.15 and 10.14 IPCC 2006 Gl.)

Livestock category	EF [kg CH_4/head/year]
Sheep	0.19
Goats	0.13
Horses	1.56
Poultry	
Broilers	0.02

Livestock category	EF [kg CH_4/head/year]
Other poultry*	0.182

** Emission factor for other poultry is calculated as weighted average of two default EFs for different breeding systems (13% wet and 87% dry systems; 0.182 = 1.2 x 0.13 + 0.03 x 0.87).*

A more detailed description of methane emissions from manure management for poultry category is presented in Tab. 5-32:

Tab. 5-32 Activity data, default emissions factors (Table 10.15 IPCC 2006 Gl.) and emissions estimated for poultry population

Poultry population	[1 000 heads] data 2024 (CzSO 2024)	EF [kg CH_4/head/year]	CH_4 emissions [kt/year]
Poultry	25 875	0.092 (IEF)	2.38
Broilers	11 479	0.02**	0.29
Other poultry	14 396	0.182*	2.09
Wet system, 13%		1.2**	
Dry system, 87%		0.03**	

** Weighted average calculated from subcategories*

*** Manure management methane emission factors (T. 10.15 IPCC 2006 Gl.)*

5.2.2.2.3 Nitrogen excretion rate

The determination of Nex rate has undergone development related to the availability of activity data and efforts to unify Nex values within the framework of UN-ECE, OECD and IPCC reporting.

Nex value in all animal categories, except cattle, were based on the national data for typical animal mass (TAM), Eq. 10.30 IPCC 2006 Gl. and the default excretion rate (Table 10.19, IPCC 2006) until NIR 2021 submission. Nex value for cattle had been calculated in a special spreadsheet, common for the calculation of emission factors used for methane emissions from enteric fermentation and manure management. This calculation was based on population data, annual average excretion rates calculated from gross energy intake (GE) and share of protein in feed and milk. The parameters for estimating the Nex value for cattle were collected from literature sources and personal communication with agricultural experts. The value of protein content in milk was obtained from relevant literature (Poustka 2007, Ingr 2003 and Turek 2000). This also applies for protein content in feed (in dry matter) of 16.5% (Zeman, the Czech feeding standards 12-21%, Central Institute for Supervising and Testing in Agriculture 18%, Karabcová, personal communication 16-18%). The Nex rate had been estimated for each cattle category and reported for dairy, non-dairy (weighted average) and as a summarized total for cattle.

The above-mentioned procedure was revised for Submission 2021 (data 2019) when the country-specific value of Nex was newly derived from the national legislation (Decree No. 377/2013 Coll.). We made the change effective since 2019, making the data in the time series inconsistent, therefore the issue to unify the inputs from 2019 among all relevant reporting (UN-ECE, OECD, EUROSTAT).

Decree No. 377/2013 Coll., on the storage and use of fertilizers states the average values of annual nitrogen production, calculated per unit of livestock (1 Livestock Unit = 500 kg live weight of animals). These values were used as coefficients to derive the Nex rate. The reported coefficients were obtained based on a study of the Ministry of Agriculture of the Czech Republic (research project No. QH82283 “Study on interaction between water, soil and environment from the point of view of manure management in sustainable agriculture”, 2008–2012). This study analysed manure production in various systems of animal housing used in the Czech Republic. The research was based on a detailed survey of the annual manure production per one livestock unit (LU), considering the technological systems of animal housing, the production of various types of manure and species and categories of animals. The results of the survey were used for in force legislation amendment from 1998 and further published in the proceedings of an

international conference in 2011 (Klír 2011). On 1 November 2021, another amendment to this regulation came into force under No. 392/2021 Coll.

Based on the review recommendation (Issue ID A7, A5) we eliminated typical animal mass fluctuations for goats, sheep and horses which arose due to a lack of suitable statistical information. We verified the TAM values by comparing the default N rate (T. 10.19, IPCC 2006 and IPCC 2019) and country-specific data provided by Decree No. 377/213 Coll. The Nex rate data was revised and corrected for the entire reporting period.

Based on validation, we adjusted the Nex rate value for some livestock categories since Submission 2023. The following adjustments were applied (Tab. 5-33), the detailed explanation is provided in the text below the table:

Tab. 5-33 Overview of input data for nitrogen excretion calculation

Livestock category	N rate	TAM	Nex rate	Nex rate
	[kg N/1 000 kg/day]	Typical animal mass	1990–2019 [kg N/head/year]	2020–2024 [kg N/head/year]
Dairy cattle	Country-specific	Country-specific	Country-specific	Country-specific
Non-dairy cattle	Country-specific	Country-specific	N rate * TAM	Country specific
Swine	Default/ Country-specific	Country-specific	N rate * TAM	Country-specific
Sheep	Default/ Country-specific	Default	N rate * TAM	Country-specific
Goats	Default/ Country-specific	Default	N rate * TAM	Country-specific
Horses	Default/ Country-specific	Country-specific	N rate * TAM	Country-specific
Poultry	Default/ Country-specific	Country-specific	N rate * TAM	Country-specific

Dairy cattle – Based on the proposal of experts from CRI, the Nex rate value for the entire time series was taken newly from OECD reporting (Tab 5-35). Estimation of the amount of excreted nitrogen is based on milk production. Country specific N rate corresponds to the default value.

Non-Dairy cattle, Swine – validation of nationally specific values was performed by comparing the default N rate value (according to IPCC 2006 and 2019 Guidelines) and the country specific N rate value that can be derived from Decree 377/2013 Coll. and whose value from the default parameters corresponds well.

Sheep and goats – validation of country specific values were performed by comparing the default N rate value (according to IPCC GL 2006 and 2019) and the nationally specific N rate value, which can be derived from Decree 377/2013 Coll. and whose value corresponds well with the default parameters. Because country specific data on sheep and goats TAM are not available, the IPCC Guidelines 2006 default values for the entire time series were used for the calculation (for sheep 49 kg, for goats 38.5 kg).

Horses – the validation of the country specific values was performed by comparing the default N rate value (according to IPCC 2006 and 2019 Guidelines) and the nationally specific N rate value, which can be derived from Decree 377/2013 Coll. and whose value corresponds well with the default parameters. Since no country specific data on horse TAM are available, the value determined by expert estimation was adjusted so that its changes were consistent in the time series. TAM has gradually increased: 520 kg (1990–1999), 530 kg (2000–2008), 540 kg (2009–2018), 550 kg (2019–2024).

All these changes were reflected in the amount of direct and indirect nitrous emissions. Overview of Nex rate values used for calculation is shown in Tab. 5-34:

Tab. 5-34 Nex rate values used for estimating nitrous emissions, data 1990–2024

Year	Value of Nex rate [kg N/head/year]					
	Non-dairy cattle	Swine	Sheep	Goats	Horses	Poultry
1990	46.87	11.54	9.7	9.7	47.5	0.7
1995	48.24	11.54	9.7	9.7	47.5	0.7
2000	51.45	11.54	9.7	9.7	48.4	0.7
2005	54.59	11.54	9.7	9.7	48.4	0.8
2010	54.97	11.17	9.7	9.7	49.3	0.8
2015	55.50	10.98	9.7	9.7	49.28	0.5
2016	57.34	10.98	9.7	9.7	49.28	0.5
2017	56.86	10.98	9.7	9.7	49.28	0.5
2018	60.25	10.98	9.7	9.7	49.28	0.5
2019	58.71	10.99	9.8	9.8	49.31	0.5
2020	58.73	10.99	9.8	9.8	49.24	0.5
2021	58.77	11.16	9.8	9.8	49.09	0.5
2022	58.77	10.51	9.8	9.8	49.13	0.5
2023	59.22	10.76	9.8	9.8	49.13	0.5
2024	59.16	10.78	9.8	9.8	49.13	0.5

In the case of dairy cattle, the Nex rate value for the entire time series was taken newly from EUROSTAT reporting (the documentation provided by the CARC team responsible for this reporting), because the calculation of the amount of excreted nitrogen is dependent on milk production, which is increasing in the Czech Republic since 1990.

This equation was used for the calculation of nitrogen excretion rate from milk production:

$$Nex\ rate = 46.787 * (\ln(annual\ milk\ yield) - 308.49)$$

Tab. 5-35 Source data for calculation of nitrogen excretion rate for dairy cattle, 1990–2024

Year	Milk production [l/year]	Milk production [kg/day]	Nex [kg N/head/day]
1990	4 002.96	10.97	78.97
1991	3 614.60	9.90	76.07
1992	3 801.79	10.42	77.05
1993	3 817.90	10.46	77.45
1994	4 047.85	11.09	79.14
1995	4 256.27	11.66	80.91
1996	4 384.75	12.01	82.83
1997	4 234.37	11.60	83.66
1998	4 666.53	12.79	88.45
1999	4 822.38	13.21	90.21
2000	5 082.99	13.93	92.33
2001	5 252.72	14.39	95.22
2002	5 656.77	15.50	96.28
2003	5 917.38	16.21	96.59
2004	6 157.19	16.87	98.58
2005	6 427.65	17.61	100.47
2006	6 547.74	17.94	101.34

Year	Milk production [l/year]	Milk production [kg/day]	Nex [kg N/head/day]
2007	6 731.33	18.44	102.63
2008	6 945.22	19.03	104.23
2009	7 061.66	19.35	104.87
2010	7 095.41	19.44	105.10
2011	7 328.05	20.08	106.59
2012	7 620.72	20.88	108.55
2013	7 650.74	20.96	108.62
2014	7 920.89	21.70	110.23
2015	8 224.82	22.53	112.00
2016	8 262.34	22.64	112.35
2017	8 453.71	23.16	113.28
2018	8 765.14	24.01	114.97
2019	8 708.86	23.86	114.67
2020	9 140.36	25.04	116.94
2021	9 165.15	25.11	117.06
2022	9 339.23	25.59	117.90
2023	9 614.10	26.34	119.30
2024	9 573.46	26.96	120.40

An overview of the estimated nitrogen excretion value used for the calculation of N_2O emissions from manure in the cattle category is presented in Tab. 5-34 and Tab. 5-37. An overview of all activity data used in the current submission is performed in Tab. 5-36.

Tab. 5-36 Activity data, input data and calculated data used for estimation of annual nitrogen excretion rate for all animal categories, current data (2024)

Livestock category	N Production Decree No. 377/2013 [kg N/1 000 kg/day]	Animal weight [kg]	Nitrogen excretion [kg N/head/year]	N Production [kg N/livestock category]
Dairy cattle	0.51	650	120.40	43 346 167
Non-dairy cattle	0.39	422*	59.16	61 369 073
Swine	0.50	59	10.78	15 326 086
Goats	0.69	38.5	9.75	239 918
Sheep	0.55	48.5	9.75	1 758 588
Horses	0.24	550	49.13	1 821 912
Poultry	0.48	1.44*	0.48	12 344 239
Total				**136 205 982**

** weighted average*

5.2.2.2.4 Direct and indirect nitrous oxide emissions CRT 3.B(b)

N_2O emissions from manure management were identified as a key source. Since 2019 (Submission 2021), Tier 2 methodology was used for estimating the emissions in all animal categories. The country-specific value of Nex was derived newly from the national legislation (Decree No. 377/2013 Coll.). The methodological level upgrade was possible due to the use of country-specific input data evaluating the rate of nitrogen excretion. Emissions were calculated based on nitrogen excretion per animal and the animal waste management system. Following the IPCC guidelines, all N_2O emissions that took place before applying manure into soils are reported under manure management (3.B). The IPCC guidelines method for estimating N_2O emissions from manure management entails multiplying the total amount of N excretion (from all animal species/categories) in each type of manure management system by the emission factor

for that type of manure management system. The overview of direct and indirect N_2O emissions is provided in Tab. 5-37.

To estimate N_2O emissions from manure management, the default emission factors for the different animal waste management systems were taken from Table 10.21 (IPCC 2006) see Tab. 5-37.

Input data consists of the mass fraction Xi,j of animal excrement in the animal category i (i = dairy cows, other cattle, pigs, …) for various types of waste management (AWMS) j (actually: j = liquid manure, solid manure, pasture, anaerobic digesters). Here, it holds that Xi, 1 + Xi, 2 + ... + Xi, 6 = 1. Within the Tier 1 method, only the values of matrix X for typical means of management of animal excrements in Europe are given. AWMS parameters presented in the IPCC 2006 Guidelines were adapted to the Czech conditions.

Tab. 5-37 Default IPCC emission factors for direct N_2O emissions used for different AWMS (T.10.21, IPCC 2006)

AWMS	Emission factor (EF3) [kg N_2O-N per kg N excreted]
Anaerobic digesters	0
Daily spread	0
Liquid/Slurry	0.005
Solid Storage	0.005

The emissions are then summed over all the manure management systems. The manure production data for individual AWMS in Submission 2026 are reported in

Tab. 5-38). Presented values reflect the different approaches to AWMS and the use of country-specific values of Nex (data 2010–2024).

Tab. 5-38 Nitrogen production of manure distributed in individual AWMS [kg N/yr], data 2010–2024

AWMS	N Production [kg N/year]						
	2010	2015	2020	2021	2022	2023	2024
Liquid system	24 231 075	12 651 200	12 094 033	12 060 168	11 341 536	11 265 192	11 707 767
Solid storage	77 860 801	74 329 247	77 832 434	79 887 544	79 385 457	78 573 209	80 905 335
Anaerobic digesters	11 421 217	23 609 129	23 810 038	23 859 872	22 842 649	23 514 711	24 168 494
Pasture	17 404 734	16 788 448	18 491 607	18 485 543	18 978 396	18 768 539	19 424 387
Other	2 010 194	0	0	0	0	0	0
Daily spread	913 463	0	0	0	0	0	0
Total	133 841 484	129 490 131	132 228 112	134 293 127	132 548 038	132 121 651	136 205 982

5.2.2.2.5 Indirect emissions from manure management (CRT 3.B.5)

Indirect emissions originate from volatile nitrogen losses that occur primarily in the form of ammonia and NO_x. The fraction of excreted organic nitrogen that is mineralized to ammonia nitrogen during manure collection and storage depends primarily on time and, to a lesser degree, temperature. Nitrogen losses begin at the point of excretion in buildings and other animal production areas and continue through on-site management in manure management systems.

Tier 1 calculation of nitrogen volatilization in the form of NH_3 and NO_x from manure management systems (MMS) is based on multiplying the amount of nitrogen excreted (from all livestock categories) and managed in each MMS by the fraction of nitrogen volatilized (Eq. 10.26 IPCC 2006). Nitrogen losses are then summed over all the MMS (Eq.10.26, Table 10.22, IPCC 2006 Gl.). For estimating indirect N_2O emissions from manure management, the fraction of nitrogen losses due to volatilization and the default indirect factor EF_4 associated with these losses were employed (Table 11.3, IPCC 2006). The fraction of the

total nitrogen volatilized from manure is about 40% of the total nitrogen excreted by all animal categories excluding MMS „pasture".

In cooperation with CARC, a specific value for the proportion of nitrogen from manure that is leached from MMS "solid storage" was estimated. The results of the recent research (Klír et al. 2018) were used for estimating the country-specific $Frac_{leachMS}$ value. The value is 1% of solid manure stored outdoors or in feedlots.

Tier 1 calculation of nitrogen losses due to leaching from MMS is based on Eq. 10.28, IPCC 2006, where the amount of nitrogen from the solid fraction of annual production of manure per animal is multiplied by the percentage of managed manure nitrogen losses for the livestock category (country-specific value) $Frac_{leachMS}$. Emission factors EF_4 and EF_5 from Table 11.3, IPCC 2006 are used in this estimation.

An overview of indirect and direct N_2O emissions estimated during the period 1990–2024 is presented in Tab. 5-39.

Tab. 5-39 Indirect and direct N_2O emissions from manure management [kt N_2O/year], 1990–2024

Year	N_2O emissions of N from manure management [kt N_2O/year]				
	Indirect			Direct	Total N_2O emissions
	Volatilisation IPCC Eq. 10.27	Leaching IPCC Eq. 10.28	Total		
1990	1.61	0.02	1.63	2.05	3.68
1995	1.05	0.01	1.06	1.33	2.39
2000	0.97	0.01	0.98	1.22	2.20
2005	0.85	0.01	0.86	1.04	1.90
2010	0.72	0.01	0.73	0.83	1.57
2015	0.70	0.01	0.70	0.70	1.41
2016	0.71	0.01	0.72	0.70	1.41
2017	0.71	0.01	0.72	0.70	1.43
2018	0.74	0.01	0.75	0.74	1.49
2019	0.72	0.01	0.73	0.71	1.44
2020	0.72	0.01	0.73	0.71	1.43
2021	0.73	0.01	0.74	0.72	1.46
2022	0.72	0.01	0.72	0.71	1.44
2023	0.71	0.01	0.72	0.71	1.43
2024	0.74	0.01	0.75	0.73	1.47

Coordination with the reporting under the Convention on Long - Range Transboundary Air Pollution

Since 2021, the effects of measures to reduce ammonia emissions have been included in the calculations of the national emission inventory of ammonia and NO_X. These are emissions originating from manure management, manure application and mineral fertilizers application.

For Submission 2023, we ensured that the data on AWMS were updated and adjusted with respect to the likely development of manure handling, in particular to remove jump changes in individual management systems shares. The current form of AWMS respects the gradual onset of anaerobic digestion in full compliance with the UN-ECE reporting. It is an important step to complete the harmonization of ammonia and NO_x reporting and nitrous oxide reporting.

Since 2024, as part of the harmonization of the outputs of the national greenhouse gas emission inventory (NID) and pollutant reporting under the Convention on Long-Range Transboundary Air Pollution (IIR),

attention is focused on assessing the impact of measures to reduce ammonia emissions on the production of greenhouse gas emissions, especially on the amount of indirect N_2O emissions from manure management. Cooperation in this field will continue.

5.2.2.3 Uncertainty and time-series consistency

Uncertainty estimates are based on the expert judgment. The uncertainty in the activity data equals 5%. The uncertainty in the emission factor equals 20% for estimation of CH_4 emissions and 30% for the estimation of N_2O emissions. The combined uncertainty for CH_4 emissions equals 20.6% and that for N_2O emissions equals 30.4%.

The time series consistency was negatively affected by unequal development of the individual manure systems distribution. The first expert judgement (Mudřík, Hons 2004) had assumed an important decrease in the proportion of the liquid fraction in the dairy cattle category and a decrease in the proportion of solid fraction in the non-dairy cattle category caused by the change in the technology of cattle breeding from the early 1990s. This expectation had not been met and, until the 2019 submission, the manure distribution retained at its original values. This trend was interrupted by the implementation of new AWMS for the concerned time series in 1990–2023 in Submission 2023 and the folowing.

The determination of the Nex rate also underwent development. A significant change was the transition to country-specific data in 2019. The leap changes in the development of Nex values were implemented since Submission 2023, it fulfilled two objectives - the data was consistent across the time series and was fully harmonized with the input data used to derive national nutrient balance (EUROSTAT, OECD) and ammonia emissions reporting (UN-ECE). There is important progress in harmonization activities mentioned several times in review reports.

5.2.2.4 Source-specific QA/QC and verification

QA/QC includes checking the activity data, emission factors and methods employed. All the differences are discussed and, if necessary, also corrected. The procedure of inventory compiling is initiated by IFER, where all the necessary data, obtained from the Czech Statistical Office (CzSO), are inserted into the Excel spreadsheets and verified by other IFER experts. Country-specific Nex rate data are calculated according to the annexes of the Czech Decree No. 377/2013 Coll. and up to date population data (CzSO) as a weighted average of the individual animal category. The zoo-technical national data is supplied by experts from the agricultural institutes (see above). The appropriate values in the calculation spreadsheets are updated at IFER, replacing the older values. The verified data is transferred to ETF Reporting Tool, where the data is technically verified again. A completeness check of the ETF tables was performed for final time-series approval.

Special attention was paid to the validation of the country-specific animal waste management systems – the proportion of individual management systems was estimated by the experts from CARC as well as nitrogen excretion rate. An example of deriving Nex for pigs is shown in Tab. 5-40.

Tab. 5-40 Example of the derived values of Nex for swine with support of data from Decree No. 377/2013 Coll., data for 2024

Swine category	Population [1 000 heads]	N Production [kg N/head]	Total production [t N]
Pigs <20 kg live weight	398.64	2.10	837
Pigs 20+ and <50 kg live weight	336.37	7.35	2 472
Fattening pigs 50+ and <80 kg live weight	256.66	11.70	3 003
Fattening pigs 80+ and <110 kg live weight	236.56	17.10	4 045
Fattening pigs ≥110 kg	67.68	21.60	1 462

Boars ready to breed	1.41	29.61	42
Covered sows	100.38	31.49	3 161
Sows not covered – total	24.13	12.60	304
Total	1 421.82	10.78 (WA)*	15 326
Relative share [%]			100%

** Calculated as weighted average of N production per listed swine categories*

The emission factor for methane production from manure management is calculated by Tier 2 methods for both cattle categories and swine. The default values of emission factors (Table 10.14, IPCC 2006) are higher than the country-specific ones (Tab. 5-41):

Tab. 5-41 Comparison of methane emission factors for manure management, IPCC 2006 Gl. default and country-specific values (Submission 2026)

Livestock category	CH_4 emission factor for manure management [kg CH_4/head/year]	
	IPCC default value (Table 10.14, IPCC 2006 Gl.)	Country-specific value (Submission 2026)
Dairy cattle	21	12.35
Non-dairy cattle	6	3.63
Market swine	6	1.72
Breeding swine	9	2.64

The nitrogen excretion rate for dairy cattle and other cattle was compared with the default nitrogen excretion rate factors available for the Western Europe region in IPCC 2006 Gl. (Table 10.19). The updated country-specific data based on Decree No. 377/2013 Coll. are close to the default values (Tab. 5-43).

Tab. 5-42 Overview of N rate values, IPCC 2006 default and country-specific values (long-term average and Submission 2026 values)

Cattle category	N rate [kg N/1 000 kg animal mass/day]		
	IPCC default value (Table 10.19, IPCC 2006)	Country-specific value (long-term average)	Country-specific value (Submission 2026)
Dairy cattle	0.48	0.467	0.507
Non-dairy cattle	0.33	0.390	0.390

Tier 2 procedures were used for estimating the VS parameters for cattle. The country-specific values calculated from national input data were compared with the default value available in IPCC 2006 Guidelines (Tables 10A-4 and 10A-5):

Tab. 5-43 Overview of daily volatile solid excreted values, IPCC 2006 default and country-specific values (long-term average and Submission 2026 values)

Cattle category	VS [kg dry matter/head/day]		
	IPCC default value (Table 10A-4/10A-5, IPCC 2006)	Country-specific value (long-term average)	Country-specific value (Submission 2026)
Dairy cattle	5.10	5.18	6.41
Non-dairy cattle	2.66	2.96	3.33

5.2.2.5 Source-specific recalculations, including changes made in response to the review process and impact of emission trends

During the QAQC process, discrepancy was identified between the AWMS proportion performed by CARC and the NID data – the discrepancy related to the proportion of pasture and solid storage in AWMS for the horse category. Until last submission, we reported this proportion of 40% solid manure, 60% pasture, but the correct ratio is 50% solid storage and 50% pasture. Based on the findings, the entire dataset has been

corrected. As a result of the correction, emissions in the direct emission category have increased by 0.350 kt CO_2 eq./year. Overall, emissions from Manure management have increased by 0.1% per year.

For the period 1990 to 2022, livestock data were reported as of April 1 each year. Since the Submission 2025, data as of December 31 each year are only available for cattle, swine and poultry. The data for other livestock categories (goats, sheep, horses) are expected to be available every three years. Therefore, for the current submission, the same data as in 2023 (Submission 2025) have been used for other livestock categories.

During the quality control (QA) process, all input livestock data were checked and corrected according to the latest statistical data available (C_ZSO 2025). Population data have been corrected for sheep (input for 1991, 1992, 2001), horses (1990–2021), swine (2001) and poultry (2001). Changes in population numbers are insignificant and have not significantly affected the emission estimate.

5.2.2.6 Source-specific planned improvements, including tracking of those identified in the review process

The planned update of emission estimates from manure management category was postponed by a year or two due to the complexity of preparing activity data and editing tables. Only a preparatory phase with data relevant to 2024 was carried out. Updating the entire series is time-consuming, requiring additional verification and control.

Interim results:

- The climatic zones prepared for regional specification in the 3.D category can be used for update Methane Conversion Factor (MCF) for cattle and swine.
- The default Methane Emission Factors used for sheep, goats and poultry in Tier 1 estimates retain a comparable value when derived according to the IPCC 2019 methodology. By the same way derived Methane Emission Factor for horses is by about 50% higher (1.56 kg CH_4/animal/year according to IPCC 2006, 2.325 kg CH_4/animal/year according to IPCC 2019). Such a variance must be further verified.
- The first version of the AWMS update (Tab. 5-44) based on the results of sample surveys in agricultural holdings as provided by CARC has not yet yielded sufficient data to update the entire time series.

Tab. 5-44 Share of AWMS in 2024, results of CARC survey among agricultural holdings in Czech Republic (CARC, 2025)

Livestock category	Type of AWMS Fraction of manure N per AWMS [%]					
	Solid storage, uncovered	Solid storage, covered	Liquid system, without natural crust cover	Liquid system, covered	Anaerobic digesters	Pasture
Dairy cattle	54.9	1.9	10.7	0.0	32.5	0.0
Non-dairy cattle	60.1	2.1	6.8		2.6	28.5
Swine	31.4	1.1	18.9		48.6	0.0
Sheep	50.0		0.0		0.0	50.0
Goats	40.0		0.0		0.0	60.0
Poultry	91.9		0.0		8.1	0.0
Horses	50.0		0.0		0.0	50.0

- The table above shows that the CARC targeted survey has not yet been able to obtain data on the covering of liquid slurry storage sites. This data is crucial for the IPCC 2019 emissions estimate, as it significantly affects the $Frac_{gasMS}$ and $Frac_{leachMS}$ values.

Activities supporting the implementation of IPCC 2019 in category 3.B will continue so that we can take advantage of the methodological update as soon as possible.

5.3 Rice cultivation (ETF 3C)

At present, no commercial rice cultivation is being carried out in the Czech Republic. The "NO" notation key is reported in the ETF tables.

5.4 Agricultural soils (CRT 3.D)

5.4.1 Source category description

This source category includes the direct and indirect nitrous oxide emissions from agricultural soils. Both subcategories (direct and indirect emissions) are the key sources of N_2O emissions (Tab. 5-1). Nitrous oxide is produced from agricultural soils because of microbial nitrification and denitrification processes. The processes are influenced by the chemical and physical characteristics (availability of mineral N substrates and carbon, soil moisture, temperature, and pH). Thus, the addition of mineral nitrogen in the form of synthetic fertilizers, animal manure and other organic nitrogen applied to soils, crop residue/renewal and sewage sludge enhance the formation of nitrous oxide emissions.

In connection with the gradual transition of the methodology to a higher level of estimation (Tier 2), emission factors and volatilized and leaching nitrogen fractions included in the estimation of emissions were updated according to IPCC 2019. These changes allow considering the specific climatic characteristics of the regions in the Czech Republic in the estimates.

For estimates of N_2O emissions from the application of nitrogen fertilizers to agricultural land, it is important whether the application takes place in a wet or dry climate zone. The climate classification procedure into individual zones is prescribed by the IPCC (IPCC 2019) for the whole world in Chapter 3, Volume 4 (AFOLU). Data on the average annual temperature, the total amount of precipitation, the number of days with a temperature lower than 0 ^{o}C and the ratio between the annual total of precipitation and potential evapotranspiration are decisive.

To improve some of the N_2O emission estimates experts from CzechGlobe (GCRI) prepared an analysis of climatic conditions in the Czech Republic for the period 1990–2024, which allowed to specify the area of agricultural land belonging to a wet or dry climate zone. The geographical location and topographical complexity of the area mean that climatic conditions change significantly from year to year (Tab. A3 17 in the Annex). This of course has a significant impact on the use of synthetic and organic fertilisers and the amount of greenhouse gas emissions released. The results of the climate analysis and the impact of climate variability on the amount of emissions released have been consulted with both CzechGlobe and CARC experts and have become the basis for joint scientific publication by the entire agriculture sector team (Beranova et al. 2025). In the estimetes of emissions for each year, the share of agricultural land corresponding to wet and dry climate zones was implemeted to calculation of relevant emission factors

(T 11.1, T 11.3 IPCC 2019). The consideration of climatic conditions in the estimation of emissions raised the level of methodology in this category from Tier 1 to Tier 2.

Nitrous oxide emissions from agricultural managed soils include these subcategories:

- Direct emissions (synthetic fertilizers, animal manure applied to soils, crop residues, sewage sludge and other organic fertilizers applied to soils)
- Emissions from pasture manure (PRP)
- Amount of nitrogen mineralized in mineral soils considered for Cropland remaining Cropland and nitrogene from cultivated organic soils.
- Indirect emissions (atmospheric deposition and nitrogenous substances flushed into water courses and reservoirs – leaching).

An overview of direct and indirect emissions by individual sources is presented in Tab. 5-45.

Tab. 5-45 Direct and indirect N_2O emissions from agricultural soils [kt N_2O], 1990–2024

Year	Total emissions	Synthetic fertilizers	Organic fertilizers*	Crop residues	Mineral. soil**	PRP	Atmosph. deposition	Leaching
	[kt N_2O]							
1990	9.9	4.9	1.2	2.0	0.03	0.1	0.9	0.8
1995	10.1	4.8	0.8	1.8	0.03	0.1	0.9	1.7
2000	7.9	4.0	0.7	1.5	0.03	0.1	0.7	0.9
2005	9.5	5.2	0.6	1.4	0.03	0.1	0.8	1.3
2010	12.0	6.7	0.7	1.4	0.03	0.1	1.0	2.1
2015	6.6	3.7	0.6	1.3	0.03	0.1	0.6	0.2
2016	10.1	5.8	0.7	1.6	0.03	0.1	0.8	1.1
2017	10.0	5.9	0.7	1.4	0.03	0.1	0.9	1.1
2018	5.8	3.1	0.6	1.2	0.03	0.1	0.5	0.2
2019	7.3	3.9	0.7	1.4	0.03	0.1	0.6	0.6
2020	9.8	5.2	0.7	1.6	0.03	0.1	0.8	1.4
2021	10.1	5.5	0.7	1.5	0.03	0.1	0.9	1.4
2022	7.7	4.1	0.7	1.4	0.03	0.1	0.7	0.7
2023	7.8	3.9	0.7	1.5	0.03	0.1	0.7	1.0
2024	10.1	5.6	0.7	1.4	0.03	0.1	0.9	1.3

** Animal manure + Sewage sludge + Digestate*

*** Loss of soil C through change in land use + Cultivation of (managed/drained) organic soils (LULUCF sector)*

In 2024, 87% of the total N_2O emissions from agriculture originated from agricultural soils, while the rest originated from manure management (13%). The trend in N_2O emissions from this category is not significant. The lowest emissions were recorded in 2003, 2018 and 1992, the highest emissions in 2010, 2013 and 2001. The difference between the lowest and highest estimated emissions is 6.88 kt N_2O (1 824 CO_2 equivalents).Emissions have fluctuated around an average of 8.85 kt N_2O. Tab. 5-45 and Fig. 5-4 show N_2O emissions from agricultural soils by individual sub-categories. The fluctuation is caused both by the influence of changing climatic conditions and by the unbalanced consumption of synthetic fertilizers.



Fig. 5-4 N_2O emissions from Agricultural soils by individual sub-categories [kt N_2O], 1990–2024

5.4.2 Methodological aspects

Emissions from managed agricultural soils are a key source, the emissions of N_2O are estimated and analysed using the Tier 2 approach of IPCC 2019 Guidelines. The estimation considers the regional climatic conditions of the given year. For several years, a set of interconnected spreadsheets in MS Excel has been used for the relevant calculations. The emissions from nitrogen excreted by livestock on pastures and paddocks were reported under livestock production in the ETF table.

5.4.2.1 Activity data

The standard calculation according to Tier 1/Tier 2 required the following input information:

- Amount of nitrogen applied to soil in the form of industrial nitrogen fertilizers (CzSO data, Statistical Yearbooks, Ministry of Agriculture, CARC, 1990–2024);
- Managed manure nitrogen available for application to soil (NID data, Eq.10.34, IPCC 2006 Gl.);
- Annual yields (harvest/production area) (CzSO data, Statistical Yearbooks, 1990–2024);
- Annual amount of urine and dung N deposited by grazing animals on PRP (NID data, Eq.11.5, IPCC 2006 Gl.) ;
- Amount of sewage sludge applied directly to agricultural soils (CzSO data, Statistical Yearbooks, 2002–2024, retrospective analysis for the period 1990–2001);
- Amount of mineralized N in soils, in association with loss of soil C in the Cropland remaining Cropland category (provided by LULUCF sector);
- N_2O Emissions from area of cultivated organic soils (provided by LULUCF sector);
- Amount of organic nitrogen inputs applied to soil (digestate, compost), statistical survey and CARC analysis and UN-ECE reporting);
- Data on climate distribution (GCRI data).

In the previous NID, for the first time, the original Climatic Zone layer (IPCC 2006) was updated with country specific data and provided in much higher spatial and temporal resolution and included also more advanced method of PET computation. Climate data are based on daily weather dataset (1961-present) that are collected by the CHMI in the national station network which after quality control checks and detection of outliers constitutes up to 800 precipitation stations and almost 200 climate stations that collect minimum and maximum air temperature, mean relative air humidity, global radiation or sunshine duration, and wind speed data. The daily data are interpolated to regular 500x500 m grid by a regression via kriging, which uses geographical coordinates, elevation and other terrain characteristics as predictors. In the Czech Republic, the average minimal distance between two neighbouring stations is approximately 22 km for elements measured at climatological stations and less than 10 km for those measured at precipitation stations. The daily incident solar radiation for each grid accounts for slope, aspect and horizon obstruction using the methodology proposed and tested by Schaumberger (2005). The PET calculation is based on the Penman-Montheith formula, as suggested by Allen et al. (1998), and carried through the means of the SoilClim model (Hlavinka et al., 2011, Trnka et al., 2020). For each year the daily PET totals are summed up as well as precipitation. For the puproses of the inventory the wet grids are defined as those where ratio of total annual precipitation to total annual PET is greater or equal to 1. As dry are defined those with the same ratio below 1. This procedure allows to account for the conditions in individual years as there is a significant difference in the extent of wet and dry areas among individual years (Fig. A3 23 and Tab. A3 18 in the Annex A 3.8 of this report). This constitutes significant improvement compared to the original 5 arc seconds CRU Climate Research Unit) climatology.

5.4.2.2 Direct emissions from managed soils (ETF 3.D.1)

The emission factors used for the calculation of the direct N_2O emissions are shown in Tab. 5-46. The IPCC 2019 Guidelines default values suitable for wet and dry climate are used to estimate direct N_2O emissions.

Tab. 5-46 Emission factors for estimating direct emissions from managed soils (Table 11.1, IPCC 2019).

	Emissions source	Wet climate condition	Dry climate condition
Direct emissions	Synthetic fertilizers	EF_1 = 0.016 kg N_2O-N/kg N	EF_1 = 0.005 kg N_2O-N/kg N
	Animal waste, digestate	EF_1 = 0.006 kg N_2O-N/kg N	EF_1 = 0.005 kg N_2O-N/kg N
	Sewage sludge	EF_1 = 0.006 kg N_2O-N/kg N	EF_1 = 0.005 kg N_2O-N/kg N
	N-crop residues	EF_1 = 0.006 kg N_2O-N/kg N	EF_1 = 0.005 kg N_2O-N/kg N
	Mineralized N	EF_1 = 0.006 kg N_2O-N/kg N	EF_1 = 0.005 kg N_2O-N/kg N
	Cultivated organic soils	EF = 8.2 kg N_2O-N/ha/year	
Pasture, range & paddock manure	Cattle, swine, poultry	EF_3 = 0.004 kg N_2O-N/kg N	EF_3 = 0.004 kg N_2O-N/kg N
	Sheep, others	EF_3 = 0.003 kg N_2O-N/kg N	EF_3 = 0.003 kg N_2O-N/kg N

5.4.2.2.1 Synthetic N fertilizers (FSN, ETF 3.D.1.a)

The application of agricultural fertilizers had been formerly intense in the Czech Republic but decreased radically after 1990. The activity data is taken from the official statistical source (CzSO) and data inputs to Nitrogene Balance of the Czech Republic prepared by CARC. The amount of nitrogen fertilizers applied in 1990 equalled more than 418 kt, which decreased to 180 kt in 1993. From that year, nitrogen consumption slowly grew to 407 kt in 2016 (the highest value). This negative trend ended in 2017. Consumption decreased in 2023 (237 kt) but returned to the level of previous years in 2024 (329 kt).

Low consumption of sythetic fertilizers in the Czech Republic during 1991–1993 was primarily associated with the transition from a centrally planned economy to a market economy after 1989. It resulted from a combination of economic, institutional, and structural changes.

Following price liberalization in the early 1990s, input prices—including fertilizers—rose significantly. Agricultural enterprises suddenly had to purchase these inputs at market prices without state subsidies,

which led to a substantial reduction in their use. At the same time, the system of state subsidies and support was dismantled. Under the socialist regime, fertilizers had been heavily subsidized, but after 1990 these supports were rapidly reduced or completely abolished, making it financially difficult for many enterprises to maintain previous application levels.

The transformation of the agricultural sector also played a crucial role. The dissolution of collective farms (JZDs) and state farms, combined with property restitution and the emergence of new private farms, introduced a high degree of uncertainty and led to a decline in investment. Newly established entities often adopted more cautious management strategies and sought to minimize costs, including expenditures on fertilizers.

In parallel, livestock production declined significantly. The reduction in livestock numbers decreased the demand for feed, which in turn reduced the intensity of crop production and lowered the demand for fertilizers. Moreover, both domestic and international markets were undergoing substantial changes, resulting in decreased demand for certain agricultural commodities. This weakened the pressure to achieve high yields and consequently reduced the need for intensive fertilizer use.

Financial constraints further exacerbated the situation. Many agricultural enterprises faced a shortage of capital and serious cash flow problems, forcing them to limit purchases of costly inputs such as fertilizers. At the same time, farming practices shifted toward more extensive systems of production. This temporary extensification of agriculture was characterized by lower input intensity, including reduced fertilizer application rates.

It is possible to say that the low consumption of fertilizers during this period was not driven by a single factor but rather reflected a broader economic shock and the comprehensive restructuring of agriculture after 1989, particularly due to rising input prices, the removal of subsidies, and pervasive uncertainty within the sector. Recent fluctuations in the consumption of mineral N-fertilizers depends mainly on the price of fertilizers. Consumption in 2023 was extremely low, because fertilizers were expensive. The usual and "reasonable" average consumption in the Czech Republic is around 90 kg N/ha of used agricultural land, given the yield level, production quality requirements (higher protein content in food wheat grain) and nitrogen supply from other sources (organic matter, symbiotic N fixation). The actual trend is presented in Fig. 5-5.



Fig. 5-5 Consumption of nitrogen from synthetic fertilizers [kt N], 1990–2024

5.4.2.2.2 Organic N applied as fertilizer (FON incl. animal manure and sewage sludge, digestate, ETF 3.D.1.b)

The amount of managed manure nitrogen available for application to managed soils (F_{AM}) is calculated as the product of the annual average N excretion per animal per species and the fraction of the manure management system and (1 – $Frac_{lossMS}$). The default value of the fraction $Frac_{lossMS}$ is given in Table 10.23, Equations 10.34 and 11.4 (IPCC 2006).

The data on sewage sludge applied to soils has been officially available since 2002. The data for the previous period was estimated by statistical methods. Specifically, linear regression was used to estimate the trend from known activity data from 2003 to 2016 (r^2 = 0.62). This trend was used to estimate the missing AD from 1990. The regressed values are not used in the period where AD is available from CzSO. The country-specific value of nitrogen content of 3.7% (Černý et al. 2009) and default emission factor (EF_1, Table 11.1., IPCC 2019) were employed for estimating the emissions from sewage sludge (F_{SEW}).

Implementation of the anaerobic digestion in AWMS was also reflected in N_2O emissions from managed soils. The corresponding amount of animal manure available for managed soils was reduced, but, on the other hand, a new source of nitrogen was added as "Other organic fertilizers applied to soils" – digestate and or compost (F_{OOA}). The amount of digestate is estimated as a share of total digestate produced by the biogas station. The share corresponds to the amount of manure used for biogas production (Klír 2021).

The total amount of organic N fertilizer applied to soils (F_{ON}) is calculated as the sum of F_{AM} + F_{SEW} + F_{OOA}. An overview of activity data inputs is presented in Tab. 5-47.

Tab. 5-47 Activity data inputs to calculation of F_{ON}: annual amount of animal manure N (FAM), annual amount of sewage sludge N (F_{SEW}) and annual amount of digestated N and compost N (F_{OOA}) [t N/year], 1990–2024

Year	F_{AM}	F_{SEW}	F_{OOA}	F_{ON}
		[t N/yr]		
1990	144 347	253	0	144 600
1995	91 582	656	0	92 238
2000	82 908	1 059	0	83 967
2005	71 818	1 275	785	73 878
2010	59 762	2 244	7 474	69 480
2015	54 008	2 333	21 630	77 971
2016	53 556	2 314	21 835	77 706

Year	F_{AM}	F_{SEW}	F_{OOA}	F_{ON}
		[t N/yr]		
2017	54 045	2 792	21 865	78 702
2018	56 121	3 289	21 857	81 267
2019	54 669	3 355	21 941	79 964
2020	54 350	2 333	21 951	78 634
2021	55 334	2 445	21 952	79 731
2022	54 505	2 341	21 925	78 771
2023	54 253	2 341	21 902	78 496
2024	55 852	2 618	21 920	80 390

5.4.2.2.3 Urine and dung N deposited on pasture by grazing animals (FPRP, ETF 3.D.1.c)

The annual amount of N deposited by grazing animals on pasture, range and paddock soils was estimated using Eq. 11.5 (IPCC 2019) based on the number of animals of each livestock species, the annual average amount of N excreted by each livestock species and the fraction of this N deposited on pasture, range and paddock soils by each livestock species. The data needed for this estimation can be obtained from the estimation of nitrogen content in AWMS and the share of PRP in the relevant livestock category. The trend of the development of the total amount of nitrogen from pasture was the steady state for the whole reporting period, while the trend of total excreted N decreased rapidly because of the substantial changes in the livestock population (Fig. 5-6 and .

Tab. 5-48).

There are insufficient data to estimate the distribution of animals on pasture within the Czech Republic. It follows from climate analysis that both a wet and a dry climate zone must be considered. Therefore, the default value of the emission factor EF_3 is used to estimate emissions in this category. Two default emission factors (Tab. 5-49) are used for estimating emissions from different animal categories (Table 11.1, IPCC 2019).

Tab. 5-48 Development of the amount of N and emissions from urine and dung from grazing animals, 1990–2024

Year	F_{PRP} cattle, swine, poultry	F_{PRP} horses, goats, sheep	Total F_{PRP}	N_2O missions
		[t N/yr]		[kt/year]
1990	17 600	2 969	20 570	0.125
1995	16 564	1 495	18 059	0.111
2000	14 182	1 172	15 354	0.095
2005	13 272	1 255	14 528	0.089
2010	15 582	1 823	17 405	0.107
2015	14 665	2 114	16 779	0.102
2016	15 054	2 010	17 064	0.104
2017	15 935	2 072	18 007	0.110
2018	16 981	2 109	19 090	0.117
2019	16 682	2 120	18 802	0.115
2020*	16 392	2 100	18 492	0.113
2021	16 629	1 857	18 486	0.113
2022	17 074	1 904	18 978	0.116
2023	16 840	1 928	18 769	0.115
2024	17 490	1 934	19 424	0.119
Relative difference 2024/1990 [%]	1%	35%	6%	4%



Fig. 5-6 Trend of total amount of nitrogen excretion from AWMS and nitrogen excretion from pasture, 1990–2024

The fraction of livestock N excreted and deposited onto soils during grazing ($Frac_{graz}$) varied from 0.073 in 1990 to 0.143 in 2024.

Tab. 5-49 IPCC default emission factors for animal waste management system: pasture, range and paddock (PRP), (T 11.1, IPCC 2019)

AWMS	EF_3 [kg N_2O-N per kg N excreted]
PRP (cattle, swine, poultry)	0.004
PRP (sheep, others)	0.003

5.4.2.2.4 N-crop residues (FCR, ETF 3.D.1.d)

This category includes the amount of N in crop residues (above-ground and below-ground), including the N of N-fixing crops returned to soils annually. It also includes the nitrogen from N-fixing and non-N-fixing forages mineralized during forage or pasture renewal and straw used for bedding. A part of crop residues is used in biogas stations for energy production, and it is returned to the field as a digestate. This amount is reported in this chapter as well.

N-crop residues were estimated from crop yield statistics (CzSO) and the default factors for above/below-ground residues: yield ratios and residual N contents (see Tab. 5-52). The zero values were applied as parameters $Frac_{remove}$ (excluding grains and green maize for which the country specific data are available) and $Frac_{burn}$, because no survey data is available from experts in the country as required on page 11.14, IPCC 2019.

An overview of the annual yield of agriculture products is presented in Tab. 5-50 and Tab. 5-51. The 2024 yield of agricultural products was lower compared to the same data for the previous year 2021 - 2023.

Since different crop types vary in residues, yield ratios, renewal time and nitrogen contents, separate calculations were performed for major crop types and then the nitrogen values for all the crop types were summed. Crops were segregated into: 1) non-N-fixing grain crops, 2) N-fixing grains and pulses, 3) potatoes, 4) sugar beets, 5) N-fixing forage crops (alfalfa, clover) 6) soya and 7) rape. Eq. 11.6 was used for estimating N from crop residues and forage/pasture renewal for the Tier 1 approach. The default values of input factors and country-specific value of the dry matter content used in the estimation are presented in Tab. 5-52.

For nitrogen sources from plant residues, the 1-$Frac_{remove}$ coefficient was newly adjusted for grains and green-harvested corn. An estimate of 10% of cereal straw is taken from the field for feed, and 10% of the straw is leaving agriculture entirely for bioenergy (to be burned). Thus, 80% of the straw of cultivated cereal remains on the soil in the form of bedding manure. In the case of green maize, 60% of the grown biomass is used for silage (feeding). The rest, i.e. 40%, is taken to BGS and returned to the soil in the form of digestate. This modification was proposed by experts from CARC where the same procedure is used for EUROSTAT/OECD reporting (Tab. 5-52, Tab. 5-53).

Tab. 5-50 Annual yield of agricultural products, 1990–2024

Year	Grains	Pulses	Potatoes	Sugar beet	Soya beans	Rape
			[t/ha]			
Average crop area (ha)	*1 503 743*	*43 477*	*46 831*	*73 232*	*8 148*	*309 418*
1990	5.42	2.68	16.00	33.89	3.67	2.43
1995	4.17	2.38	17.04	39.63	1.29	2.43
2000	3.92	2.09	21.32	45.62	1.25	2.61
2005	4.81	2.44	28.08	53.31	2.04	2.88
2010	4.71	1.86	24.56	54.36	1.69	2.79
2015	5.83	2.89	22.26	59.38	1.64	3.43
2016	6.36	2.37	29.88	67.81	2.64	3.46
2017	5.50	2.34	29.42	66.56	2.41	2.91
2018	5.21	2.26	25.50	54.96	1.66	3.43
2019	5.65	2.20	27.19	61.84	2.27	3.05
2020	6.04	2.46	29.16	61.51	2.33	3.38
2021	6.11	2.60	29.44	67.69	2.61	2.99
2022	5.93	2.72	30.22	69.64	2.30	3.39
2023	6.07	2.15	27.39	65.20	2.39	3.45
2024	5.75	1.65	28.82	69.56	2.60	2.76

Tab. 5-51 Annual yield of fodder [t/ha] including total crop area, 1990–2024

Year	Fodder dry matter	Silage maize fresh matter	Perennial fodder fresh matter	Annual Fodder fresh matter	Total area
	[t/ha]				[ha]
1990	6.77				1 099 907
1995	6.13				872 494
2000	5.60				725 252
2005	6.20				491 881
2010	6.05				406 450
2015		30.84	6.16	19.02	458 266
2016		39.52	7.42	22.20	484 835
2017		34.50	6.55	17.11	465 391
2018		29.88	5.50	14.77	468 328
2019		35.63	5.94	17.91	498 628
2020		37.62	6.42	20.42	515 335
2021		38.86	6.29	16.99	495 292
2022		35.96	6.28	17.19	467 085
2023		32.25	6.04	16.23	464 596
2024		31.87	5.76	17.69	485 784

Tab. 5-52 Default values of input factors used for estimating F_{CR} (Table 11.2, IPCC 2006 and 2019), calculated data (Submission 2026)

	Grains	Pulses	Potatoes	Sugar beets	Soya beans	Rape*
Dry mater (CS)	0.85	0.85	0.22	0.22	0.91	0.91
R_{AG}, calculated	1.27	2.10	0.27	0.40	2.10	1.50
AG_{DM}, calculated	6.21	2.44	1.69	2.59	3.55	3.76
$Frac_{remove}$ (CS)	0.200	0.0	0.0	0.0	0.0	0.0
N_{AG}	0.006	0.008	0.019	0.019	0.008	0.011
R_{BG}-BIO	0.499	0.520	0.253	0.234	0.449	0.475
N_{BG}	0.009	0.008	0.014	0.014	0.008	0.017

Note: Parameters R_{AG} and AG_{DM} are calculated by using Eq. 11.6 and 11.7A (IPCC 2019) and adequate parameters.
** Input data for rape are derived from Edwards et al., 2019.*

Tab. 5-53 Default value of input factors used in estimation of fodder (Table 11.2, IPCC 2006), calculated data (foder dry matter 2014, silage maize and perennial and annual fodder, Submission 2026)

	Fodder dry matter 2014	Silage maize fresh matter	Perennial fodder fresh matter	Annual fodder fresh matter
Dry mater (CS)		0.35	0.85	0.17
R_{AG}, calculated	0.30	0.30	0.30	0.30
AG_{DM}, calculated	2.29	3.35	1.47	0.90
$Frac_{remove}$ (CS)	0.0	0.6	0.0	0.8
N_{AG}	0.027	0.027	0.027	0.027
R_{BG}-BIO	0.52	0.442	0.502	0.520
N_{BG}	0.022	0.022	0.022	0.022

Note: The parameters R_{AG} and AG_{DM} are calculated by using Eq. 11.6 and 11.7A (IPCC 2019) and adequate parameters.

Data on crop yield statistics (yields and area harvested, by crop) was obtained from national sources (CzSO). Since yield statistics for many crops are reported as field-dry or fresh weight, a correction factor was employed to estimate dry matter yields where appropriate (Eq. 11.7). The default values for dry matter content from Table 11.2 were employed or country specific data if available. Only forage production activity data is presented as dry matter in the CzSO statistics.

Since 2015, CzSO has also been providing data on maize that is harvested green and used as fodder. For this reason, since 2015, the fodder data has been divided into green maize, perennial fodder and annual fodder crops.

5.4.2.2.5 Mineralization/Immobilization Associated with Loss of Soil Organic Matter (FSOM, ETF 3.D.1.e)

The annual amount of N in mineral soils that are mineralised because of the loss of soil carbon from soil organic matter (F_{SOM}), is a result of land-use changes or management practices. The emission of N_2O associated with soil disturbance during land-use changes are estimated in the LULUCF sector (see chapter 6.5.2.2).

N_2O emissions from mineralisation due to management changes on Cropland remaining Cropland are calculated using Eq. 11.8 (IPCC 2006), employing a default emission factor of 0.01 kg N_2O-N/kg N (EF_1, IPCC 2006), and C:N ratio of 10. The activity data are represented by the carbon loss under subcategory 4.B.1 Cropland remaining Cropland (ETF Table 4.B.1) due to mineralization. That amount of carbon loss in category 4.B.1 is based on the detailed land-use change matrices and carbon maps, in connection with the set of emission factors applicable to seven crop subcategories. For this NID 2026 Submission the above source activity data were recalculated in the LULUCF sector for the entire reporting period. Therefore, they

also affected the estimates of N_2O emissions from N mineralization/immobilization, which were accordingly recalculated for the entire reporting period since 1990.

Tab. 5-54 Overview of activity data and N_2O emissions from loss of soil organic matter (F_{SOM})

Year	Net carbon stock change in soils CL/CL [kt C]	Conversion C to N (DV 10) [kg N]	N_2O emission [kt N_2O]
1990	0.13	NO	NO
1991	0.01	NO	NO
1992	-0.06	5 613	0.000053
1993	0.03	NO	NO
1994	0.07	NO	NO
1995	0.08	NO	NO
1996	0.10	NO	NO
1997	0.10	NO	NO
1998	0.18	NO	NO
1999	0.17	NO	NO
2000	0.18	NO	NO
2001	0.14	NO	NO
2002	0.04	NO	NO
2003	-0.37	37 364	0.000352
2004	-0.64	63 949	0.000603
2005	-0.84	84 366	0.000795
2006	-0.91	90 614	0.000854
2007	-0.91	90 966	0.000858
2008	-0.94	94 216	0.000888
2009	-0.65	64 624	0.000609
2010	-0.65	65 201	0.000615
2011	-0.47	46 910	0.000442
2012	-0.27	27 331	0.000258
2013	-0.37	37 440	0.000353
2014	-0.42	42 057	0.000397
2015	-0.53	52 598	0.000496
2016	-0.57	57 220	0.000539
2017	-0.47	47 356	0.000447
2018	-0.40	39 603	0.000373
2019	-0.13	13 437	0.000127
2020	0.15	NO	NO
2021	0.59	NO	NO
2022	1.11	NO	NO
2023	1.83	NO	NO
2024	2.55	NO	NO

Note: NO = no net loss of soil carbon from soil carbon in the given year

5.4.2.2.6 Cultivation of organic soils (FOS, ETF 3.D.1.f) 3.D.1.f. Cultivation of organic soils

In this submission, greenhouse gas emissions from drained organic soils are newly reported. Their estimation was carried out based on the suggested technical correction by the EEA review in 2025. The vast majority of emissions from drained organic soils (all emissions from peatlands on forest land, CO_2 and CH_4 emissions from drained organic soils on agricultural land) are reported within the LULUCF sector; only the corresponding N_2O emissions from cultivated organic soils on agricultural land (cropland or grassland

categories) are reported in accordance with IPCC (2006) Guidelines in the sector Agriculture under category 3.D.1.

Regarding agricultural land, organic soils in the Czech Republic are located only in the Grassland category, not Cropland. Their total area (12 698 ha) was determined based on data from Research Institute for Soil and Water Conservation (VÚMOP), as was the assumed proportion of their drainage (20%) – see the LULUCF chapter for more details.

The N_2O emissions from drained organic soils are estimated using Eq. 2.7 (Wetlands Supplement, 2013) with default emission factors for deep-drained, nutrient-rich Grassland in the temperate zone (8.2 kg N_2O-N/ha/year, Table 2.5).

The resulting estimates of annual emissions from Grassland are 32.7 kg N_2O for 2024 (Tab. 5-55).

Tab. 5-55 Direct emissions from cultivation of organic soils (F_{OS}) 1990-2024

Parameters/Fractions	Area of cultivated organic soils [ha]	EF_2 IPCC 2013, default [kg N_2O-N/ha/yr]	N_2O emission [kt N_2O/yr]
1990-2024	2 539.60	8.2	0.03272456

5.4.2.3 N_2O emissions Indirect emissions from managed soils (ETF 3.D.2)

In addition to the direct emissions of N_2O from managed soils that occur through a direct pathway (i.e. directly from soils to which N is applied), emissions of N_2O also take place through two indirect pathways. The first of these ways is the volatilization of N as NH_3 and oxides of N (NO_x), and the deposition of these gases and their products NH_4^+ and NO_3^- onto soils and the surface of lakes and other waters.

The method for estimating indirect N_2O emissions includes two emission factors (Tab. 5-57): one associated with volatilized and re-deposited N (EF_4), and the second associated with N lost through leaching/runoff (EF_5). The overall value for EF_5 equals 0.0075 kg N_2O-N/kg N leached/ in runoff water. The method also requires using values for the fractions of N that are lost through volatilization ($Frac_{gasF}$ and $Frac_{gasM}$) or leaching/runoff ($Frac_{leach}$). The default values of these fractions are presented in Tab. 5-56.

Tab. 5-56 IPCC default parameters/fractions used for estimating indirect emissions (Table 11.3, IPCC 2019, methods in Annex 11A.9.)

Parameters/Fractions	Default value
$Frac_{gasM}$ (volatilization from organic N fertlizers and PRP)	0.21
$Frac_{gasF}$ (volatilization from synthetic N fertilizers	0.11
$Frac_{leach-(H)}$ – wet climate	0.24
$Frac_{leach-(H)}$ – dry climate	0

The estimation considers the regional climatic conditions of the given year, and the different emissions factors were used for relevant share of agricultural land.

Tab. 5-57 Emission factors (EFs) used for estimating indirect emissions (T 11.3, IPCC 2019)

Indirect emissions, wet climate zone	Atmospheric Deposition	EF_4 = 0.014 kg N_2O-N per kg emitted NH_3 and NO_X
	Nitrogen Leaching	EF_5 = 0.011 kg N_2O-N per kg of leaching N
Indirect emissions, dry climate zone	Atmospheric Deposition	EF_4 = 0.005 kg N_2O-N per kg emitted NH_3 and NO_X
	Nitrogen Leaching	EF_5 = 0.011 kg N_2O-N per kg of leaching N

Volatilization

The N_2O emissions from atmospheric deposition of N volatilized from managed soils are estimated using Equation 11.9. The equation inputs are estimated for direct emissions from managed soils. The inputs are the annual amount of synthetic fertilizer N applied to soils, the annual amount of managed animal manure, sewage sludge N and other organic N applied to soils, the annual amount of urine and dung N deposited by grazing animals. The conversion of N_2O-N emissions to N_2O emissions for reporting purposes is performed using factor 44/28.

Leaching/Runoff

The N_2O emissions from leaching and runoff in regions where leaching and runoff occur are estimated using equation 11.10, IPCC 2006 Guidelines. The equation inputs are estimated for direct emissions from managed soils, where FON also includes sewage sludge inputs. The inputs are the annual amount of synthetic fertilizer N applied to soils, the annual amount of managed animal manure, sewage sludge N and other organic N applied to soils, the annual amount of urine and dung N deposited by grazing animals, the amount of N in Crop residues and the annual amount of N mineralised in mineral soils. The conversion of N_2O-N emissions to N_2O emissions for reporting purposes is performed using factor 44/28.

An overview of estimated values of indirect emissions is presented in Tab. 5-45.

5.4.3 Uncertainty and time-series consistency

In relation to the consistency of the emission series for N_2O (agricultural soils), it should be mentioned that the emission estimates have been calculated according to the default methodology of IPCC 2019. But all recent input data are harmonized with other national “nitrogen” reporting.

The quantitative overview and emission trends during the 1990–2024 period are shown in Fig. 5-1 and the trend in N_2O emissions from agricultural soils is summarized in Tab. 5-45. During 1990–2024, the total emissions from Agricultural soils decreased by 43% (with the minimum in 2003 when dry climate conditions covered 94% of agricultural land).

The changes in AWMS and Nex that were prepared for Submission 2023 and folowing led to the elimination of jump changes in time series and in the same way affected the inputs to the calculation of direct and indirect emissions from organic fertilizers.

Uncertainty estimates are based on expert judgment. The uncertainty in the activity data for estimation of direct and indirect emissions from agricultural soils equals 20%; this value equals 10% for Pasture, Range and Paddock Manure (PRP). The uncertainty in the emission factor for the estimation of direct and indirect emissions from agricultural soils equals 50%; this value equals 100% for the estimation of emissions from PRP. The combined uncertainty for the direct and indirect emissions from agricultural soils equals 53.9%; this value equals 100.5% for N_2O emissions from the manure management system PRP.

Missing data about the amount of sewage sludge applied to agricultural soils were added to the reported time series thanks to a statistical retrospective analysis of the available data about sewage sludge production for the previous submission (see Chapter 5.4.5., NIR 2018). The including of nitrogen from compost among organic fertilizers is the next step to harmonization of input data with UN-ECE reporting and NID. CARC provides this data biannually.

5.4.4 Source-specific QA/QC and verification

A detailed description of source-specific QA/QC and inventory verification of agriculture is presented in section 5.1.3. Inventory in this subcategory is based on Tier 1 procedures and methods because there is a lack of relevant country specific factors.

For a better understanding of how to calculate direct and indirect emissions from Managed soils, the FAO e-learning course: National GHG inventory for agriculture sectors was studied and NID reports of neighbourhood European countries as well.

As a result of the validation of activity data with CARC experts, the quantity of mineral fertilizers used in managed soils has been updated since 2000. Data on fertilizer consumption for FAOSTAT and other international reporting are provided by the Ministry of Agriculture, Department of Agricultural Commodities (Ms. Budňáková).

A workshop of experts involved in NID (IFER), IIR reporting (Dr. Dedina, CARC) and EUROSTAT reporting (Dr. Wollnerová, CARC) has happened regularly every 3 months. There is a platform for the exchange of information and data between relevant experts and share experiences.

In the frame of the research project "Development of the methodologies for reporting and projections of greenhouse gas emissions and removals including projections of usual pollutants" funded by The Technological Agency of the Czech Republic (TACR) a separate output summarizing the issue of reporting nitrous oxide emissions from the agricultural sector (3.D emissions from the management of agricultural land) was prepared based on findings and analyzes processed in the years 2019–2023. In addition, the possibility of creating a unified national nitrogen flow balance in agriculture was analyzed (Beranova 2022b). The requirements of IPCC GL 2006 and 2019 were analyzed in detail to link the reporting of air pollutants (ammonia, nitrogen oxides) carried out under the Economic Commission of the United Nations (UN-ECE) with the reporting of greenhouse gases (nitrogen oxide). Furthermore, the status of the implementation of the national nitrogen balance, which is being prepared for EUROSTAT in the reporting of nitrogen substances with the agricultural sector, was described, and the steps that were implemented during the project solution in the field of harmonization of inputs for international reporting in the field of nitrogen flow in agriculture were described in detail. The report is written in Czech, and it is available in CHMI.

During 2023, the comparison of calculation of typical specific greenhouse emissions gases from agricultural cultivation and processing on regional level (NUTS 2 and NUTS) was prepared for scientific output (certified methodology) (Dedina 2023).

5.4.5 Source-specific recalculations, including changes made in response to the review process and impact of emission trend

A close cooperation with the experts from CARC and GCRI helped to realize an important upgrade to the category of 3.D Emissions from Managed Soils. We thereby followed up on the methodological update starting in Submission 2024 when we implemented the methodological procedures of the IPCC 2019, including the values of the emission factors EF_1 and EF_4 and the fractions of nitrogen that leach and volatilize, into the estimation of emissions. Since Submission 2025 the climate zonation was used for emissions estimates in category 3.D. The effect of this significant change on the emission estimate is described in detail in the NID 2025.

According to the recommendation of TERT ID CZ-3D2-2025-0001, a revision of the estimate of N_2O emissions of category 3.D.2.b from N Leaching and Run-off for the years 1990-2023 has been carried out. In Submission 2025, there was calculated incorrectly that 24% ($Frac_{leach-(H)}$) of the N input from 3.D category (inorganic and organic fertilizers, urine and dung deposited by grazing animals, crop residues,

mineralization/immobilization associated with loss/gain of soil organic matter) is leached. This aligns with the 2019 IPCC default value for wet climates or areas with irrigation (excluding drip irrigation). Refined map and data information on ratio of wet and dry area in the country, showing that a varying ratio of the country has been considered as dry climate across the years. Due to a technical error, climatic factors were not considered when determining $Frac_{leach-(H)}$ before. Considering climatic regions has led to a reduction in emissions in the category by 53.5% on average, i.e. 341 kt CO_2 eq./year, which is less than 5% of the total emissions from the sector Agriculture. An overview of $Frac_{leach-(H)}$ values considering the climatic zonation each year is given in Tab. 5-58.

Tab. 5-58 Overview of $Frac_{leach-(H)}$ values considering the climatic zonation, 1990-2024

Year	Wet area, share [%]	Dry area, share [%]	$Frac_{leach-(H)}$
1990	22.1	77.9	0.05
1995	75.9	24.1	0.18
2000	42.7	57.3	0.10
2005	57.8	42.2	0.14
2010	98.6	1.5	0.24
2015	8.7	91.3	0.02
2016	36.9	63.1	0.09
2017	39.9	60.1	0.10
2018	6.0	94.0	0.01
2019	22.7	77.3	0.05
2020	59.4	40.6	0.14
2021	57.2	42.8	0.14
2022	27.4	72.6	0.07
2023	48.5	51.5	0.12
2024	53.5	46.5	0.13
1990–2024	46.7	53.3	0.11



Fig. 5-7 Comparison of N_2O emission estimates (Submission 2025 and recalculated data / Submission 2026) from Leaching and runoff from managed agricultural soils [kt CO_2 eq.], 1990-2024

The other improvements have had an unsignificant impact to the total emissions:

Mineralization/Immobilization Associated with Loss of Soil Organic Matter (F_{SOM}, ETF 3.D.1.e)

N_2O emissions from mineralisation due to the management changes on Cropland remaining Cropland are calculated using Eq. 11.8 (IPCC 2006), employing a default emission factor of 0.01 kg N_2O-N/kg N (EF_1, IPCC 2006), and C:N ratio of 10. The activity data are represented by the carbon loss under subcategory 4.B.1. Cropland remaining Cropland (CRT 4.B.1) due to mineralization. These carbon loss estimates in category 4.B.1 are based on the detailed land-use change matrices and carbon maps, paired with the set of emission factors applicable to seven crop subcategories. In this Submission the above source activity data have been recalculated in the LULUCF sector for the entire reporting period. Therefore, they have slightly affected also the estimates of N_2O emissions from N mineralization/immobilization, which have been recalculated accordingly for the entire reporting period since 1990.

Cultivation of Organic Soils (F_{OS} ETF 3.D.1.f)

In this submission, greenhouse gas emissions from drained organic soils have been newly reported. Their estimation has been carried out based on a technical correction prepared by the EU review team as a part of the last year's NID (2025). The vast majority of emissions from drained organic soils (all emissions from peatlands on forest land, CO_2 and CH_4 emissions from drained organic soils on agricultural land) are reported within the LULUCF sector; only the corresponding N_2O emissions from cultivated organic soils on agricultural land (Cropland or Grassland categories) have been reported in accordance with IPCC (2006) Guidelines within the sector Agriculture under category 3.D.1.

Regarding the agricultural land, organic soils in the Czech Republic are only located in the Grassland category, not Cropland. Their total area (12.698 ha) has been determined based on the data from the Research Institute for Soil and Water Conservation (VÚMOP) as has been the assumed proportion of their drainage (20%) – see the LULUCF chapter for more details.

N_2O emissions from drained organic soils are estimated using Eq. 2.7 (Wetlands Supplement, IPCC 2013) with the default emission factors for the deep-drained, nutrient-rich Grassland in the temperate zone (8.2 kg N_2O-N/ha/year, Table 2.5.1 IPCC 2013).

The average annual N_2O emissions from drained organic soils in the land-use category Grassland remaining Grassland (4.C.1), calculated over the entire reporting period since 1990, has been 32.7 kg N_2O-N/ha/year. This change has caused the increase of the estimated emissions by 8.67 kt CO_2 eq. per year, which is 0.1% of the total reported emissions from Agriculture sector per year.

Nitrogen excreted on pasture and paddock (ETF 3.D.1.c)

The decrease in the ratio of nitrogen excreted by horses on pasture and paddock has caused a slight decrease in emissions from grazing, by approximately 0.265 kt CO_2 per year.



Fig. 5-8 Comparison of N_2O emission estimates (Submission 2025 and recalculated data / Submission 2026) from Pasture, range and paddock category from horses [kt CO_2 eq.], 1990-2024

5.4.6 Source-specific planned improvements, including tracking of those identified in the review process

Since 2024, the team cooperates with the AdAgriF project "Advanced methods of greenhouse gases emission reduction and sequestration in agriculture and forest landscape for climate change mitigation" (CZ.02.01.01/00/22_008/0004635), funded by Ministry of Education and coordinated by GCRI (prof. Trnka). The aim of the cooperation is to gradually increase the methodological level of estimates in 3.D category.

5.5 Prescribed burning of savannas (CRT 3.E)

This activity is prohibited by the Czech Legislation (Air Protection Act), and thus, prescribed burning of savanna does not occur in the Czech Republic.

5.6 Field burning of agricultural residues (CRT 3.F)

This activity is prohibited by the Czech Legislation (Air Protection Act), and thus, field burning of agricultural residues does not occur in the Czech Republic.

5.7 Liming (CRT 3.G)

5.7.1 Source category description

Liming is used to reduce soil acidity and to improve plant growth in managed systems, particularly agricultural soils, and managed forests. Adding carbonates to soils in the form of lime (e.g. limestone or

dolomite) leads to CO_2 emissions as the carbonate lime dissolves and releases bicarbonate, which decomposes to CO_2 and water. Liming on all the managed soils is reported under this category, i.e. arable lands, grasslands, and forest lands.

5.7.2 Methodological aspects

However, the reactions associated with limestone application also led to the evolution of CO_2, which must be quantified. The activity data is derived from the official national statistics and Green Report of Forestry (see Tab. 5-59). Of the total reported limestone applied in agriculture, 95% was ascribed to agricultural soils in cropland (5% to grassland) based on the expert judgment (Klement, Central Institute for Supervising and Testing in Agriculture, personal communication 2005).

The Statistical Yearbook of the Czech Republic does not provide any data on the consumption of limestone and dolomite separately. Based on ERT recommendation and lack of country-specific information, the total amount of lime applied to soils was reported as corresponding to 90% limestone and 10% dolomite until 2017.

The more accurate activity data about dolomite consumption were obtained from the Ministry of Agriculture, Department of Agricultural Commodities (Ms. Budňáková) for 2018–2021. These data made it possible to estimate accurately the proportion of limestone and dolomite consumption 2018–2021. The missing data about dolomite proportion of liming was adjusted according to the information available on this proportion from the last two submissions. The share of dolomite was decreased to 60% over the entire timeperiod. The exact data about consumption of limestone and dolomite are available for EUROSTAT and are provided by CARC experts from 2021.

The share of liming of forest lands in the total liming in the Czech Republic was the highest in the period 2000–2002, when its value was over 10% and as much as 18% in 2000. In 2019, the liming of forests equalled almost 3.9% and no liming was applied to the forest land during 2021–2024 (Tab. 5-59).

Tab. 5-59 Amount of limestone and dolomite applied to managed soils [1 000 tons]

Year	Lime applied to Cropland and Grassland	Lime applied to Forest Land	Total amount of lime applied	Amount of Limestone	Amount of Dolomite	CO_2 emissions from liming
			[kt]			
1990	2 650	27	2 677	1 071	1 606	1 237
1995	248	2	251	100	150	116
2000	209	47	255	102	153	118
2005	143	3	145	58	87	67
2010	135	5	140	56	84	65
2015	353	18	371	148	222	171
2016	366	13	379	152	227	175
2017	345	13	358	143	215	166
2018	340	13	354	141	212	163
2019	402	16	418	175	243	193
2020	338	16	354	112	243	165
2021	318	0	318	140	178	146
2022	337	0	337	192	145	154
2023	264	0	264	141	124	121
2024	292	0	292	181	110	132

The quantification followed the Tier 1 method (Eq. 11.12, IPCC 2006), with the emission factor of 0.12 t C/t $CaCO_3$ and 0.13 t C/t $CaCMgCO_3$. To convert CO_2–C emissions into CO_2, the factor of 44/12 was used. Application of agricultural limestone used to be intensive in this country, but decreased radically during the 1990s, then increased slightly from 2010. This increase ended in 2020, when the amount applied is continuously decreasing. The activity data corresponds to the trend reported for the use of fertilizers, which decreased a lot in the early 1990s (Sálusová et al. 2006).

The application of limestone to agricultural land (incl. forest) in 2024 was 292 kt. No application was performed to forest areas. Total emissions from liming equalled 132 kt CO_2 eq. In 2024, there is no trend in consumption of limestone and dolomite in the Czech Republic.

5.7.3 Uncertainties and time-series consistency

Uncertainty estimates are based on expert judgment (AD) and the default values (EF). The uncertainty in the activity data for estimating the emissions from liming equals 20% and the uncertainty in the emission factor equals 50%. The combined uncertainty of emission estimates from liming equals 53.9%.

5.7.4 Source-specific QA/QC and verification

A detailed description of source-specific QA/QC and inventory verification of agriculture is presented in section 5.1.3

5.7.5 Source-specific recalculations, including changes made in response to the review process and impact of emission trend

No recalculation was made in this chapter.

5.7.6 Source-specific planned improvements, including tracking of those identified in the review process

No improvements are planned in this chapter.

5.8 Urea Application (CRT 3.H)

5.8.1 Source category description

Adding urea to soils during fertilization leads to a loss of CO_2 that was fixed in the industrial production process. Urea is converted into ammonium and hydroxyl ions and bicarbonate in the presence of water and urea enzymes. This source category is included because the CO_2 removal from the atmosphere during urea manufacturing is estimated in the Industrial Processes and Product Use Sector (IPPU Sector).

5.8.2 Methodological issues

Tier 1 and Eq. 11.13 (IPCC 2006) are utilized for estimating CO_2 emissions. Domestic production records for urea and DAM (synthetic fertilizer, the share of urea is 32.6%) were used to obtain an approximate estimate of the amount of urea applied to soils on an annual basis (Tab. 5-60). The default emission factor is 0.20 for carbon emissions from urea applications, which is equivalent to the carbon content of urea on an atomic weight basis. For estimating the total CO_2-C emissions, the product of the amount of urea is multiplied by the emission factor. CO_2-C emissions are converted to CO_2 by multiplying by a factor of 44/12.

Two different data sources were used for estimating: the first one was the data on urea application from the Czech Statistical Office used from 1990 to 1999. The values of urea application to agricultural land ranged from 92 to 195 thousand tons.

From 2000, a new source of activity data was obtained and employed in the inventory estimation. The statistical production data were replaced by more accurate data, corresponding to the real consumption of fertilizers, by the Ministry of Agriculture, Department of Agricultural Commodities (Ms. Budňáková). These data available from 2000 until 2020 were based on farmers fertilizer records and annual nutrient intake from urea and DAM. At the beginning of the 21st century, there was an extreme decrease in urea production and its application to farmland because of the significant restrictions on Czech production and the transition to import policy. The extreme consumption started in 2015 and finished in 2017.

Since 2021, CARC has been providing input data on urea and DAM consumption, as this is an input component of the Nitrogen Balance of the Czech Republic, which it is preparing.

The application of urea to agricultural land in 2024 reached 261 kt. This amount corresponds to the average consumption from 2014 to 2024 and correspods with higher consumption of synthetic fertilizers in 2024.

Tab. 5-60 Estimated consumption of urea and urea in DAM (IPPU) applied to managed soils in the Czech Republic during reporting period (MA, 2025) and estimated emissions [kt CO_2 eq.]

Year	Urea consumption	Urea in DAM consumption	Total consumption	CO_2 emissions
		[kt]		
1990	148	-	148	109
1991	180	-	180	132
1992	148	-	148	109
1993	127	-	127	93

Year	Urea consumption	Urea in DAM consumption	Total consumption	CO_2 emissions
		[kt]		
1994	124	-	124	91
1995	149	-	149	109
1996	137	-	137	100
1997	92	-	92	67
1998	195	-	195	143
1999	120	-	120	88
2000	66	92	158	116
2001	107	107	214	157
2002	88	92	180	132
2003	85	79	164	120
2004	97	109	206	151
2005	103	97	200	146
2006	114	99	213	156
2007	169	100	269	197
2008	139	106	244	179
2009	118	83	202	148
2010	154	65	219	161
2011	153	129	282	207
2012	188	93	281	206
2013	174	96	270	198
2014	79	99	177	130
2015	259	106	365	268
2016	292	103	395	290
2017	222	85	307	225
2018	174	79	253	185
2019	132	72	203	149
2020	160	52	213	156
2021	182	57	239	176
2022	207	55	262	192
2023	174	28	202	148
2024	214	48	261	191

5.8.2.1 Uncertainties and time-series consistency

Uncertainty estimates are based on expert judgment (AD) and the default values (EF). The uncertainty in the activity data for estimating the emissions from urea application equals 20%, the uncertainty in the emission factor equals 50%. The combined uncertainty of emission estimates from urea application equals 53.9%.

5.8.3 Source-specific QA/QC and verification

A detailed description of source-specific QA/QC and inventory verification of agriculture is presented in section 5.1.3.

The review process identified the inconsistency in activity data in use by crosschecking NID input with FAOSTAT data. The same activity data is used for reporting in other national reports (Transboundary convention, EUROSTAT/OECD).

5.8.4 Source-specific recalculations, including changes made in response to the review process and impact of emission trend

No recalculation was performed in this submission.

5.8.5 Source-specific planned improvements, including tracking of those identified in the review process

The analysis of uncertainties is in progress.

5.9 Acknowledgement

We greatly appreciate the support of Martin Dědina, CARC, related to harmonizing the reporting of ammonia emissions by using well documented national data. Thanks, belong to IFER employees Martina Roubalová and Tereza Fukalová for the maintenance of the specific calculation spreadsheets and for very effected technical support. The biggest thanks go to colleagues from CARC (Dr. Wollnerová, Dr. Klír) who with great patience helped to improve reporting in this sector. Special thanks to Prof. Trnka, the coordinator of the AdAgriF project "Advanced methods of reducing and sequestering greenhouse gas emissions in agriculture and forest landscapes to mitigate climate change" (CZ.02.01.01/00/22_008/0004635), funded by the Ministry of Education, Culture and Sports. The project outputs support the gradual increase in the methodological level of estimates.

6 Land Use, Land-Use Changes and Forestry (CRT Sector 4)

6.1 Overview of sector

The emission inventory of the Land Use, Land Use Change and Forestry (LULUCF) sector includes emissions and removals of greenhouse gases (GHG) resulting from land use, land-use change and forestry. The inventory is based on the application of the 2006 IPCC Guidelines for National Greenhouse Gas Inventories (IPCC 2006) that are linked to the previously used methods outlined in Chapter 3 of GPG for LULUCF (IPCC 2003). The current LULUCF reporting is also guided by the 2013 Revised Supplementary Methods and Good Practice Guidance Arising from the Kyoto Protocol (IPCC 2014a), IPCC Wetlands supplement (IPCC 2013) and 2019 Refinement to the 2006 IPCC Guidelines for National Greenhouse Gas Inventories (IPCC 2019). This methodological guidance is used to prepare the assessment and reporting of annual changes in carbon stocks in IPCC land-use categories, and emission contribution from the Harvested Wood Products (HWP).

The current inventory of the LULUCF sector uses the recommended reporting structure. In terms of land use representation and land-use change identification required for emission estimation for the LULUCF land use categories, the Czech inventory employs a system of land use representation and land-use change identification at the level of the individual cadastral units, based on the data administered nationally by the Czech Office for Surveying, Mapping and Cadastre (COSMC). The Czech LULUCF inventory remains in the process of continuous refinement and consolidation, but it represents a solid system for providing information on GHG emissions and removals in the LULUCF sector.

The current LULUCF inventory includes CO_2 emissions and removals, and emissions of non-CO_2 gases (CH_4, N_2O, NO_X and CO) from biomass burned in forestry and disturbances associated with land-use conversion, and from organic soils. The inventory incorporates all major LULUCF land-use categories, namely 4.A Forest Land, 4.B Cropland, 4.C Grassland, 4.D Wetlands, 4.E Settlements and implicitly 4.F Other Land, all linked to the Czech cadastral classification of lands. It also includes the HWP contribution, which is reported under category 4.G Harvested Wood Products. The emissions and/or removals of greenhouse gases are reported for all the mandatory categories.

The current submission covers the whole reporting period from the base year of 1990 to 2024. The currently reported estimates changed in comparison with the previously reported values due to methodological improvements, refinements in activity data and adopted emission factors affecting emission estimates for some categories that resulted in recalculations for the entire reporting period. Also, this inventory includes the global warming potential values (GWP) applicable to CH_4 and N_2O as recommended by IPCC Fifth Assessment Report (AR5).

The current sectoral estimates of GHG emissions and removals are shown in Fig. 6-1. For 2024, the most recent reported year, the LULUCF sector represented a net sink of GHG emissions equal to -4.63 Mt CO_2 eq. This represents a solid recovery from the period 2019–2022, where the sector temporarily represented a net source of emissions. This was due to the exceptionally high sanitation harvest after an unprecedented, cumulated drought period in the region since 2015, and the following extreme bark-beetle outbreak experienced in the Czech forestry. The data shown in Fig. 6-1 include emissions and removals for all land use categories including HWP contribution. Detailed information on the current emission estimates, implemented changes and performed recalculations is provided below for the individual LULUCF categories.



Fig. 6-1 Currently reported estimates of emissions for the LULUCF sector. The negative values correspond to net removals of green-house gases. The positive values are net emissions of green-house gases reported for the years 2019–2022, when the emission balance turned temporarily positive due to the development in the forestry sector.

6.1.1 Estimated emissions and removals

Tab. 6-1 provides a summary of the LULUCF GHG estimates for the base year of 1990 and the most recently reported year, 2024. They are listed by the major LULUCF categories and their sub-categories.

Tab. 6-1 GHG estimates in Sector 4 (LULUCF) and its categories in 1990 (base year) and 2024

Sector/category	Emissions 1990 [kt CO_2 eq.]	Emissions 2024 [kt CO_2 eq.]
4 Total LULUCF	-9 465	-4 630
4.A Forest Land	-8 363	-2 905
4.A.1 Forest Land remaining Forest Land	-8 159	-2 274
4.A.2 Land converted to Forest Land	-204	-631
4.B Cropland	285	98
4.B.1 Cropland remaining Cropland	-13	-26
4.B.2 Land converted to Cropland	298	124
4.C Grassland	-189	-818
4.C.1 Grassland remaining Grassland	65	-402
4.C.2 Land converted to Grassland	-253	-416
4.D Wetlands	-15	12
4.D.1 Wetlands remaining Wetlands	(0)	(0)
4.D.2 Land converted to Wetlands	-15	12
4.E Settlements	497	269
4.E.1 Settlements remaining Settlements	(0)	(0)
4.E.2 Land converted to Settlements	497	269
4.F Other Land	(0)	(0)
4.G Harvested Wood Products	-1 680	-1 285

Note: Emissions of non-CO_2 gases (CH_4 and N_2O) are also included.

In 2024, the net GHG flux for the LULUCF sector, estimated as the sum of emissions and removals, equalled -4 630 kt CO_2 eq. It represents a sink of GHG gases reported for the LULUCF sector in the country, and a solid recovery from the previous four years 2019–2022, where the sector temporarily represented a source of GHG emissions. In relation to the estimated emissions in other sectors for the inventory year 2024, the estimated sink of GHG emissions generated in the LULUCF sector represents an offset of 4.8% of the total

GHG emissions in the country. Correspondingly, for the base year of 1990, the total emissions and removals in the LULUCF sector equalled -9 465 kt CO_2 eq. In relation to the emissions generated in all the other sectors, the inclusion of the LULUCF estimate reduces the total emissions by 4.9% for the base year of 1990. It is important to note that – in contrast to other sectors - the emissions within the LULUCF sector exhibit high inter-annual variability (Fig. 6-1) and the values shown in Tab. 6-1 should be interpreted with care.

The aggregated emissions estimates reported for the major LULUCF categories (i.e., by land use and HPW contribution) are shown Tab. 6-2. The entire data series can be found in the corresponding CRT Tables.

Tab. 6-2 Estimated emissions and removals for the major land-use categories and HWP contribution for the entire reporting period 1990 to 2024 by 5-year intervals and annually since 2020. IE for 4.F Other land – included within 4.E Settlements.

Sector	4.A Forest land	4. B Cropland	4.C Grassland	4.D Wetlands	4.E Settlements	4.F Other land	4.G HWP	4. LULUCF Total
				[kt CO_2 eq.]				
1990	-8 363	285	-189	-15	497	IE	-1 680	-9 465
1995	-10 630	262	-485	-25	343	IE	-827	-11 363
2000	-9 637	247	-632	13	387	IE	-1 271	-10 893
2005	-8 752	207	-636	-2	446	IE	-1 434	-10 172
2010	-7 496	232	-615	28	377	IE	-1 620	-9 094
2015	-9 013	202	-620	6	279	IE	-478	-9 623
2020	12 477	97	-663	26	276	IE	-2 792	9 422
2021	8 515	100	-727	7	316	IE	-2 390	5 822
2022	4 571	99	-768	49	262	IE	-1 979	2 234
2023	-2 046	101	-808	-15	258	IE	-1 246	-3 756
2024	-2 905	98	-818	12	269	IE	-1 285	-4 630

Tab. 6-3 Key categories of the LULUCF sector (2024)

Category	Gas	KC A1	KC A2	KC A1[1]	KC A2[1]	% of total GHG[1]
4.E.2 Land converted to Settlements	CO_2		LA		Yes	0.29
4.C.1 Grassland remaining Grassland	CO_2	LA, TA	LA, TA	Yes	Yes	-0.44
4.C.2 Land converted to Grassland	CO_2	LA	LA	Yes	Yes	-0.45
4.A.2 Land converted to Forest Land	CO_2	LA	LA	Yes	Yes	-0.69
4.G Harvested wood products	CO_2	LA, TA	LA, TA	Yes	Yes	-1.40
4.A.1 Forest Land remaining Forest Land	CO_2	LA, TA	LA, TA	Yes	Yes	-2.49

KC: key category
[1] including LULUCF

Within the LULUCF sector, six categories were identified as key categories according to the IPCC 2006 for 2024. The most important is 4.A.1 Forest Land remaining Forest Land with a contribution of -2.49%, which is the major LULUCF category identified by both the level and trend assessment (Tab. 6-3). The emissions in this category are mostly determined by changes in living biomass carbon stock (see more in Section 6.4). The category 4.A.2 Land converted to Forest Land contributes with -0.69% and is identified as a key category by the level assessment. The other two categories are 4.C.1 Grassland remaining Grassland and 4.C.2 Land converted to Grassland, with a contribution of less than -0.5% each. The fifth key category is 4.G Harvested wood products that offset -1.40% of the total GHG emissions in the country and the sixth key category is 4.E.2 Land converted to Settlements with 0.29% contribution. Tab. 6-3 lists all key categories evaluated based on the approach 1 (KC A1) and approach 2 (KC A2) specified in IPCC 2006 Guidelines (IPCC 2006).

6.1.2 Coverage of pools and methodological tiers

The current inventory submission of the LULUCF sector includes all the mandatory categories and carbon pools (Tab. 6-4), as well as emissions related to HWP. The specific information related to methodological

tiers and pools included in the category estimates is provided under the individual chapters by the IPCC land use categories (Chapters 6.4 to 6.9) and the category of HWP contribution (Chapter 6.10).

Tab. 6-4 Carbon pools in LULUCF and in their finer resolution under the former KP LULUCF reporting

Carbon pools in LULUCF reporting	Carbon pools in KP LULUCF format	Definition
Living biomass	Aboveground biomass	All biomass above stump height (1% of tree height)
	Belowground biomass	All biomass below stump height (1% of tree height)
Dead organic matter	Deadwood	Standing deadwood, dead stumps, roots and logs (min. 7 cm diameter)
	Litter	Needles, leaves and branches up to a diameter of 7 cm, organic layers of mineral soil, including FM horizons
Soils	Soil organic matter	Mineral soils up to 30 cm depth and organic soils

6.2 Information on approaches used for representing land areas and on land-use databases used for the inventory preparation

The reporting format requires the estimation of GHG emissions into the atmosphere by sources and sinks for six land-use categories and, since reporting year 2013, also for the land-unspecific category of Harvested wood products (4.G). The land-use categories are Forest Land, Cropland, Grassland, Wetlands, Settlements and Other Land. Each of these categories is divided into lands remaining in the given category during the inventory year, and lands that are newly converted into the category from a different one. Accordingly, IPCC 2006 Guideliens (IPCC 2006) outline the appropriate methodologies for estimation of green-house gas emissions.

Consistent representation of land areas and identification of land-use changes constitute the key steps in the inventory of the LULUCF sector in accordance with the IPCC 2006 Gl. (IPCC 2006). The adopted system of land-use representation and land-use change identification was constructed gradually. Since the 2008 NIR submission, this has been exclusively based on the cadastral land use information of the Czech Office for Surveying, Mapping and Cadastre (COSMC; www.cuzk.cz). The Czech land-use representation and the land-use change identification system use annually updated COSMC data, elaborated at the level of about 13 thousand individual cadastral units. The system was constructed in several steps, including 1) source data assembly 2) linking land-use definitions 3) identification of land-use change 4) complementing time series. These steps are described below. The result is a system of consistent representation of land areas having the attributes of both Approach 2 and Approach 3 (IPCC 2006), permitting accounting for all land-use transitions in the annual time step. The individual steps are described below.

6.2.1 Source data compilation

The methodology requirements and principles associated with the approaches recommended by the IPCC 2006 Gl. (IPCC 2006) imply that, for the reported period of 1990 to 2024, the required land use should be available for the period starting from 1969. Information on land use was obtained from the Czech Office for Surveying, Mapping and Cadastre (COSMC), which administers the database of “Aggregate areas of cadastral land categories” (AACLC). The AACLC data were compiled at the level of the individual cadastral units (1992–2024) and individual districts (since 1969). There are over 13 000 cadastral units, the number of which varies due to separation or division for various administrative reasons. In the period from 1992 to 2024, the total number of cadastral units varied between 13 027 and 13 091.

To identify the administrative separation and division of cadastral units within a given year, two approaches were employed. Before 2004, the cadastral units were crosschecked by comparing the areas in subsequent years using a threshold of half-hectare difference. Starting in 2004, the explicit change in land use was quantified within and for each year directly by the data provider, i.e., COSMC, at the request of the inventory team. The latter approach does not require reconciliation of individual cadastral units between the consecutive years, as it adopts the addressed land use change information available in the national database of COSMC.

To obtain information on land-use and land-use changes prior to 1993, a complementary data set from COSMC at the level of 77 district units was prepared. It covered the period since 1969 and was required for application of the IPCC default transition time of 20 years for carbon stock change in soils. The spatial coverage of cadastral and district units is also shown in Fig. 6-2.

6.2.2 Linking land-use definitions

The analysis of land use and land-use change is based on the data from the "Aggregate areas of cadastral land categories" (AACLC), centrally collected and administered by COSMC and regulated by Act No. 265/1992 Coll., on Registration of proprietary and other material rights to real estate, and Act No. 344/1992 Coll., on the real estate cadastre of the Czech Republic (the Cadastral Act), both as amended by later regulations. AACLC distinguishes ten land categories, six of them belonging to land utilized in agriculture (arable land, hop fields, vineyards, gardens, orchards, grassland) and four under other use (forest land, water surfaces, built-up areas and courtyards, and other land). For the explicitly addressed within-year land use change identification, two additional specific land-use subcategories were distinguished, namely other land – waterlogged soil and other land – unfertile land. The AACLC land use categories and sub-categories of the COSMC database were linked to most closely match the default definitions of the six major land-use categories (Forest Land, Cropland, Grassland, Wetlands, Settlements and Other Land) as given by the 2006 Guidelines for National Greenhouse Gas Inventories (IPCC 2006). The country-specific definition content of the IPCC land use categories is summarized in Tab. 6-5 and it can also be found in the respective Chapters 6.4 to 6.9 devoted to each of the major land-use categories.



Fig. 6-2 Cadastral units (grey lines; n = 13 074 in 2024) and districts (black lines; n=77), the basis of the Czech land use representation and land use change identification system.

Tab. 6-5 Linking the Czech national cadastral (COSMC) land-use categories to the IPCC land-use categories. COSMC codes in parenthesis combine types of properties and their dominant use.

IPCC land-use category		CRT coding	Czech national cadastral (COSMC) ID code and land-use category
Forest land		4.A	10. Forest land - Land with forest stands and land, where forest stands were removed to permit their regeneration, forest break and unpaved forest road, not wider than 4 m, and land, where forest stands were temporarily removed due to a decision of state forest administration (Forestry Act 289/1995)
Cropland		4.B	2. Arable land - Land of arable soil according to the Agriculture Act 3. Hop fields - Land of hop field according to the Agriculture Act 4. Vineyards - Land of vineyard according to the Agriculture Act 5. Gardens - Land for permanent and dominant production of vegetables, flowers and other garden products or land with fruit trees and shrubs close to residential and industrial buildings 6. Fruit orchard - Land of fruit orchard according to the Agriculture Act
Grassland		4.C	7. Permanent grassland - Land of permanent grassland according to the Agriculture Act
Wetlands		4.D	11. Water area - Land of watercourse and riverbeds, water reservoir, marsh, wetland or swamp

IPCC land-use category		CRT coding	Czech national cadastral (COSMC) ID code and land-use category
			(22). Other area – waterlogged area - Land of Other area that is waterlogged (marsh, wetland or swamp)
Settlements		4.E	13. Built-up area and courtyard - Land with buildings including courtyard, common yard, 14. Other area - Land not classifying under 2, 3, 4, 5, 6, 7, 10, 11 and 13, such as transport infrastructure, manipulation areas, depot, landfill, photovoltaic power station and others (21). Other area – unfertile land - Land not suited for production and other use
Other land		4.F	IE since 2018 NIR submission - it is included within 4.E Settlements, while earlier represented by (21) Other area – unfertile land)

6.2.3 Land-use change identification

The critical issue of any LULUCF emission inventory is the quantitative determination of land-use change. This inventory adopts two approaches for identifying and quantifying land-use changes on an annual basis: i) until 2003 by balancing the six major land-use areas for each of the individual or integrated cadastral units on use of the subsequent years of the available period and ii) since 2004, using the within-year explicitly addressed land-use conversions registered and estimated by COSMC, the authorized administrator of cadastral information in the country. Although both the approaches are in principle identical, the later approach is more accurate, as it captures virtually all changes within each individual cadastral unit, including theoretically possible bi-directional changes involving the same pair of land use categories within one particular year. In practice, the actual effect of the more advanced, latter approach is not significant under the conditions of the Czech Republic. However, it greatly improves the transparency of the system, and the data are basically readily usable as supplied by the data provider (COSMC) without further processing. The resolution of the implemented land use representation and land use change identification system is demonstrated in Fig. 6-3. In the example of the cadastral unit of Kácov (ID 656305), it can be observed that during 2011, two land-use categories lost their land, while the other two increased their area. However, as shown in the table, there were six specific land-use conversions involved in these land use changes, where Forest land and Grassland were partly converted to Settlements and Cropland. The latter approach and more detailed data available since 2004 also allowed an explicit estimation of changes associated with the category Other land representing unfertile land with no specific type of land use, which was considered constant until 2003. All identified land-use transfers estimated at the individual cadastral unit level are summarized by each type of land-use change on an annual basis to be further used for estimation of the associated emissions.

Year (date)	ID CU (Name)	Forest land	Cropland	Grassland	Wetlands	Setttlements	Other land	Total
31-12-2010	661635 (Kácov)	1992637	2627349	1186759	376350	1415821	NO	7598916
31-12-2011	661635 (Kácov)	1979724	2633115	1181825	376350	1427904	NO	7598918
Difference		**-12913**	**5766**	**-4934**	0	**12083**	-	2

Conversion type	Area (m^2)
Forest land - Cropland	977
Forest land - Settlements	11936
Cropland - Settlements	247
Grassland - Cropland	4897
Grassland - Settlements	38
Settlements - Cropland	139

Fig. 6-3 Example of land-used change identification for 2011 and the cadastral unit 661635 (Kácov) – total difference between years for all land-use categories as well as the specific conversions between concrete land use categories as provided by COSMC. The spatial unit is m^2. Not occurring (NO) noted for Other land.

6.2.4 Complementing time-series

The above-described estimation of land-use changes at the level of individual cadastral units was performed from 1993 to 2024, because the data on that spatial resolution has been available only since 1992. For the years preceding 1993, i.e., for the land-use change attributed to 1970 to 1992, an identical approach to that described above was used, but with aggregated cadastral input data at the level on the individual districts. Due to the IPCC default period of 20 years used for reporting the converted land, the source information contains data on land use in the Czech Republic since 1969.

6.2.5 Land use representation and land use change identification system - status and development

Development of the Czech LULUCF land use representation and land use change identification system as described above involved collaboration with the Czech Office for Surveying, Mapping and Cadastre (COSMC; www.cuzk.cz), which administers the source information on land use used in the LULUCF emission inventory. Based on internal analysis and the recommendations of COSMC, the current inventory retains exclusively use of the original data on land use without any further corrections and provides explicit information on land use for the basic IPCC land use categories.

For the coming NID submissions (2026 to 2027), the inventory team plans to superimpose the information on forests qualifying by the FAO definition that occurs on other cadastral land-use categories besides Forest land, adjusting (enlarging) it accordingly on account of the individual non-forest cadastral land use categories. That information became recently available from the NFI inventory operated by the Czech Forestry Institute (CFI), Brandýs n. Labem. This methodological improvement is one of the anticipated methodological changes associated with the full adoption of the NFI data in the coming GHG emission inventory documents.

6.3 Land-use definitions and the classification systems used and their correspondence to the land use, land-use change and forestry categories

The IPCC land use categories were linked to the Czech cadastral classification system, namely that of “Aggregate areas of cadastral land categories” (AACLC), centrally collected and administered by COSMC, as described in detail in Section 6.2 above. The specific attribution and linking of cadastral land use

categories to IPCC land use categories is summarized in Tab. 6-5 and provided in the source category description text under the corresponding Sections 6.4 to 6.9 below.

6.3.1 Land-use change – overall trends and annual matrices



Fig. 6-4 Trends in areas of the six major land-use categories in the Czech Republic between 1970 and 2024 (based on information from the Czech Office for Surveying, Mapping and Cadastre). 4.F Other land (IE) is included within 4.E.

The overall trends in the areas of the major land-use categories in Czech Republic for the period 1970 to 2024 are shown in Fig. 6-4. The largest quantitative change is associated with the Cropland and Grassland land-use categories.

Tab. 6-6 Land-use matrices describing annual initial and final areas of particular land-use categories and the identified annual land-use conversions among these categories, shown for 1990 and 2024

1990		Initial (1989)						*Area [kha]*
	Category	Forest land	Cropland	Grassland	Wetlands	Settlements	Other land	
Final (1990)	Forest Land	2 628.6	0.5	0.4	0.0	0.0	0.0	**2 629.5**
	Cropland	0.0	3 454.5	0.4	0.0	0.1	0.0	**3 455.0**
	Grassland	0.1	8.8	823.6	0.0	0.0	0.0	**832.5**

	Wetlands	0.0	0.4	0.4	155.9	0.8	0.0	**157.5**
	Settlements	0.3	3.7	3.7	0.1	804.1	0.0	**811.9**
	Other Land	0.0	0.0	0.0	0.0	0.0	0.0	**0.0**
	Area [kha]	2 629.0	3 467.9	828.5	156.1	805.0	0.0	**7 886.4**

2024		**Initial (2023)**						***Area [kha]***
	Category	Forest land	Cropland	Grassland	Wetlands	Settlements	Other land	
Final (2024)	Forest Land	2 681.4	0.4	0.3	0.0	1.0	0.0	**2 683.1**
	Cropland	0.0	3 145.5	1.9	0.0	0.9	0.0	**3 148.4**
	Grassland	0.0	6.0	1 036.0	0.1	1.3	0.0	**1 043.4**
	Wetlands	0.1	0.3	0.3	170.6	1.1	0.0	**172.3**
	Settlements	0.2	2.9	0.7	0.1	836.1	0.0	**839.9**
	Other Land	0.0	0.0	0.0	0.0	0.0	0.0	**0.0**
	Area [kha]	2 681.8	3 155.0	1 039.2	170.8	840.4	0.0	**7 887.1**

An insight into the net trends shown in Fig. 6-4 is provided by the analysis of gross land-use changes as described in Section 6.2. Tab. 6-6 shows a product of that analysis (for the base year 1990 and the latest reporting year 2024), namely the areas of land-use change among the major land-use categories in the form of land-use change matrices for the individual years. This is available for all years of the reporting period. It is important to note that the annual totals for the individual years in the matrices do not necessarily correspond to the areas that appear in the CRT files, which account for the progressing 20-year transition period that began in 1970. This is the recommended assumption of IPCC (2006) for estimation of changes in soil carbon stock.

6.4 Forest Land (CRT 4.A)



Fig. 6-5 Forest land in the Czech Republic – distribution calculated as a spatial share of the category within individual cadastral units (as of 2024)

6.4.1 Source category description

The Czech Republic is a country with a long forestry tradition. Practically all the forests can be considered as temperate-zone managed forests under the IPCC definition of forest management (IPCC 2006 Gl., Volume 4). Within the Czech land use representation and land use change identification system, land use category 4.A Forest Land is represented by the Forest Land (ID 10) category of the Czech cadastral system administered by COSMC. With respect to the definition thresholds of the Marrakesh Accords, forest is defined as land with woody vegetation and with a tree crown cover of at least 30%, over an area exceeding 0.05 ha containing trees able to reach a minimum height of 2 m at maturity[2]. As this definition of forest excludes some areas of currently (temporarily) unstocked cadastral forest land, such as forest roads, forest nurseries and land under power transmission lines, these are discounted in all emission estimates involving Forest Land using the annually updated information on the ratio of timberland to cadastral forest land. In this way, the area of cadastral forest land is also linked to the national definition of timberland (Czech Forestry Act 289/1996). These areas and the related activity data on forests (see more below) are collected as a bottom-up process based on the mandatorily elaborated forest management plans (FMPs). FMPs

[2] *These parameters, together with the minimum width of 20 m for linear forest formations, were given in the Czech Initial Report under the Kyoto Protocol. Thereafter, these parameters were used in subsequent policies on forestry (e.g., KP II for 2013-2020 or EU Regulation on LULUCF 2018/841).*

and/or forest management guidelines (for forest properties under 50 ha) serve for overall assessments of the state of forests, which are requested under the Czech Forestry Act (289/1996).

In 2024 (1990), the area of Forest Land equalled 2 683 (2 629) th. ha, whereas the stocked forest area (timberland) corresponded to 2 618 (2 583) thousand ha, representing 97.6 (98.2)% of the cadastral forest land in the Czech Republic. Hence, the temporarily unstocked area, not accounted in forest biomass emission estimates, represents 2.4 (1.8)% of the forest land according to the Czech cadastral data as of 2024 (1990).

Forests (cadastral forest land) currently occupy 34.2% of the area of the country (based on MA, 2025). The tree species composition is dominated by conifers, which represent 66.8% of the timberland area. The four most important tree species in this country are spruce, pine, beech and oak, which account for 45.1, 15.9, 10.0 and 8.0% of the timberland area, respectively (MA, 2025). Broadleaved tree species have been favoured in afforestation since 1990. The proportion of broadleaved tree species increased from 21% in 1990 to 31% in 2024. The total growing stock (merchantable wood volume) in forests in the country has increased during the reported period from 564 mil. m^3 in 1990 to 679 mil. m^3 (under bark) in 2024 (MA, 2025).

Several sources of information on forests are available in the Czech Republic. The primary official source of activity data on forests in the country, which are also used for this emission inventory, is the forest taxation data in Forest Management Plans (further denoted as FMPs). These data are administered centrally by the Czech Forestry Institute (CFI), Brandýs n. L., representing an official source of information on forest resources in the country. With a forest management plan of 10 years, the annual update of the FMP database is related to 1/10 of the total forest area scattered throughout the country. The information in an FMP represents an ongoing national stand-wise type of forest inventory. An auxiliary source of information is the data from the statistical (sample based, tree level) National Forest Inventory (NFI). The first NFI cycle (NFI1) was performed during 2001–2004 by CFI and its aggregated results were released three years later (CFI, 2007). The second NFI cycle (NFI2) ran during the years 2011 to 2015. Its results were gradually released during the period from 2016 to 2019 (Kučera and Adolt 2019). Since 2016, CFI initiated a continuous inventory with a 5-year cycle on individual plots. The pilot assessments of that inventory (NFI3) were released in 2023 (Máslo et al. 2023), with a set of key results published thereafter. Another auxiliary statistical information on forests at a country level is provided by the Czech landscape inventory (CzechTerra; www.czechterra.cz), which run as a project funded by the Ministry of Environment (Černý 2009, SP/2d1/93/07), complementing its first cycle (CZT1) in 2008/2009. The second CzechTerra cycle (CZT2) was conducted in 2014/2015 as part of a project funded by the Czech Science Foundation (GA ČR 14-12262S). These results were published by the end of 2015 (Cerny et al. 2015, Cienciala et al. 2015). Some of these data have been used in this inventory document as a basis for tree species allometry and for verification purposes. However, the GHG emission inventory is still primarily based on the FMP data, which were the main continuous data source used for domestic and international reporting on forests in the Czech Republic since 1990 until last year (2024). Since 2025, the Czech Forestry Institute (CFI) implements the NFI data for the national reporting to international bodies such as FAO FRA and Forest Europe. Consequently, the full implementation of NFI data in the national GHG emission inventory of the LULUCF sector is currently in process and expected to be used for the coming GHG inventory submissions (NID 2027 and later).



Fig. 6-6 Activity data – area for the four major tree species groups and clear-cut area during 1990 to 2024 (total area of Forest Land shown)



Fig. 6-7 Activity data – mean growing stock volume against stand age for the four major groups of species during 1990 to 2024; each line corresponds to an individual inventory year. The symbols identify only the situation in 1990 and 2024.

The FMP data were aggregated in line with the country-specific approaches at the level of the four major tree species (i-beech: all broadleaved species except oaks, ii-oak: all oak species, iii-pines, iv-spruce: all conifers except pines) and age-classes (10-year intervals). For these categories, growing stock (merchantable volume, defined as a tree stem and branch volume under the bark with a minimum diameter threshold of 7 cm), the corresponding areas and other auxiliary information were available for each inventory year. It can be observed that the area of broadleaved species has steadily increased during the reporting period, mainly at the expense of spruce (Fig. 6-6). Fig. 6-7 shows the average growing stock for all tree species groups. According to the official data based on FMP (MA 2025), it has increased steadily for broadleaved tree species groups since 1990 in this country.

On the contrary, tree species area for the coniferous tree species steadily declined since 1990 (Fig. 6-6). This decline accelerated during the period 2019–2024, when also a reduction in spruce growing stock volume was detected. This is coherent with the actual independent estimation on growing stock based on NFI sample-based monitoring, which also suggests a significant reduction of the growing stock of coniferous trees, which is mainly related to the accelerating spruce forest decline (Adolt et al., 2020, Máslo et al. 2023).

In addition to the four major categories by predominant tree species, clear-cut areas are also distinguished (Fig. 6-6), forming another specific sub-category of Forest Land. A clear-cut area is defined as a temporarily unstocked area following final or salvage harvest of forest stands. It ceases to exist once it is reforested, which must occur within two years according to the Czech Forestry Act. There is no detectable carbon stock change for this category, and it is introduced solely for the purpose of consolidated, transparent and consistent reporting of forest land. In 2024, clear-cut areas represented 2.7% of the timberland area within Forest Land according to FMP data and the published official national information based on these data (MA 2025). Note, however, that this may differ from actual clear-felled areas as detected by remote sensing (https://www.kurovcovamapa.cz/) for the most recent period. Although this is an example of the inadequate representation of clear-felled areas during the current calamity outbreak, it does not explicitly impact the reported harvest volumes, which are obtained independently as described below.

The annual harvest volume constitutes the other key information related to forestry. This value is available from the Czech Statistical Office (CzSO). CzSO collects this information based on about 600 country respondents (relevant forest companies and forest owners) and includes commercial harvest and fuel wood, with compensation for the forest areas not covered by the respondents. According to this information, the base harvest of merchantable wood from forests increased from 13.3 mil. m^3 in 1990 to 17.8 mil. m^3 in 2024. This is markedly less than in 2020, when the highest ever harvest volume was recorded in the country, reaching 35.8 mil. m^3, and less than 18.5 mil. m^3 recorded in the previous reported year 2023 (all data refer to under-bark volumes, MA 2025). This verifies a turnover of the recent (2017–2020) drought-induced bark-beetle calamity trend. Also, the share of sanitary volume successively declined from 95% in 2020 to 45% in 2024. Sanitary felling is mandatorily prioritized in reaction to the bark-beetle outbreak during the recent years. Although the share of sanitary felling remains a concern, it is confirmed that both sanitary and total harvests peaked in 2020, and the positive trend indicating the stabilization of the Czech forestry sector since then is expected to continue in the coming years.

The Czech emission inventory also includes the harvest loss, which represents the additional removal of wood and forest residues associated with planned harvest and natural disturbance events. This additional harvest drain estimate is officially reported by the Czech Statistical Office (CzSO), which became available since 2009 and included since year 2011 (J. Kahuda, CzSO, personal communication 2013). It consistently complements the previously employed harvest loss estimates, increasing the base (wood industry) reported harvest by an extra 2.5 and 4% of the final and salvage logging volumes, respectively (see Section 6.4.2 below). The additional removals of solid wood and forest residues enter the estimation using partitioning of 10 and 90% between the two woody components, respectively, which represents a conservative estimate of the extra harvest while preventing double counting. Hence, the total woody drain is the sum of the base merchantable harvest and the estimated fraction of additional woody extraction (0.26 mill. m^3 in 2024), as graphically show in Fig. 6-9. See also explanatory pictures in Fig. 6-8 providing more transparency into this topic. The additional harvest loss represents about 2.4% of the base harvest volume across the entire reporting period. We note that the estimation of additional extraction of harvest residues remains uncertain and will be further verified once the new empirical evidence of the National Forest Inventory (NFI) becomes implemented in the emission inventory of the LULUCF sector.

Fig. 6-8 Illustration of base harvest (left) and additional (extra) harvest (right) volume as reported by CsSO and used as activity data as described in the text.



Fig. 6-9 The applicable total annual harvest for coniferous (Conif.) and broadleaved (Broadl.) tree species, which includes both the reported quantities of merchantable wood for the two categories (Conif. merch, Broadl. merch.) and the estimated/reported additional harvest drain (Conif. extra, Broadl. extra) for the entire reporting period of 1990 to 2024.

Salvage logging operations in this country are predominantly related to stands affected by windstorms, snow and bark-beetle calamities. On this basis, the Czech emission inventory includes an explicit estimate of disturbance, which includes the categories of natural disasters, pollution, insects and other effects (CzSO, J. Kahuda, personal communication 2013). The actual share of salvage logging is annually reported by CzSO and elsewhere (MA 2025). In 2024, the applicable salvage volume of the total annual base harvest reached 8.0 mill. m^3, down by 25.9 mill. m^3 from the recorded maximum estimated for 2020, and down by 3.0 mill. m^3 estimated for 2023. Although this is a clear improvement and evidence of stabilization in the Czech forestry, the share of the sanitary harvest observed for 2024 (45% of the total base harvest) remains excessive, representing a sustained concern for the forest management in the country. The total harvest applicable for the emission inventory by tree species groups for the entire reporting period since 1990 to 2024 is shown in Fig. 6-9. The information on the reported harvest, share of salvage logging, quantity of harvest by disturbance type and applicable additional harvest is also provided in Tab. 6-7.

Tab. 6-7 The reported harvest, total share of salvage logging in the reported harvest, quantity of salvage logging by disturbance type (source data CzSO) and total applicable additional harvest extraction (source information IFER, CzSO)

Variable	Unit	Year									
		1990	2000	2005	2010	2015	2020	2021	2022	2023	2024
Reported base harvest	Mm^{-3}	13.3	14.4	15.5	16.7	16.2	35.8	30.3	25.1	18.5	17.8
Share of salvage logging	% of reported harvest	74	23	29	39	50	95	87	79	60	45
- abiotic/natural	Mm^{-3}	8.70	2.39	2.30	4.07	4.39	4.60	4.86	5.86	3.42	3.92
- pollutants	Mm^{-3}	0.29	0.08	0.04	0.03	0.03	0.01	0.02	0.00	0.00	0.00
- insect outbreaks	Mm^{-3}	0.18	0.32	0.98	1.79	2.31	26.2	18.3	11.5	5.58	2.39
- other	Mm^{-3}	0.65	0.50	1.22	0.57	1.43	3.06	3.11	2.37	2.03	1.71
Additional extraction of harvest residues (IFER, CzSO)	Mm^{-3}	0.48	0.41	0.46	0.52	0.20	0.27	0.29	0.29	0.25	0.26
Total harvest removals	Mm^{-3}	13.8	14.9	16.0	17.3	16.4	36.0	30.5	25.4	18.7	18.1

As apparent from Tab. 6-7, the most notable disturbance type requiring salvage logging is the insect outbreak in the country that peaked in 2020 with a trend reversal in 2021. Also important is damage by abiotic factors, such as wind, snow and other climatic phenomena. On the contrary, damage attributable to pollutants became insignificant in the two recent decades and compared to the late 1980s and early 1990s, when the region suffered from significant air pollution impacts. However, residuals from that period can still be detected in soils, which remain regionally acidified and apparently degraded in terms of nutrients (Hruska and Cienciala 2003). In this context, it is also important to note that a causal attribution of factors responsible for declining tree health is complex and forest management evidence, which is the basis of information shown in Tab. 6-7, does not discern the underlying factors such as sensitivity to drought or unfavorable soil chemistry, but reports on the final visible phenomena of affected trees (Cienciala et al. 2017). It is generally agreed that the recent insect outbreak calamity was induced by exceptional cumulative drought conditions combined with above-average temperatures (MA 2019), which the country has been experiencing since 2015. The recently published literature confirmed that the cumulative drought observed for 2015–2018 was unprecedented for over two millenia in the country (Büntgen et al. 2021). In the context of the reported harvest logging estimates, it is important to understand that the inventory team is not in a position to conduct any independent verification of the national information on disturbance types and additional harvest (Tab. 6-7). Hence, the information provided centrally by CzSO remains the official national source of information on harvest levels in the country, and it is used consistently for the entire reporting period.

6.4.2 Methodological issues

Category 4.A Forest Land includes emissions and sinks of CO_2 associated with forests, non-CO_2 gases generated by burning in forests, non- CO_2 gases from organic soils and N_2O emissions from mineralization for land use conversions with soil carbon loss. This category is composed of 4.A.1 Forest Land remaining Forest Land, and 4.A.2 Land converted to Forest Land. The following text describes the major methodological aspects related to emission inventories for forest sub-categories. The methods of area identification described in Section 6.1.2 distinguish the areas of forest with no land-use change over the 20 years prior to the reporting year. These lands are included in subcategory 4.A.1 Forest Land remaining Forest Land. The other part represents subcategory 4.A.2 Land converted to Forest Land, i.e., forest areas “in transition” that were converted from other land-use categories over the 20 years prior to the reporting year. The areas of forest subcategories, i.e., 4.A.1 and 4.A.2 accumulated over a 20-year rolling period can be found in the corresponding CRT Tables. The annual matrices of identified land-use and land-use changes are given in Tab. 6-6 above.

In terms of emission estimations, the earlier inventory submission (NIR 2022) introduced a major methodological upgrade applicable to 4.A Forest Land (as well as to the then mandatory KP LULUCF activities) by adopting Tier 3 estimation methodologies facilitated by the Carbon Budget Model of the Canadian Forest Sector (CBM-CFS3, ver. 1.2, here denoted also as CBM; Kurz et al. 2009, Kull et al. 2019). An overview of the emission categories and carbon pools affected by the improved methodological tier is shown in Tab. 6-8 for the UNFCCC land use categories concerned as well as the corresponding former KP LULUCF activities. The methodological changes implemented in the NIR 2023 submission additionally included changes in living biomass for Forest land converted to other land use (Deforestation), which is estimated solely by CBM, in coherence with other subcategories of 4.A Forest land (Tab. 6-8). The current inventory submission retains these methodological approaches, while it improves the estimates of input activity data (extraction of harvest residues as above) and rectifies the proportions of dead organic matter components and bark within the model.

Tab. 6-8 Methodological tier indicating use of CBM in estimation carbon pools for the concerned land use categories and the former KP LULUCF activities. *Carbon stock change in organic soil is not included in this table, but it is estimated using T1/T2 methodologies.

Emission category (UNFCCC) or Activity (KP LULUCF)	Carbon pool UNFCCC	Carbon pool KP LULUCF	Methodological tier and comment
4.A.1 FL remaining FL Forest Management	Living biomass	Aboveground biomass	T3, CBM
		Belowground biomass	T3, CBM
	Dead organic matter (DOM)	Deadwood	T3, CBM
		Litter	T3, CBM
	Soil (Mineral soils)*	Soil (Mineral soils)	T3, CBM
4.A.2 Land converted to FL Afforestation/Reforestation	Living biomass	Aboveground biomass	T3, CBM
		Belowground biomass	T3, CBM
	Dead organic matter (DOM)	Deadwood	T2/T3, CBM
		Litter	T2/T3, CBM
	Soil (Mineral soils)*	Soil (Mineral soils)	T2/T3, Soil carbon maps
4.B.2.a FL converted to Cropland 4.C.2.a FL converted to Grassland 4.D.2.a FL converted to Wetland 4.E.2.a FL converted to Settlements Deforestation	Living biomass	Aboveground biomass	T3, CBM
		Belowground biomass	T3, CBM
	Dead organic matter (DOM)	Deadwood	T2/T3, CBM
		Litter	T2/T3, CBM
	Soil (Mineral soils)*	Soil (Mineral soils)	T2/T3, Soil carbon maps
Harvested Wood Products	Harvested Wood Products	Harvested Wood Products	T2, Production approach

6.4.2.1 Description of the CBM-CFS3 carbon model application

We provide a detailed model description, its country-specific calibration and independent verification in Annex 3.6 of this NID submission. In the text below, we give essential methodological information on model-aided estimations of emissions resulting from changes in individual carbon pools. Hence, the readers are advised to seek the detailed CBM-specific information in Annex A 3.6 to complement understanding of the estimation approach.

In general, application of the CBM model was set up to resemble the NIR/NID reporting strategy (key input data use, stratification) adopted in the gradually developing Czech emission inventory of the LULUCF sector. The CBM simulation run is set to start in 1990 and progresses in an annual step until 2024, i.e., for the entire reporting period. The model integrates the key activity data used in the emission inventory to the present. These include land-use areas related to forests, data on growing stocks by tree species and age class from the national stand-wise inventory of FMP and the related volume increment data, and data on disturbances (management practices).

CBM simulates the transfer of carbon between pools and the atmosphere (Fig. 6-10). Specifically, it simulates mortality and litter fall representing transfers from biomass to other dead organic matter (DOM) pools resulting from tree, foliage, branch and root mortality (Kurz et al. 2009). The calibrated country-

specific equations to convert volumes to biomass components, turnover and transfer rates between DOM pools are specified in the AIDB database (a CBM-specific database in MS Access format, Kull et al. 2019). The detailed model handling of carbon turnover including DOM pools was one of the fundamental reasons for implementing this Tier 3 modelling approach to ensure that the complete carbon cycling in forest ecosystems was fundamentally captured. This is important specifically in the recent conditions of significantly changing wood harvest and mortality in the country, which directly affect inputs into and emissions from the DOM pools. Decomposition of DOM pools is modelled using a temperature dependent decay rate function (Kurz et al. 2009). Disturbances including forest management interventions such as thinning, harvest and afforestation are each defined in a matrix describing the proportion of carbon transferred between pools, fluxes to the atmosphere, and transfers to the DOM pools and the timber sector (Fig. 6-10). The emission contribution of HWP is calculated separately as described in Section 6.10.



Fig. 6-10 Conceptual diagram of CBM (taken from Kurz et al. 2009) showing the individual biomass and dead organic matter (DOM) carbon pools and key governing simulated processes (in ovals) and transfers in forest ecosystem carbon balance.

The key input activity data and parameters used in CBM include:

- Land use areas of forest land, land use conversions to Forest Land (former KP LULUCF activity Afforestation/Reforestation) and from Forest land (former KP LULUCF activity Deforestation) as described in Section 6.2 and 6.4.1. These activity data come from the Czech Office for Surveying, Mapping and Cadastre (COSMC). Other related details are described in Section A 3.6.2.1.

- Growing stock by age classes categorized into four main species groups (beech, oak, pine, spruce) as described and visualized in Section 6.4.1. CBM simulation is initiated with the state of the forest resources, i.e., growing stock volume by species groups and age classes as of 1990 (see section A 3.6.2.1). These activity data were provided by Forest Management Institute, Brandys n. Labem (CFI).

- Volume increment data used in CBM are derived from the identical source as described in Section 6.4.2.2. However, CBM uses a specific concept of current and historical growth curves (yield tables, CYTs and HYTs, respectively), which is detailed in Annex A 3.6.2.2. In brief, the current yield tables (CYTs) are derived from the current annual increment (CAI) using the official increment estimates as provided by CFI as shown in Fig. 6-11. CYT and HYT curves were derived from the age class structure for the individual species-group strata. While HYTs correspond to the initial state of the forest resources as of 1990, the CYT growth curves were fitted on data as of 2004, representing the middle of the reporting period. Thereafter, a set of relative scaling factors applicable to individual tree species groups and the reporting period 1990 to 2024 were used within CBM to assure the full correspondence of the CYTs with the input activity data on the CAI shown in Fig. 6-11. Annex 3.6.2.2 provides complete information on this parameterization and applicable scaling factors by individual tree species groups.

- Country-specific allometric equations to estimate individual tree components and biomass proportions as a function of tree age are an essential step of CBM calibration to local conditions. To provide biomass estimates for individual tree parts, a set of relevant national allometric studies and/or biomass compilations that include data from equations of the Czech Republic was used. These sources are coherent with those used in the earlier Tier 2 estimates (NIR 2021), but the calibration procedure was extended as required by CBM according to Boudewyn et al. (2007), Kurz et al. (2009) and Kull et al. (2019). Specifically, we used the following sources of allometry: beech (Vonderach et al. 2018, Wutzler et al. 2008 for leaves only), oak (Cienciala et al. 2008a), pine (Cienciala et al. 2006b), spruce (Vonderach et al. 2018) and complementarily birch (Marklund 1988, Repola 2008 for leaves only). The calibration process is detailed in Annex A 3.6.2.4.

- Turnover rates and transfer to DOM carbon pools are based on the values published for CBM in the European CBM-specific database AIDB by Pilli et al. (2018), with stem biomass mortality derived from the Czech NFI (Adolt et al. 2016). Parameters related to litter and soil carbon pools for this inventory (NID 2026) were tuned using the newly released activity data on organic and mineral soil horizons in forest soils (project ForCarbo, TACR - Technology Agency of the Czech Republic No. SS06010148). Respiratory processes of all DOM pools are driven by air temperature in CBM-CFS3. The information on biomass turnover, designated DOM pools and litter transfer rates as applied by CBM is provided for individual pools in Annex A 3.6.2.4.

- Forest management interventions and other disturbances represent the changes to forest ecosystems that are specifically defined by disturbance matrices for individual intervention (disturbance) types. They define the changes in carbon pools and transfers between them. Forest management interventions include commercial thinning, salvage logging either with or without resulting clearcuts, and final cut. Disturbances such as wildfires and slash and burn are used to initialize DOM pools. Additionally, deforestation events leading to other land-use (Cropland, Grassland, Wetlands, Settlements) are also governed by specific matrices. All disturbances used by CBM are detailed in full in Annex A 3.6.2.5.

6.4.2.2 Forest Land remaining Forest Land

The carbon stock change in category 4.A.1 Forest Land remaining Forest Land is given by the sum of changes in living biomass, dead organic matter, and soils.

Until NIR 2021, the carbon stock change in living biomass was estimated using the default method[3] according to eq. 2.7 of IPCC (2006). This method is based on a separate estimation of increments and removals, and their difference. Since the 2022 submission (NIR, 2022), the living biomass carbon stock change has been solely estimated by the Tier 3 method using CBM. The earlier estimates by the Tier 2 approach (as in NIR 2021) serve only as an independent verification of the CBM estimates of carbon stock changes in living biomass (Annex A 3.6.3).

The reported growing stock of merchantable volume from the database of FMP forms the basis for assessment of the carbon increment in living biomass for the Tier 3 CBM estimates. The key input to calculate the carbon increment is the volume increment (I_v) data. In the Czech Republic, these values have been calculated at CFI (FMP database administrator; see also Acknowledgment) and reported to the national and international statistics. The calculation is performed at the level of the individual stands and species using the available growth and yield data and models. The increment data were partly revised in the earlier NIR (2008) to unify two different base information sources (Schwappach 1923, Černý et al. 1996) for increment estimates and to employ only the latest source across the entire reporting period. This procedure was implemented to comply with the reporting requirements of consistent time series. No change thereafter, apart from entering the actual increment for the latest reported year, has been made to the increment in the inventory submissions (Fig. 6-11).



Fig. 6-11 Current annual increment (Increment, mil. m³ under bark) by the individual tree species groups as used in the reporting period 1990 to 2024 (source data CFI).

The merchantable volume increment (I_v) is used as an input to CBM following the procedure described above and detailed in Annex A 3.6.2.

The estimation of carbon loss in the category 4.A.1 Forest Land remaining Forest Land uses the annual amount of total harvest removals reported by CzSO for individual tree species in the country as well as the

[3] *Alternative approaches of the stock-change method (Eq. 2.8; IPCC 2006) were also earlier analysed (Cienciala et al. 2006a) for this category. However, for several reasons the default method was finally adopted and is discussed in the cited study.*

associated harvest loss, which is explicitly reported nationally by CzSO since 2009. Therefore, the total harvest drain (*H*) covers thinning and final cut, the amount of fuel wood, which is reported as an assortment under the conditions of Czech Forestry, as well as the associated harvest loss that is also linked to the amount of salvage logging (disturbances). To include the biomass loss associated with harvest, a fraction F_{HL} was added to the reported harvest volume; this was calculated from the annual harvest data and the share of salvage logging, assuming a 2.5% loss under planned forest harvest operations and 4% for accidental/salvage harvest that concern forest stands affected by natural disturbances. Hence, the harvest volume entering the actual emission calculation (Fig. 6-12 below) includes a correction by the above-described fraction, F_{HL}. This estimate was used to account for harvest losses associated with the reported harvest of merchantable wood volume and share of salvage logging until 2010. Since 2011, however, the introduced harvest loss estimate available from CzSO is used exclusively. The additional removals of solid wood and other harvest residues enter the estimation using a partitioning of 10 and 90% between the two woody components, respectively. This represents a conservative estimate of additional harvest losses that otherwise would not be accounted for. The total harvest loss is shown in Fig. 6-9. For CBM, this input is disaggregated by individual species groups and disturbance types relevant to harvest (Annex A 3.6.2.5), specifically thinning (Dist. 2 in CBM, Annex A 3.6.2.5), salvage felling resulting in clearcut (Salvage A, Dist. 3a in CBM), smaller-scale (spot-wise) salvage felling without clearcut (Salvage B, Dist. 3b in CBM) and planned, regular final cut (Dist. 4 in CBM). These harvest quantities by harvest types and species groups, as prescribed for the individual years of the reporting period, are shown in Fig. 6-12. Detailed information on the disturbance types and associated carbon matrices is included in Annex A 3.6.2.5.



Fig. 6-12 Harvest of merchantable volume (mill. m³) by species groups (Beech, Oak, Pine, Spruce) and type of harvest including thinning, salvage felling with (A) or without (B) clearcut and the planned final cut for the reporting period 1990 to 2024, serving as the prescribed management/disturbance inputs in CBM (converted to carbon units).

Hence, the impact of disturbances is included in full within the total harvest drain volume (*H*). Disturbances in the country are mandatorily registered in terms of salvaged wood volumes. Therefore, the available data on salvage logging from CzSO (and MA 2025) are also traceable in terms of disturbance origin by categories including natural disaster, air pollution, insect and other (Tab. 6-7 above). This information is also obligatorily reported by the forestry practice, which must always prioritize salvage logging on account

of the planned harvest. Consequently, any salvage felling is allocated to the total amount of wood removals, and it is thereby accounted for in the reported harvest volumes as shown in Fig. 6-12. Merchantable wood volume entering the requested disturbance quantity in the CBM input file was first converted to biomass using the prescribed species-specific wood densities (IPCC 2006) for beech and oak (0.58 t/m^3), pine (0.42 t/m^3) and spruce (0.40 t/m^3). Secondly, a carbon fraction of 0.5 was used for all species groups. Under-bark to overbark harvest entering the model as carbon quantities is finally estimated using species-specific coefficients derived from allometric equations used for the country-specific model parameterization, representing mass (biomass and/carbon) type of conversion, not volume. For comparative purposes, applicable volume under- to over-bark coefficients are 1.1 for all species groups except oaks, for which a value 1.15 is used. The detailed biomass and dead organic matter allocation pattern linked to harvest-disturbance types applied in CBM is described by the disturbance matrices included in Annex A 3.6.2.

The assessment of the net carbon stock change in dead organic matter, including deadwood and litter, and transfers to soil for category 4.A.1 was fully revised in the earlier (NIR 2022) inventory submission using the Tier 3 approach using CBM. Earlier (until NIR 2021 inclusive), a stock difference method according to Eq. 2.8 of IPCC (2006) was used to assess two deadwood components (lying deadwood wood and standing dead trees with a mean diameter of at least 7 cm) taken from the two NFI campaigns (Kučera and Adolt 2019). The assessment by CBM differs substantially, as it covers the entire carbon budget (including the essential biomass components less than 7 cm; see Annex Tab. A3 10 for the carbon pool attribution) and key ecosystem processes involved as represented by CBM (Fig. 6-10). Next, the adopted Tier 3 approach uses an annual time step covering the entire reporting period, avoiding any extrapolation as used earlier. This is specifically important for the conditions of dynamically changing harvest intensity in recent years, which inherently affect the entire biomass and DOM carbon turnover.

As for the litter pool of DOM in CBM, it includes three specific components (Annex Tab. A3 10). For an initial empirical verification, only data of the CzechTerra campaign 2008/2009 (CZT1) were available, providing a reference mean carbon stock held in litter (11.1 t C/ha; Cienciala et al. 2015). These data were not adequate for confirming carbon stock change estimates in litter for category 4.A.1, which resorted to using the Tier 1 assumption of no change (IPCC 2006) for this category until NIR 2021. Since NIR 2022 inventory submission, Tier 3 estimates by CBM are exclusively used to include emissions and removals from carbon stock changes in this DOM pool component. This estimate was further refined for NID 2026 using a newly released independent calibraton data (map of soil organic layer) of the ForCarbo project mentioned abobe (TACR No. SS06010148).

Similarly, the NIR 2022 inventory submission adopted the Tier 3 estimate of soil carbon stock change in mineral soils by CBM for category 4.A.1, including its two relevant components (Annex Tab. A3 10). This replaces the earlier Tier 1 (default) assumption of carbon stock changes considered to equal zero (Tier 1, IPCC 2006) in the earlier (until NIR 2021) submissions. Similarly, as for noted litter, this inventory submission (NID 2026) further refines the estimate of mineral soil carbon poll in the country-specific CBM-CFS3 model application using the newly released independent calibraton data (map of soil mineral layer 0 to 30 cm) of the ForCarbo project mentioned abobe (TACR No. SS06010148).

The adoption of the Tier 3 estimation for carbon stock changes in both litter and mineral soil by CBM can partly be substantiated with the empirical estimates of corresponding soil layer. However, even better verification data representing forest soil carbon stock changes under category 4.A.1 may become available once the NFI program in the country (Kučera and Adolt 2019) conducts and evaluates the repeated quantitative forest soil surveys. This can be expected by the mid- to late 2020s.

The estimated emissions and removals for individual carbon pools can be found in the corresponding reporting tables. For transparency, the estimated emissions by major pools for category 4.A.1 are displayed also graphically in Fig. 6-13.



Fig. 6-13 Carbon stock changes estimated for the category 4.A.1 Forest Land remaining Forest Land by major pools, namely living biomass, dead organic matter (litter including organic soil layers, and deadwood) and mineral soil (0 to 30 cm depth).

Emissions from organic soils are newly reported based on a technical correction suggested by the 2025 EEA review. It affects the areas of 4.A.1 Forest Land remaining Forest Land, and 4.C.1 Grassland remaining Grassland. Although organic soils on forest land in the country predominantly represent protected peat areas in mountainous regions dominated by spruce stands with no specific management practices, some locations of organic soils were drained in the past, which have been assessed and quantified in terms of their associated emissions in the NID 2026 inventory submission.



Fig. 6-14 Map of organic soils including their attribution to Forest land and Grassland.

We used geospatial data on organic soils from Research Institute for Soil and Water Conservation (RISWC; J. Vopravil, T. Khel, personal communication 2025) and a forest typology map to identify locations of organic soils. The total estimated area of organic soils in the country is 33 416 ha. They are located on land use categories Forest land and Grassland (Fig. 6-14). The area attributed to Forest land is 20 178 ha based on forest typology mapping (CFI).

Emissions are estimated exclusively for drained organic soils, which represent 10% of the organic soil area on Forest land, and 20% of those located on Grassland. This attribution was derived from the map of soil ameliorations obtained from RISWC. The reporting of emissions covers CO_2 from the soil (CO_2-$C_{on\text{-}site}$), CO_2 from dissolved organic carbon (CO_2-C_{DOC}), CH_4 from soil and drainage ditches, and N_2O from soil. The estimation involves multiplying the drained peatland areas per sub-category by corresponding land-use-specific emission factors (Eqs. 2.3 and 2.4; Wetlands Supplement IPCC 2013).

On-site emissions of CO_2 are calculated with the default emission factors of Table 2.1 (2.6 t C/ha/yr for Forest land – temperate climate zone). In addition, the off-site emissions from drainage of organic soils were estimated following Eq. 2.4 of the Wetlands Supplement and by using the default DOC emission factors from Table 2.2 for temperate climate (0.31 t C/ha/yr). The resulting annual on- and off-site CO_2 emissions from drained organic Forest land reached 22.1 kt CO_2 in 2024.

CH_4 and N_2O emissions from drained organic soils also follow the methodology of IPCC (2013). For CH_4, Eq. 2.6 and a default fraction of total area of drained organic soil which is occupied by ditches for the drained soil (EFCH4_land Table 2.3) and for ditches (EFCH4_ditch, Table 2.4) for drained Forest land in temperate zone were used, resulting in average annual emissions from Forest land of 16.3 kg CH_4 for 2024. N_2O emissions from drained organic soils are estimated by Eq. 2.7 (IPCC 2013) using default emission factors for drained forest land in temperate zone (2.8 kg N/ha/yr, Table 2.5). The resulting estimates of annual emissions from Forest land are 9.12 kg N_2O for 2024.

Emissions in category 4.A.1 Forest Land remaining Forest Land include, in addition to CO_2, other greenhouse gases (CH_4, CO, N_2O and NO_X) resulting from burning. This encompasses both prescribed fires associated with the burning of biomass residues associated with harvest, and emissions due to wildfires. The emissions from prescribed burning of biomass residues were estimated according to Eq. 2.27 of IPCC (2006) and the emission and combustion factors in Tables 2.5 and 2.6, respectively (IPCC 2006). Equation 2.27 reads as

$$L_{fire} = A \times M_B \times C_f \times G_{ef} \times 10^{-3} \quad (1)$$

where $L_{fire}$is the amount of greenhouse gas emissions from fire in tons of the gas considered (CH_4, N_2O), A is the area burnt (ha), $M_B$the mass of fuel available for combustion (t/ha), C_f the combustion factor (-) and G_{ef} the emission factor (g/kg).

Under the conditions in this country, part of the biomass residues is occasionally burned in connection with the final cut. Hence, this practice (prescribed burning) is limited to category 4.A.1 and does not occur in 4.A.2 Land converted to Forest land. There is no official estimate of the biomass fraction burned in forests in the country. The expert judgment employed in this inventory based on the reports from Czech Forest, s.a., considers that 1% of the biomass residues including bark is burned. This is less than assumed for the inventory years until 2000 (10%), 2010 (5%) and after 2011 (1%), respectively. It corresponds with the trend in current forest management practices in the country. The biomass fraction burned was quantified based on the annually reported amount of final felling volume of broadleaved and coniferous species, $BCEF_h$ and CF, as applied to harvest removals (above). The amount of biomass burned (dry matter) was estimated as 221 kt in 1990 and 23.2 kt in 2024. These values, as well as the applicable factors used in Eq. 1 to estimate emissions from fire, are listed in Tab. 6-9.

Tab. 6-9 Specific input data and factors used to estimate emissions of N_2O and CH_4 from prescribed burning in forests (1990 and 2024 shown) according to Eq. (1)

Variable or conversion factor	Unit	Year 1990	Year 2024
Amount of biomass burnt (AxM_B)	kt	220.8	23.2
Combustion factor (C_f)	-	0.62	0.62
Emission factor (G_{ef}) for $_{CH4}$	g.kg^{-1} dry matter burnt	4.7	4.7
Emission factor (G_{ef}) for N_2O	g.kg^{-1} dry matter burnt	0.26	0.26

Note that Tab. 6-9 does not show a factor associated with the release of CO_2 in prescribed burning (only CH_4 and N_2O are listed). This is to prevent double counting, as that part of emissions is already included within the harvest loss. Finally, Tab. 6-9 also does not list the factors used to estimate gases of CO and NO_X, which are complementarily estimated using Eq. 1 together with emission factor (G_{ef}) equal to 107 and 3, respectively.

The emissions of greenhouse gases due to wildfires were estimated based on known areas burned annually by forest fires and the average biomass stock in forests according to Eq. 2.14 (IPCC 2006). The associated amounts of non-CO_2 gases (CH_4, CO, N_2O and NO_X) were estimated according to Eq. 2.27 (IPCC 2006), which is listed above as Eq. 1. The combustion factor (C_f) used was 0.45 (Table 2.6, IPCC 2006), whereas emission factors for individual gases as well as carbon fraction were identical as those for prescribed burning listed above. The amount of biomass (dry matter) burned in wildfires was estimated as 10.2 kt in 1990 and 10.5 kt in 2024. The most extreme year of the reporting period was 1997, when about 228 kt of biomass was burned due to wildfires in an area of almost 3.5 th. ha. In 1990 and 2024, the reported forest areas under wildfire were 168 and 140 aha, respectively. The largest single recorded wildfire event in the country was recorded in 2022 resulting in 1060 ha of burned area of the Bohemian-Switzerland National Park (Kudláčková et al. 2023). During the reporting period since 1990, there has not been a single year without reported wildfire. The mean annual forest area affected by forest wildfires reached 593 ha in the period 1990 to 2024 with no significant trend. The full time series of forest wildfires in terms of areal extent and number of fires per year is shown in Fig. 6-15. The associated emissions of non-CO_2 gases can be found in the corresponding CRT Tables.

There are no direct N_2O emissions from N fertilization on Forest Land, as there is no practice of nitrogen fertilization of forest stands in the Czech Republic.



Fig. 6-15 Wildfires on forest land since 1990 – annual area (ha; left; bars) and number of fires per year (n; right; filled symbols).

6.4.2.3 Land converted to Forest Land

The methods employed to estimate emissions in the 4.A.2 Land converted to Forest Land category are identical or coherent with those for the category 4.A.1 Forest Land remaining Forest Land (cf. Tab. A3 9 in Annex A 3.6.1). The exception is mineral soil, which under 4.A.2 includes other land-use categories not covered by CBM, and the previously developed Tier 2 methodology based on soil carbon map layers is retained.

For estimation of the net carbon stock change in living biomass on Land converted to Forest Land according to IPCC 2006 Gl. (IPCC 2006), the carbon increment is proportional to the extent of afforested areas and the growth of biomass. The adopted methodology to identify land-use change (Section 6.2) provides areas of all conversion types updated annually, which are directly used by CBM. Land areas are under conversion for a period of 20 years, according to the default assumption of IPCC (2006). Under the conditions in this country, all newly afforested lands are considered as managed lands under the prescribed forest management rules as specified by the Czech Forestry Act.

The increment, as well as the entire CBM calibration routine, is fully applicable to age classes I and II (stand age up to 20 years, i.e., category 4.A.2) as estimated from the actual wood volumes and areas per major species groups, as described in detail in Annex Tab. A3 6. It should be noted that the CBM model uses a curve-smoothing algorithm to estimate above-ground biomass when there is little or no merchantable volume (see more in Kurz et al. 2009), which aids estimations for small-growth (young) stands.

Since the specific tree species composition of the newly converted land is unknown, the information of tree species share used for afforestation in category 4.A.2 in CBM utilized 40, 10, 20 and 30% for beech, oak, pine and spruce tree species groups, respectively. These proportions were identified iteratively to match the observed development of species composition for the reporting period (see more details in Annex A 3.6.2).

Similarly, the carbon loss associated with biomass disturbance in terms of management and mortality in the category of Land converted to Forest Land was coherent with that applied for 4.A.1 as described elsewhere. Specifically for 4.A.2, turnover and transfer rates are applied identically as detailed in Annex A 3.6.3, whereas the effect of management interventions is insignificant (zero) for forest stands until

reaching 20 years. This is because the first significant thinning occurs in older age classes, which is implicitly accounted for within the category Forest Land remaining Forest Land. It is also important to note (in response to the previous inventory reviews) that under the conditions in this country, there is no biomass loss due to natural disturbance on land that is newly converted to forest land. As is also apparent from the national statistics, there is no volume of salvage logging reported for this category, which reflects the actual conditions of forest ecosystems of the age concerned. Loss of existing living biomass for land-use coversions from agricultural land (Cropland, Grassland) is newly accounted for using the default values in Tables 5.9 and 6.4 of IPCC (2019).

The net changes of carbon stock in dead organic matter (DOM) applicable to 4.A.2 were estimated in accordance with the guidance of the Tier 2 methods (IPCC 2006), using the CBM estimates of carbon stocks in forest DOM pool components (deadwood and litter) as reference values (Fig. 6-16). This approach assumes that deadwood and litter carbon pools increase linearly from zero to the reference values for the given country-specific conditions. For deadwood, a conservative value of the transition period for developing the deadwood carbon stock of 100 years was used, while for litter, the default (IPCC 2006) period of 20 years was used.



Fig. 6-16 Mean carbon stock (t C/ha) of DOM components litter (incl. soil organic layer) and deadwood for the reporting period.

The net change of carbon stock in mineral soils was estimated using the country-specific Tier 2/Tier 3 method. This was based on vector maps of topsoil organic carbon contents (ForCarbo project TACR No. SS06010148 for forest soils, Vopravil and Khel 2020, 2025 for agricultural soils, see Fig. 6-17). Both forest and agricultural mineral soils represent organic carbon contents to a reference depth of 30 cm.

Hence, this submission improves the estimates of soil organic carbon for both forest and agricultural land. Until the NID submission 2025, forest soil organic carbon was based on soil sampling combined with forest typology maps, while newly adopted soil carbon layers from ForCarbo project (TACR No. SS06010148) used dominantly soil sampling of the National Forest Inventory in the country (Kučera and Adolt 2019). As for agricultural land, soil organic carbon layer was prepared by experts from RISWC and detailed in Vopravil and Khel (2020). This inventory submission (NID 2026) further refines the content of the mineral soil on Grassland based on the update of Vopravil and Khel (2025).

The polygonal compilation of the source maps was used to obtain the mean carbon content per individual cadastral unit (n = 13 074 in 2024), serving as reference levels of soil carbon stocks applicable to Forest land, Cropland and Grassland land use categories (Fig. 6-17). This system permitted an estimation of the

soil carbon stock change among these categories. The estimated quantities of carbon stock change at the level of individual spatial units were entered into 20-year accumulation matrices distributing carbon into fractions over 20 years (IPCC 2006). These quantities, together with the accumulated areas under the specific conversion categories, were used for estimating the associated emissions and removals of CO_2.



Fig. 6-17 Top - topsoil (30 cm) organic carbon content map adapted from ForCarbo project (2025), Vopravil and Khel (2025) estimated as cadastral unit means from the source maps {bottom] –topsoil carbon content for agricultural (left) and forest (right). The unit (t/ha) and unit categories are identical for all the maps

In 2024, the area-weighted mean carbon stock in mineral soil per cadastral unit reached 66.1, 53.1 and 74.1 kg C/ha for Forest land, Cropland and Grassland, respectively.

There are no organic soils linked to category 4.A.2 Land converted to Forest land. Therefore, no emission estimates from organic soils are attributed to this category.

The estimated emissions and removals for individual carbon pools for category 4.A.2 can be found in the corresponding reporting tables. For transparency, the estimated emissions by major pools are also displayed graphically in Fig. 6-18.



Fig. 6-18 Carbon stock changes estimated for the category 4.A.2 Land converted to Forest Land by major pools, namely living biomass, dead organic matter (litter and deadwood) and mineral soil.

Non-CO_2 emissions from burning are not estimated for category 4.A.2 Land converted to Forest Land, as this practice is not employed in this category in the country.

Since this inventory submission (NID 2026) emissions of N_2O due to mineralization are estimated for the category 4.A.2. The estimation follows the Tier 1 approach of Eqs. 2.25 and 11.8 (IPCC 2006). Accordingly, direct N_2O emissions were quantified based on the detected changes in mineral soils employing a default emission factor of 0.01 kg N_2O-N/kg N (EF1, IPCC 2006), and C:N ratio of 12 (grassland and wetlands soils). Linked to this, indirect N_2O emissions from atmospheric deposition of N volatized from managed soils were estimated using Eq. 11.10 and the emission factor 0.011 (EF5, IPCC 2019).

No N_2O emissions from nitrogen fertilization apply to forest land in this country.

6.4.3 Uncertainties and time-series consistency

The methods used in this inventory were consistently employed throughout the whole reporting period from the base year of 1990 to 2024.

The uncertainty estimation was guided by Approach 1 outlined in IPCC 2006 Gl. (IPCC, 2006) employing the following equations:

$$U_{total} = \sqrt{U_1^2 + U_2^2 + \ldots + U_n^2} \qquad (2)$$

where U_{total} is the percentage uncertainty in the product of the quantities and U_i denotes the percentage uncertainties with each of the quantities (Eq. 3.1, Volume 1, Chapter 3, IPCC 2006 Gl.).

For the quantities that are combined by addition or subtraction, we used the following equation to estimate the uncertainty:

$$U_{total} = \frac{\sqrt{(U_1 * x_1)^2 + (U_2 * x_2)^2 + \ldots + (U_n * x_n)^2}}{|x_1 + x_2 + \ldots + x_n|} \quad (3)$$

where U_{total} is the percentage uncertainty of the sum of the quantities, U_i is the percentage uncertainty associated with source/sink i, and x_i is the emission/removal estimate for source/sink i (Eq. 3.2, Volume 1, Chapter 3, IPCC 2006 Gl.).

It should be noted, however, that Eq. 3 is not well applicable for the LULUCF sector. Summing negative (removals) and positive (emission) members (x_i) in the denominator of Eq. 3 may produce unrealistically high uncertainties and theoretically lead to division by zero, which is not possible. In this respect, this approach is not correct. In previous inventory reports, we stressed this issue and recommended focusing on individual uncertainty components prior to the resulting product of Eq. 3.

The adopted uncertainty values are listed below and/or under the corresponding subchapters of other land use categories. Since this inventory newly implemented Tier 3 modelling approach using CBM for several carbon pools, it makes the rigorous uncertainty estimation challenging. Most commonly, modelled estimates require the use of Monte Carlo analyses (Approach 2 of IPCC 2006), conducting many model runs or repeated analyses with varied input parameters to represent the uncertainty in individual input data (Kurz et al. 2016). This has not been performed yet due to the time and capacity constraints. Hence, for this inventory, the interim uncertainty estimate is based on a conservative expert judgement and literature, including the recent NIR (2021) inventory submissions of Canada and Ireland, where CBM (CBM-CFS3) was also used. Specifically, we assume for the Tier 3 carbon stock change estimates for living biomass, DOM (both litter and deadwood) and mineral soil the overall uncertainty 25, 50 and 100%, respectively. Also, a more conservative value of 50% was used biomass carbon stock change estimates under land use conversions associated with forest land.

For all other (Tier 2) estimates, the source information for adjusted uncertainty values was obtained from the conducted CzechTerra statistical (sample-based) landscape inventory of the Czech Republic (Černý et al., 2009, Cienciala et al. 2015). Otherwise, the uncertainty estimation utilized primarily the default uncertainty values as recommended by UNFCCC (2005) and IPCC (2006) that concern areas of land use (5%), biomass increment (6%), amount of harvest (20%), carbon fraction in dry wood mass (7%), root/shoot factor (30%) and combustion factors used in calculation of emissions from prescribed (20%) and forest fires (36%), respectively, based on the information in Table 2.6 (IPCC 2006). The uncertainty applicable to *BCEF* was 22%, which was derived from the work of Lehtonen et al. (2007). The uncertainty associated with fractions of unregistered loss of biomass under felling operations was set by expert judgment at 30%. The stem volume mortality estimate is accompanied with an uncertainty of 12% based on Adolt et al. (2016).

The approach of uncertainty combination for individual sub-categories of tree species is based on calculating the mean error estimate from the components of carbon stock increase and carbon stock loss, which are both given in identical mass units of carbon per year. At the same time, we retained the recommended logic of combining uncertainties on the level of the entire land use category or on the level of the entire LULUCF sector according to Eq. 3. This is calculated based on CO_2 or CO_2 eq. units and the corresponding uncertainty estimates respect the actual direction of the source and sink categories to be combined.

For 2024, the uncertainty estimates for categories 4.A.1 Forest Land remaining Forest Land and 4.A.2 Land converted to Forest Land using the above-described approach reached 54% and 21%, respectively. Correspondingly, the uncertainty for the entire 4.A Forest Land category reached 42%.

6.4.4 Source-specific QA/QC and verification

Following the recommendation of the previous in-country review, a sector-specific QA/QC plan was formulated, tightly linked to the corresponding QA/QC plan of the National Inventory System. The plan describes the key procedures of inventory compilation and provides a table of personal responsibilities and a timetable of sector-specific QA/QC procedures. This plan consolidates the quality assurance procedures and facilitates effective quality control of the LULUCF inventory.

All the calculations are based on the activity data taken from the official national sources, such as the Forest Management Institute and the Ministry of Agriculture, the Czech Statistical Office, the Czech Office for Surveying, Mapping and Cadastre (COSMC) and the Ministry of the Environment. Data sources are verifiable and updated annually. The gradual improvement of survey methods, information technology implementation, checking procedures, and quality assurance should result in increasingly accurate emission estimates. The QA/QC procedures generally cover the elements listed in Table 6.1 of IPCC (2006) Guidelines, Volume1, Chapter 6.

The input information and calculations are archived by the expert team and the coordinator of the National inventory system. Hence, all the background data and calculations are verifiable.

Apart from the official review process, emission inventory methods and results are internally reviewed among the technical experts involved in the emission inventory of the Agriculture and LULUCF sectors. Whenever feasible, the methods are documented in peer-review scientific publications, and by expert team reviews within the relevant national research projects.

6.4.5 Source-specific recalculations, including changes made in response to the review process and impact on emission trends

Since the last submission, the emission estimates were recalculated for category 4.A (Forest land) across the entire reporting period. This was due to the revised parameterization of biomass equations needed for the CBM-CFS3 modeling tool following the fundamental concepts of Boudewyn et al. (2007), based on the newly acquired pameterization data from the Czech National Forest Inventory (J. Máslo, CFI, 2025 – personal communication). This required a revised handling of input activity data in the model retaining under-bark units consistent with all harvest activity data in the country (Ch. 6.4.1) used in the CBM-CFS3 model. These changes affected the estimates in all carbon pools in category 4.A. Other changes implemented in this inventory submission for category 4.A include new emission estimates for organic soils, and N_2O estimates associated with carbon loss from land-use conversions. Furthermore, this inventory submission (NID 2026) improved the national CBM-CFS3 calibration by implementing air temperature data recompiled from available meteorogical measurements in the country that spatially represent the areas of forest land. Finally, the new soil carbon layers implemented in this inventory submission affected emission estimates for litter and mineral soils. The implemented revisions resulted in an on average 4.3% increased sink for 4.A Forest land over the reporting period (excluding the last year), compared to the previous NID submission. Most of that difference was attributed to the 4.A.1 subcategory, while the quantitative impact on 4.A.2 was about 1% (increased sink).

For transparency, the estimates for category 4.A Forest land are displayed graphically in Fig. 6-19, including the current (NID 2026) and previous (NID 2025) inventory submission.



Fig. 6-19 Estimated emissions for category 4.A Forest land – the current (NID 2026) and previous (NID 2025) inventory submission.

With respect to the issues identified by the latest inventory review (ARR 2022) that concern 4.A Forest land, these were addressed in detail in the earlier NIR (2023) submission. Since no new UNFCCC review was conducted in 2024 and 2025 (a new UNFCCC in-country review is scheduled for March 2026), we retain the response from the earlier inventory submissions with respect to the ARR 2022 issues L.3, L.10 and L.11.

- L.3 - addressing consistency issue for estimates of additional harvest fraction: In addition to enhanced information on harvest activity data (Sections 6.4.1, 6.4.2), the harvest fractions for additional harvest were modified (Ch. 6.4.1). Currently, they represent on average a quantity of 0.41 Mm^3/year for the reporting period. The inventory team works on additional verification and validation of these estimates. Note, however, that its quantitative importance remains minor, in fact corresponding to only 2.6% of the base harvest for the reporting period.

- L.10 – (text retained from the NIR 2023 submission with amended evidence of the NID 2025 submission where explicitly noted) question on IEF for litter and verification analysis for carbon stock change in the litter and deadwood pools on 4.A.1 Land remaining Forest land. Apart from the information already provided in the NIR/NID and to the Expert Review Team in 2022 in response to this request, we state that carbon stock change (CSC) in the litter pool is driven by harvest inputs and respiration loss of the entire litter stock that is caused by respiration and accumulation over several years, hence the dynamics in CSC are not directly comparable with harvest quantities. For the period prior to the current bark-beetle outbreak (not including recent exceptional years), there is no significant relationship between CSC in the litter pool and harvest level since the respiration processes over accumulated litter stock would be decoupled from annual harvest volumes. This was checked by a linear regression analysis, which for the period 1990–2015 showed zero explained variability (R^2=0.0) and no significance (p=0.908). With respect to the questioned absolute quantities of CSC in litter, please note that they reflect the specific (and – at least within European countries - exceptional) trend of harvest due to the historically unprecedented dieback of coniferous stands due to drought-induced bark-beetle infestation – as described e.g. in Section 6.4.1. This can also be substantiated by the latest IEF for CSC in litter that dropped to 0.19 in 2021, i.e., 46% of the 2020 peak and matching the range of the observed values for other countries as noted by ERT in ARR 2022 (Note: Estimates were revised in NID 2024 in association with improvements in disturbance matrices affecting DOM pools. In NID 2025, further corrections to DOM estimates and IEFs were incorporated). This development of CSC in litter is

also fully in accordance with the observed reversal of harvest trend and hence emissions for this category. Deadwood estimates are inconsistent observations from statistical forest inventories, such as the Czech NFI (Kučera and Adolt 2019) or Landscape inventory CzechTerra (Cienciala et al. 2016). However, no observation-based forest inventory can capture all carbon pool components at the scale of the country. For this reason, the estimates from modeling tools such as CBM-CFS3 (Kurz et al. 2009, Kull et al. 2019), which represent Tier 3 methods, are the only practicable approaches at that scale and time resolution of individual years. They allow insight into carbon stock changes covering the entire ecosystem and changes in all pools involved (for example, using 21 carbon compartments in CBM-CFS3). Since the simulated ecosystem is fully constrained in the model, the independent verification provided for living biomass provides a reliable basis for estimating other carbon pools, based on the use of verified decay rate constants, country-specific tree allometry, forest structure, increment rates and known harvest volumes. Since this explanation is rather technical, it is not integrated in the main text but provided here for the forthcoming expert reviews.

- L.11 – (text retained from the NIR 2023 submission) transparency issue (attributed to 4.A.2 Land converted to Forest land) on reference mean carbon stock values for litter and its development over time. Section 6.4.2 presents empirical estimates from Landscape inventory CzechTerra that closely match CBM estimates. Without repeated field assessments that would allow estimating CSC in litter, the adoption of Tier-3 approach using the nationally calibrated CBM-CFS3 model is the only solution providing transparent estimation of CSC for the entire reporting period. The litter CSC trend reflects the fluxes and processes affecting this pool – most prominently the applied tree species group-specific harvest intensity and decay rates. Litter and deadwood estimates are consistent with those from similar conditions in other countries (e.g., Slovenia). The trends in the litter pool correspond to both growing stock development and harvest intensity changes. Using different reference estimates for the litter pool in 4.A.2 than for 4.A.1 would simply be incoherent, and hence inadvisable. Similarly, as for issue L.10 above, this reasoning is not integrated in the main text but provided here for the fothcomming reviews.

The most recent 2025 EEA review identified five issues, all of which have been addressed in this inventory submission. The specific information is provided below:

- CZ-4A1-2025-0002 – Emissions from drainage of organic soils. The revision followed the technical correction prepared by review team, updating the underlying activity data as described in Section 6.4.2.2.

- CZ-4-2025-0002 – N_2O emissions for all land-use conversion types and instances resulting in carbon loss in mineral soil, see Section 6.4.2.3.

- CZ-4A1-2025-0001 – Transparency issue regarding information on controlled burning of biomass residues after harvest is addressed in Section 6.4.2.2.

- CZ-4A2-2025-0001 – Biomass loss (initial biomass) component for land-use conversion categories is newly included, see Section 6.4.2.3.

- CZ-4D2-2024-0001 – Mineral soils in wetlands are explicitly considered and accounted for in all relevant land-use conversions affecting carbon stock changes and corresponding emission estimates.

6.4.6 Source-specific planned improvements, including those in response to the review process

The inventory team initiated a collaboration with the Czech Forestry Institute (former Forest Management Institute), Brandýs n. Labem, to revise the methodology for category 4.A Forest land, fully utilizing the sample-based National Forest Inventory (NFI) and its recently completed third campaign (NFI3, Máslo et al. 2023). These data will serve as a basis for revised CBM-CFS3 model calibration at NUTS3 spatial resolution (Annex Tab. A3 6; Cienciala and Melichar 2024). Recalibration work on the model using new NFI activity data is ongoing, with pilot implementation scheduled for the NID 2027 submission. While current Tier 3 approaches using CBM adequately address ecosystem carbon balance complexity under recent forest decline conditions, more timely calibration and verification data from the NFI program are needed to increase model robustness and accuracy. Additionally, NFI data will identify forest stands not designated in cadastral records—and hence not covered by management plans or Forest Act regulations—but meeting FAO forest definitions. Attributing NFI plots to cadastral land use categories will enable inclusion of these additional forest resources in the emission inventory, while accordingly adjusting areas of non-forest land use categories.

The full implementation of NFI data for the LULUCF inventory and sectoral projections is now supported by a new collaborative project funded by the Ministry of Agriculture (NAZV QL26020203, 2026-2028). This collaborative framework enables the consortium institutions to better integrate and utilize research results from their respective related projects, thereby enhancing the overall quality and coherence of the LULUCF inventory.

6.5 Cropland (CRT 4.B)

6.5.1 Source category description

In the Czech Republic, Cropland (Fig. 6-20) is predominantly represented by arable land (91.7% of the category in 2024), while the remaining area includes hop-fields, vineyards, gardens and orchards. These categories correspond to five of the six real estate categories for agricultural land from the database of “Aggregate areas of cadastral land categories” (AACLC), collected and administered by COSMC.

Cropland is spatially the largest land-use category in the country. At the same time, the area of Cropland has constantly been decreasing since the 1970s, with a particularly strong decreasing trend since 1990 (Fig. 6-4). While, in 1990, Cropland represented approx. 43.8% of the total area of the country, this share decreased to 39.9% in 2024. It can be expected that this trend will continue. The conversion of arable land to grassland is actively promoted by state subsidies. Conversion to grassland concerns mainly lands of less productive areas of mountainous regions. In addition, there is a growing demand for land for infrastructure and settlements.



Fig. 6-20 Cropland in the Czech Republic – distribution calculated as a spatial share of the category within individual cadastral units (as of 2024)

6.5.2 Methodological issues

The emission inventory of Cropland concerns sub-categories 4.B.1 Cropland remaining Cropland and 4.B.2 Land converted to Cropland. The emission inventory of Cropland considers changes in living biomass, dead organic matter, and soil. In addition, N_2O emissions associated with soil disturbance during land-use conversion to cropland are quantified for this category.

6.5.2.1 Cropland remaining Cropland

For category 4.B.1 Cropland remaining Cropland, the changes in biomass can be estimated only for perennial woody crops. Under the conditions in this country, this is applicable to the categories of vineyards, gardens (one half of the area considered used for perennial vegetation) and orchards. These activity data are shown in Fig. 6-21.



Fig. 6-21 Trend in perennial cropland area in the Czech Republic for the period 1970 to 2024

In NIR 2021, the estimation of emissions associated with biomass accumulation on Cropland was revised and updated according to the new biomass accumulation rates of 0.43 t C/ha/year for orchards and 0.28 t C/ha/year for vineyards as recommended by IPCC (2019). This also applies for maximum carbon stock at harvest (8.5 t C/ha for orchards and 5.5 t C/ha for vineyards, IPCC, 2019).

In the NIR 2022 inventory report, the estimation procedure was also revised. While earlier the carbon stock change in perennial biomass was solved as a difference between consecutive years, it is newly estimated from the perennial cropland area 20 years ago. This respects the 20-year harvest cycle for orchards and vineyards (IPCC, 2019). The estimation can be written as:

Annual change of biomass = (remaining area of perennial cropland x annual carbon accumulation rate) – (remaining area of perennial cropland before 20 years x 1/20 (i.e., rate of area at end of rotation period) x biomass carbon stock at end of rotation period)

Overall, the perennial cropland area has an increasing trend (Fig. 6-21) for the period 1970–2024 (137 503 ha in 1970, 156 163 ha in 2024). Therefore, the carbon pool of living biomass within 4.B.1 represents a CO_2 sink for the entire period.

The carbon stock change of dead organic matter follows the Tier 1 method assumption of IPCC (2006) that dead wood and litter stocks are not present on Cropland or are at equilibrium. Hence, no change is assumed for this pool.

The carbon stock change in soil in the category Cropland remaining Cropland is given by changes in mineral and organic soils. Organic soil basically does not occur on Cropland; they occur as peatland in mountainous regions on Forest Land and Grassland. Since the NIR 2021 submission, the estimation of emissions from agricultural soil was revised using a new soil carbon layer map with a reference depth of 30 cm.

Seven specific categories were defined for Cropland remaining Cropland (Tab. 6-10). They discern non-perennial and perennial vegetation categories and their specific subtypes and lead the choice of emission factors.

For the calculation of F_I, in addition to IPCC default values, published data from the experiments for different intensities of fertilization in the Czech Republic were also used (Kubat et al., 2006; Menšík et al., 2019 and Šimon et al., 2011). Then, a specific set of practices associated with input (e.g., share of residues,

amount of mineral or organic fertilization, use of intercrops etc.) were attributed to each crop species, based on expert knowledge from Czech Agrifood Research Center (CARC). Since most crops deploy two or more practices with different F_I (usually a combination of default and specific factors), an activity weighted F_I for each crop was calculated. Finally, an average crop species area weighted F_I was defined. Similarly for the management factor (F_{MG}), a typical management approach for a given crop was defined by expert knowledge (CRI). To each group of defined tillage activities (e.g., types and frequency of tillage, soil preparation, etc.) an IPCC default F_{MG} was ascribed and calculated for a given crop. Finally, an average crop species area weighted F_{MG} was estimated and used for a given vegetation category. This was revised for the NID 2025 inventory submission for vegetation categories I and II (Tab. 6-10) using the soil carbon map data (Vopravil et al. 2025). Other emission factors related to land use (F_{LU}) and input (F_I) correspond to the recommended values of Table 5.5 for the temperate moist region (IPCC 2006, 2019). These categories and factors are summarized in Tab. 6-10.

Tab. 6-10 Categories of management activities by vegetation category on Cropland remaining Cropland, attributed land use, tillage (management) and input factors and corresponding areas (1990 and 2024 shown)

Management activity by vegetation category	Land use F_{LU}	Tillage F_{MG}	Input F_I	Area in 1990 [kha]	Area in 2024 [kha]
I. Non-perennial, arable land, no fallow	0.70	1.07	1.01	2 961.9	2 749.6
II. Non-perennial, arable land, fallow	0.82	1.27	0.92	191.0	109.3
III. Non-perennial, gardens (1/2)	0.70	1.04	0.92	78.9	93.4
IV. Non-perennial, hop fields	0.70	1.04	0.92	11.3	8.6
V. Perennial, gardens (1/2)	1.00	1.09	0.92	78.9	93.4
VI. Perennial, orchards	1.00	1.09	0.92	51.1	42.0
VII. Perennial, vineyards	0.72	1.04	0.92	15.8	20.8

The emission estimation follows Eq. 2.25, assuming a 20-year default period for time dependence of stock change factors (D) and using the soil carbon layer in cropland mineral soils. The national source of activity data required for the adopted categorization of management on cropland is COSMC as for the annually updated areas of basic vegetation categories that determine management activities listed in Tab. 6-10. The assumption was made on share of perennial and non-perennial gardens, which was attributed identically by one half of the reported areal extent of gardens. Next, the share of fallow arable is currently obtained from CzSO and earlier from the periodic Farm Structure Surveys conducted in 2016, 2013, 2007, 2005, 2003 and Agricultural Census 2010.

Next, the detailed spatially explicit land-use conversion data including cropland vegetation categories (Tab. 6-10) were made available from COSMC at the level of individual cadastral units for the period 2002–2024. This allowed spatially explicit identification of changes related to land management. This, together with geographical layer of soil organic carbon in agricultural land and emission factors expressing the applicable management facilitated estimation of the related soil carbon stock changes.

For the period 1990 to 2001, the emission estimates used information on cropland vegetation categories only at the country level. To make this information consistent with the more recent detailed data since 2002, a post-calibration based on the data from the period 2002–2024 using linear regression (R^2=0.97, $p<0.001$, n=23) relationship that was applied on the former data estimates (period 1990–2001) to ensure methodological coherency for entire reporting period. This methodological improvement corrected the previous estimates. Specifically, the approach avoided possible double counting of emissions in categories 4.B.1 and 4.B.2.

Until the NIR submission 2014, the Cropland category also included emissions due to liming. Due to the specific trend in lime application in this country, emissions from lime application made the former 4.B.1 Cropland remaining Cropland the key category by trend. However, since the NIR 2015 submission, the emissions from liming are excluded from 4.B.1 Cropland remaining Cropland and reported under category 3.G Liming in the sector of Agriculture instead.

Non-CO_2 greenhouse gas emissions from burning (CH_4, N_2O) do not occur in category 4.B.1 Cropland remaining Cropland, as this practice is not implemented on Cropland in this country.

6.5.2.2 Land converted to Cropland

Category 4.B.2 Land converted to Cropland includes land conversions from other land-use categories. Cropland has generally decreased in area since 1990, by far mostly converted to Grassland. However, the adopted detailed system of land-use representation and land use change identification system can detect land conversions in the opposite direction, i.e., to Cropland.

The estimation of carbon stock changes in living biomass in category 4.B.2 Land converted to Cropland was based on quantifying the difference between the carbon stock before and after the conversion, including the estimation of one year of cropland growth (4.7 t C/ha; Table. 5.9, IPCC 2019), which follows Tier 1 assumptions of IPCC (2006) and the recommended default values for annual cropland.

Until the NIR 2022 submission, the estimation of the total carbon loss (L_{Def}) associated with wood removals under Forest land converted to Cropland, followed Eq. 2.14 (AFOLU 2006) applied as

$$L_{Def} = A_{Def} \times V_{ab} \times BCEF_{Def} \times (1 + R) \times CF \times fd \quad (4)$$

where A_{def} is the area (ha) of forest land converted to other land use (Cropland in this case), V_{ab} is the mean aboveground merchantable volume, $BCEF_{Def}$ represents the biomass expansion and conversion factor applicable to harvested volumes under deforestation, derived from national studies or regional compilations that include the data from the Czech Republic, representing species-specific volume-weighted mean of all age classes and individual dominant tree species, as the actual stand age of those harvested deforested volumes is unknown. The carbon fraction (*CF*) in woody currently used for broadleaved and coniferous tree species represented temperate forest categories as reported by Thomas and Martin (2012), volume weighted mean from the actual species composition. The ratio of below-ground biomass to above-ground biomass (*R*) was estimated for individual species groups and corresponding actual growing stock volumes based on the recommended values for forests in temperate-zone in Table 4.4 of IPCC (2006). This formerly applied approach, activity data and emission factors are detailed in the earlier (NIR 2022) submission.

Since the NIR 2023 inventory submission, for deforestation events represented by the Convention categories of Forest land converted to other land use categories (4.B.2.a, 4.C.2.a, 4.D.2.a, 4.E.2.a), loss of carbon in living biomass is quantified fully by CBM (Tier 3, Tab. 6-8) using the corresponding deforestation areas from annually updated Land use representation and land-use change identification system based on the data from COSMC (Sections 6.2 and 0). Since the species composition of deforested areas is unknown, these areas in the CBM runs were technically attributed to Spruce, the most represented tree species group. This makes estimation of deforestation impact somewhat more conservative in terms of carbon loss as compared to the previous Tier 2 estimates used for the corresponding land-use conversions earlier. This is because the spruce forest type has the largest growing stock volume per hectare relative to other tree species groups, which in somewhat different proportions also applies for mean aboveground biomass and carbon held in it. The quantitative impact of these differences is included in the comparison of former NIR/NID and current NID submissions (Section 6.5.5), while other details can be found in the corresponding CRT tables, including the applicable deforested areas in each year of the reporting period.

For biomass carbon stock on Grassland prior to the conversion, the default factor of 6.8 t/ha for above-ground and below-ground biomass was used (Table 6.4, IPCC 2006). A biomass content of 0 t/ha was assumed after land conversion to 4.B Cropland, while including the assumend annual cropland growth (4.7 t C/ha; Table. 5.9, IPCC 2019).

The estimation of net carbon stock changes in dead organic matter pools concerns land use conversion from Forest Land. These were assessed as conservative loss of litter and aboveground deadwood using the Tier 3 CBM estimates of mean carbon stock in these DOM pool components (Fig. 6-22).



Fig. 6-22 Mean carbon stock (t C/ha) of DOM components litter and aboveground (AG) deadwood for the reporting period.

Estimation of the carbon stock change in soils for category 4.B.2 Land converted to Cropland in the Czech Republic concerns mineral soils. The soil carbon stock changes following the conversion from Forest Land, Grassland, Wetlands and Settlements were quantified by the country-specific Tier 2/Tier 3 approach and are described in detail in Section 6.4.2.2 above.

The Land converted to Cropland category represents a source of non-CO_2 gases, namely emissions of N_2O due to mineralization. The estimation followed the Tier 1 approach of Eqs. 2.25 and 11.8 (IPCC 2006). Accordingly, direct N_2O emissions were quantified based on the detected changes in mineral soils employing a default emission factor of 0.01 kg N_2O-N/kg N (EF1, IPCC 2006), and C:N ratio of 21.8 (forest land soils, For Carbo project 2025), 12 (grassland and wetlands soils, following NID2025 for Austria) and 15 (settlements). Linked to this, indirect N_2O emissions from atmospheric deposition of N volatized from managed soils were estimated using Eq. 11.10 and the emission factor 0.011 (EF5, IPCC 2019).

Other non-CO_2 emissions may be related to those from burning. However, this is not an adopted practice in this country and no other non-CO_2 emissions besides those described above are reported in the LULUCF sector.

6.5.3 Uncertainties and time-series consistency

The methods used in this inventory were consistently employed across the whole reporting period from the base year of 1990 to 2024, and this also applies to the Cropland land-use category. The uncertainty estimation was guided by the Tier 1 methods outlined in the IPCC 2006 Gl. (IPCC 2006) and described in Section 6.4.3. The uncertainty estimation utilized primarily the default uncertainty values as recommended by UNFCCC (2005) and IPCC (2006, 2019). The following uncertainty values were used: land use areas 5%, biomass accumulation rate 46%, change in living biomass assessed by CBM 50% for deforestation events, stock change factor for land use 50%. Uncertainty associated with reference soil carbon was 10% and uncertainty of array of individual emission factors used for mineral carbon stock change estimation were taken from Table 5.5 of IPCC (2006). The adopted uncertainty associated with the

emission factors involved in estimation of direct and indirect N_2O emissions was 250% (Table 11.1., IPCC 2006).

For 2024, using the above uncertainty values, the total estimated uncertainty for category 4.B.1 Cropland remaining Cropland was 35%. The corresponding uncertainty for category 4.B.2 Land converted to Cropland was 20%. The overall uncertainty for category 4.B Cropland was estimated to be 28% (noting the effect of combining positive and negative values of emission quantities estimated in the respective emission categories as discussed in Section 6.4.3).

6.5.4 Source-specific QA/QC and verification

The emission estimates are based on the activity data taken from the official national sources and follow the recommendations of the IPCC 2006 GI. (IPCC 2006). The data sources are verifiable and updated annually. All the input information and calculations are archived by the expert team and the coordinator of NID. Hence, all the background data and calculations are verifiable. Other QA/QC elements were adopted in the same manner as described in Section 6.4.4 above, following the application of the QA/QC plan applicable for the LULUCF sector.

6.5.5 Source-specific recalculations, including changes made in response to the review process and impact on emission trend



Fig. 6-23 Estimated emissions for category 4.B Cropland – the current (NID 2026) and previous (NID 2025) inventory submission.

Since the last submission, the emission estimates related to carbon stock changes were recalculated for both the categories 4.B.1 Cropland remaining Cropland and 4.B.2 Land converted to Cropland.

Overall, the estimated emissions increased by 102% for the entire category 4.B (Fig. 6-23), resulting from the implemented revisions involving new activity data (soil organic carbon layer). In 4.B.1, the changes were quantitatively minor, representing in average a 2% emission sink decrease. Most of the changes are attributed to cagegory 4.B.2. They represent an emission increase by 97% when comparing the identical period (1990–2023). These changes are due to new soil carbon activity data in all land-use categories, and due to adding N_2O emissions from additional land conversion categories.

None of the individual emission categories of Cropland qualifies among the key categories by quantity or trend in this inventory submission.

For transparency, the estimates for category 4.B Cropland are displayed graphically in Fig. 6-23, including the current (NID 2026) and previous (NID 2025) inventory submission.

6.5.6 Source-specific planned improvements, including those in response to the review process

The inventory will continue implementing spatially explicit expression of carbon stock changes emission estimates on the level of individual cadastral units. Similarly, as for other categories, additional efforts will be exerted to further consolidate the current estimates for Cropland. Specific attention will be paid to estimates of soil carbon stock changes and uncertainty estimates.

Since 2024, the inventory team cooperates with the AdAgriF project “Advanced methods of greenhouse gases emission reduction and sequestration in agriculture and forest landscape for climate change mitigation”, (CZ.02.01.01/00/22_008/0004635), funded by Ministry of Education and coordinated by GCRI (prof. Trnka). The aim of the cooperation is to gradually increase the methodological level of the estimates in the categories related to agricultural land (4B Cropland, 4C Grassland).

6.6 Grassland (CRT 4.C)

6.6.1 Source category description



Fig. 6-24 Grassland in the Czech Republic – distribution calculated as a spatial share of the category within individual cadastral units (as of 2024)

Through its spatial share of 13.2% in 2024, the category of Grassland ranks third among land-use categories in the Czech Republic. Its area has been increasing since 1990, specifically in the early 1990s, but also in recent years (Fig. 6-4). Grassland as defined in this inventory corresponds to the grassland real estate category, one of the six such categories of agricultural land in the database of "Aggregate areas of cadastral land categories" (AACLC), collected and administered by COSMC. This land is mostly used as pastures for cattle and meadows for growing feed. It is distinctively spread mostly in hilly parts of the country (Fig. 6-24).

The importance of Grassland gradually increases in this country, both for its role in production and for preserving biodiversity in the landscape. According to the national agricultural programs, the spatial share of Grassland should further increase to about 18% of the area of the country. The dominant portion should be converted from Cropland, the share of which is still considered excessive. After implementation of subsidies since 1990, the area of Grassland has increased by 25% as of 2024.

6.6.2 Methodological issues

The emission inventory of 4.C Grassland concerns sub-categories 4.C.1 Grassland remaining Grassland and 4.C.2 Land converted to Grassland. The emission inventory of 4.C Grassland considers changes in living biomass, dead organic matter, and soil.

6.6.2.1 Grassland remaining Grassland

The assumption of no change in carbon stock held in living biomass was employed for category 4.C.1 Grassland remaining Grassland, in accordance with the Tier 1 approach of IPCC (2006). This is a safe assumption for the conditions in this country, and any application of higher tier approaches would not be justified with respect to data requirements and the expected insignificant carbon stock changes.

Similarly, as for living biomass, the carbon stocks associated with dead organic matter (DOM), including deadwood and litter, are considered to be at equilibrium, i.e., it is assumed that there are no changes in carbon stocks.

The emissions from changes in soil carbon stock were estimated for category 4.C.1 Grassland remaining Grassland. These are given by changes in mineral and organic soils. The estimation procedure for mineral soil was revised in the NIR 2021 submission using an improved layer of country-specific average carbon content on Grassland estimated and derived from the detailed soil carbon maps (Fig. 6-17). Since NIR 2023 submission, the area of grassland was newly stratified according to specific management activities that determine attribution of appropriate management and input stock change factors according to updated Table 6.2 of IPCC (2019). Three specific categories were defined for Grassland remaining Grassland. These categories and applicable relative stock change factors are summarized in Tab. 6-11.

Tab. 6-11 Categories of management activities by vegetation category on Grassland remaining Grassland, attributed land use, tillage (management) and input factors and corresponding areas (1990 and 2024 shown) – relevant for mineral soil.

Management categories on grassland	Land use F_{LU}	Management F_{MG}	Input F_I	Area in 1990 (kha)	Area in 2024 (kha)
I. Grassland – high intensity grazing	1	0.90	-	736.8	544.3
II. Grassland – nominally managed	1	1.00	-	8.2	358.0
III. Grassland not used for production	1	0.70	-	7.9	11.8

The estimation follows Eq. 2.25, assuming a 20-year default period for time dependence of stock change factors (D) and using country-specific mean value for the reference carbon stock values in mineral soils (74.1 t C/ha). The national source of activity data required for the adopted categorization of grassland is COSMC as for the annually updated grassland areas and management activities listed in Tab. 6-11. Next, the share of high intensity grazing grassland, nominally managed (extensive) grassland and grassland not used for production was obtained from the periodic Farm Structure Surveys conducted in 2023, 2020, 2016 and 2013, and from Agricultural Census conducted in 2010. Data were linearly interpolated for other years of the reporting period. These surveys are prepared in the European Union member countries following requirements of EU/EC legislation. In the Czech Republic, the survey is conducted based on the Act No 89/1995 Coll., on the State Statistical Service, as amended; and of the Programme for Statistical Surveys for the year 2016. These data are available at CsSO. The emission factors used as listed in Tab. 6-11 correspond to the recommended values of updated Table 6.2 for grassland management (IPCC 2019). After 2013, the share of nominally managed grassland increased on account of intensively managed grassland. This results in an increasing carbon sink in the category 4.C.1 Grassland remaining Grassland.

Emissions from organic soils are newly reported in this submission (NID 2026) based on the suggested technical correction by the EEA review in 2025. The area of organic soils attributed to Grassland is 12 698 ha, derived on geospatial data from Research Institute for Soil and Water Conservation (RISWC; J. Vopravil, T. Khel, personal communication 2025).

Emissions are estimated exclusively for drained organic soils, which represent 20% of those located on Grassland. This attribution was derived from the map of soil ameliorations obtained from RISWC. The reporting of emissions covers CO_2 from the soil (CO_2-$C_{on\text{-}site}$), CO_2 from dissolved organic carbon (CO_2-C_{DOC}) and CH_4 from soil and drainage ditches. Associated N_2O emissions from soil are reported in sector Agriculture (3.D.1.f) in line with IPCC (2006) Guidelines. The estimation includes multiplying the drained

peatland areas per sub-category by corresponding landuse-specific emission factors (Eqs. 2.3 and 2.4; Wetlands Supplement IPCC 2013).

On-site emissions of CO_2 are calculated with the default emission factors of Table 2.1 (6.1 t C/ha/yr for deep-drained, nutrient-rich Grassland – temperate climate zone). In addition, the off-site emissions from drainage of organic soils were estimated following Eq. 2.4 of the Wetlands Supplement and by using the default DOC emission factors from Table 2.2 for temperate climate (0.31 t C/ha/yr). The resulting annual on- and off-site CO_2 emissions from drained organic Grassland reached 59.7 kt CO_2 in 2024.

CH_4 emissions from drained organic soils also follow the methodology of IPCC (2013). For CH_4, Eq. 2.6 and a default fraction of total area of drained organic soil which is occupied by ditches for the drained soil (EFCH4_land Table 2.3) and for ditches (EFCH4_ditch, Table 2.4), for deep drained nutrient-rich Grassland in temperate climate were used, resulting in average annual emissions from Forest land of 186.5 kg CH_4 for 2024.

Until the 2014 NIR submission, the Grassland category also included emissions due to liming. However, similarly as for Cropland, since the 2015 NIR submission the emissions from liming have been reported under category 3.G Liming in the sector of 3 Agriculture instead.

Non-CO_2 greenhouse gas emissions from burning (CH_4, N_2O) do not occur in category 4.C.1 Grassland remaining Grassland, as this practice does not occur on Grassland in this country.

6.6.2.2 Land converted to Grassland

For category 4.C.2 Land converted to Grassland, the estimation is related to carbon stock changes in living biomass, dead organic matter and soils.

For living biomass, the calculation used eq. 2.11 (IPCC 2006) with the assumed carbon content before the conversion of 4.B Cropland set at 4.7 t C/ha (Table. 5.9, IPCC 2019). As for Forest Land converted to Cropland (category 4.C.2.a), loss of carbon in living biomass is quantified fully by CBM (Tier 3, Tab. 6-8) using the corresponding deforestation areas from annually updated Land use representation and land-use change identification system based on the data from COSMC (Sections 6.2 and 0). This was a new implementation for the earlier (NIR 2023) inventory submission, enhancing the use of Tier 3 estimates facilitated by CBM (Tab. 6-8). More details relevant to this pool and category are given in Section 6.5.2.2 (Land converted to Cropland). The biomass carbon content immediately after the conversion (except for deforestation) was assumed to equal zero and carbon stock from one-year growth of grassland vegetation following the conversion was assumed to be 6.8 t C/ha (Table 6.4; IPCC 2006).

For dead organic matter, emissions are reported due to changes in deadwood and litter that are both relevant for the category 4.C.2 Forest Land converted to Grassland. Apart from the actual areas concerned, the emission estimation is identical to that described in Section 6.5.2.2 (Land converted to Cropland) above.

The estimation of soil carbon stock change for category 4.C.2 Land converted to Grassland in the Czech Republic is related solely to the changes in mineral soils. The soil carbon stock changes following the conversion from 4.A Forest Land, 4.B Cropland, 4.D Wetlands and 4.E Settlements were quantified by the country-specific Tier 2/Tier 3 approach described in detail in Section 6.4.2.2 above.

6.6.3 Uncertainties and time series consistency

Similarly, as for other land-use categories, the methods used in this inventory for Grassland were consistently employed across the whole reporting period from the base year of 1990 to 2024. The uncertainty estimation was guided by the Tier 1 methods outlined in 2006 IPCC Gl. (IPCC 2006) and described in Section 6.4.3. The uncertainty estimation utilized primarily the default uncertainty values as recommended by IPCC (2003, 2006). The following uncertainty values were used: converted land use areas 5%, carbon, average biomass stock in cropland prior conversion 75%, biomass carbon stock after land-use conversion 75%, change in living biomass assessed by CBM 50% for deforestation events, stock change factor for land use 50%, stock change factor for management regimes 8 to 40% (as in Table 6.2 of IPCC (2019)).

For 2024, using the above uncertainty values, the total estimated uncertainty for category 4.C.1 Grassland remaining Grassland reached 35%. The corresponding uncertainty for category 4.C.2 Land converted to Grassland reached 43%. The overall combined uncertainty for category 4.C Grassland is 28%.

6.6.4 Source-specific QA/QC and verification

The emission estimates are based on the activity data taken from the official national sources and follow the recommendations of the adopted IPCC 2006 Gl. (IPCC 2006). Data sources are verifiable and updated annually. All the input information and calculations are archived by the expert team and the coordinator of the National Inventory System. Hence, all the background data and calculations are verifiable. Other QA/QC elements were adopted in the same manner as described in Section 6.4.4 above, following the application of the QA/QC plan applicable for the LULUCF sector.

6.6.5 Source-specific recalculations, including changes made in response to the review process and impact on emission trend

Since the last submission, recalculations for 4.C.1 were conducted due to the newly incorporated estimates of emisions related to organic soil. This contributed to a decreased sink of 62%. In the subcategory 4.C.2 Land converted to Grassland, the recalculations represent a sink increase of 83%. This is due to the changes in activity data (new soil organic carbon layers). Totally on average for 4.C, the revised emission estimates quantitatively represent a sink increase by 50% as compared to the previously reported estimates on the comparable period (1990 to 2023).

For transparency, the estimates for category 4.C Grassland are displayed graphically in Fig. 6-25, including the current (NID 2026) and previous (NID 2025) inventory submission.



Fig. 6-25 Estimated emissions for category 4.C Grassland – the current (NID 2026) and previous (NID 2025) inventory submission.

6.6.6 Source-specific planned improvements, including those in response to the review process

Further efforts to consolidate the emission estimates are expected for the category of Grassland. Specific attention will be paid to improving estimates of soil carbon stock changes, involving additional activity data (such as those on likely fire events on grassland), extent of management categories on grassland and better substantiated emission factors.

Since 2024, the team cooperates with the AdAgriF project "Advanced methods of greenhouse gases emission reduction and sequestration in agriculture and forest landscape for climate change mitigation", (CZ.02.01.01/00/22_008/0004635), funded by Ministry of Education and coordinated by GCRI (prof. Trnka). The aim of the cooperation is to gradually increase the methodological level of the estimates in the categories related to agricultural land (4B Cropland, 4C Grassland).

6.7 Wetlands (CRT 4.D)

6.7.1 Source category description



Fig. 6-26 Wetlands – distribution calculated as a spatial share of the category within individual cadastral units (as of 2024)

Category 4.D Wetlands classified in this emission inventory includes riverbeds and water reservoirs such as lakes and ponds, wetlands and swamps. These areas dominantly correspond to the real estate category of water area (ID 11) of the "Aggregate areas of cadastral land categories" (AACLC), collected and administered by COSMC. Additionally, the water-logged areas classified under AACLC ID 14 "Other lands" are also included under 4.D Wetlands (Tab. 6-5). The specific land use details of the land use category water area are given in Amendment to Act No. 357/2013 Coll (Act on Cadastre). They include definitions of ponds (artificial water reservoir designed primarily for fish farming with complete and regular discharge), riverbeds natural or modified, artificial riverbeds of watercourse, natural water reservoirs, artificial water reservoirs, wetlands (march, wetland, swamp) and water areas with building. The inventory team makes no further alteration of the default categorization provided by COSMC. Accordingly, reporting 4.D Wetlands as defined above (in compliance with the national definition of wetland) resorts to subcategory Other wetlands (remaining or land converted to) in the CRT tables.

The area of 4.D Wetlands covers 2.2% of the total territory. It has been increasing steadily since 1990 (by 9.3% until 2024) with an even stronger trend earlier (Fig. 6-4). It can be expected that this trend will continue, and that the area of Wetlands will further increase. This is mainly due to programs aimed at increasing the water retention capacity of the landscape[4], specifically in relation to adaptation strategies

[4] *Based on the land-use history, the growth potential could be considered to be rather large. For example, as of 1990, the category included 50.7 th. ha of ponds, which represented only 28% of their extent during the peak period in the 16th Century (Marek 2002).*

proposed to deal with changing climate and associated increase frequency and severity of drought in the Czech landscape (e.g., Trnka *et al*. 2015).

6.7.2 Methodological issues

The emission inventory of sub-category 4.D.1 Wetlands remaining Wetlands can address the areas in which the water table is artificially changed, which correspond to peatland draining or lands affected by water bodies regulated through human activities (flooded land). Both categories are practically not occurring under the conditions in this country. Peat extraction basically ceased in the country in the early 1990s following Act No. 114/92 on nature protection. Peat for industrial use relies on import, with the exception of peat used in balneology. Hence, sub-category 4.D.1 Wetlands remaining Wetlands cannot be attributed to either flooded land or peat extraction lands. Hence, all wetland areas are reported under category 4.D.1.c Other Wetlands remaining Other Wetlands. Correspondingly, the emissions for 4.D.1 Wetlands remaining Wetlands were not explicitly estimated for this sub-category.

Emission estimates in sub-category 4.D.2 Land converted to Wetlands encompasses conversion from 4.A Forest Land, 4.B Cropland, 4.C Grassland and 4.E Settlements. This corresponds to a very minor land-use change identified in this country, which corresponds to the category of Land converted to Other Wetlands. The emissions associated with this type of land-use change are derived from the carbon stock changes in living biomass and soil, and, for conversion from Forest land, also in litter and deadwood. The emissions were generally estimated using the Tier 1 approach and Eq. 2.11 of the 2006 IPCC Guidance for LULUCF, which simply relates the biomass stock before and after the conversion. As for Forest Land converted to Wetlands (category 4.D.2.a), loss of carbon in living biomass is quantified fully by CBM (Tier 3, Tab. 6-8) using the corresponding deforestation areas from annually updated Land use representation and land-use change identification system based on the data from COSMC (Sections 6.2 and 0). This was a new implementation since NIR 2023 inventory submission, enhancing the use of Tier 3 estimates facilitated by CBM (Tab. 6-8). More details relevant to this pool and category are given in Section 6.5.2.2 (Land converted to Cropland). The corresponding default values were employed: the biomass stock after conversion equaled zero, while the mean biomass stock prior to the conversion in the 4.A Forest Land, 4.B Cropland and 4.C Grassland categories was estimated and/or assumed identically as described above in Sections 6.4.2.2 and 6.5.2.2. The latter section also describes the estimation of emissions related to deadwood and litter components, which was applied identically in this land use category.

Introduced in this submission, the estimation of carbon stock change for category 4.D.2 Land converted to Wetlands concerns mineral soils. Considering that carbon stock in Wetlands corresponds to that in Grassland, the soil carbon stock changes following the conversion from Forest Land, Cropland, Grassland and Settlements were quantified by the country-specific Tier 2/Tier 3 approach and are described in Section 6.4.2.2.

6.7.3 Uncertainties and time series consistency

The methods used in this inventory for Wetlands were consistently employed across the whole reporting period from the base year of 1990 to 2024. Similarly, as for the other land-use categories, the uncertainty estimation was guided by the Tier 1 methods outlined in IPCC 2006 Gl. (IPCC 2006) and described in Section 6.4.3. It utilized primarily the default uncertainty values as recommended by IPCC (2006). The following uncertainty values were used: converted land use areas 5%, average biomass stock in cropland and

grassland prior conversion 75%, biomass carbon stock after land-use conversion 75%, change in living biomass assessed by CBM 50% for deforestation events, reference soil carbon 10%.

Since the emission estimate concerns only category 4.D.2 Land converted to Wetlands, the uncertainty is estimated for this category. For 2024, the estimated uncertainty for category 4.D.2 was 83%.

6.7.4 Source-specific QA/QC and verification

The emission estimates are based on the activity data taken from the official national sources and follow the recommendations of IPCC 2006 Gl. (IPCC 2006). Data sources are verifiable and updated annually. All the input information and calculations are archived by the expert team and the coordinator of the National Inventory System. Hence, all the background data and calculations are verifiable. Other QA/QC elements were adopted in the same manner as described in Section 6.4.4 above, following the application of the QA/QC plan applicable for the LULUCF sector.

6.7.5 Source-specific recalculations, including changes made in response to the review process and impact on emission trend

The emission estimates for the category 4.D Wetlands were recalculated in its subcategory 4.D.2. This was due to the new activity data (soil carbon layers). These changes decreased emissions for category 4.D (4.D.2) by 96% relative to the previous NID submission, which represents -29 kt CO_2 eq./year, which is quantitatively negligible.

None of the individual emission categories of Wetlands qualifies among the key categories by quantity or trend in this inventory submission.

For transparency, the estimates for category 4.D Wetlands are displayed graphically in Fig. 6-27, including the current (NID 2026) and previous (NID 2025) inventory submission.



Fig. 6-27 Estimated emissions for category 4.D Wetlands – the current (NID 2026) and previous (NID 2025) inventory submission.

6.7.6 Source-specific planned improvements, including those in response to the review process

Depending on capacities, more transparent wetlands classification will be worked on to increase transparency of the reporting.

6.8 Settlements (CRT 4.E)



Fig. 6-28 Settlements, incl. other land – distribution calculated as a spatial share of the category within individual cadastral units (as of 2024)

6.8.1 Source category description

Category 4.E Settlements is defined by IPCC (2006) as all developed land, including transportation infrastructure and human settlements. The area definition under category 4.E Settlements was revised previously for the NIR 2013 submission to better match the IPCC (2006) default definition. Next, the NIR inventory submission of 2018 incorporated an additional change to this category, namely merging the land areas previously attributed under category 4.F Other land. This decision was substantiated by the fact that in the conditions of the country, these areas mostly do not remain untouched and may undergo land-use change, hence do not meet the condition of no possible management interventions. This makes land attribution more consistent and transparent, enhancing the ability to track land-use conversions. This solution was also endorsed by the latest in-country expert review team. In this way, the category 4.E Settlement currently includes two categories of the "Aggregate areas of cadastral land categories" (AACLC) database, collected and administered by COSMC, namely ID 13 "Built-up areas and courtyards" and ID 14 "Other lands". Of the latter AACLC category, all types of land-use as defined in Amendment to Act No. 357/2013 Coll (Act on Cadastre) are covered, including "Unproductive land" that was previously attributed

to category 4.F Other Land. The only exception is the water-logged area under ID 14 “Other land”, which is included within 4.D Wetlands (see also Tab. 6-5). The category 4.E Settlements also includes all land used for infrastructure, as well as that of industrial zones and city parks. Finally, it also includes all military areas (earlier considered as Grassland) in the country.

The category of Settlements as defined above currently (as of 2024) represents 10.6% of the area of the country. The area of this category has increased since 1990 by about 3%, especially during the most recent years (see Fig. 6-4).

6.8.2 Methodological issues

Following Tier 1 assumption of IPCC (2006), the carbon stocks in biomass, dead organic matter (dead wood and litter) and soil are considered in equilibrium for category 4.E.1 Settlements remaining Settlements. Hence, the emission inventory for this category concerns primarily 4.E.2 Land converted to Settlements.

Correspondingly, emissions quantified for this category are related to sub-category 4.E.2 Land converted to Settlements. Specifically for Forest land converted to Settlements, the emissions result from changes in biomass carbon stock, dead organic matter (DOM) and soil. The biomass carbon stock change was quantified based on eq. 2.11 (IPCC 2006) and default values applicable for biomass components as in Table 5.9 (IPCC 2019) and 6.4 (IPCC 2006) for land-use conversions from Cropland and Grassland, respectively.

Changes in DOM were related to the deadwood carbon pool that is considered lost.

The estimate of soil carbon stock changes involving land-use change to Settlements was first included in the NIR 2019 inventory submission. The reference value of carbon stock pool in Settlements was derived based on the data from the Landscape inventory CzechTerra (CZT). CZT in its remote-sensing component identified proportions of land cover that constitute the land use category Settlements. These proportions of land cover (area of trees, arable land, grass cover as well as the build-up, paved surfaces) were assessed from a sample of 289 625 categorized grid points) and used to construct the reference carbon stock value applicable for 4E1 Settlements. For this, soil carbon pool values of Forest land, Cropland and Grassland at the level of individual cadastral unit (n>13 000) were linked to the specific land cover types and their spatial representation within Settlements, i.e., trees (13.5%), arable land (1.7%) and grass cover (34.8%). The remaining part assumes 20% soil carbon loss for paved over areas in line with the 2006 IPCC Guidelines (vol. 4, chap. 8, p.8.24). The resulting reference carbon stock applicable to Settlements has its area-weighted mean of 59.7 t C/ha, ranging from 30.4 to 101.8 t/ha for individual cadastral areas. This approach allows estimation of the associated land-use conversions (categories 4.E.2.a, 4.E.2.b and 4.E.2.c), for the sake of consistency adopting the identical time dependence (IPCC 2006 default) period of 20 year for these soil carbon pool changes similarly as for other land use conversion types.

The corresponding values were employed for emission estimates due to land use conversion: the biomass stock after conversion equaled zero, while the mean biomass stock prior to the conversion was estimated and/or assumed identically as described above in Sections 6.5.2.2 and 6.6.2.2. The latter section describes estimation of the emissions related to the dead organic matter components that were treated identically in this land use category. The carbon stock prior conversion was estimated as described in Section 6.4.2. All biomass is assumed to be lost during the conversion, according to the Tier 1 assumption of IPCC (2006, 2019). As for Forest Land converted to Settlements (category 4.E.2.a), loss of carbon in living biomass is quantified fully by CBM (Tier 3, Tab. 6-8) using the corresponding deforestation areas from annually updated Land use representation and land-use change identification system based on the data from COSMC (Sections 6.2 and 0). This was a new implementation since the NIR 2023 inventory submission, enhancing the use of Tier 3 estimates facilitated by CBM (Tab. 6-8). More details relevant to this pool and category are given in Section 6.5.2.2 (Land converted to Cropland). The latter section also describes the

estimation of emissions related to deadwood and litter components, which was applied identically in this land use category. Finally, soil carbon pool estimates applicable for land use conversions to Settlements used the spatially specific carbon pool values as described above.

Introduced since this inventory submission are N_2O emission estimates from land-use conversion categories and instances with carbon loss.

6.8.3 Uncertainties and time series consistency

The methods used in this inventory for 4.E Settlements were consistently employed across the whole reporting period from the base year of 1990 to 2024. The uncertainty estimation was guided by the Tier 1 methods outlined in IPCC 2006 Gl. (IPCC 2006) and described in Section 6.4.3. It utilized primarily the default uncertainty values as recommended by IPCC (2006). The following uncertainty values were used: land use areas 5%, reference biomass carbon stock prior and after land-use conversion 75%, change in living biomass assessed by CBM 50% for deforestation events, reference soil carbon 10%. The adopted uncertainty associated with the emission factors involved in estimation of direct and indirect N_2O emissions was 250% (Table 11.1., IPCC 2006).

The emission estimate concerns only category 4.E.2 Land converted to Settlements; therefore, the uncertainty is estimated only for this category. For 2024, the estimated uncertainty for category 4.E.2 was 39%.

6.8.4 Source-specific QA/QC and verification

The emission estimates are based on the activity data taken from the official national sources and follow the recommendations of the IPCC 2006 Gl. (IPCC 2006). The data sources are verifiable and updated annually. All the input information and calculations are archived by the expert team and the coordinator of the National Inventory System. Hence, all the background data and calculations are verifiable. Other QA/QC elements were adopted in the same manner as described in Section 6.5.4 above, following the application of the QA/QC plan applicable for the LULUCF sector.

6.8.5 Source-specific recalculations, including changes made in response to the review process and impact on emission trend



Fig. 6-29 Estimated emissions for category 4.E Settlements– the current (NID 2026) and previous (NID 2025) inventory submission.

The emission estimates for the category 4.E Settlements were recalculated in its subcategory 4.E.2. This was due to the revised activity data (soil organic carbon maps). Additionally, N_2O emissisons from N mineralization were newly estimated with this NID submission These changes increased emission estimates for category 4.E (4.E.2) by 7% relative to the previous NID submission.

None of the individual emission categories of Settlements qualifies among the key categories by quantity or trend in this inventory submission.

For transparency, the estimates for category 4.E Settlements are displayed graphically in Fig. 6-29, including the current (NID 2026) and previous (NID 2025) inventory submission.

6.8.6 Source-specific planned improvements, including those in response to the review process

Further efforts to consolidate the emission estimates are expected for the category of Settlements. The inventory team intends to verify the activity data needed for verifying carbon stock change estimates in living biomass and mineral soils for this category in coherence with the plans of full implementation of NFI data as noted in section 6.4.6.

6.9 Other Land (CRT 4.F)

6.9.1 Source category description

Since the NIR 2018 inventory submission, the IPCC category 4.F Other land is not represented by any land use category within the Czech conditions and the national system of land use representation and land use change identification. Prior to this submission, category 4.F Other Land represented unmanaged

(unmanageable) land areas, matching the default definition of IPCC (2006). These areas were assessed from the database of "Aggregate areas of cadastral land categories" (AACLC), collected and administered by COSMC. It is part of the AACLC "Other lands" category with the specific land use category "Unproductive land" assessed from the 2006 land census of COSMC. Under that definition, the category 4.F. Other land represented 1.3% of the territory of the country. Since 2018 NIR submission, these areas have fully been included under category 4.E Settlements. The reasons for that decision are described in section 6.8.1 above.

6.9.2 Methodological issues

Since the earlier inventory submission (NIR 2018), no areas have been attributed to category 4.F Other land. Hence, no methodological issues are applicable for this category.

6.9.3 Uncertainties and time series consistency

Since the earlier inventory submission (NIR 2018), no areas have been attributed to category 4.F Other land. Hence, no uncertainty estimates, as well as time series consistency issues, are applicable for this category.

6.9.4 Source-specific QA/QC and verification

Since the earlier inventory submission (NIR 2018), no areas have been attributed to category 4.F Other land. Hence, no specific QA/QC and verification issues are applicable for this category.

6.9.5 Source-specific recalculations, including changes made in response to the review process and impact on emission trend

With the earlier (NIR 2018) adopted attribution of lands, no emission estimates are applicable for category 4.F Other Land.

6.9.6 Source-specific planned improvements, including those in response to the review process

Since NIR 2018, the inventory team includes the former areas of 4.F Other land within category 4.E Settlements, which improves reporting consistency and transparency, while enhancing the ability to track land-use conversions. No other improvements are planned for category 4.F Other land.

6.10 Harvested Wood Products (CRT 4.G)

6.10.1 Source category description

The contribution of Harvested wood products (HWP), mandatorily included by Decision 2/CMP7 in emission inventories under UNFCCC and KP since the 2015 inventory submission, is also estimated for the Czech emission inventory. Changes in the pool of HWP may represent CO_2 emissions or removals, which are included within the LULUCF sector as a specific category (CRT 4.G) in addition to the six IPCC land use

categories. The HWP pool considers primary woody products generated from wood produced in the country. Hence, these emissions originate in land use category 4.A Forest land. The eventual fraction of wood from deforested land, i.e., Forest land converted to any other land use category, is also considered, although it is treated differently (see Section 6.10.2 below).

6.10.2 Methodological issues

The methodology for estimating the contribution of HWP to emissions and removals was based on IPCC (2006) and IPCC (2014b). The latter material was followed to adopt the agreed principles on accounting for HWP, which includes only domestically produced and consumed HWP. The estimation follows the Tier 2 method of first order decay, which is based on Eq. 2.8.5 (IPCC 2014b). This equation considers carbon stock in the particular HWP categories, which is reduced by an exponential decay function using the specific decay constants. The default half-life constants were used for the major HWP categories: 35 years for sawnwood, 25 years for wood-based panels and 2 years for paper and paperboard. The second part of Eq. 2.8.5 (IPCC 2014) adds the material inflow in the particular year and HWP categories.

The activity data (production and trade of sawnwood, wood-based panels and paper and paperboard) were derived and/or directly used from the FAO database on wood production and trade (http://faostat3.fao.org/download/F/FO/E). The data have been available since 1961 as an aggregate for the former Czechoslovakia. Since 1993, when Czechoslovakia was split into the Czech Republic and Slovakia, data have been available specifically for the two countries. To estimate the corresponding share of HWP in the 1961 to 1992 period, the data applicable for Czechoslovakia were multiplied by a country-specific share that was derived for each HWP category from the data reported for each follow-up country in the 1993 to 1997 period (Cienciala and Palán 2014). The conversion factors are used for disaggregated HWP categories as in Table 2.8.1 (IPCC, 2014b). Since the FAO database have recently become updated with a larger time delay, the input data were crosschecked with the Czech colleagues at the Czech Ministry of Agriculture and Forest Management Institute (Michal Synek, personal communication, Jan. 2023). Based on that, some of the recent activity data were revised – specifically, these revisions concern all major HWP categories (except wood pulp) for the most recent two or three years. The adopted national activity data are reported in the CRT tables (4.Gs2) for the period 1961 to 2024. Eventually, the identical data will become available at the FAO database for the country, but with a considerable delay.

The fraction corresponding to source material originating from deforested land was estimated based on deforested areas as reported under Activity 3.3 Deforestation of the former Kyoto protocol. Although quantitatively insignificant (0.016% and 0.014% in 1990 and 2024, respectively), the HWP contribution of this fraction was estimated using instantaneous oxidation, which was the formal requirement of the IPCC guidelines (IPCC 2014b) for estimation of HWP contribution under the former Kyoto Protocol. This conservative approach remains adopted for the HWP estimates under the Convention, too.

Tab. 6-12 The country-specific shares applicable for the HWP quantities given for the former Czechoslovakia in the FAO database, derived from the period 1993–1997

	Production		Import		Export	
Country / HWP category	Czech Republic	Slovakia	Czech Republic	Slovakia	Czech Republic	Slovakia
Sawn wood	0.834	0.166	0.868	0.132	0.723	0.277
Wood-based panels	0.716	0.284	0.719	0.281	0.851	0.149
Paper and paperboard	0.655	0.345	0.772	0.228	0.598	0.402

The resulting estimates of the HWP contribution, including domestically produced and used wood for the reporting period 1990 to 2024, are shown in Tab. 6-2. The emissions fluctuated during the reporting period, where the mean contribution reached -1 172 kt CO_2/year. The estimated HWP contribution reached -1 680 and -1 285 kt CO_2 in 1990 and 2024, respectively.

6.10.3 Uncertainties and time series consistency

The uncertainty estimates use the following inputs: roundwood harvest 20%, sawnwood, wood panel and paper products 15%, wood density factors 25%, carbon content in wood products 10%, half-life factors 50%. Using Eq. 4 for combining uncertainties, this gives an approximate uncertainty estimation of 62% for the HWP contribution, which is general for all HWP categories.

Time series consistency is ensured as the inventory approaches and/or assumptions are applied identically across the whole reporting period from the base year of 1990 to 2024.

6.10.4 Source-specific QA/QC and verification

The QA/QC elements were adopted in the same manner as described in Section 6.5.4 above, following the application of the QA/QC plan applicable for LULUCF sector, limited to those elements relevant for this specific land-use category.

6.10.5 Source-specific recalculations, including changes made in response to the review process and impact on emission trend

No recalculation was made for the category 4.G HWP except the most recent years due to slightly changed activity data at FAO database on wood production and trade, the primary source of the activity data used for estimation of HWP emission contribution for the entire reporting period. These activity data were crosschecked and rectified based on the discussion with the country correspondents for reporting to FAO (see section 6.10.2 above). These affected only the estimates of HWP contribution for 2023. Hence, the estimates differ between the current and the previous submission marginally, namely by -0.01% (decreased sink).

For transparency, the estimates for category 4.G HWP are displayed graphically in Fig. 6-30, including the current (NID 2026) and previous (NID 2025) inventory submission.



Fig. 6-30 Estimated emissions for category 4.G HWP – the current (NID 2026) and previous (NID 2025) inventory submission.

6.10.6 Source-specific planned improvements, including those in response to the review process

No specific improvements are planned for this category for the next submission.

6.11 Acknowledgement

The authors would like to thank Jan Hána and Michal Synek, Czech Forestry Institute, Brandýs n. Labem, for compiling the required increment data concerning forests and providing the updated activity data needed for HWP. We also thank Jan Máslo and his NFI team for providing some of the essential background data for CBM-CFS3 parameterization. Jan Vopravil and Tomas Khel from RISWC kindly provided the essential activity data related to soil carbon on agricultural lands aiding estimates for both mineral and organic soils. Luboš Borůvka and Radim Vašát, Czech Univ. Life Sciences Prague, and Vít Šrámek, Forestry and Game Manageemnt Institute, kindly provided newly introduced forest soil carbon maps generated in ForCarbo project (TACR No. SS06010148). We thank Petr Štěpanek, Global Change Research Institute CAS, for compiling the forest-area-relevant air temperature data. We appreciate the assistance of the staff at the Czech Office for Surveying, Mapping and Cadastre, specifically Petr Souček, David Legner, Zuzana Loulová, Bohumil Janeček and Helena Šandová, related to data on land use areas. We thank our former colleague Jan Albert for his help with the CBM-CFS3 model implementation for the Czech conditions. We also pass our thanks to the colleagues of the entire Canadian team supporting development of CBM-CFS3 model used in this inventory (specifically Stephen Kull and Werner Kurz), as well as to European colleagues for sharing their expertise with CBM application (specifically Roberto Pilli, Viorel Blujdea and Kevin Black).

Some underlying analysis for emission estimates on agricultural land were made with the support of AdAgriF—Advanced methods of greenhouse gases emission reduction and sequestration in agriculture and forest landscape for climate change mitigation (CZ.02.01.01/00/22_008/0004635)".

7 Waste (CRT sector 5)

7.1 Overview of sector

The waste sector comprises emissions from human activities associated with waste management in general. Most human and economic activities result in the production of waste; therefore, the performance of this sector is closely connected with the population and the economic state of the country. Most processes in the sector originate in biological or biochemical processes and therefore it takes longer for changes in management practices to be reflected in emissions. An overview of the whole sector is on Fig. 7-1.

This sector encompasses several categories. In 2024, the total GHG emissions from the Waste sector in the Czech Republic were 5 521 kt CO_2 eq. and approximately 94% of these emissions accounted for CH_4. The main source category of this sector is 5.A - Solid Waste Disposal. In 2024, this category emitted approximately 137 kt of CH_4 (see Fig. 7-2), equalling 3 824 kt of CO_2 eq. The second largest source category is 5.D - Wastewater Treatment and Discharge, followed by 5.B Biological treatment and 5.C. Waste incineration and open burning of waste. An additional category quantifying emissions from waste management is the incineration of waste for energy purposes which is, reported in category 1.A.1.a.i Other Fuels.

The Waste sector as a final output sector for all economic activities is very dependent on the state of the economy, the purchasing power of the population and waste management policies. In 2024, there is a slightly increasing trend in emissions from landfilling. Almost 90% of all wastes produced are used (recycled, used for energy purposes etc.). However, it is partly caused by a huge amount of building and demolition waste which influences the whole waste statistics. For the rest of the categories such as municipal solid waste (MSW), there is recovered approximately only a half of it. The total amount of waste composted increased in 2005-2021 because of new law.



Fig. 7-1 The development of gas emissions from the Waste sector, 1990-2024

Anaerobic digestion technology has been widely adopted due to subsidies for biogas production and therefore became another growing source category (5.B.2.). The growth of the category from 2003 to 2013 stopped and the biogas production is stable now. Although, there are still efforts to increase the

energy recovery from waste instead of landfilling or incineration without energy recovery. Emissions from industrial wastewater increased steadily until 2019. While emissions from domestic wastewaters 5D1 have decreased since 1990, emissions from industrial wastewaters 5D2 have generally increased. In 2024, emissions from both sources were nearly the same value. Since 2014, the Waste sector has been quantified and managed by CHMI, between 2019 and 2024 by the Czech Environmental Information Agency (CENIA), and previously by the Charles University Environment Center (CUEC).

There are four categories of sources evaluated by the analyses described in IPCC 2006 Guidelines as the key categories in the waste sector. The sources overview, including their contribution to the aggregate emissions, is given in Tab. 7-1.

Tab. 7-1 The overview of significant source categories in the Waste sector (2024)

Category	Gas	KC A1	KC A2	KC A1[1]	KC A1[2]	KC A2[1]	KC A2[2]	% of total GHG[1]	% of total GHG [2]
5.A Solid Waste Disposal	CH_4	LA, TA	LA, TA	Yes	Yes	Yes	Yes	4.17	3.97
5.D Wastewater treatment and discharge	CH_4	LA	LA, TA	Yes	Yes	Yes	Yes	0.93	0.89
5.B Biological treatment of solid waste	CH_4	LA, TA	LA, TA	Yes	Yes	Yes	Yes	0.55	0.52
5.D Wastewater treatment and discharge	N_2O		LA			Yes	Yes	0.22	0.21

KC: key category
[1] including LULUCF
[2] excluding LULUCF

7.2 Solid Waste Disposal (CRT 5.A)

7.2.1 Managed Waste Disposal Sites (CRT 5.A.1)

7.2.1.1 Source category description

The treatment and disposal of municipal, industrial and other solid waste could produce significant amounts of methane (CH_4). CH_4 is released in the case of decomposition without the presence of oxygen. In some solid waste disposal sites (SWDS) the arising CH_4 (as a part of landfill gas) is caught by piping in the body of the landfill and then collected. This gas can be (and in the Czech Republic is in some cases) used for energy recovery.

The decomposition of organic material derived from biomass sources (e.g. crops, food, textile, wood), is the primary source of CO_2 released from waste. These CO_2 emissions are not included in the national totals because the carbon is of biogenic origin and net emissions are accounted for under the LULUCF.

CRT 5.A.1 might also produce emissions of other micropollutants, such as non-methane volatile organic compounds (NMVOCs), as well as smaller amounts of nitrous oxide (N_2O), nitrogen oxides (NO_X) and

carbon monoxide (CO). In line with the IPCC 2006 Guidelines (IPCC, 2006), only CH_4 is addressed in this chapter. An overview of this category is shown in Fig. 7-2.



Fig. 7-2 Development of emissions from SWDS and total amount of waste disposed to SWDS 1990–2024

7.2.1.2 Methodological issues

Waste disposal to Solid Waste Disposal Sites (SWDS)

The key activity data for CH_4 quantification from 5.A.1.a is the amount of waste disposed in landfills. The annual disposal is given in Tab. 7-2. The data for the annual disposal are obtained from mixed sources since the application of the FOD (first-order decay) model requires data from 1950 to the present day. These historical data are not available in the country, therefore assumptions about the past had to be used. These



Fig. 7-3 Disposal of Municipal Solid Waste (MSW) to SWDS and GDP, Czech Republic, 1950–1990

assumptions are described in the working paper (Havránek, 2007). Briefly, the method interpolates and extrapolates between points in time and uses the correlation of the waste production with the social product (the predecessor of the current gross domestic product, GDP) as a test method (Fig. 7-3). The trends are similar, and the higher of the two estimates was used in the quantification.

Tab. 7-2 MSW and IW (municipal solid waste + industrial waste) disposal to SWDS in the Czech Republic [kt], 1990–2024

Year	Waste disposed to SWDS	Year	Waste disposed to SWDS	Year	Waste disposed to SWDS	Year	Waste disposed to SWDS
1990	2 631	**1999**	2 892	**2008**	3 684	**2017**	2 843
1991	2 648	**2000**	3 063	**2009**	3 666	**2018**	2 918
1992	2 744	**2001**	3 086	**2010**	3 445	**2019**	2 956
1993	2 803	**2002**	3 180	**2011**	3 241	**2020**	2 997
1994	2 821	**2003**	3 212	**2012**	3 046	**2021**	3 073
1995	2 881	**2004**	3 260	**2013**	2 952	**2022**	2 915
1996	2 943	**2005**	3 330	**2014**	2 830	**2023**	2 733
1997	2 999	**2006**	3 481	**2015**	2 759	**2024**	2 925
1998	3 064	**2007**	3 574	**2016**	2 783		

After period of decrease 2009–2015, the waste deposited in landfills has increased slightly till 2021. Nowadays there is an obvious decrease again (see Tab. 7-2) as a decrease in landfilled waste is a long-term target of the Czech national environmental policy.



Fig. 7-4 Amount of waste produced in the Czech Republic - comparison of data from Eurostat and ISOH, 2010–2018

The data used for present years are based on annual report of indicators to Plan of waste management – a strategic document about waste management in the Czech Republic. Similar values can be found in public information system (database) for waste management in the Czech Republic (VISOH) and its non-public version (ISOH - information system on waste management). Both are managed by Czech Environmental Information Agency (CENIA). The values of the indicators are calculated based on the ISOH database, which includes bottom-up data from around 60 000 respondents. Reporting to this system is mandated by national law and it is controlled by Czech Environmental Inspectorate, regional authorities and municipalities. Additionally, the Czech Statistical Office (CzSO) developes waste statistics that are subsequently reported to Eurostat. ISOH data are used for the inventory because they are evidence-based and verified by CENIA during the reporting procedure. In 2018, CENIA compared SWDS data from ISOH and CzSO and concluded that ISOH is more accurate because the data fit better with fees and levies collected in the waste management sector. Fig. 7-4 and Fig. 7-5 show the differences between data from Eurostat and ISOH for waste production and the amount of waste disposed to SWDS between 2010 and 2018, both for total amount of waste and for municipal solid waste. Eurostat reports two kinds of data for household waste: "Household and Similar Wastes" and "Municipal Waste". For the comparison in Submission 2020, the "Household and Similar Wastes" database was used. In subsequent research, the "Municipal Waste" database was considered more suitable due to a better match between the waste definition and waste categories used in the Czech Republic. However, differences between ISOH and Eurostat are still apparent.



Fig. 7-5 Amount of waste disposed to SWDS in the Czech Republic - comparison of data from Eurostat and ISOH, 2010-2018

ISOH provides higher values than Eurostat, see Fig. 7-5. The data on the amount of waste disposed to solid waste disposal sites are for MSW in all four years higher from ISOH, although in case of the total the trend is unnoticeable.

The difference between data from Eurostat and ISOH is caused by different data collection methods and other methodological approaches. ISOH is the official waste database of the Ministry of the Environment (MoE), administered by CENIA. ISOH receives data directly from waste producers, who must report the amount of waste they produce or treat. Thus, the ISOH database contains comprehensive data on waste management in the Czech Republic. Eurostat receives data from the Czech Statistical Office (CzSO), which uses statistical methods – data collected from a smaller number of waste producers, with the total amount then estimated based on the collected data. Both data sources are official, and reducing the differences between them is the subject of long-term discussion. Additionally, the CzSO waste section recently changed its methods. Since the reference year 2021, CzSO has been using the same database as CENIA. Moreover, the definition of statistically determined waste streams has been further harmonised. Therefore, CENIA and CzSO waste data will better match in the future.

National laws on landfill management are based on European legislation. There were also legal regulations before Czech membership in the EU, but the transition to European legislation brought a more detailed approach to waste management practices and their reporting. In general, this framework sets the conditions under which landfilling can be carried out and specifies the relevant actors and state bodies responsible for administration and control, as well as the duties and obligations of all stakeholders. The main regulations in this area before membership in the EU were Act 238/1991 Coll. “Act on Waste” and the later Act on Waste 185/2001 Coll. The Act on Waste from 2001 was replaced by the new Act 541/2020 Coll. at the end of 2020. The main decree relevant to landfilling under Act 185/2001 Coll. was Decree 294/2005 Coll. “Decree on the conditions for depositing waste in landfills and its use on the surface of the ground” and Decree 383/2001 Coll. “Decree on details on waste treatment practices”, which has now been amended by Decree 273/2021 Coll. The Ministry of the Environment website provides the full regulatory framework for waste management.

Industrial waste, sludge and dual data

Category 5.A distinguishes various categories of waste. Some are not included as a special category in ISOH; for example, there is no category of “industrial waste” (IW). Based on a suggestion from the Annual Review Report (ARR) ISOH data containing IW (but do not discern them as such) are adjusted by a residual factor from CzSO, derived from IW statistics.

The method to estimate methane emissions from this source category is the Tier 1 FOD approach (first-order decay model). The first-order decay model assumes the gradual decomposition of waste disposed in landfills. The GHG (greenhouse gas) emissions were calculated using the IPCC Spreadsheet for Estimating Methane Emissions from Solid Waste Disposal Sites, which is a part of the 2006 Guidelines (IPCC, 2006), hereafter referred to as the IPCC model (IPCC, 2006).

Waste composition, sludge, k-rate and Degradable Organic Carbon (DOC)

Waste composition is crucial for estimating emission from SWDS. Several attempts have been made to obtain country-specific data on waste composition (Tab. 7-3). The data for 1990–1995 are based on the IPCC default values for Eastern Europe, while the data for 1996–2000 and 2002–2004 are based on interpolation between data points. The data for 2001 and for the period 2005–2009 come from waste surveys carried out in R&D projects dealing with waste composition. For the period 2012–2020, data from company EKO-KOM are available. EKO-KOM surveys MSW composition every even-numbered year. For 2012, 2014, 2016, 2018 and 2020 EKO-KOM values were used and the odd years are calculated as the average between the two adjacent even-numbered years. For 2024, the composition was taken from the 2020 EKO-KOM analysis, as same as for the reference year 2021 and 2022.

Tab. 7-3 MSW composition for the Czech Republic used in the quantification (fractions of total, 1950–2024)

	Paper	Food	Textile	Wood and straw	DOC (calculated)
k-*rate*	0.06	0.185	0.06	0.03	
DOC (default)	0.4	0.15	0.24	0.43	
		Share of particular waste streams			
1950–1995	0.22	0.3	0.05	0.08	0.179
1996	0.22	0.29	0.05	0.08	0.178
1997	0.23	0.28	0.06	0.08	0.183
1998	0.24	0.27	0.06	0.08	0.185
1999	0.25	0.26	0.07	0.08	0.190
2000	0.26	0.25	0.07	0.08	0.193
2001	0.27	0.23	0.08	0.08	0.196
2002	0.24	0.25	0.08	0.09	0.191
2003	0.22	0.27	0.07	0.11	0.193
2004	0.19	0.3	0.07	0.13	0.194
2005	0.16	0.32	0.07	0.14	0.189
2006	0.16	0.32	0.07	0.14	0.189
2007	0.17	0.32	0.08	0.13	0.191
2008	0.16	0.32	0.07	0.14	0.189
2009–2011	0.16	0.35	0.08	0.13	0.192
2012	0.14	0.30	0.08	0.18	0.198
2013	0.13	0.30	0.06	0.20	0.197
2014	0.12	0.30	0.04	0.22	0.197
2015	0.12	0.27	0.04	0.26	0.207
2016	0.11	0.25	0.03	0.30	0.217
2017	0.10	0.28	0.03	0.30	0.220
2018	0.10	0.32	0.03	0.30	0.223
2019	0.10	0.32	0.02	0.31	0.224
2020	0.10	0.31	0.02	0.31	0.226
2021	0.10	0.31	0.02	0.31	0.226
2022	0.08	0.32	0.02	0.37	0.242
2023	0.08	0.32	0.02	0.37	0.242
2024	0.09	0.26	0.05	0.35	0.237

As seen in Tab. 7-3, the table includes only some waste streams that might be deposited in a landfill; items like sludge are missing. Although small amounts of sludge might end up in landfills, sludge is excluded from MSW; therefore, the projects from which the expert derived the waste composition neglect sludge as part of the waste mixture. However, due to bottom-up data, sludge deposited as waste is included in the total amount of waste landfilled: the average DOC obtained using the current waste mixture for landfills including sludge is larger than the default DOC for sludge. Therefore, the total emissions should not be underestimated. More detailed insight into this issue is planned in the coming years. Tab. 7-3 also contains the methane generation rate (k-rate) employed. This rate is closely related to the composition of a particular substance and the available moisture. The IPCC default k-rates for a wet temperate climate were used (the average temperature of the Czech Republic is around 8 °C, and the annual precipitation is, on

average, higher than the potential evapotranspiration). The average DOC for a particular waste stream is also based on the IPCC default values for individual categories of waste. The average DOC for each year is given in the last column of Tab. 7-3.

Methane correction factor

The methane correction factor (MCF) is a value expressing the overall management of landfills in the country. Better-managed and deeper landfills have a higher MCF value. Shallow SWDS ensure that far more oxygen penetrate the body of the landfill and aerobically decompose DOC; thus the MCF is lower. The suggested IPCC values are in Tab. 7-4, and the values used in this inventory are in Tab. 7-5. The choice of values is based on data from recent years (1992+) and expert judgment in the early years of the timeline. In recent years only managed anaerobic SWDS are considered to occur in the Czech Republic.

Tab. 7-4 Methane correction factor values (IPCC, 2006)

	MCF
Unmanaged, shallow	0.4
Unmanaged, deep	0.8
Managed, anaerobic	1.0
Managed, semi-aerobic	0.5
Uncategorised	0.6

Tab. 7-5 MCF values employed, 1950–2024

	MCF
1950–1959	0.6
1960–1969	0.6
1970–1979	0.8
1980–1989	0.9
1990–2024	1.0

Oxidation factor

As methane moves from the anaerobic zone to the semi-aerobic and aerobic zones close to the landfill surface, part of it oxidizes to CO_2. There is no conclusive agreement in the scientific community on the intensity of methane oxidation. Oxidation is site-specific and depends on local conditions (including fissures and cracks, compacting, landfill cover, etc.). Neither representative measurements nor reliable estimations of the oxidation factor are available for the Czech Republic. According to the literature, (Straka et al., 2001), a non-zero oxidation factor appears to be site-specific, and values are very high compared to the default value, perhaps due to specific practices at the site. Therefore, they cannot be used as a standard for the whole country. However, the IPCC (2006) suggests that an oxidation factor greater than 0.1 should not be used if no site measurements are available, as a higher value increases uncertainty**.** The recommended oxidation factor of 0.1 was therefore used in the inventory**.**

Delay time

When waste is disposed of at SWDS, decomposition (and methanogenesis) does not start immediately. The IPCC model assumes that the reaction begins on the first of January in the year after deposition, equivalent to an average delay time of six months before decay to methane commences. Good practice assumes an average delay of two to six months. To use a value greater than six months, evidence must be provided. The Czech Republic has no representative country specific value for delay time; therefore, the default value of six months is used.

Fraction of methane

The fraction of methane (F) is a parameter that indicates the mass share of methane in the total amount of landfill gas (LFG). A value of 0.61 was used in previous calculations of methane emissions from SWDS (NIR, 2004), and a value of 0.55 has been used in more recent years. The first value (0.61) is based on a limited number of site measurements (Straka, 2001) and is higher than the range of 0.5–0.6 suggested by IPCC. A subsequent revision of the F value was based on data collected by the Ministry of Industry and Trade (MIT, 2005+). MIT receives annual reports from landfills capturing LFG; SWDS report the net calorific value of their captured LFG. This value was compared with the gross calorific value of pure methane and yielded a value of 0.55, which fits well within the IPCC range and was therefore used in the quantification up to the 2020 NIR. Nevertheless, the F value has been changed in this report from the country-specific 0.55 to the IPCC default of 0.5. A review team recommended this change due to unclear documentation of the origin of the 0.55 factor. In the 2021 submission, the value 0.5 was used and the time series was recalculated. Since then, F = 0.5 has been applied; however, more detailed research on LFG composition in the Czech Republic and on factor F will be carried out in the coming years.

Recovered methane

In most cases, landfill gas is collected by an LFG collection system in the body of the landfill and then used for energy production. Based on the 2006 IPCC Guidelines (IPCC, 2006), this methane (from LFG), which is converted to CO_2 and has a biogenic origin, is not considered to constitute GHG emissions; therefore, recovered methane (R) is subtracted from total emissions. There is no default value for R, so country-specific estimates were used, based on various sources originating from the Ministry of Industry and Trade. The data on LFG volume and the number of landfills capturing LFG are official and available on the Ministry of Industry and Trade's website (Ministry of Industry and Trade, 2021). Data on the energy obtained from recovered LFG are obtained on request; the Ministry of Industry and Trade does not publish them. As mentioned above, the Ministry of Industry and Trade conducts an annual survey of all SWDS, and all energy data on LFG used for energy purposes are collected. An attempt has been made to update older estimates. Since the survey started in 2005, it has been possible to provide estimates for the time series between 2003 and 2014. Estimates from Straka (2001) were used for the 1990–1996 period, and linear interpolation of recovered methane was used between 1996 and 2003. In 2024, 65 facilities were recovering LFG in the country. In recent years, a decrease in recovered CH_4 has been observed. It is assumed that this may be correlated with the decreasing trend in landfilling in previous years and with the time delay in gas generation, but this has not yet been confirmed.

Total methane emissions are calculated using the IPCC CH_4 model equation. Havránek (2007) provides detailed time series from 1950, including a breakdown into individual waste components. Tab. 7-6 lists methane emissions from this category.

Tab. 7-6 Methane from SWDS [kt], 1990–2024

	CH_4 generation	CH_4 recovery	CH_4 emission
1990	82.93	3.25	71.71
1991	86.58	3.25	75.00
1992	89.97	3.45	77.87
1993	93.52	3.45	81.06
1994	97.03	3.45	84.22
1995	100.31	3.45	87.17
1996	104.71	6.03	88.81
1997	109.02	6.58	92.19
1998	113.24	7.12	95.50
1999	117.45	7.67	98.80
2000	120.54	8.22	101.09
2001	124.28	8.76	103.97
2002	127.93	9.31	106.76
2003	131.94	9.86	109.87

	CH_4 generation	CH_4 recovery	CH_4 emission
2004	135.92	15.58	108.31
2005	139.92	18.00	109.73
2006	144.00	20.58	111.08
2007	148.16	25.93	110.01
2008	152.92	24.58	115.50
2009	157.30	24.50	119.52
2010	162.31	24.66	123.89
2011	165.63	26.59	125.14
2012	167.57	26.56	126.90
2013	167.11	24.20	128.62
2014	166.23	25.72	126.47
2015	164.86	22.72	127.93
2016	163.11	21.30	127.63
2017	161.51	19.38	127.92
2018	161.20	17.82	129.04
2019	162.07	17.09	130.48
2020	163.06	16.67	131.75
2021	164.19	16.37	133.03
2022	165.66	15.91	134.77
2023	166.59	15.25	136.20
2024	166.64	14.89	136.58

7.2.1.3 Uncertainties and time-series consistency

Overall quantification of the uncertainty for this category is incomplete. This is considered a high priority and will be carried out in the coming years as soon as budget constraints permit. A key difficulty is that uncertainty permeates the entire waste management period 1950–2024 and therefore cannot be correctly quantified by simple analysis. Combined uncertainty was estimated by expert judgement based on default factors and activity data uncertainties (see Tab. 7-7).

Tab. 7-7 Uncertainty estimates for 5.A category

Gas	Category	AD uncertainity [%]	EF uncetrainity [%]	Origin of the parameters
CH_4	5.A.1 SWDS	30	40	Combined uncertainty of quantification parameters; expert judgement M. Havránek. verification P. Slavíková (CENIA)

7.2.1.4 Source-specific QA/QC and verification

Quality assurance entails structured checklists of activities, which are dated and signed by the sector reporter and verified by external control of the activity data.The activity data used for this sector are approved by the data producer, who verifies them before they are used for further calculations.

Since the Waste sector is relatively small, external QC is not provided; instead, QC is performed by the NIS coordinator and the results are communicated to the sectoral expert.

The activity data from national agencies and ministries are subject to internal QA/QC mechanisms, and the NIS team has only limited insight into them. Processes are in place at all state agencies and ministries to ensure that they produce accurate data.

7.2.1.5 Source-specific recalculations, including changes made in response to the review process

AD were updated backwards for 2023 in 5.A.1.a – Waste per capita.

7.2.1.6 Source-specific planned improvements, including those in response to the review process

Based on TERT encouragement Czechia plans to reassess data on the amount of industrial solid waste, which is currently based on a calculated average that is constant for all years. The industrial production index used in category 5.D could be used in the future for estimation.

7.2.2 Unmanaged Waste Disposal Sites (CRT 5.A.2)

This category is not relevant for the Czech Republic.

7.2.2.1 Source-specific planned improvements, including those in response to the review process

Based on TERT recommendations, Czechia will estimate emissions from the 5.A.2 category to ensure the completeness of the emission estimates from SWDS.

7.2.3 Uncategorized Waste Disposal Sites (CRT 5.A.3)

This category is not relevant for the Czech Republic.

7.3 Biological Treatment of Solid Waste (CRT 5.B)

The biological treatment of waste includes two categories: 5.B.1 Composting and 5.B.2 Anaerobic digestion. Composting is mostly an aerobic process and thus the production of methane is insignificant. Anaerobic digestion is a process deliberately leading to the generation of methane (as a part of biogas). However, it is a controlled process mainly directed towards capturing the produced biogas, and thus the emissions from this source category are also relatively small. Anaerobic digestion increased significantly between 2006 and 2016 and has since oscillated around 550 kt CO_2 eq**.** An overall overview of this source category is shown in Fig. 7-6.

7.3.1 Composting (CRT 5.B.1)

7.3.1.1 Source category description

This category quantifies emissions from industrial composting facilities. Emissions from household compost heaps are not estimated because there are no available data on household composting in the Czech Republic. These emissions are considered negligible because household compost heaps are usually smaller than industrial facilities, and the amount of biowaste deposited is also small. Nevertheless, they are taken into account



Fig. 7-6 The development of emissions from biological treatment of solid waste, 2003–2024 (2003 and 2004 only anaerobic digestion)

conceptually, and a new methodology is planned, although all these factors will introduce high levels of uncertainty in the results.

7.3.1.2 Methodological issues

This source category quantifies emissions from composting based on data on waste management. The composting data are obtained from the ISOH system (for more details about ISOH, see source category 5.A).

Following the IPCC 2006 Guidelines, composted waste was split into the following groups: municipal solid waste (MSW) and other waste. Municipal solid waste includes waste from households and similar waste from commercial entities. "Other waste" comprises all composted waste except municipal waste. Both categories use an identical emission factor (EF). Fresh (wet) weight data and the default EF from the IPCC 2006 Guidelines are used. No data were available for either category before 2005, and further research has been launched to determine the reasons for this data gap. The amount of composted MSW has increased gradually since 2016. Since 2016, all municipalities have been obliged to ensure the collection of biowaste for their inhabitants. Increasing composting is a long term objective of Czech environmental policy. The overall development of the category is shown in Tab. 7-8.

Tab. 7-8 Emissions of GHG (and related parameters) from composting, 2005–2024

	2005	2006	2007	2008	2009	2010	2011	2012	2013	2014
MSW [kt]	48.8	61.5	79.8	114.4	134.6	144.1	181.9	153.5	202.8	303.1
Other waste [kt]	288.8	222.7	296.4	428.7	221.3	358.2	190.1	228.3	247.0	217.2
CH_4 emission factor [kg CH_4/t]	4									
N_2O emission factor [kg N_2O/t]	0.24									
Total Composting emissions CH_4 [kt]	1.35	1.14	1.50	2.17	1.42	2.01	1.49	1.53	1.80	2.08
Total Composting emissions N_2O [kt]	0.08	0.07	0.09	0.13	0.09	0.12	0.09	0.09	0.11	0.12
Total composting GHG [kt CO_2 eq.]	59.3	49.9	66.1	95.4	62.5	88.2	65.3	67.0	79.0	91.4
	2015	**2016**	**2017**	**2018**	**2019**	**2020**	**2021**	**2022**	**2023**	**2024**
MSW [kt]	374.0	583.5	615.1	639.8	721.7	751	760.4	732.5	729.2	725.1
Other waste [kt]	249.4	305.9	283.3	278.9	305.0	289.0	280.2	273.1	242.9	268.9
CH_4 emission factor [kg CH_4/t]	4									
N_2O emission factor [kg N_2O/t]	0.24									
Total Composting emissions CH_4 [kt]	2.49	3.56	3.59	3.67	4.11	4.16	4.16	4.02	3.89	3.98
Total Composting emissions N_2O [kt]	0.15	0.21	0.22	0.22	0.25	0.25	0.25	0.24	0.23	0.24
Total composting GHG [kt CO_2 eq.]	109.5	156.2	157.8	161.3	180.3	182.6	182.7	176.6	170.7	174.5

7.3.1.3 Uncertainties and time-series consistency

This category has default uncertainty, as only default factors are used. The uncertainty of the reported activity data is estimated to be small (+/- 5%); however, the largest source of uncertainty is neglected in the official data – the uncertainty in household composting.

Time series consistency is ensured as the inventory approaches concerned are employed identically across the whole reporting period from the base year 1990 to 2024. However, the data for composting of waste are available from the year 2005.

7.3.1.4 Source-specific QA/QC and verification

The sector's QA/QC plan was updated in 2016. Quality assurance entails structured checklists of activities, which are dated and signed by the sector reporter and verified by external control of the activity data. The activity data used for this sector are approved by the data producer, who verifies them before they are used for further calculation.

Since the waste sector is fairly small, external QC is not provided; instead, QC is performed by a NIS coordinator and the results are communicated to the sectoral expert.

Activity data from national agencies and ministries are the subjects of internal QA/QC mechanisms and the NIS team has only limited insights into them. Processes in place at all state agencies and ministries to ensure that they produce accurate data.

7.3.1.5 Source-specific recalculations, including changes made in response to the review process

No recalculations were made in this subsector.

7.3.1.6 Source-specific planned improvements, including those in response to the review process

No specific improvements are planned for this category for the next submission.

7.3.2 Anaerobic Digestion at Biogas Facilities (CRT 5.B.2)

7.3.2.1 Source category description

Anaerobic digestion (AD) is a process of transforming biowaste into gas (biogas). However, emissions reported in this category are not equal to the total amount of gas produced (see Methodological issues). AD in the Czech Republic has increased from 86 digesting facilities in 2009 to 402 in 2024. However, 2009 was already after the main boom in the construction of biogas plants had begun. In 2005, there were only 5 AD facilities in the whole Czech Republic. This rapid increase was driven by the increasing availability of technology and governmental subsidies for energy from biogas produced using AD. The number of AD facilities has been almost unchanged over the last nine years.

7.3.2.2 Methodological issues

Default emission factors were used to estimate emissions from AD. Since biogas production at AD facilities is carefully monitored (due to government subsidies), data on biogas production were used as activity

data. The Ministry of Industry and Trade monitors the amount of biogas and additional data, such as the calorific value of the produced gas, the energy produced and the total gas volume. The heating value of methane was used to convert the above mentioned values to mass units of produced methane. Biogas production does not necessarily mean that all of the gas is emitted. The previous submission used the default emission factor (EF) of 5% from the IPCC 2006 Guidelines. The new country specific EF of 3.1% has been applied since the 2025 submission. This value is based on research by M. Havránek et al. in the Theta TACR project (CENIA, 2021).

Since production data are used as activity data, all potential emissions from AD are calculated, not only emissions from waste formally classified as such. Some of the materials used in AD may not be considered waste under Czech legislation (e.g. agricultural residues, industrial by products, etc.), but they still generate biogas and it is logical to include them. An overview of the sector is shown in Tab. 7-9.

Tab. 7-9 Emissions and related parameters from Anaerobic digestion facilities, 2003–2024

	2003	2004	2005	2006	2007	2008	2009	2010	2011	2012	2013
Number of biogas stations	8	10	9	14	21	49	86	115	186	317	388
Energy [TJ]	142	122	120	325	589	1 129	2 807	4 660	7 547	12 721	21 040
Conversion [TJ/kt]						50.009					
Activity data – R CH_4 [kt]	2.84	2.44	2.40	6.50	11.78	22.58	56.13	93.18	150.91	254.37	420.72
Emissions CH_4 (CS 3.1%) [kt]	0.088	0.076	0.074	0.201	0.365	0.700	1.740	2.889	4.678	7.886	13.042
	2014	**2015**	**2016**	**2017**	**2018**	**2019**	**2020**	**2021**	**2022**	**2023**	**2024**
Number of biogas stations	404	403	404	404	404	402	398	400	400	408	408
Energy [TJ]	22 472	22 870	22 357	22 669	22 544	21 652	22 297	22 181	22 430	22 368	22 368
Conversion [TJ/kt]						50.009					
Activity data – R CH_4 [kt]	449.36	457.32	447.06	453.3	450.8	432.96	445.86	443.55	448.53	447.29	447.29
Emissions CH_4 (CS 3.1%) [kt]	13.93	14.18	13.86	14.05	13.98	13.42	13.82	13.75	13.90	13.87	13.87

7.3.2.3 Uncertainties and time-series consistency

The time series 2003–2024 is consistent, since the same method, factors and the data source are used throughout. Uncertainty in this source category is characterised by an emission factor (EF) range of -100 % to +100 %.

Tab. 7-10 Uncertainity estimates for 5.B category

Gas	Category	AD uncertainity [%]	EF uncetrainity [%]	Origin of the parameters
CH_4	5.B.1 Composting	20	NA	AD Expert judgement M. Havránek; EF IPCC default, verification of AD Jiří Valta (CENIA)
N_2O	5.B.1 Composting	20	NA	AD Expert judgement M. Havránek; EF IPCC default, verification of AD Jiří Valta (CENIA)
CH_4	5.B.2 Anaerobic digestion	20	100	AD Expert judgement M. Havránek; EF IPCC default, verification of AD Jiří Valta (CENIA)

7.3.2.4 Source-specific QA/QC and verification

The QA/QC plan was updated in 2014. Quality assurance entails structured checklists of activities that are dated and signed by the sector reporter and verified by external control of the activity data. Activity data used for this sector are approved by the data producer, who verifies them before they are used for further calculations.

Since the Waste sector is fairly small, external QC is not provided; instead, QC is performed by the NIS coordinator and the results are communicated to the sectoral expert.

The activity data from national agencies and ministries are subject to internal QA/QC mechanisms, and the NIS team has only limited insight into them. Processes are in place at all state agencies and ministries to ensure that they produce accurate data.

7.3.2.5 Source-specific recalculations, including changes made in response to the review process

No recalculations were made in this subsector.

7.3.2.6 Source-specific planned improvements, including those in response to the review process

No specific improvements are planned for this category for the next submission.

7.4 Incineration and Open Burning of Waste (CRT 5.C)

In the Czech Republic, some incineration plants incinerate waste without energy recovery. Incineration plants that recover energy, together with the waste used as fuel, are included in the Energy sector (category 1.A.1.a.i). This chapter includes only waste that is disposed of by incineration or is openly burned, which is an illegal activity in the Czech Republic but sometimes occurs, e.g. in the case of unintentional (or occasionally deliberate) landfill or waste bin fires. The chapter and values on open burning of waste (5.C.2) have been reported from the submission 2022

7.4.1 Waste incineration (CRT 5.C.1)

This category contains emissions from waste incineration in the Czech Republic. Waste incineration is defined as the combustion of waste in controlled incineration facilities. Modern waste incinerators have tall stacks and specially designed combustion chambers that ensure high combustion temperatures, long residence times and efficient waste agitation, while introducing air for more complete combustion.



Fig. 7-7 Development of emissions from waste incineration, 1990–2024

The types of solid waste incinerated include industrial waste, hazardous waste, clinical waste, municipal solid waste (MSW) and sewage sludge (IPCC, 2006). However, under Czech law it is difficult to distinguish these categories clearly, as some are embedded within other categories and, for example, no specific category called "industrial waste" exists. Category 5.C.1 (Waste incineration) includes emissions of CO_2, CH_4 and N_2O from these practices. However, almost all emissions are caused by CO_2. Development of the category is shown in Fig. 7-7.

7.4.1.1 Source category description

There are several tens of facilities incinerating or co incinerating different kinds of waste (mostly other than MSW) without energy recovery. Their emissions are presented in this category.

7.4.1.2 Methodological issues

In this source category, only CO_2 emissions resulting from oxidation of the fossil (non biogenic) carbon fraction in the waste (e.g. plastics, rubber, liquid solvents, waste oil) during incineration are considered in the net emissions and are included in the national CO_2 emission estimates. In addition, incineration plants produce small amounts of methane and nitrous oxide. All these emissions are reported in category 5.C.1. Since 2021, category 5.C.1 has been divided into four waste streams: MSW, clinical waste, sewage sludge and industrial waste (including residual waste). No separate category "hazardous waste" is reported, as under Czech law hazardous waste is included in all four of these categories. Some sludges are hazardous, some fractions of MSW are hazardous and even clinical waste is not entirely hazardous but consists of both hazardous and non hazardous parts. As mentioned earlier, there is also no specific category "industrial waste"; therefore, the IPCC category Industrial waste is filled with residual data – the incinerated waste that does not fall into the categories MSW, clinical waste or sewage sludge. However, this "industrial waste" is mostly composed of waste from industry and can therefore be considered industrial waste (this category also includes both hazardous and non hazardous waste). The four subcategories mentioned above are reported with emissions split into biogenic and non biogenic parts. However, CO_2 emissions of biogenic origin are reported only as an information item and are not included in the national totals. The entire time series was divided into these four waste subcategories, but the total amount of combusted waste did not change.

Estimations of CO_2 emissions are based on the Tier 1 approach (IPCC, 2006). MSW composition is needed to estimate emissions from MSW. In this case, the MSW composition used in category 5.A is applied

instead of the 2006 IPCC Guidelines composition. Category 5.A also uses more recent country specific values instead of the IPCC default values. MSW composition is necessary for calculating MSW emission factors, which are not given as a single value but only separately for each MSW component (type). Total MSW emission factors (presented in Tab. 7-12) are calculated by multiplying the specific EFs for each type of MSW by the MSW composition; the final EF is a weighted mean. In the case of sewage sludge, values from the IPCC 2019 Refinement to the 2006 Guidelines are used, because sewage sludge is the only item affected by this Refinement. However, sewage sludge is considered to contain only biogenic carbon, so only biogenic CO_2 emissions are affected by the use of the 2019 Refinement, and these emissions are very low. All parameters used, together with their origin, are listed in Tab. 7-11.

The calculation method assumes that total fossil CO_2 emissions depend on the amount of carbon in the waste, the fraction of fossil carbon and the combustion efficiency of waste incineration. Due to a lack of country specific data for the necessary parameters, default data from the IPCC Guidelines were used for the calculations, with the exception of combustion efficiency, which does not reach the default value and has been reduced to a country specific (CS) value of 0.995. The default factor of 1.0 is considered unrealistic in light of evidence from the literature and from bottom ash measurements, where the share of unburnt carbon can be determined; this indicates that not all carbon in the fuel is incinerated. The literature supporting this assumption is reviewed in Annex A5.4. The impact on the inventory is negligible; however, using a factor lower than 100% is easier to handle when assessing uncertainty.

Tab. 7-11 Parameters of incineration used for each type of waste and their origin

	MSW		Clinical		Sewage sludge		Industrial (+ residues)	
Total carbon content	**0.4**	Tab. 2.4 + MSW composition	**0.6**	Tab. 5.2	**0.3**	Tab. 5.2*	**0.5**	Tab. 5.2
Fossil carbon fraction	**0.3**	Tab. 2.4 + MSW composition	**0.4**	Tab. 5.2	**0**	Tab. 5.2	**0.9**	Tab. 5.2
Combustion efficiency	**0.995**	CS	**0.995**	CS	**0.995**	CS	**0.995**	CS
C-CO_2 ratio	**3.7**	Eq. 5.1	**3.7**	Eq. 5.1	**3.7**	Eq. 5.1	**3.7**	Eq. 5.1
Dry matter content	**0.7**	Tab. 2.4 + MSW composition	**0.65**	Tab. 2.6 (from water content)	**0.1**	Chap. 2.3.2	**0.9**	Tab. 2.5 (from water content - "Other")
CH_4 emission factor [kt CH_4/kt wet waste]	**2.0E-07**	Tab. 5.3	**2.0E-07**	Tab. 5.3	**9.7E-06**	Chap. 5.4.2	**2.0E-07**	Tab. 5.3
N_2O emission factor [kt N_2O/kt wet waste]	**5.0E-05**	Tab. 5.6	**1.0E-04**	Tab. 5.6 (as industrial)	**9.0E-04**	Tab. 5.6	**1.0E-04**	Tab. 5.6

*Tab. = Table (and its number) in 2006 IPCC Guidelines (IPCC, 2006), Eq. = Equation (and its number) from 2006 IPCC Guidelines (IPCC, 2006), Chap. = Chapter (and its number) from 2006 IPCC Guidelines where the value is written in text (IPCC, 2006), * = values from 2019 Refinement (IPCC, 2019), MSW composition used for the Czech Republic*

The activity data (amount of waste incinerated in each category) are based on the ISOH database. The system uses categorization of waste management activities and this source category is listed under code D10 – incineration on land. The problem is that the database misses data before 2002 and incineration data in ISOH have been consistent since 2005 when the new methodology began to be used; hence, estimates obtained from MIT were used before the date. MIT issued a special report on the history of incineration in the Czech Republic, which was used to derive data for this category before 2005. These derived data are for the total amount of waste incinerated. The total waste was separated into the four categories before 2005 by extrapolation of the share of categories in the timeline 2005–2024. The waste data are presented in Tab. 7-12. All waste data that are used for the calculation are in wet weight.

Correction factors for dry matter content are used for CO_2 emissions. Methane and nitrous oxide emission factors are for wet waste, hence no correction is applied. Emissions for every GHG are divided into biogenic and non-biogenic part. To save room in Tab. 7-13, where GHG emissions from waste incineration for each type of waste 1990–2024 are presented, the results are divided into biogenic and non-biogenic waste fractions only for the important gas – CO_2. Furthermore, only the non-biogenic (fossil) part is counted to the total. Methane and nitrous oxide are listed together in the table although they are reported in the UNFCCC reporter separately for the biogenic and fossil waste fractions.

Tab. 7-12 Waste incinerated [kt] by types 1990–2024 (2005–2024 data from ISOH, prior to 2005 extrapolation)

	1990	1991	1992	1993	1994	1995	1996	1997	1998	1999	2000	2001
MSW	0.01	0.03	0.05	0.11	0.21	0.31	0.38	0.47	0.54	0.63	0.58	0.88
Clinical waste	0.28	0.54	0.86	1.50	2.59	3.42	3.95	4.68	5.24	5.91	5.33	7.91
Sewage sludge	0.40	0.47	0.53	0.71	0.97	1.06	1.03	1.04	1.01	1.00	0.79	1.04
Industrial (+ residual)	13.40	15.85	18.37	24.73	34.58	38.28	37.94	39.18	38.79	39.04	31.70	42.64
	2002	2003	2004	2005	2006	2007	2008	2009	2010	2011	2012	2013
MSW	1.21	1.76	2.32	1.74	2.13	2.55	2.01	2.06	2.33	2.25	2.11	2.84
Clinical waste	11.76	13.82	13.53	14.91	17.39	18.39	20.04	21.72	20.46	22.85	24.27	24.56
Sewage sludge	1.52	2.26	1.41	0.82	0.81	1.10	1.41	1.23	1.22	1.20	1.12	1.00
Industrial (+ residual)	61.07	99.15	92.66	64.87	83.41	50.70	52.96	43.69	60.43	50.36	48.78	50.84
	2014	2015	2016	2017	2018	2019	2020	2021	2022	2023	2024	
MSW	3.95	3.71	3.15	3.5	3.93	3.68	4.43	3.47	3.51	3.38	3.12	
Clinical waste	25.46	27.03	28.12	28.97	29.55	27.53	28.76	33.99	33.87	32.66	30.28	
Sewage sludge	0.69	0.46	0.58	0.42	0.39	0.5	0.44	0.43	0.52	0.36	0.37	
Industrial (+ residual)	50.14	49.46	48.93	57.39	59.69	58.55	55.13	48.18	40.09	30.05	32.17	

Tab. 7-13 GHG emissions from waste incineration for each type of waste 1990–2024

	1990	1991	1992	1993	1994	1995	1996	1997	1998	1999	2000	2001
MSW CO_2 emissions – Fossil [kt]	0.00	0.01	0.01	0.03	0.06	0.09	0.12	0.14	0.17	0.19	0.18	0.27
MSW CO_2 emissions – Biogenic [kt]	0.01	0.02	0.03	0.08	0.15	0.22	0.27	0.33	0.39	0.45	0.41	0.63
MSW CH_4 emissions [kt]	3E-09	5E-09	9E-09	2E-08	4E-08	6E-08	8E-08	9E-08	1E-07	1E-07	1E-07	2E-07
MSW N_2O emissions [kt]	7E-07	1E-06	2E-06	5E-06	1E-05	2E-05	2E-05	2E-05	3E-05	3E-05	3E-05	4E-05
	2002	2003	2004	2005	2006	2007	2008	2009	2010	2011	2012	2013
MSW CO_2 emissions – Fossil [kt]	0.37	0.54	0.71	0.53	0.65	0.78	0.62	0.63	0.72	0.69	0.65	0.87
MSW CO_2 emissions – Biogenic [kt]	0.86	1.26	1.66	1.25	1.52	1.82	1.44	1.47	1.67	1.61	1.51	2.03
MSW CH_4 emissions [kt]	2E-07	4E-07	5E-07	3E-07	4E-07	5E-07	4E-07	4E-07	5E-07	4E-07	4E-07	6E-07
MSW N_2O emissions [kt]	6E-05	9E-05	1E-04	9E-05	1E-04	1E-04	1E-04	1E-04	1E-04	1E-04	1E-04	1E-04
	2014	2015	2016	2017	2018	2019	2020	2021	2022	2023	2024	

MSW CO_2 emissions – Fossil [kt]	1.21	1.14	0.96	1.07	1.2	1.13	1.36	1.06	1.07	1.04	0.96	
MSW CO_2 emissions – Biogenic [kt]	2.82	2.65	2.25	2.5	2.81	2.63	3.17	2.48	2.51	2.42	2.23	
MSW CH_4 emissions [kt]	7.9E-07	7.4E-07	6.3E-07	7.0E-07	7.9E-07	7.4E-07	8.9E-07	6.9E-07	7.0E-07	6.8E-07	6.2E-07	
MSW N_2O emissions [kt]	2.0E-04	1.9E-04	1.6E-04	1.7E-04	2.0E-04	1.8E-04	2.2E-04	1.7E-04	1.8E-04	1.7E-04	1.6E-04	
	1990	**1991**	**1992**	**1993**	**1994**	**1995**	**1996**	**1997**	**1998**	**1999**	**2000**	**2001**
Clinical waste CO_2 emissions – Fossil [kt]	0.16	0.30	0.49	0.85	1.47	1.94	2.25	2.66	2.98	3.36	3.03	4.50
Clinical waste CO_2 emissions – Biogenic [kt]	0.24	0.46	0.74	1.28	2.21	2.92	3.37	3.99	4.48	5.05	4.55	6.75
Clinical waste CH_4 emissions [kt]	6E-08	1E-07	2E-07	3E-07	5E-07	7E-07	8E-07	9E-07	1E-06	1E-06	1E-06	2E-06
Clinical waste N_2O emissions [kt]	3E-05	5E-05	9E-05	2E-04	3E-04	3E-04	4E-04	5E-04	5E-04	6E-04	5E-04	8E-04
	2002	**2003**	**2004**	**2005**	**2006**	**2007**	**2008**	**2009**	**2010**	**2011**	**2012**	**2013**
Clinical waste CO_2 emissions – Fossil [kt]	6.69	7.86	7.70	8.49	9.90	10.77	11.40	12.36	11.65	13.00	13.81	13.98
Clinical waste CO_2 emissions – Biogenic [kt]	10.04	11.80	11.55	12.73	14.85	16.16	17.11	18.55	17.47	19.50	20.72	20.96
Clinical waste CH_4 emissions [kt]	2E-06	3E-06	3E-06	3E-06	3E-06	4E-06	4E-06	4E-06	4E-06	5E-06	5E-06	5E-06
Clinical waste N_2O emissions [kt]	1E-03	1E-03	1E-03	1E-03	2E-03	2E-03	2E-03	2E-03	2E-03	2E-03	2E-03	2E-03
	2014	**2015**	**2016**	**2017**	**2018**	**2019**	**2020**	**2021**	**2022**	**2023**	**2024**	
Clinical waste CO_2 emissions – Fossil [kt]	14.49	15.38	16.00	16.49	16.82	15.67	16.37	19.35	19.28	18.59	17.23	
Clinical waste CO_2 emissions – Biogenic [kt]	21.74	23.07	24.00	24.73	25.23	23.50	24.55	29.02	28.92	27.88	25.85	
Clinical waste CH_4 emissions [kt]	7E-06	5E-06	6E-06	4E-06	4E-06	5E-06	4E-06	4E-06	5E-06	3E-06	4E-06	
Clinical waste N_2O emissions [kt]	6E-04	4E-04	5E-04	4E-04	4E-04	5E-04	4E-04	4E-04	5E-04	3E-04	3E-04	
	1990	**1991**	**1992**	**1993**	**1994**	**1995**	**1996**	**1997**	**1998**	**1999**	**2000**	**2001**
Sewage sludge CO_2 emissions – Fossil [kt]	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Sewage sludge CO_2 emissions – Biogenic [kt]	0.04	0.05	0.06	0.08	0.11	0.12	0.11	0.11	0.11	0.11	0.09	0.11

Sewage sludge CH_4 emissions [kt]	4E-06	5E-06	5E-06	7E-06	9E-06	1E-05	1E-05	1E-05	1E-05	1E-05	8E-06	1E-05
Sewage sludge N_2O emissions [kt]	4E-04	4E-04	5E-04	6E-04	9E-04	1E-03	9E-04	9E-04	9E-04	9E-04	7E-04	1E-03
	2002	**2003**	**2004**	**2005**	**2006**	**2007**	**2008**	**2009**	**2010**	**2011**	**2012**	**2013**
Sewage sludge CO_2 emissions – Fossil [kt]	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Sewage sludge CO_2 emissions – Biogenic [kt]	0.17	0.25	0.15	0.09	0.09	0.12	0.15	0.14	0.13	0.13	0.12	0.11
Sewage sludge CH_4 emissions [kt]	2E-05	1E-05	8E-06	8E-06	1E-05	1E-05	1E-05	1E-05	1E-05	1E-05	1E-05	1E-05
Sewage sludge N_2O emissions [kt]	2E-03	1E-03	7E-04	7E-04	1E-03	1E-03	1E-03	1E-03	1E-03	1E-03	1E-03	9E-04
	2014	**2015**	**2016**	**2017**	**2018**	**2019**	**2020**	**2021**	**2022**	**2023**	**2024**	
Sewage sludge CO_2 emissions – Fossil [kt]	0	0	0	0	0	0	0	0	0	0	0	
Sewage sludge CO_2 emissions – Biogenic [kt]	0.08	0.05	0.06	0.05	0.04	0.06	0.05	0.05	0.06	0.04	0.04	
Sewage sludge CH_4 emissions [kt]	7E-06	5E-06	6E-06	4E-06	4E-06	5E-06	4E-06	4E-06	5E-06	3E-06	4E-06	
Sewage sludge N_2O emissions [kt]	6E-04	4E-04	5E-04	4E-04	4E-04	5E-04	4E-04	4E-04	5E-04	3E-04	3E-04	
	1990	**1991**	**1992**	**1993**	**1994**	**1995**	**1996**	**1997**	**1998**	**1999**	**2000**	**2001**
Industrial waste CO_2 emissions – Fossil [kt]	19.80	23.42	27.14	36.55	51.10	56.57	56.05	57.89	57.32	57.68	46.83	63.00
Industrial waste CO_2 emissions – Biogenic [kt]	2.20	2.60	3.02	4.06	5.68	6.29	6.23	6.43	6.37	6.41	5.20	7.00
Industrial waste CH_4 emissions [kt]	3E-06	3E-06	4E-06	5E-06	7E-06	8E-06	8E-06	8E-06	8E-06	8E-06	6E-06	9E-06
Industrial waste N_2O emissions [kt]	1E-03	2E-03	2E-03	2E-03	3E-03	4E-03	4E-03	4E-03	4E-03	4E-03	3E-03	4E-03
	2002	**2003**	**2004**	**2005**	**2006**	**2007**	**2008**	**2009**	**2010**	**2011**	**2012**	**2013**
Industrial waste CO_2 emissions – Fossil [kt]	90.23	145.0	136.91	95.85	123.24	74.91	78.26	64.56	89.29	74.42	72.07	75.12
Industrial waste CO_2 emissions – Biogenic [kt]	10.03	16.28	15.21	10.65	13.69	8.32	8.70	7.17	9.92	8.27	8.01	8.35
Industrial waste CH_4 emissions [kt]	1E-05	2E-05	2E-05	1E-05	2E-05	1E-05	1E-05	9E-06	1E-05	1E-05	1E-05	1E-05
Industrial waste N_2O emissions [kt]	6E-03	1E-02	9E-03	6E-03	8E-03	5E-03	5E-03	4E-03	6E-03	5E-03	5E-03	5E-03
	2014	**2015**	**2016**	**2017**	**2018**	**2019**	**2020**	**2021**	**2022**	**2023**	**2024**	
Industrial waste CO_2 emissions – Fossil [kt]	74.09	73.09	72.3	84.8	88.19	86.52	81.45	71.19	59.24	44.40	47.54	

Industrial waste CO_2 emissions – Biogenic [kt]	8.23	8.12	8.03	9.42	9.8	9.61	9.05	7.91	6.58	4.93	5.28	
Industrial waste CH_4 emissions [kt]	1E-05	1E-05	1E-05	1E-05	1E-05	1E-05	1E-05	1E-05	8E-06	6E-06	6E-06	
Industrial waste N_2O emissions [kt]	5E-03	5E-03	5E-03	6E-03	6E-03	6E-03	6E-03	5E-03	4E-03	3E-03	3E-03	

Tab. 7-13 shows the emissions for the whole category 5.C.1. As can be seen, almost all emissions are caused by the incineration of industrial and clinical waste. Categories MSW and sewage sludge are negligible (non-biogenic emissions from sewage sludge are zero at all because the fossil carbon fraction is neglected (Tab. 7-11). In the opposite of Tab. 7-12, more emissions come from 1 kt of industrial waste than from the second biggest source – clinical waste (eg. the year 2021: industrial waste incinerated 48.18 kt, clinical 33.99 kt). It is mainly caused by the emission factors, especially the fossil carbon fraction which is for industrial 0.9 but for the clinical only 0.4. Whilst the amount of the clinical waste incinerated is approximately half of the industrial waste incinerated, the emissions from clinical waste are much lower than half of the industrial emissions. In conclusion, the total amount of incinerated waste remains almost the same opposite to the total emissions that decreased by units up to tens of kt CO_2 eq.

7.4.1.3 Uncertainties and time-series consistency

The activity data come from two sources; hence there may be inconsistencies due to different data providers. An effort has been made to address this inconsistency by choosing 2005 as the year of transition to the new activity data source and by harmonising the methodology in that year. However, switching to ISOH is a more sustainable solution, as the system has institutional and legal backing at the Ministry of the Environment and provides, and is expected to continue providing, more reliable data on waste incineration in the future.

Tab. 7-14 Uncertainty estimates for 5.C.1 category

Gas	Category	AD uncertainity [%]	EF uncertainity [%]	Origin of the parameters
CO_2	5.C.1 Waste incineration	15	50	AD Expert judgement M. Havránek; EF IPCC default + expert judgement
N_2O	5.C.1 Waste incineration	20	70	AD Expert judgement M. Havránek; EF IPCC default
CH_4	5.C.1 Waste incineration	20	80	AD Expert judgement M. Havránek; EF IPCC default

7.4.1.4 Source-specific QA/QC and verification

The QA/QC plan of the National Inventory System is applied to the entire Waste sector.

For this particular subcategory, bottom up data provided by official sources (Ministry of Industry and Trade, MIT) and data from ISOH are used. However, the inaccuracy or uncertainty of these data is not quantified directly but is estimated by expert judgment. The compiler cross checked the incineration data against top down data produced by other state agencies.

7.4.1.5 Source-specific recalculations, including changes made in response to the review process

AD were updateted backwards for 2023 in 5.C.1 – Municipal solid waste

7.4.1.6 Source-specific planned improvements, including those in response to the review process

In accordance with TERT recommendations, Czechia will ensure time-series consistency when estimating missing emission values for category 5.C.1, for which activity data are unavailable.

7.4.2 Open Burning of Waste (CRT 5.C.2)

Open burning of waste is illegal in the Czech Republic. Inhabitants are not allowed to burn their waste, except for some garden residues. There is evidence of accidental landfill and bin or container fires. Research on these phenomena was launched and a country specific methodology for calculating GHG emissions was finalised in 2021. In 2024, results on emissions from open burning of waste for the period since 2010 were presented. These emissions are considered negligible; therefore, the methodology was not applied to all years, nor to the reference year 2024. The method will be applied once every few years to check whether the situation has changed.

7.4.2.1 Source category description

This subcategory consists of accidental fires involving waste, or fires that should be accidental, because (as stated above) it is illegal to burn waste. Thousands of fires involving waste occur in the Czech Republic each year. Approximately 1 000 of these are landfill fires, where larger amounts of waste are burned. These fires usually last longer than, for example, bin fires, because the affected area is larger, the terrain of a landfill is demanding for firefighters and landfills represent a hazardous environment. The duration of the fire is prolonged by landfill gas, which provides additional fuel – methane. Fires at dumps or other locations with accumulated waste are included, with the exception of waste burning in households.

7.4.2.2 Methodological issues

In this source category, CO_2, CH_4 and N_2O emissions are estimated. CH_4 and N_2O emissions are more important here than in 5.C.1, because open burning represents a much more imperfect combustion process than incineration in plants, and emissions of a wider range of gases occur. The category is also divided into biogenic and non biogenic parts. In principle, the category could be further differentiated into more subcategories (such as MSW, industrial waste, etc.), but only one category is reported because the amount of waste openly burned is small and highly uncertain.

The data used for this category come from several sources. The first source is the ISOH database and its waste section, which also includes a register of waste management facilities and their descriptions. Another source is data on fires from the fire brigade, which describe each fire in which waste was burning. Finally, physicochemical tables on the properties of substances or materials are used for the calculations.

The firefighters' database contains information about the place and time of the fire and the main substances that were burning. These data are used to calculate the amount of waste burned at landfills. The amount (mass) of waste is crucial for the emission estimate and is then inserted into the IPCC equations (2006 IPCC Guidelines) for emissions from incineration and open waste burning. As the amount of openly burned waste is small and its uncertainty is large, the amounts of waste burned at landfills are included in the landfilled waste in category 5.A.

Given the various types of burned waste and the variability of their default emission factors, a combined emission factor is calculated and used for each year. The basic data are linked to category 5.A and its MSW composition, because some parameters exist only for subcategories of MSW (see 5.C.1). Therefore, MSW

composition and the default factors are combined into weighted means. The combined emission factors are in Tab. 7-15.

Tab. 7-15 Emission factors for open burning of waste for each year

	Carbon fraction	Fosil carbon fraction	Dry matter ratio	Oxidation factor (combustion efficiency)	C-CO_2 ratio	EF CH_4 [kt/kt waste]	EF N_2O [kt/kt waste]
2010	0.42	0.29	0.72	0.58	3.7	6.50E-03	1.50E-04
2011	0.42	0.29	0.72				
2012	0.43	0.32	0.75				
2013	0.42	0.32	0.75				
2014	0.42	0.33	0.75				
2015	0.43	0.32	0.76				
2016	0.43	0.32	0.77				
2017	0.43	0.29	0.75				
2018	0.43	0.26	0.74				
2019	0.43	0.26	0.74				
2020	0.43	0.26	0.74				
2021	0.43	0.26	0.74				
2022	0.43	0.26	0.74				
2023	0.43	0.26	0.74				
2024	0.43	0.26	0.74				

The calculated emissions and the amount of waste open burned in the last thirteen years are in Tab. 7-16. Only CO_2 is divided into biogenic and non biogenic parts, as in 5.C.1; the remaining emissions are not split. Emissions are calculated for the years 2010, 2013, 2016 and 2018. For the other years, only interpolation is used, as the methodology is time consuming and complex, while the emissions account for only a small share of the total.

Tab. 7-16 Amount of waste open burned and generated emissions 2010–2024

	Waste open burned [kt]	Emissions of CO_2 - Fossil [kt]	Emissions of CO_2 - Biogenic [kt]	Total emissions of CH_4 [kt]	Total emissions of N_2O [kt]
2010	39.36	7.39	18.1	0.26	0.005
2011	35.01	6.58	16.1	0.23	0.005
2012	34.41	7.42	15.9	0.22	0.005
2013	20.01	4.38	9.17	0.13	0.003
2014	33.23	7.38	15.1	0.22	0.005
2015	32.63	7.33	15.28	0.21	0.005
2016	51.49	11.7	24.84	0.33	0.008
2017	31.45	6.32	15.4	0.2	0.005
2018	21.45	3.78	10.63	0.14	0.003
2019	30.26	5.33	15.09	0.2	0.005
2020	29.67	5.22	14.87	0.19	0.004
2021	29.1	5.12	14.59	0.19	0.004

	Waste open burned [kt]	Emissions of CO_2 - Fossil [kt]	Emissions of CO_2 - Biogenic [kt]	Total emissions of CH_4 [kt]	Total emissions of N_2O [kt]
2022	28.48	5.01	14.28	0.19	0.004
2023	27.89	4.91	13.98	0.18	0.004
2024	27.30	4.81	13.69	0.18	0.004

Calculating emissions from activity data will continue every two or three years, with interpolation used for the remaining years. Unfortunately, the number and intensity of fires vary between years and depend, for example, on meteorological conditions or the cause of the fire. Thus, the fact that a single large fire can produce emissions comparable to those from hundreds of smaller fires in the same year is not explicitly reflected in the estimates.

As mentioned above, large uncertainties occur in many parts of the calculation. Data from the fire brigade have lower uncertainty than the ISOH data, and the uncertainty in the physico chemical tables is considered very small. Despite efforts to reduce uncertainty in the data, some aspects remain outside our control: time series consistency depends on the data providers, and the fire brigade is not obliged to share data with CHMI.

Tab. 7-17 Uncertainty estimates for 5.C.2 category

Gas	Category	AD uncertainity [%]	EF uncetrainity [%]	Origin of the parameters
CO_2	5.C.2 Open burning of waste	70	30	AD Expert judgement J. Esterlová; EF IPCC default + expert judgement
N_2O	5.C.2 Open burning of waste	70	40	AD Expert judgement J. Esterlová; EF IPCC default
CH_4	5.C.2 Open burning of waste	70	40	AD Expert judgement J. Esterlová; EF IPCC default

7.4.2.3 Source-specific QA/QC and verification

For this particular subcategory, bottom up data provided by official sources were used. However, the inaccuracy or uncertainty of these data is not quantified directly but is estimated by expert judgment. The compiler did not cross check the data on open burning of waste with data from other sources because this was not possible. The national methodology for estimating emissions from open burning of waste was certified and reviewed by the NIS QA/QC coordinator.

7.4.2.4 Source-specific recalculations, including changes made in response to the review process

No recalculations were made.

7.4.2.5 Source-specific planned improvements, including those in response to the review process

The Czech Republic plans to verify the availability of better activity data from the fire department and update the emission calculation.

7.5 Wastewater Treatment and Discharge (CRT 5.D)

This source category consists of two subcategories: 5.D.1. emissions from domestic wastewater treatment and 5.D.2 emissions from industrial wastewater treatment. The overall development of emissions from this source category is shown in Fig. 7-8. Emissions of CH_4 and N_2O are presented. The main drivers of the emissions are population size, industrial production growth and the share of the particular treatment options.



Fig. 7-8 Development of GHG emissions from wastewater treatment and discharge. 1990–2024

7.5.1 Domestic Wastewater Treatment (CRT 5.D.1)

7.5.1.1 Source category description

Domestic wastewater treatment in the Czech Republic is mostly centralised and more than 86% of the population is connected to the sewage systems. The rest of the population, mainly the rural population in small municipalities, has on-site treatment facilities: septic tanks, sump tanks, latrines or household treatment plants. Wastewater Treatment Plants (WWTP) treat 97.7% of all the collected water. Anaerobic technology is being increasingly used to produce biogas from sludge.



Fig. 7-9 Development of 5.D.1 emission of CH_4 by types of treatment, 1990–2024

This category was recalculated in past years to fully reflect the complexity and pathways of wastewater treatment in Czechia, effectively replacing Tier 1. Development of 5.D.1 emission of CH_4 by types of treatment represents Fig. 7-9. In 2024, emissions decreased significantly compared to 2023 due to a higher fraction of collected wastewater (AD provided by CSO). The fraction of collected wastewater increased gradually almost every year, typically from +0.07% to +1.53%. However, the change between 2023 and 2024 reached +4.15% – significantly higher than the average historical pace (see Tab. 7-18). As a consequence, emissions from uncollected wastewaters are lower and difference was higher than the significance threshold.

7.5.1.2 Methodological issues

The content of organic pollution in the water is the basic factor for determining methane emissions from wastewater management. The content of organic pollution in municipal wastewater and sludge is given as BOD_5 (the Biochemical Oxygen Demand).



Fig. 7-10 The scheme of total organic waste flow in 5.D.1

The IPCC methodology employs BOD for municipal wastewater and sludge evaluation and Chemical Oxygen Demand (COD) for industrial wastewater. The method is based on default Tier 1 where sludge treatment is neglected; however available data on biogas production from sludge treatment are used to reduce TOW (Total Organic Waste). A scheme of TOW flow is given in the following figure (Fig. 7-10).

The basic activity data (and their sources) for determining emissions from this subcategory are as follows, an overview of those factors is in Tab. 7-18 to Tab. 7-20.

- The number of inhabitants (source: Czech Statistical Office, CzSO).
- The organic pollution produced per inhabitant (source: IPCC default value).
- The conditions under which the wastewater is treated (source: Czech Statistical Office, with some specific national factors).
- The amount of proteins in the diet of the population (source: FAO).
- The amount of biogas produced from WWTP (source: MIT).

The methodological steps are as follows:

- Estimation of the total TOW of the country by using the population and default BOD value production.
- Split total TOW into two streams, one corresponding to TOW collected by central wastewater treatment plants and the other to uncollected TOW (mixture of latrines, septic tanks, root treatment plants, household biodisc plants, etc.).
- Uncollected TOW is multiplied by the implied EF based on IPCC 2006 GI resulting in methane emissions.
- Collected TOW is multiplied by the default co-discharge correction factor.
- Biogas produced by WWTP is converted to the TOW required to produce this biogas and is subtracted from collected TOW.
- Collected TOW is divided into two streams treated TOW and untreated TOW.

- Treated TOW is treated by well-managed central treatment plants (default factors) resulting in methane emissions.
- Untreated TOW is discharged into watersheds resulting in methane emissions.
- Methane emissions from all three sources are summed up resulting in emissions from this source category.

Tab. 7-18 Activity data used for 5.D.1 category, 1990–2024

	Total population [thous. pers.]	Sewer connection [%]	Water treated [%]		Total population [thous. pers.]	Sewer connection [%]	Water treated [%]
1990	10 362	72.60	72.60	**2008**	10 429	81.11	95.32
1991	10 308	72.30	69.60	**2009**	10 492	81.30	95.25
1992	10 317	72.70	77.80	**2010**	10 517	81.90	96.20
1993	10 331	72.80	78.90	**2011**	10 497	82.62	96.83
1994	10 336	73.00	82.20	**2012**	10 509	82.54	97.08
1995	10 331	73.20	89.50	**2013**	10 511	82.82	97.39
1996	10 315	73.30	90.30	**2014**	10 525	83.90	96.90
1997	10 304	73.50	90.90	**2015**	10 543	84.20	97.00
1998	10 295	74.40	91.30	**2016**	10 565	84.70	97.30
1999	10 283	74.60	95.00	**2017**	10 590	85.50	97.50
2000	10 273	74.80	94.80	**2018**	10 626	85.50	97.60
2001	10 224	74.90	95.50	**2019**	10 669	85.50	97.70
2002	10 201	77.40	92.60	**2020**	10 700	86.10	97.50
2003	10 202	77.70	94.49	**2021**	10 500	87.40	97.50
2004	10 207	77.90	94.44	**2022**	10 760	87.30	97.70
2005	10 234	79.10	94.60	**2023**	10 878	86.70	97.70
2006	10 267	80.00	94.16	**2024**	10 887	90.30	97.74
2007	10 323	80.80	95.80				

Tab. 7-19 Parameters used for 5.D.1 category, 1990–2024

Used parameters			
B_0 [kg CH_4/kg BOD]	TOW [g BOD/person/day]	Correction factor for industrial co-discharge	NCV of CH_4 [MJ/kg]
0.6	**60**	**1.25**	**50.009**

Tab. 7-20 Methane emissions from 5.D.1 category, 1990–2024

	Uncollected TOW emissions CH_4 [kt]	Untreated TOW emissions CH_4 [kt]	Treated TOW emissions CH_4 [kt]	Biogas reduction (fraction of treated TOW)	Total CH_4emissions [kt]
MCF	**0.5**	**0.1**	**0.039**		
1990	18.65	2.71	2.8	0.2	24.16
1991	18.76	2.98	2.66	0.2	24.4
1992	18.51	2.19	2.99	0.2	23.68
1993	18.46	2.09	3.04	0.2	23.59
1994	18.34	1.76	3.18	0.2	23.28
1995	18.19	1.04	3.47	0.2	22.7
1996	18.1	0.96	3.5	0.2	22.56
1997	17.94	0.91	3.53	0.2	22.37
1998	17.32	0.88	3.58	0.2	21.77
1999	17.16	0.5	3.73	0.2	21.4
2000	17.01	0.53	3.73	0.2	21.27
2001	16.86	0.45	3.75	0.2	21.06
2002	15.15	0.77	3.75	0.2	19.66

	Uncollected TOW emissions CH_4 [kt]	Untreated TOW emissions CH_4 [kt]	Treated TOW emissions CH_4 [kt]	Biogas reduction (fraction of treated TOW)	Total CH_4 emissions [kt]
MCF	**0.5**	**0.1**	**0.039**		
2003	14.95	0.58	3.87	0.19	19.4
2004	14.82	0.57	3.78	0.21	19.17
2005	14.05	0.55	3.76	0.23	18.37
2006	13.49	0.61	3.81	0.23	17.91
2007	13.02	0.45	3.97	0.22	17.44
2008	12.95	0.5	3.93	0.24	17.38
2009	12.89	0.51	3.99	0.23	17.39
2010	12.51	0.4	3.99	0.25	16.91
2011	11.99	0.33	3.98	0.26	16.3
2012	12.06	0.31	4.06	0.25	16.42
2013	11.86	0.28	4.07	0.25	16.22
2014	11.13	0.34	4.19	0.24	15.66
2015	10.91	0.34	4.26	0.23	15.52
2016	10.65	0.3	4.3	0.23	15.26
2017	10.1	0.28	4.38	0.23	14.76
2018	10.1	0.27	4.32	0.24	14.69
2019	10.18	0.27	4.35	0.24	14.8
2020	9.79	0.29	4.44	0.23	14.52
2021	8.69	0.29	4.46	0.22	13.45
2022	8.98	0.27	4.54	0.23	13.79
2023	9.51	0.27	4.48	0.24	14.25
2024	6.94	0.28	4.73	0.23	11.95

The MCF in the category "uncollected TOW" is 0.5, because this value is the default MCF in 2006 IPCC GLs, vol. 5, ch. 6, table 6.3 for septic systems, which are the most common option for uncollected wastewater treated on site. For the category “untreated TOW” the used MCF value is 0.1, which is the default value in 2006 IPCC GLs, vol. 5, ch. 6, table 6.3 for sea, river and lake discharge, as the untreated wastewater ends mostly in rivers. The MFC value for “treated TOW” is derived from 2016 values for the WWTP, where 87% were not overloading and 13% were overloading, and 13% resulted in an average MCF for WWTP of 0.039. The information source for this determination is an overview of CZ WWTP, which gives details of every individual WWTP and indicates whether they comply with existing legislation (European Commission, 2016).

Determining of the N_2O emissions from municipal wastewater is a part of a broader complex of calculations, particularly in agriculture. Tier 1 calculation is based on the number of inhabitants and estimation of the average annual protein consumption, together with a correction for co-discharge from industry. Data and factors used for the estimates of this source subcategory are in Tab. 7-21.

Tab. 7-21 Indirect N_2O emissions [kt] from 5.D.1 and 5.D.2, 1990–2024

	Proteins [g/capita/day*]	Population [number, thous. pers.]	Fnpr [kg N/kg protein]	Fnon-con**	Find-com**	N efluent [kg N/yr]	EF [kg N_2O/kg N]	Emissions N_2O [kt]
1990	105.77	10 362				100 016 115		0.79
1991	92.98	10 308				87 463 239		0.69
1992	87.37	10 317	0.16	1.25	1.25	82 258 845	0.005	0.65
1993	92.75	10 331				87 432 447		0.69
1994	88.36	10 336				83 338 924		0.65

	Proteins [g/capita/day*]	Population [number, thous. pers.]	Fnpr [kg N/kg protein]	Fnon-con**	Find-com**	N efluent [kg N/yr]	EF [kg N_2O/kg N]	Emissions N_2O [kt]
1995	93.14	10 331				87 801 379		0.69
1996	95.59	10 315				89 976 569		0.71
1997	93.31	10 304				87 730 746		0.69
1998	96.91	10 295				91 038 567		0.72
1999	91.4	10 283				85 760 989		0.67
2000	90.29	10 273				84 634 767		0.66
2001	92.84	10 224				86 615 776		0.68
2002	92.97	10 201				86 538 394		0.68
2003	92.99	10 202				86 564 452		0.68
2004	96.08	10 207				89 487 156		0.7
2005	99.33	10 234				92 760 403		0.73
2006	95.26	10 267				89 242 564		0.7
2007	95.06	10 323				89 541 327		0.7
2008	93.79	10 429				89 260 824		0.7
2009	92.58	10 492				88 631 338		0.7
2010	92.8	10 517				89 060 048		0.7
2011	90.82	10 497				86 989 332		0.68
2012	86.86	10 509				83 296 338		0.65
2013	87.47	10 511				83 892 749		0.66
2014	87.3	10 525				83 841 737		0.66
2015	87.7	10 543				84 371 211		0.66
2016	95.7	10 565				92 262 663		0.72
2017	95.9	10 590				92 667 618		0.73
2018	95.9	10 626				92 990 561		0.73
2019	95.4	10 669				92 879 133		0.73
2020	95.6	10 700				93 342 802		0.73
2021	96.1	10 500				92 083 266		0.72
2022	96.8	10 760				95 038 884		0.76
2023	96.8	10 878				96 085 745		0.75
2024	96.8	10 887				96 160 728		0.76

** The latest available data is used for 2017; data for Czechoslovakia are used for 1990–1992.*
*** Fnpr - Fraction of Nitrogen in Protein*
Fnon-con - Factor for Non-consumed Protein Added to the Wastewater
Find-com - Factor for Industrial and Commercial Co-discharged Protein into the Sewer System

The values of the factors in the table are the default factors. Factor Fnon-con is the average between the default factor for developed countries (1.4) and developing countries (1.1) to reflect the nature of the Czech wastewater treatment system in transition. The activity data about the population are from the Czech Statistical Office and the protein consumption in the Czech Republic comes from the nutrition statistics of FAO (Faostat, 2021).

7.5.1.3 Uncertainties and time-series consistency

The uncertainty in this category is high because the data on organic pollution are based on the population alone and the science behind the formation of N_2O is also not robust and varies significantly.

Tab. 7-22 Uncertainty estimates for 5.D.1 category

Gas	Category	AD uncertainity [%]	EF uncertainity [%]	Origin of the parameters
CH_4	5.D.1 Domestic wastewater	21	50	Combined uncertainty of quantification parameters Expert judgement M. Havránek
N_2O	5.D.1 Domestic wastewater	26	50	AD Expert judgement M. Havránek; EF IPCC default

7.5.1.4 Source-specific QA/QC and verification

Quality assurance entails structured checklists of activities dated and signed by the sector reporter and verified by external activity data control. Activity data used for this sector are approved by the data producer, who verifies them before they are used for calculation.

Because the waste sector is fairly small, an external subject is not used to provide QC; instead, QC is performed by a NIS coordinator and the results are communicated to the sectoral expert.

Activity data from national agencies and ministries are the subjects of internal QA/QC mechanisms and the NIS team has only limited insights into them. Processes are in place for all state agencies and ministries to ensure that state agencies produce the correct data.

7.5.1.5 Source-specific recalculations, including changes made in response to the review process

In category 5.D.1. N_2O emissions were transferred from Plants in Effluent based on CZ-5D-2025-0001 observation

7.5.1.6 Source-specific planned improvements, including those in response to the review process

No specific improvements are planned for this category for the next submission.

7.5.2 Industrial Wastewater (CRT 5.D.2)

7.5.2.1 Source category description

This source category deals with emissions from the treatment of industrial wastewater. Most industrial plants have their wastewater treatment systems; however, a significant fraction are part of municipal sewage systems. Both categories 5.D.1 and 5.D.2 are based on production statistics. Industrial waste water (IWW) treatment at bigger companies is mostly managed *in situ*. Although the usage of anaerobic sludge treatment is increasing, industrial plants are usually using aerobic techniques. In category 5.B, the data allow division between waste AD and water treatment digestion (and are sufficiently precise to a division between domestic wastewater and IWW). Therefore double counting is omitted. Separated sludge not used for biogas production is treated by a mixture of aerobic treatment options.



Fig. 7-11 Development of emissions from 5.D.2 by types of emission sources

Development of the category is in Fig. 7-11.

7.5.2.2 Methodological issues

The category was recalculated in recent years. The recalculation method was based on Tier 1 with country-specific data to ensure that it was based more on the available statistics. The main activity data for estimating the methane emissions from this subcategory is determining the amount of degradable pollution in industrial wastewater. This part is identical to the previous calculation and stayed unchanged. Specific production of pollution – the amount of pollution per production unit – kg COD/kg product is used in the source category. The value is multiplied by the production or the value obtained from the overall amounts of industrial wastewater and a qualified estimate of their concentrations (in kg COD/m^3). The approach used is based on the IPCC 2006 Gl. The necessary activity data were taken from the annual report of CzSO (Statistical Yearbook) and the other parameters required for the calculation were taken from the 2006 Guidelines (IPCC, 2006). In addition, it was estimated that the amount of sludge equalled 10% of the total pollution in industrial waters (25% was assumed in the Meat and Poultry, Paper and Pulp and Vegetables, Fruits and Juices categories). These estimates are based on Dohanyos and Zábranská (2000); and Zábranská (2004), see Tab. 7-23. The fraction of industrial water treated by a particular technology is based on CzSO data on industrial wastewater treatment. Wastewater is divided into two followings groups. First, untreated water is released into the watershed without treatment (now almost non-existent). Second, treated water is managed in well-maintained aerobic facilities. Sludge separated from IWW is treated aerobically or anaerobically for methane production. Since sludge data is generally unavailable in the country we reverse the use of R – recovered methane. Based on R we estimate the necessary amount of sludge COD subtracted from the total. The effect on the total emissions is identical, but treatment streams remain separated. Data on R have been obtained annually from MIT renewable statistics since 2003; data on R before 2003 are based on expert estimates. The detailed flow of quantification is shown in Fig. 7-12.

Tab. 7-23 Industrial production data and used water generation and COD content factors, 1990–2024

	Alcohol Refining	Dairy Products	Beer & Malt	Meat & Poultry	Organic Chemicals	Petroleum Refineries	Plastics and Resins	Pulp & Paper (combined)	Soap and Detergents	Starch production	Sugar Refining	Vegetable Oils	Vegetables, Fruits & Juices	Wine & Vinegar
COD suggested	11	2.7	2.9	4.1	3	1	3.7	9	0.9	10	3.2	0.9	5	1.5

	Alcohol Refining	Dairy Products	Beer & Malt	Meat & Poultry	Organic Chemicals	Petroleum Refineries	Plastics and Resins	Pulp & Paper (combined)	Soap and Detergents	Starch production	Sugar Refining	Vegetable Oils	Vegetables, Fruits & Juices	Wine & Vinegar
[kg/m³]														
Wastewater [m³/ton of product]	24	7	6.3	13	67	0.6	0.6	162	3	9	11	3.1	20	23
Industrial production [mil. tonnes]														
1990	0.08	1.33	2.34	0.85	0.27	7.3	0.69	0.71	0.12	0.03	0.57	0.14	0.14	0.05
1991	0.09	1.12	2.18	0.78	0.19	6.45	0.55	0.57	0.08	0.02	0.57	0.12	0.14	0.06
1992	0.09	1.06	2.26	0.59	0.21	6.62	0.56	0.56	0.08	0.03	0.53	0.14	0.14	0.05
1993	0.09	1.14	2.12	0.5	0.23	6.21	0.58	0.52	0.05	0.04	0.52	0.09	0.14	0.05
1994	0.08	1.09	2.17	0.46	0.3	7.17	0.73	0.62	0.04	0.03	0.43	0.1	0.13	0.05
1995	0.08	0.91	2.2	0.44	0.3	7.1	0.67	0.49	0.04	0.03	0.51	0.12	0.14	0.05
1996	0.08	0.87	2.21	0.45	0.33	7.08	0.74	0.47	0.05	0.03	0.6	0.12	0.13	0.05
1997	0.07	0.9	2.24	0.46	0.29	7	0.8	0.53	0.05	0.03	0.6	0.13	0.13	0.06
1998	0.06	0.96	2.24	0.49	0.31	7	0.83	0.59	0.05	0.03	0.49	0.13	0.13	0.06
1999	0.07	0.95	2.2	0.5	0.31	7	0.86	0.47	0.05	0.04	0.42	0.13	0.13	0.06
2000	0.07	0.95	2.2	0.5	0.31	7	0.86	0.47	0.05	0.04	0.42	0.13	0.13	0.06
2001	0.06	0.85	2.34	0.53	0.22	7	0.87	0.6	0.05	0.05	0.48	0.11	0.13	0.06
2002	0.06	0.87	2.46	0.65	0.2	3.54	0.82	0.67	0.06	0.07	0.52	0.1	0.13	0.09
2003	0.06	0.87	2.46	0.65	0.2	3.54	0.82	0.67	0.06	0.07	0.52	0.1	0.13	0.09
2004	0.04	0.98	2.54	0.65	0.15	3.56	1.26	0.71	0.05	0.07	0.53	0.1	0.12	0.08
2005	0.05	0.98	2.54	0.62	0.16	5.24	1.32	0.71	0.04	0.07	0.57	0.1	0.14	0.09
2006	0.06	1.12	2.31	0.67	0.16	-	-	0.75	0.03	0.07	0.49	0.1	0.09	0.08
2007	0.06	1.12	2.36	0.42	0.17	-	1.1	0.75	0.03	0.08	0.38	0.11	0.11	0.06
2008	0.02	1.12	3.28	0.5	0.17	-	0.6	0.76	0.03	0.08	0.42	0.12	0.12	0.06
2009	0.02	1.12	3.28	0.5	0.17	-	0.6	0.76	0.03	0.08	0.42	0.12	0.12	0.06
2010	0.02	1.12	3.28	0.5	0.18	-	0.6	0.83	0.03	0.08	0.42	0.12	0.12	0.06
2011	0.02	1.23	3.28	0.35	0.15	-	0.55	0.83	0.03	0.08	0.57	0.12	0.11	0.06
2012	0.02	1.23	3.28	0.35	0.15	-	0.55	0.83	0.03	0.08	0.57	0.12	0.11	0.06
2013	0.02	1.23	3.28	0.35	0.15	-	0.55	0.83	0.03	0.08	0.57	0.12	0.11	0.06
2014	0.02	1.19	2.76	0.33	0.15	-	1.25	0.88	0.02	0.08	0.56	0.12	0.12	0.06
2015	0.02	1.24	2.88	0.34	0.16	-	1.31	0.92	0.02	0.09	0.59	0.13	0.13	0.07
2016	0.02	1.28	2.97	0.35	0.16	-	1.34	0.95	0.02	0.09	0.6	0.13	0.13	0.07
2017	0.02	1.36	3.16	0.37	0.18	-	1.43	1.01	0.02	0.09	0.64	0.14	0.14	0.07
2018	0.02	1.4	3.26	0.38	0.18	-	1.47	1.04	0.02	0.1	0.66	0.15	0.14	0.07
2019	0.02	1.4	3.25	0.38	0.18	-	1.47	1.04	0.02	0.1	0.66	0.15	0.14	0.07
2020	0.02	1.3	3.02	0.36	0.17	-	1.36	0.96	0.02	0.09	0.61	0.13	0.13	0.07
2021	0.02	1.49	3.22	0.38	0.18	-	1.46	1.03	0.02	0.1	0.65	0.14	0.14	0.07
2022	0.02	1.42	3.3	0.39	0.18	-	1.5	1.06	0.02	0.1	0.67	0.15	0.15	0.08
2023	0.02	1.41	3.26	0.39	0.18	-	1.48	1.04	0.02	0.1	0.66	0.15	0.14	0.07
2024	0.02	1.40	3.24	0.38	0.18	-	1.47	1.04	0.02	0.10	0.66	0.14	0.14	0.07



Fig. 7-12 The outline of the total organic waste flow in 5.D.2

By the 2006 Guidelines (IPCC, 2006), the maximum theoretical methane production B_0 was considered equal to 0.25 kg CH_4/kg COD. This value is by the national factors, presented in Dohanyos and Zábranská (2000).

Calculation of the emission factor for wastewater is based on the amount of recovered methane and the qualified estimate of the ratio of the use of individual technologies, during the entire recalculated time series. The MCFs used for quantification are in Tab. 7-24.

Tab. 7-24 Used MCF for Industrial waste water treatment

	Sea, river and lake discharge	Aerobic treatment plant (well managed)	Aerobic treatment plant (ill managed)	Anaerobic digester for sludge	Anaerobic reactor	Anaerobic shallow lagoon	Anaerobic deep lagoon
Lower bound	0	0	0.2	0.8	0.8	0	0.8
Default MCF	0.1	0	0.3	0.8	0.8	0.2	0.8
Upper bound	0.2	0.1	0.4	1	1	0.3	1

For the quantification, we assume that wastewater, treated in WWTP (i.e. not released into the watershed), is separated into wastewater and sludge. Wastewater is treated aerobically. Because the default MCF values were used, this treatment has zero emissions. The sludge is divided into two parts. One is treated anaerobically producing methane (that is recovered) and emissions. The second part of the sludge is treated aerobically resulting also in emissions.

Tab. 7-25 Emissions of CH_4 [kt] from 5.D.2, 1990–2024

	1990	1991	1992	1993	1994	1995	1996	1997	1998	1999	2000	2001	2002
CH_4 emission	14.5	17.6	15.2	14	16.2	12.6	11.9	13	14.3	11.7	11.7	13.1	14.7
Recovered CH_4	1.6	1.6	1.6	1.6	1.6	1.6	1.6	1.6	1.6	1.6	1.6	1.6	1.6
	2003	**2004**	**2005**	**2006**	**2007**	**2008**	**2009**	**2010**	**2011**	**2012**	**2013**	**2014**	**2015**
CH_4 emission	14.9	14.6	14.7	15.4	14.8	15	15	16.3	16	15.4	15.4	15.9	16.6
Recovered CH_4	1.8	1.7	1.5	1.2	1.5	1.7	2	2.1	2.4	4.7	4.6	6.6	7
	2016	**2017**	**2018**	**2019**	**2020**	**2021**	**2022**	**2023**	**2024**				
CH_4 emission	16.9	17.9	18.6	18.6	17.3	18.5	18.9	18.8	18.6				

Recovered CH_4	8	9.2	8.3	8	7.5	8	8.4	7.9	7.8				

7.5.2.3 Uncertainties and time-series consistency

The uncertainty in most factors (default IPCC values) is determined according to the IPCC 2006 Guidelines. The overall uncertainty assessment (e.g. Monte-Carlo variation of uncertainty ranges) has not yet been fully quantified, and it is anticipated that a software tool will be implemented for this purpose in the coming years.

In previous years, an IPCC expert team reviewed the waste sector and suggested and developed new uncertainty ranges, see Tab. 7-26. During recalculation, all the variables were inserted in the equation as parameters with lower and upper ranges and central (default where applicable) values. Based on this parametrisation, we assessed the emission upper and lower limits estimate for 5.D.2, see Fig. 7-13. The range now corresponds to the full scale of the uncertainty assessment, and indicates the minimum and maximum obtainable values by the distribution of the parameters used in the emission estimates; we foresee that running a parametrized Monte Carlo simulation will lower the uncertainty range.



Fig. 7-13 Maximum uncertainty range for 5.D.2, 1990–2024 (log scale)

Tab. 7-26 Uncertainty estimates for 5.D.2 category

Gas	Category	AD uncertainty [%]	EF uncetrainty [%]	Origin of the parameters
CH_4	5.D.2 Industrial wastewater	40	50	Combined uncertainty of quantification parameters + IPCC Default values, Expert judgement M. Havránek

7.5.2.4 Source-specific QA/QC and verification

Quality assurance entails structured checklists of activities, dated and signed by the sector reporter and verified by external control of the activity data. Activity data taken for this sector are approved by the data producer, who verifies them before they are used for calculation.

Because the waste sector is fairly small, we do not use an external subject to provide QC; instead, QC is performed by a NIS coordinator and results are communicated to the sectoral expert.

Activity data from national agencies and ministries are the subjects of internal QA/QC mechanisms but the NIS team has limited insights into them.

7.5.2.5 Source-specific recalculations, including changes made in response to the review process

No recalculations were made in this subsector.

7.5.2.6 Source-specific planned improvements, including those in response to the review process

No specific improvements are planned for this category for the next submission.

7.6 Other (CRT 5.E)

This category is not relevant for the Czech Republic.

7.7 Long-term storage of carbon (CRT 5.F)

The long-term stored carbon in SWDS is reported as an information item in the Waste sector. Fossil and non-degradable biogenic carbon disposed in SWDS remains stored underground and does not contribute to anthropogenic climate change. The amount of carbon stored in SWDS is estimated by the FOD model described in 5.A.1 using the same data described there. The results are shown in Tab. 7-27. The reporting format of this category in NID was harmonised with CRT which requires reporting of kt of CO_2 rather than kt of C.

Tab. 7-27 Long-term stored carbon, 1990–2024, Czech Republic

	Long-term stored carbon [kt CO_2]	Accumulated long-term stored carbon (since 1950) [kt CO_2]
1990	765	15 558
1991	770	16 328
1992	801	17 129
1993	820	17 949
1994	826	18 775
1995	917	19 692
1996	950	20 642
1997	983	21 625
1998	1 020	22 645
1999	978	23 623
2000	1 055	24 678
2001	1 082	25 760
2002	1 110	26 870
2003	1 116	27 986
2004	1 127	29 113
2005	1 145	30 259
2006	1 178	31 436
2007	1 248	32 685
2008	1 253	33 938
2009	1 282	35 219
2010	1 203	36 422
2011	1 131	37 553
2012	1 081	38 634
2013	1 046	39 680
2014	1 000	40 681
2015	1 019	41 700
2016	1 073	42 773
2017	1 111	43 884
2018	1 156	45 040
2019	1 181	46 221
2020	1 301	47 429

	Long-term stored carbon [kt CO_2]	Accumulated long-term stored carbon (since 1950) [kt CO_2]
2021	1 239	48 668
2022	1 247	49 915
2023	1 167	51 082
2024	1 230	52 312

8 Other (CRT sector 6)

No sector 6 is defined in the Czech inventory.

9 Indirect CO_2 and nitrous oxide emissions

9.1 Description of sources of indirect emissions in GHG inventory

The estimation of indirect CO_2 and N_2O emissions is based on the official Czech inventories for the precursor gases (CO, NMVOC, NH_3 and NO_x) reported under the United Nations Economic Commission for Europe (UNECE) Convention on Long-Range Transboundary Air Pollution (CLRTAP) and the CH_4 emissions reported to the UNFCCC.

A detailed description of the methodology used to estimate these emissions should be available in Czech Informative Report (IIR), Submission under UNECE / CLRTAP Convention. Precursor gases totals correspond under both submissions, the differences between reporting formats (NFR-CRT) are taken into account.

In this chapter, precursor gases are reported from all sectors, but indirect emissions are estimated from sectors Energy, IPPU and Waste. Emissions from Agriculture are considered biogenic. Tab. 9-1 presents a summary of emissions estimates for the full time series 1990 – 2024 for NOx, CO, NMVOC, SO_X and NH_3, which in the ETF reporting tool are called the other emissions,and the National Emission Ceilings (NEC) as set out in the 1999 Gothenburg Protocol to Abate Acidification, Eutrophication and Ground-level Ozone. NECs should have been met by 2010 by Parties to the UNECE / CLRTAP Convention and have ratified this Protocol.

Emissions of precursor gases decreased in the period from 1990 to 2024 for NMVOC by 73.7%, for CO by 75.5% and for NO_X by 83.7%. SO_X (reported as SO_2) emissions decreased by 97.5% compared to 1990 level. NH_3 decreased by 69.4% in 2024 compared to the year 1990 (estimated data).

Tab. 9-1 The total other emissions and their trends from 1990–2024

	NO_X	NO_X w/o LULUCF	CO	CO w/o LULUCF	NMVOC	SO_X	NH_3
1990	762.78	762.34	2927.98	2912.24	837.49	1753.82	10.01
1991	722.01	721.69	2854.78	2843.54	763.63	1649.74	9.34
1992	676.51	676.01	2848.25	2830.64	733.70	1381.96	8.77
1993	549.55	549.00	2607.56	2588.12	691.12	1302.42	8.41
1994	456.24	455.72	2488.69	2470.38	659.54	1158.97	8.36
1995	386.89	386.47	2303.40	2288.44	601.38	1058.82	5.44
1996	366.61	365.88	2445.82	2419.67	617.47	914.32	3.88
1997	339.24	338.24	2249.68	2213.95	575.71	694.36	4.14
1998	323.63	323.05	1785.73	1765.20	492.19	425.31	3.84
1999	271.64	271.22	1527.18	1512.17	443.69	231.88	3.73
2000	278.70	278.30	1474.42	1460.23	435.38	233.71	3.37
2001	280.63	280.44	1457.54	1450.72	429.96	228.68	3.24
2002	276.53	276.31	1383.42	1375.52	411.00	223.37	3.15
2003	283.37	282.90	1406.32	1389.78	407.78	218.37	3.16
2004	285.59	285.31	1375.01	1365.03	396.64	215.08	2.90
2005	285.80	285.55	1231.39	1222.47	373.04	208.47	3.39
2006	281.72	281.39	1243.04	1231.26	377.48	206.76	3.28
2007	284.11	283.73	1235.00	1221.71	365.56	212.07	3.34
2008	268.43	268.16	1164.49	1155.07	358.47	170.10	3.37
2009	253.32	253.07	1189.82	1180.99	362.20	168.77	3.34
2010	247.98	247.71	1243.94	1234.47	370.36	163.88	3.29
2011	236.76	236.65	1234.83	1230.90	363.30	167.51	3.36
2012	224.94	224.77	1218.59	1212.30	359.37	160.20	3.42
2013	212.41	212.35	1248.70	1246.64	362.83	145.25	3.43
2014	207.17	207.02	1184.02	1178.45	349.47	134.49	3.29

	NO_X	NO_X w/o LULUCF	CO	CO w/o LULUCF	NMVOC	SO_X	NH_3
2015	201.64	201.51	1189.20	1184.88	354.59	129.86	3.25
2016	191.80	191.72	1175.25	1172.37	346.52	115.63	3.42
2017	186.79	186.70	1163.19	1159.79	341.94	109.73	3.34
2018	176.67	176.47	1126.67	1119.53	332.15	96.58	3.47
2019	164.99	164.75	1074.46	1066.09	314.41	79.09	3.31
2020	148.74	148.51	1083.20	1074.75	302.79	67.15	3.20
2021	152.74	152.55	1121.90	1114.94	301.66	60.23	3.25
2022	145.74	145.27	1054.50	1037.85	286.38	64.18	3.23
2023	130.61	130.51	851.03	847.46	245.03	48.46	3.04
2024	124.26	124.18	718.09	715.43	220.06	43.83	3.06
Trend %	**-83.71**	**-83.71**	**-75.47**	**-75.43**	**-73.72**	**-97.50**	**-69.37**
NEC	**286**			**-**	**220**	**265**	**101**



Fig. 9-1 Indexed emissions of precursor gases for 1990–2024 (1990 =100%), [%] (left); Overall trend in percentage share of precursor gases (right)

On Fig. 9-1 can be observed the overall decreasing trend, in percentage of precursor gases, where year 1990 is equal to 100%, further the overall trend in percentage share of total indirect GHG can be examined.

The categories with highest amounts of precursor gases for NO_X are 1.A.3 Transport, 1.A.1 Energy Industries, and 1.A.2 Manufacturing industries and construction; for CO are 1.A.4 Other sectors, 1.A.2 Manufacturing industries and construction and 1.A.3 Transport; for NMVOC are 1.A.4 Other sectors, 2.D Non-energy products from fuels and solvent use and 1.A.3 Transport; for SO_X are 1.A.1 Energy industries, 1.A.4 Other sectors and 1.A.2 Manufacturing industries and construction. Total production from the main CRT categories can be seen on Tab. 9-2.

Tab. 9-2 The total other emissions in sectors of origin for 2024

	NO_X [kt]	CO [kt]	NMVOC [kt]	SO_X [kt]	NH_3 [kt]
Total emissions	124.26	718.09	220.06	43.83	3.06
1. Energy	105.61	658.93	127.92	39.25	1.62
1.A Fuel combustion	105.23	658.83	123.74	34.95	1.62
1.A.1 Energy Industries	23.70	8.07	4.37	14.58	0.07
1.A.2 Manufacturing industries and construction	14.72	68.93	1.60	9.79	0.26
1.A.3 Transport	48.47	65.00	12.85	0.19	0.89
1.A.4 Other sectors	18.28	516.75	104.92	10.38	0.41
1.A.5 Other	0.05	0.08	0.01	0.01	0.00
1.B Fugitive emissions from fuels	0.38	0.10	4.18	4.30	0.01

	NO_X [kt]	CO [kt]	NMVOC [kt]	SO_X [kt]	NH_3 [kt]
2. Industrial processes and product use	1.32	48.65	51.51	4.57	0.22
2.A Mineral industry	-	-	0.01	0.15	0.06
2.B Chemical industry	0.99	0.10	1.68	4.24	0.05
2.C Metal industry	0.25	47.43	0.83	0.15	0.00
2.D Non-energy products from fuels and solvent use	-	-	45.63	-	0.00
2.G Other product manufacture and use	0.08	1.11	3.34	0.03	0.11
3. Agriculture	16.77	-	38.25	-	-
4. LULUCF	0.07	2.66	-	-	-
5.Waste	0.49	7.85	2.38	0.02	1.22

9.2 Production of indirect emissions from precursor gases

Following precursor and indirect emission estimates are from sectors Energy, IPPU and Waste. Emissions from Agriculture are considered biogenic. Agriculture and LULUCF indirect emissions are not reported here, but under their own category according the 2006 IPCC guidelines.

9.2.1 Indirect N_2O emissions from nitrogen oxides



Fig. 9-2 Indirect N_2O emissions from NO_X emissions in 2024

Emissions of NO_X are formed during the combustion of fuels, depending on the temperature of combustion, the content of nitrogen in fuels and the excess of combustion air. Emissions of NO_X precursors decreased from 738.0kt to 107.4kt during the period 1990–2024. In 2024, NO_X precursor emissions were 85.5% below the 1990 level. Slightly less than 95% of indirect N_2O emissions from NO_2 precursor emissions originate from 1.A Fuel combustion, mainly subsectors 1.A.1 Energy industries (22.1%), with subsector 1.A.1a Public electricity and heat production (21.4%); 1.A.3 Transport (45.1%), with 1.A.3.b Road transportation (40.9%), 1.A.4 Other sectors (17.0%), mainly from 1.A.4.b Residential stationary combustion (7.6%) and 1.A.2 Manufacturing industries and construction (13.7%) (Fig. 9-2). Hence the indirect N_2O emissions from NOx correspondingly decreased from 3.5 kt to 0.5 kt from 1990 to 2024, which is 85.5% less than in 1990.

9.2.2 Indirect N_2O from ammonia



Fig. 9-3 Indirect N_2O emissions from NH_3 emissions in 2024

Indirect N_2O emissions from anthropogenic NH_3 precursors for 2024 are mainly produced from categories; 5.B.2 Anaerobic Digestion at Biogas Facilities (38.1%), 1.A.4 Other sectors (13.3%), 1.A.3 Transport (28.9%) and 1.A.2 Manufacturing industries and construction (8.3%)). The other (10.6%) includes sectors 1.A.1 Energy Industries (2.2%), 5.D Wastewater Treatment and Discharge (1.7%), 1.B Fugitive emissions from fuels (0.2%) and 2. Industrial processes and product use (7.2%) (Fig. 9-3). In 2024, emissions of NH_3 were 3.6 kt. The overall trend is decreasing from 1990 to 2024. Total indirect N_2O emissions from NH_3 in 2024 are 0.04 kt, which is 69.4% less than in 1990.

9.2.3 Indirect CO_2 from carbon monoxide



Fig. 9-4 Indirect CO_2 emissions from CO emissions in 2024

Emissions of CO are produced during the combustion of carbon-containing fuels at low temperatures and by insufficient amount of combustion air. In 2024, emissions of CO precursors were 56.6 kt with an increasing trend from 1990. Reason for the increasing trend from 1990 to 2024 is growth of metal industry production in Czechia. However, the most recent trend is decreasing due to closing of metal factories. Indirect CO_2 emissions from CO precursor emissions for 2024 are mainly produced from categories; 2.C Metal Industry (83.8%), 5.C Incineration (13.9%) and 2.G Other Product Manufacture and Use (2.0%) (Fig. 9-4). Total indirect CO_2 emissions from CO in 2024 are 88.9 kt.

9.2.4 Indirect CO_2 from non-methane volatile organic compounds



Fig. 9-5 Indirect CO_2 emissions from NMVOC emissions in 2024

The release of NMVOC emissions is partly regulated, but most of these pollutants are released in the form of fugitive emissions and their reduction has been difficult. NMVOC emissions are also produced by insufficient combustion of fossil fuels. Emissions of NMVOC precursors decreased from 225.2 kt to 55.9 kt during the period 1990 and 2024. In 2024, NMVOC emissions were 75.1% below the 1990 level. The main source of indirect CO_2 emissions from NMVOC precursor emissions is category 2.D Non-energy products from fuels and solvent use (81.7%) followed by 1.B Fugitive emissions from fuels (7.5%) and 2.G Other Product Manufacture and Use (6.0%). The rest consist of sector 5. Waste (0.4%), 2.B Chemical Industry (3.0%), 2.C Metal Industry (1.5%) and 2.A Mineral Industry (0.1%). Total indirect emissions of CO_2 from NMVOC in 2024 are 123.3 kt, which is 75.1% less than in 1990.

9.2.4.1 Indirect CO_2 from 2.D Non-energy products from fuels and solvent use



Fig. 9-6 Indirect CO_2 emissions from 2.D Non-energy products from fuels and solvent use in 2024

In 2024, 26.5% of all indirect CO_2 emissions originated from NMVOC emissions from 2.D Non-energy products from fuels and solvent use. The same sector produced 81.7% of indirect CO_2 emissions from all NMVOC. The main NMVOC source categories in 2.D Non-energy products from fuels and solvent use are; 2.D.3.d Coating applications (38.0%), 2.D.3.g Chemical products (13.5%), 2.D.3.a Domestic solvent use including fungicides (28.8%), 2.D.3.e Degreasing (3.7%) and 2.D.3.h Printing (4.3) (Fig. 9-6). The rest (Other) are 2.D.3.i Other solvent use , 2.D.3.f Dry cleaning, 2.D.3.b Road paving with asphalt and 2.D.3.c Asphalt roofing together (12.4%). Total indirect emissions of CO_2 from 2.D Non-energy products from fuels and solvent use in 2023 are 100.6 kt.

9.2.5 Indirect CO_2 from methane



Fig. 9-7 Indirect CO_2 emissions from methane in 2024

In 2024, 45.1% of all indirect CO_2 emissions originated from methane. Indirect CO_2 emissions from CH_4 precursor emissions are mainly produced from categories 1.B Fugitive emissions from fuels (48.0%); 1.B.1 Solid fuels (27.0%), 1.B.2 Oil and natural gas and other emissions from energy production (21.1%) and 5.D Wastewater treatment and discharge (48.3%) and 2.B Chemical Industry (2.9%) (Fig. 9-7). For more information on CH_4 emissions, consult respective chapters. Total indirect CO_2 emissions from CH_4 produced in 2024 are 174.2kt, which is 83.8% less than in 1990.

9.3 Production of indirect CO_2 and N_2O emissions from source categories

Estimations of indirect CO_2 and N_2O for the whole time series for each sector can be observed on Tab. 9-3.

Tab. 9-3 Time series and trend of indirect emissions per sector and total 1990–2024

	Energy		IPPU		Waste		Total	
	CO_2 [kt]	N_2O [kt]	CO_2 [kt]	N_2O [kt]	CO_2 [kt]	N_2O [kt]	CO_2 [kt]	N_2O [kt]
1990	1020.18	3.54	454.90	0.09	119.73	0.03	1594.82	3.66
1991	930.61	3.36	370.96	0.09	128.85	0.03	1430.42	3.47
1992	864.33	3.15	345.89	0.09	120.21	0.03	1330.43	3.27
1993	911.92	2.56	331.70	0.08	116.65	0.02	1360.27	2.67
1994	872.26	2.11	321.67	0.08	121.66	0.02	1315.60	2.22
1995	861.04	1.78	308.49	0.05	110.18	0.02	1279.72	1.85
1996	858.09	1.68	294.11	0.03	107.87	0.02	1260.07	1.73
1997	833.43	1.55	287.53	0.02	110.27	0.02	1231.23	1.60
1998	807.65	1.48	281.79	0.02	112.20	0.02	1201.65	1.52
1999	732.69	1.24	284.68	0.02	104.02	0.02	1121.39	1.28
2000	619.41	1.27	303.24	0.02	103.62	0.02	1026.27	1.30
2001	538.79	1.28	299.65	0.02	107.07	0.02	945.51	1.31
2002	523.17	1.25	292.19	0.02	107.50	0.01	922.85	1.28
2003	506.02	1.28	286.64	0.02	107.30	0.01	899.96	1.31
2004	481.42	1.30	278.63	0.02	105.79	0.01	865.84	1.32
2005	534.34	1.31	275.41	0.02	104.07	0.01	913.82	1.33
2006	551.68	1.28	295.45	0.02	104.73	0.01	951.86	1.31
2007	505.73	1.30	296.08	0.02	101.72	0.01	903.53	1.32
2008	502.09	1.22	278.32	0.02	102.10	0.01	882.51	1.25
2009	432.79	1.16	251.31	0.01	102.08	0.01	786.18	1.18
2010	395.61	1.13	250.27	0.02	104.94	0.01	750.82	1.15
2011	382.61	1.07	236.16	0.01	102.55	0.01	721.31	1.10
2012	365.84	1.01	219.64	0.02	101.17	0.01	686.66	1.04
2013	299.01	0.94	223.55	0.01	100.40	0.02	622.96	0.97
2014	304.90	0.91	230.34	0.01	100.32	0.02	635.56	0.94
2015	292.23	0.87	228.20	0.01	101.86	0.02	622.29	0.91
2016	252.73	0.83	229.99	0.02	102.30	0.02	585.02	0.86
2017	223.69	0.81	224.97	0.01	103.18	0.02	551.84	0.84
2018	205.20	0.76	229.00	0.01	104.89	0.02	539.10	0.80
2019	179.06	0.71	215.73	0.01	105.39	0.02	500.18	0.74
2020	122.67	0.64	284.31	0.01	100.87	0.02	507.85	0.67
2021	128.35	0.65	286.77	0.02	101.16	0.02	516.28	0.69
2022	113.04	0.62	261.64	0.01	103.23	0.02	477.92	0.66
2023	94.99	0.55	222.26	0.01	104.10	0.02	421.35	0.58
2024	93.02	0.53	195.98	0.01	97.37	0.02	386.37	0.55
Trend %	**-90.88**	**-85.14**	**-56.92**	**-90.11**	**-18.67**	**-34.36**	**-75.77**	**-84.88**

All sectors have a decreasing trend in indirect emissions. In the Energy sector, both trends are steadily decreasing, but the Waste sector trends fluctuate slightly while decreasing overall. The economic recession in Czechia in 2012 explains the drop in the IPPU sector and the global Covid pandemic is reason for the high fluctuations in 2019 – 2022 for the same sector. Total CO_2 indirect emissions are decreasing 75.8% and total N_2O indirect emissions are decreasing 84.9% to the 1990 level.

Fig. 9-8 presents shares of indirect emissions of CO_2 and N_2O between the examined sectors.



Fig. 9-8 Division of indirect emission of CO_2 (left) and N_2O (right) between the producing sectors for 2024 (in %)

Energy sector covers 24.0% of the total production of indirect CO_2 and 95.1% of the total production of indirect N_2O. 99.6% of the indirect N_2O emissions from Energy are from 1.A Fuel combustion; (46.4%) 1.A.3 Transport, 1A.4 Other sectors (17.7%) and followed by 1.A.1 Energy industries (21.8%). 57.2% of indirect CO_2 emissions from Energy are from 1.B.1 Fugitive Emissions from Solid Fuels.

IPPU sector covers 50.7% of the total production of indirect CO_2 and for the indirect N_2O the share is 1.7%. The two main subcategories producing indirect CO_2 in the IPPU sector are 2.C Metal industry (39.4%), with its CO production, and 2.D Non-energy products from fuels and solvent use (51.4%), with its NMVOC production. Indirect N_2O emissions from IPPU are divided between four categories: 2.B Chemical industry (58.6%), 2.C Metal industry (13.2%), 2.G Other product manufacture and use (19.1%) and 2.A Mineral industry (9.0%).

Waste sector covers 25.2% of the total production of indirect CO_2 and only 3.3% of the total production of indirect N_2O. Most of the indirect CO_2 emissions from the Waste sector are emitted from category 5.D Wastewater Treatment and Discharge (86.4%) followed by 5.C Incineration and Open Burning of Waste (13.6%) and 5.E Other (0.1%). Most of the N_2O is emitted from the category 5.B Biological Treatment of Solid Waste (83.4%) and the rest are from the category 5.C Incineration and Open Burning of Waste (12.9%) and the category 5.D Wastewater Treatment and Discharge (3.7%).

9.4 Methodological issues

The above reported data is obtained from the Czech Informative Report (IIR), Submission under UNECE / CLRTAP Convention. The inventory is performed every year, in accordance with the national legislation for the prevention of air polluting and reduction of air pollution from 2012 and its latest amendments. The inventory combines the direct approach, i.e. the collection of data reported by the sources operators with the data from model calculations based on data, reported by the sources operators or gained within statistical surveys, carried out primarily by CzSO. The results of emission inventories are presented as emission balances processed according to various territorial and sector structures. Further, after obtaining the data, synchronization between the two reporting systems categorization (NFR-CRT) is conducted. NFR emission values applied to the CRTs and to the NID are from version 1, 14.2.2026.

Precursor gases from Agriculture are added to the CRT for the completeness, but as they are considered biogenic, no indirect emissions are estimated. The ETF tool tables have no place for NO_x in 3B2 causing difference of 0.7kt in 2024 for the NO_X between the NFR and CRT Czechia data.

9.4.1 Indirect CO_2 emissions

Indirect emissions of CO_2 were calculated using the default IPCC Tier 1 method. The following equations were used for calculating the indirect emissions, respectively from CO, CH_4 and NMVOC.

$$Emissions_{CO2} = Emissions_{CO} \cdot \frac{44}{28}$$

$$Emissions_{CO2} = Emissions_{CH4} \cdot \frac{44}{16}$$

$$Emissions_{CO2} = Emissions_{NMVOC} \cdot Percent\ carbon\ in\ NMVOC\ by\ mass \cdot \frac{44}{12}$$

where percent carbon in NMVOC used for sectors Energy, IPPU (except category 2.D) and Waste is the default 60% given in IPCC 2006 Gl. (IPCC 2006).

For estimation of indirect emissions from NMVOC from category 2.D Non-energy products from fuels and solvent use, it was assumed for years 1990–2023 that the average percent of carbon content is 80% by mass based on IPCC 2006 Gl. This factor was used for subcategories:

- Asphalt roofing
- Road paving

For the other subcategories of 2.D it was assumed for the whole time period that the average carbon content is 60% by mass according to the IPCC 2006 Gl. (IPCC 2006) and it was used for the following NFR categories:

- Domestic solvent use including fungicides
- Coating applications
- Degreasing
- Dry cleaning
- Chemical products
- Printing
- Other solvent use.

9.4.2 Indirect N_2O emissions

The indirect N_2O emissions from atmospheric deposition of nitrogen other than agriculture and LULUCF sources are estimated based on the amount of nitrogen emitted in the country multiplied with an emission factor, assuming 1% (default) of the nitrogen in the emissions to be converted to N_2O. The calculation method is the IPCC default Tier 1. Indirect N_2O emissions were calculated using equation 7.1 (IPCC 2006, Vol. 1, section 7.3.1.).

9.5 Uncertainties and time-series consistency

In the process of calculation of emission inventories, data provided by the operators of stationary sources of air pollution, statistic data of the Czech Statistical Office (data on fuel consumption, number of vehicles, number of livestock and area of cultivated land) and data from the Population and housing census which was conducted in 2021 (information on household heating) are used. Further, emission factors and other sources of data are applied.

The data, from which the inventory has been compiled, are of varying quality. Emissions of individual point sources set on the basis of measurements are determined with less uncertainty than the emissions calculated on the basis of statistical data. The uncertainty of the emissions from point sources is below 5% (e.g. emissions from large combustion sources), the uncertainty of emission data based on a sophisticated model (e.g. emissions from household heating and exhaust emissions from transport) ranges between 10–15%. The uncertainty of emissions calculated from statistical data and predefined emission factors is estimated according to the methodology of the EMEP/EEA air pollutant emission inventory guidebook and ranged from 50 up to 200% (e.g. emissions from the use of solvents, animal production and non-combustion emissions from transport).

9.6 Source-specific QA/QC and verification

The emission estimates are based on the activity data taken from the Czech Informative Report (IIR), Submission under UNECE / CLRTAP Convention and follow the recommendations and QA/QC procedures of IPCC 2006 Gl. (IPCC 2006). Source specific QA/QC is conducted in line with the QA/QC plan (Tier 1) of the National Inventory System.

Recalculation of the time series for the gases NO_x, CO, NMVOC, SO_x and NH_3 caused changes to the precursor gas calculation spreadsheet which were checked by sum checks and by using the previous data sets to compare the results. The sum checks were performed for the totals and for the sectors to ensure no data was lost. Automated QC sum tests follow the data from the NFR files to the indirect emission calculation file with comparison to resulting CRT values. Therefore the reported emissions can be tracked correctly to the source. In 2026, ETF Reporting Tool added indirect CO_2 emissions from the LULUCF sector to the total indirect CO_2 emissions. In the NID report, indirect emissions from Agriculture and LULUCF sector are reported in their respective chapters, not in the chapter 9.

The Czech IIR team exchanges information about precursor data with the person responsible of the chapter 9 in the Czech NID ensuring correct transfer of NFR data into the CRT.

9.7 Source-specific recalculations, including changes made in response to the review process and impact on emission trend

Recalculations were made for the whole time series from 1990 to 2023. Percentage changes are lower in the recent years. The highest kt difference compared to the previous submission is for the year 2012 for the indirect CO_2 emissions and 2019 for the indirect N_2O emissions. The trend of the indirect CO_2 emissions difference is fluctuating between -10.90% in 2012 and -3.78% in 2023. The trend of the indirect N_2O emissions recalculation has higher fluctuations from 2016 and the highest in 2019 (-2.50%).

The shown impact on indirect N_2O emissions is from changes in the activity data in the NFR in gases NO_x and NH_3. Impact on indirect CO_2 emissions is not from CH_4 in the current submission, but from recalculation of CO and NMVOC precursor gases in the NFR. Recalculations of NMVOC and CO have lowered indirect CO_2 -77.07 kt in 1990 to the lowest impact -16.53 kt in 2023. The highest impacts are for years 2010 – 2012 up to -84.02 kt. All the trends and impacts can be observed in the Tab. 9-4.

Tab. 9-4 Recalculation of indirect CO_2 and N_2O total emissions between 1990–2024

Submission	2025		2026		Difference [kt]		Difference [%]	
	CO_2 [kt]	N_2O [kt]	CO_2 [kt]	N_2O [kt]	CO_2 [kt]	N_2O [kt]	CO_2 [%]	N_2O [%]
1990	1671.89	3.65	1594.82	3.66	-77.07	0.01	-4.61	0.14
1991	1499.88	3.47	1430.42	3.47	-69.46	0.00	-4.63	0.14
1992	1394.50	3.26	1330.43	3.27	-64.08	0.01	-4.60	0.19
1993	1423.38	2.66	1360.27	2.67	-63.11	0.01	-4.43	0.19
1994	1375.34	2.22	1315.60	2.22	-59.74	0.01	-4.34	0.23
1995	1340.70	1.84	1279.72	1.85	-60.99	0.00	-4.55	0.23
1996	1320.08	1.72	1260.07	1.73	-60.01	0.00	-4.55	0.24
1997	1288.21	1.60	1231.23	1.60	-56.97	0.00	-4.42	0.18
1998	1256.19	1.52	1201.65	1.52	-54.54	0.00	-4.34	0.17
1999	1170.96	1.28	1121.39	1.28	-49.58	0.00	-4.23	0.20
2000	1077.34	1.30	1026.27	1.30	-51.08	0.00	-4.74	0.16
2001	997.56	1.31	945.51	1.31	-52.05	0.00	-5.22	0.13
2002	972.61	1.28	922.85	1.28	-49.75	0.00	-5.12	0.12
2003	946.87	1.31	899.96	1.31	-46.91	0.00	-4.95	0.11
2004	911.57	1.32	865.84	1.32	-45.74	0.00	-5.02	0.07
2005	959.38	1.33	913.82	1.33	-45.56	0.00	-4.75	0.10
2006	1001.00	1.30	951.86	1.31	-49.14	0.01	-4.91	0.83
2007	947.87	1.31	903.53	1.32	-44.34	0.01	-4.68	1.12
2008	926.04	1.23	882.51	1.25	-43.54	0.02	-4.70	1.42
2009	824.00	1.16	786.18	1.18	-37.82	0.02	-4.59	1.52
2010	834.42	1.14	750.82	1.15	-83.60	0.02	-10.02	1.44
2011	803.82	1.08	721.31	1.10	-82.50	0.02	-10.26	1.39
2012	770.68	1.02	686.66	1.04	-84.02	0.01	-10.90	1.27
2013	686.03	0.96	622.96	0.97	-63.07	0.01	-9.19	1.26
2014	699.74	0.93	635.56	0.94	-64.18	0.01	-9.17	1.43
2015	683.05	0.89	622.29	0.91	-60.76	0.02	-8.90	1.85
2016	635.61	0.84	585.02	0.86	-50.59	0.02	-7.96	2.22
2017	592.22	0.82	551.84	0.84	-40.39	0.02	-6.82	2.47
2018	572.00	0.78	539.10	0.80	-32.90	0.02	-5.75	2.45
2019	525.71	0.72	500.18	0.74	-25.53	0.02	-4.86	2.50
2020	543.98	0.66	507.85	0.67	-36.13	0.00	-6.64	0.59
2021	546.08	0.69	516.28	0.69	-29.80	0.00	-5.46	-0.11
2022	494.95	0.66	477.92	0.66	-17.03	-0.01	-3.44	-1.01
2023	437.88	0.60	421.35	0.58	-16.53	-0.01	-3.78	-2.30

9.8 Source-specific planned improvements, including I response to the review process

Planned improvements for the future submissions is to continue to provide more detailed examination of the indirect emissions produced from the individual categories.

10 Recalculations and improvements

The driving forces in applying recalculations in the Czech greenhouse gas inventory are provided by the implementation of the guidance given in the IPCC 2006 Gl. (IPCC, 2006) and the recommendations from the UNFCCC inventory reviews. Recalculations of previously submitted inventory data are performed following the above-mentioned IPCC manuals only to improve the GHG inventory.

Even though a QA/QC system helps to eliminate potential error sources, it is sometimes necessary to make some revisions (called recalculations) under the following circumstances:

- An emission source was not considered in the previous inventory.
- A source/data supplier has delivered new data. This could be because the previous data were only preliminary data (by estimation, extrapolation) or because the method of data collection has been improved.
- Some errors in data transfer or processing have been identified: wrong data, unit-conversion, software errors, etc.
- Methodological changes - when a new methodology must be applied to fulfil the reporting obligations for one of the following reasons:
  - to decrease uncertainties,
  - an emission source becomes a key source,
  - consistent input data needed for applying the methodology is no longer accessible,
  - input data for more detailed methodology is now available,
  - the methodology is no longer appropriate.

10.1 Explanations and justifications for recalculations, including in response to the review process

10.1.1 Recalculations performed in the submission 2026

10.1.1.1 Recalculation in sector 1 Energy – Stationary combustion

10.1.1.1.1 Recalculations due to response to the last review process

Based on the question E.21 Arr2022 (1.A.3.a Domestic aviation 1.A.5.b Mobile – liquid fuels – CO_2, CH_4 and N_2O) emission factors for all emissions were changed in 1.A.5.b and also in 1.A.4.c for liquid fuels for the whole time series. The change was done to unify emission factors reported for liquid fuels in Energy and Transportation sector.

10.1.1.1.2 Uploading errors

During the QA/QC controls was found a wrong activity data for subcategory Underground mines 1.B.1.a.i.1. Mining activities in the year 2022. Therefore, recalculation has to be done for that year.

Tab. 10-1 The recalculation in activity data will be as follows.

Sector	Type of fuel	Recalculation in years
1.B.1.a.i.1 Underground mines, mining activities	Solid fuel	2022

10.1.1.1.3 Recalculation due to improvement plan

The emission factor for mining from surface mines was changed due to a research done in this area. Before 2016, the default EF of 1.16 m^3/t (0.77 kg CH_4/t) was used. Given that methane explosions have never occurred in mines, but mining takes place at greater depths, the median EF value was chosen. At the instruction of the ERT inspection in 2016, it was necessary to use and recalculate the entire time series with the application of the highest default EF of 2 m^3/t (1.34 kg CH_4/t), which increased methane emissions from coal mining by 42%. Based on the data from the research and consultation with mining companies was decided to change the EF to 0.0556 kg CH_4/t for the whole time period.

The new ETF system did not allow to fill 1.B.2.b.6 subcategory anyway, where were only acitivty data for Storage. It was decided to moved AD from 1.B.2.b.6 to the subcategry 1.B.2.b.vi which already contains emissions for Storage Based on this change recalculation has to be done for the whole time series.

Tab. 10-2 Updated activity data due to the improvement plan

Category	Fuels	Year
1.B.1.a.1.ii Surface mines	Solid fuel	1990–2022
1.B.2.b.vi Transmission and Storage	Gaseous fuel	1990–2022

10.1.1.1.4 Recalculation due updated activity data

Based on the update of activity data from CzSO some recalculations were necessary to be done.

The most of the recalculations are tiny and occur only in couple years as the correction of the previous values. Summarization of the recalculation released from the update of Activity data is listed in the table below Tab. 10-3.

1.A.2 – Manufacturing industries and construction

Consumption of Solid fuels had to be changed for the year 2022 due to the changed of Activity data from CzSO in some subcategories, see the table below Tab. 10-3.

Based on update of activity data for Gaseous fuels in 2018 and 2022 recalculation had to be done in all subcategories, see the table below Tab. 10-3.

1.A.4 – Other sectors

Based on update of activity data from the CzSO amount of Solid fuels in 2022 in subcategory 1.A.4.a were changed. Due to the update of activity data in Gaseous fuels, recalculation had to be done in subcategories 1.A.4.a.i (2018), 1.A.4.b.i (2018) and 1.A.4.c.i for the years 2018.

Activity data for biomass were changed in 2021 and 2022, therefore recalculation in subcategory 1.A.4.b.i was done.

Tab. 10-3 Recalculations due to the updated activity data

Sector	Type of fuels	Recalculation in years
1.A.2.a Iron and steel	Solid fuels	2022
1.A.2.d Pulp, paper and print	Solid fuels	2022
1.A.2.e Food Processing, Beverages and Tobacco	Solid fuels	2022
1.A.2.f Non-Metalic Minerals	Solid fuels	2022
1.A.2.g Non-specified Industry	Solid fuels	2022
1.A.2.a Iron and steel	Gaseous fuels	2018; 2022
1.A.2.b Non-Ferrous metals	Gaseous fuels	2018; 2022
1.A.2.c Chemicals	Gaseous fuels	2018; 2022

1.A.2.d Pulp, paper and print	Gaseous fuels	2018; 2022
1.A.2.e Food Processing, Beverages and Tobacco	Gaseous fuels	2018; 2022
1.A.2.f Non-Metalic Minerals	Gaseous fuels	2018; 2022
1.A.2.g Non-specified Industry	Gaseous fuels	2018; 2022

10.1.1.2 Recalculation in sector 1 Energy – Mobile combustion

10.1.1.2.1 Recalculation due to response to the last review process

NA

10.1.1.2.2 Recalculation due to improvement plan

NA

10.1.1.2.3 Recalculation due to methodology changes and updated activity data

1.A.3 – Transport

Fuel densities for all fuels were updated in line with the Czech technical standard ČSN EN ISO 14083 (2023).

1.A.3.b – Road transportation

A new version of the COPERT programme (updated from 5.8.1 to 5.9.2) was used to calculate emissions from road transport. Following this update, the entire 1990–2024 time series was recalculated. The methodological changes include a revision of fuel consumption for LDVs running on liquid fuels, an update to CH_4 emission factors for diesel LDVs, and an update to N_2O emission factors for diesel HDVs and coaches. Several software enhancements and bug fixes were also implemented in COPERT 5.9.2; please refer to the COPERT website for the full list of updates.

The update of the emission factors mentioned above was carried out to align COPERT 5.9 with HBEFA. This revision resulted in a substantial increase in total N_2O emissions for the years 2014–2023 compared with the 2025 submission, with an average rise of more than 80%. The primary driver of this increase is the update of EFs for Euro VI diesel heavy-duty vehicles, which were the most affected by the revision. The changes in EFs between COPERT versions are presented in the table below.

Tab. 10-4 Hot N_2O emission factors of Euro VI diesel HDVs in COPERT

COPERT version	Urban Peak [g/km]	Urban Off Peak [g/km]	Rural [g/km]	Highway [g/km]
5.8	1.2	1.2	1.3	1.0
5.9	7.6	6.4	3.6	3.3

Activity data for the last four years were updated and, consequently, the years 2020–2023 were recalculated. This follows from the methodology for deriving traffic performance data (for details, see chapter 3.2.17.3 of the NID). As a result, the 2021–2024 data should be considered preliminary.

Recalculation of AD for L-category due to the update of vehicle stratification in the new COPERT version and exclusion of non-operated motorcycles. AD harmonization in the entire timeseries 1990–2024.

Diesel consumption for 2023 was updated based on the latest IEA data.

10.1.1.3 Recalculation in sector 2 Industrial Processes and Product Use

10.1.1.3.1 Recalculations due to response to the last review process

The TERT recommended that the Party collect data and information on the reuse of recovered F-gases in refrigeration, air conditioning, and other subcategories. We acknowledge the recommendation regarding the reuse of recovered F-gases in refrigeration, air conditioning, and other subcategories. At present, the available information does not allow us to quantify the impact of reused HFCs in the inventory. In line with the TERT's advice, we will seek to identify relevant data sources and collect information on F-gas reuse across different applications.

10.1.1.3.2 Recalculation due to updated activity data

2.A Mineral Industry

No changes and recalculation were made.

2.C Metal Industry

2.C.1 Iron and Steel Production activity data for Coal Tar and few other categories were updated from the questionnaire for the year 2023 which resulted in the slight correction of total emission of CO_2 in ETF data.

2.D Non-energy products from fuels and solvent use

2.D.3 Other urea catalyst – whole times series was recalculated due to the update in activity data and a new version of the COPERT programme (updated from 5.8.1 to 5.9.2)

For detailed explanation of those two changes see chapter 1.A.3.b – Road transport and March NID.

2.F Product Uses as Substitutes for ODS

2.F.1.e Mobile Air Conditioning - following changes in data from COPERT model in the whole data period 1990–2023 (more in the recalculation of 1.A.3 Transport) , activity data for calculating HFC-134a emissions from stocks were updated as well. Furthermore, the calculation of the number of vehicles containing HFC-134a was modified. Newer car types containing HFO-1234yf were excluded from the calculation **(see** Tab. 4-35**).** The activity data for operation emission estimates are obtained from the COPERT since 2017 submission.

2.G Other product Manufacture and Use

2.G.2 SF_6 and PFCs from Other Product Use - Activity data for the 2023 were updated so the emissions of SF_6 were recalculated for the subcategory 2.G.1 Electrical equipment.

2.H Other

2.H.1 Other - the activity data for the year 2023 were updated and it resulted in recalculation of the emissionsProduct Use - Activity data for the 2023 were updated so the emissions of SF_6 were recalculated for the subcategory 2.G.1 Electrical equipment.

10.1.1.4 Recalculation in sector 3 Agriculture

The total emissions estimated for 2024 (current Submission 2026) are by about 11% higher than estimated for 2023. The share of the main categories in the total GHG emissions from the sector remained without

significant changes excluding updated category 3.D. Recalculations in category 3.D led to an average emission reduction of 4%. The increase in synthetic fertilizer consumption increased the sector's total emissions by 11% compared to the results in the Submission 2025. Implemented recalculation are described in the pargraphs below.

10.1.1.4.1 Livestock (Chapter 5.2, NID)

For the period 1990 to 2022, livestock data were reported as of April 1 each year. Since the Submission 2025, data as of December 31 each year are only available for cattle, swine and poultry. The data for other livestock categories (goats, sheep, horses) are expected to be available every three years. Therefore, for the current submission, the same data as in 2023 (Submission 2025) have been used for other livestock categories.

During the quality control (QA) process, all input livestock data were checked and corrected according to the latest statistical data available (CZSO 2025). Population data have been corrected for sheep (input for 1991, 1992, 2001), horses (1990–2021), swine (2001) and poultry (2001). Changes in population numbers are insignificant and have not significantly affected the emission estimate.

10.1.1.4.2 Manure Management (3.B(b))

During the QAQC process, we identified a discrepancy between the AWMS proportion performed by CARC and the NID data – the discrepancy related to the proportion of pasture and solid storage in AWMS for the horse category. Until last submission, we reported this proportion of 40% solid manure, 60% pasture, but the correct ratio is 50% solid storage and 50% pasture. Based on the findings, the entire dataset has been corrected. As a result of the correction, emissions in the direct emission category have increased by 0.350 kt CO_2 eq./year. Overall, emissions from Manure management have increased by 0.1% per year.

10.1.1.4.3 Agricultural Soils (3.D)

Mineralization/Immobilization Associated with Loss of Soil Organic Matter (F_{SOM}, ETF 3.D.1.e)

The annual amount of N in mineral soils that is mineralised due to the loss of soil carbon from soil organic matter (F_{SOM}) is a result of land-use changes or management practices. N_2O emissions associated with soil disturbance during land-use changes are estimated in the LULUCF sector.

N_2O emissions from mineralisation due to the management changes on Cropland remaining Cropland are calculated using Eq. 11.8 (IPCC 2006), employing a default emission factor of 0.01 kg N_2O-N/kg N (EF_1, IPCC 2006), and C:N ratio of 10. The activity data are represented by the carbon loss under subcategory 4.B.1. Cropland remaining Cropland (CRT 4.B.1) due to mineralization. These carbon loss estimates in category 4.B.1 are based on the detailed land-use change matrices and carbon maps, paired with the set of emission factors applicable to seven crop subcategories. In this Submission the above source activity data have been recalculated in the LULUCF sector for the entire reporting period. Therefore, they have slightly affected also the estimates of N_2O emissions from N mineralization/immobilization, which have been recalculated accordingly for the entire reporting period since 1990.

Cultivation of Organic Soils (F_{OS} ETF 3.D.1.f)

In this submission, greenhouse gas emissions from drained organic soils have been newly reported. Their estimation has been carried out based on a technical correction prepared by the EU review team as a part of the last year's NID (2025). The vast majority of emissions from drained organic soils (all emissions from peatlands on forest land, CO_2 and CH_4 emissions from drained organic soils on agricultural land) are reported within the LULUCF sector; only the corresponding N_2O emissions from cultivated organic soils on agricultural land (Cropland or Grassland categories) have been reported in accordance with IPCC (2006) Guidelines within the sector Agriculture under category 3.D.1.

Regarding the agricultural land, organic soils in the Czech Republic are only located in the Grassland category, not Cropland. Their total area (12,698 ha) has been determined based on the data from the Research Institute for Soil and Water Conservation (VÚMOP) as has been the assumed proportion of their drainage (20%) – see the LULUCF chapter for more details.

N_2O emissions from drained organic soils are estimated using Eq. 2.7 (Wetlands Supplement, IPCC 2013) with the default emission factors for the deep-drained, nutrient-rich Grassland in the temperate zone (8.2 kg N_2O-N/ha/year, Table 2.5.1 IPCC 2013).

The average annual N_2O emissions from drained organic soils in the land-use category Grassland remaining Grassland (4.C.1), calculated over the entire reporting period since 1990, has been 32.7 kg N_2O-N/ha/year. This change has caused the increase of the estimated emissions by 8.67 kt CO_2 eq. per year, which is 0.1% of the total reported emissions from Agriculture sector per year.

Influence of climatic regions diversification on Leaching and Run-off emissions (ETF 3.D.2.b)

According to the recommendation of TERT ID CZ-3D2-2025-0001, a revision of the estimate of N_2O emissions of category 3.D.2.b from N Leaching and Run-off for the years 1990-2023 has been carried out. In Submission 2025, there was calculated incorrectly that 24% of the N input from 3.D category (inorganic and organic fertilizers, urine and dung deposited by grazing animals, crop residues, mineralization/immobilization associated with loss/gain of soil organic matter) is leached. This aligns with the 2019 IPCC default value for wet climates or areas with irrigation (excluding drip irrigation). Refined map and data information on ratio of wet and dry area in the country, showing that a varying ratio of the country has been considered as dry climate across the years. Due to a technical error, climatic factors were not considered when determining $Frac_{Leach}$ before. Considering climatic regions has led to a reduction in emissions in the category by 53.5% on average, i.e. 341 kt CO_2 eq./year, which is less than 5% of the total emissions from the sector Agriculture.

Nitrogen excreted on pasture and paddock (ETF 3.D.1.c)

The decrease in the ratio of nitrogen excreted by horses on pasture and paddock has caused a slight decrease in emissions from grazing, by approximately 0.265 kt CO_2 per year.

10.1.1.5 Recalculations in sector 4 LULUCF

10.1.1.5.1 Recalculation due to response to the last review process and recalculation due to use of country specific conditions

4.A Forest land

Since the last submission, the emission estimates were recalculated for category 4.A (Forest land) across the entire reporting period. This was due to the revised parameterization of biomass equations needed for the CBM-CFS3 modeling tool following the fundamental concepts of Boudewyn et al. (2007), based on the newly acquired pameterization data from the Czech National Forest Inventory (J. Máslo, CFI, 2025 – personal communication). This required a revised handling of input activity data in the model retaining under-bark units consistent with all harvest activity data in the country (Ch. 6.4.1) used in the CBM-CFS3 model. These changes affected the estimates in all carbon pools in category 4.A. Other changes implemented in this inventory submission for category 4.A include new emission estimates for organic soils, and N_2O estimates associated with carbon loss from land-use conversions. Furthermore, this inventory submission (NID 2026) improved the national CBM-CFS3 calibration by implementing air temperature data recompiled from available meteorogical measurements in the country that spatially represent the areas of forest land. Finally, the new soil carbon layers implemented in this inventory

submission affected emission estimates for litter and mineral soils. The implemented revisions resulted in an on average 4.3% increased sink for 4.A Forest land over the reporting period (excluding the last year), compared to the previous NID submission. Most of that difference was attributed to the 4.A.1 subcategory, while the quantitative impact on 4.A.2 was about 1% (increased sink).

The information on these recalculations is also given in Chapter 6.4.5, including a graphical comparison of the current (NID 2026) and the previous emission estimates for 4.A Forest land and the reporting period (Fig. 6-19).

4.B Cropland

Since the last submission, the emission estimates related to carbon stock changes were recalculated for both the categories 4.B.1 Cropland remaining Cropland and 4.B.2 Land converted to Cropland.

Overall, the estimated emissions increased by 102 % for the entire category 4.B (Fig. 6-23), resulting from the implemented revisions involving new activity data (soil organic carbon layer). In 4.B.1, the changes were quantitatively minor, representing in average a 2% emission sink decrease. Most of the changes are attributed to cagegory 4.B.2. They represent an emission increase by 97 % when comparing the identical period (1990–2023). These changes are due to new soil carbon activity data in all land-use categories, and due to adding N_2O emissions from additional land conversion categories.

For transparency, the estimates for category 4.B Cropland are displayed graphically in Fig. 6-23, including the current (NID 2026) and previous (NID 2025) inventory submission.

4.C Grassland

Since the last submission, recalculations for 4.C.1 were conducted due to the newly incorporated estimates of emisions related to organic soil. This contributed to a decreased sink of 62%. In the subcategory 4.C.2 Land converted to Grassland, the recalculations represent a sink increase of 83%. This is due to the changes in activity data (new soil organic carbon layers). Totally on average for 4.C, the revised emission estimates quantitatively represent a sink increase by 50% as compared to the previously reported estimates on the comparable period (1990 to 2023).

For transparency, the estimates for category 4.C Grassland are displayed graphically in Fig. 6-25, including the current (NID 2026) and previous (NID 2025) inventory submission.

4.D Wetlands

The emission estimates for the category 4.D Wetlands were recalculated in its subcategory 4.D.2. This was due to the new activity data (soil carbon layers). These changes decreased emissions for category 4.D (4.D.2) by 96% relative to the previous NID submission, which represents -29 kt CO_2 eq./year, which is quantitatively negligible.

For transparency, the estimates for category 4.D Wetlands are displayed graphically in Fig. 6-27, including the current (NID 2026) and previous (NID 2025) inventory submission.

4.E Settlements

The emission estimates for the category 4.E Settlements were recalculated in its subcategory 4.E.2. This was due to the revised activity data (soil organic carbon maps). Additionally, N_2O emissisons from N mineralization were newly estimated with this NID submission These changes increased emission estimates for category 4.E (4.E.2) by 7% relative to the previous NID submission.

For transparency, the estimates for category 4.E Settlements are displayed graphically in Fig. 6-29, including the current (NID 2026) and previous (NID 2025) inventory submission.

4.G HWP

No recalculation was made for the category 4.G HWP except the most recent years due to slightly changed activity data at FAO database on wood production and trade, the primary source of the activity data used for estimation of HWP emission contribution for the entire reporting period. These activity data were crosschecked and rectified based on the discussion with the country correspondents for reporting to FAO (see section 6.10.2 above). These affected only the estimates of HWP contribution for 2023. Hence, the estimates differ between the current and the previous submission marginally, namely by -0.01% (decreased sink).

For transparency, the estimates for category 4.G HWP are displayed graphically in Fig. 6-30, including the current (NID 2026) and previous (NID 2025) inventory submission.

10.1.1.6 Recalculation in sector 5 Waste

10.1.1.6.1 Recalculation due to updated activity data

A few recalculations occurred due to changes in Activity data provided by CENIA. Specifically, AD were updated backwards for 2023 in the following categories: 5.A.1.a – Waste per capita and 5.C.1. – Municipal solid waste.

10.1.1.6.2 Recalculation due to updated emission factor

NA

10.1.1.6.3 Recalculation due to response to the last review process and recalculation due to use of country specific conditions

In category 5.D.1. N_2O emissions were transferred from Plants in Effluent based on CZ-5D-2025-0001 observation.

10.1.1.7 Recalculations in indirect emissions

All the trends and impacts of recalculations can be observed in the Tab. 9-4 in chapter 9 regarding indirect emissions. Impact on indirect N_2O emissions is from changes in the activity data in the NFR in gases NO_x and NH_3. Impact on indirect CO_2 emissions is not from CH_4 in the current submission, but from recalculation of CO and NMVOC precursor gases in the NFR. Recalculations of NMVOC and CO have lowered indirect CO_2 -77.07 kt in 1990 to the lowest impact -16.53 kt in 2023. The highest impact -84.02 kt is for the year 2012 for the indirect CO_2 emissions.

10.2 Implications for emission levels

Tab. 10-5 Implications of recalculations on CO_2 emission levels on example on 2023 emission levels

GREENHOUSE GAS SOURCE AND SINK CATEGORIES	Previous submission (CO_2-eq, kt)	Latest submission (CO_2-eq, kt)	Difference (CO_2-eq, kt)	Difference (%)	Impact of recalculation on total emissions excl. LULUCF (%)	Impact of recalculation on total emissions incl.LULUCF (%)
Total National Emissions and Removals	79654.32	79470.66	-183.66	-0.23	-0.18	-0.19
1. Energy	74274.43	74303.18	28.75	0.04	0.03	0.03
A. Fuel combustion activities	74237.66	74234.42	-3.23	0.00	0.00	0.00
1. Energy industries	35467.03	35469.37	2.34	0.01	0.00	0.00
2. Manufacturing industries and construction	10032.19	10050.69	18.50	0.18	0.02	0.02
3. Transport	19684.04	19680.60	-3.43	-0.02	0.00	0.00
4. Other sectors	8797.04	8797.75	0.72	0.01	0.00	0.00
5. Other	257.36	236.00	-21.36	-8.30	-0.02	-0.02
B. Fugitive Emissions from Fuels	36.77	68.76	31.99	86.99	0.03	0.03
1. Solid fuels	33.85	65.84	31.99	94.53	0.03	0.03
2. Oil and natural gas	2.92	2.92	-0.01	-0.27	0.00	0.00
C. CO_2 transport and storage	NO	NO	–	–	–	–
2. Industrial processes and product use	8620.06	8618.50	-1.56	-0.02	0.00	0.00
A. Mineral industry	2595.85	2595.85	0.00	0.00	0.00	0.00
B. Chemical industry	1557.34	1557.34	0.00	0.00	0.00	0.00
C. Metal industry	4344.99	4344.99	0.00	0.00	0.00	0.00
D. Non-energy products from fuels and solvent use	121.79	119.45	-2.34	-1.92	0.00	0.00
2.E. Electronics Industry	0.00	0.00	0.00	0.00	0.00	0.00
G. Other product manufacture and use	NO	NO	–	–	–	–
H. Other	0.10	0.87	0.78	787.13	0.00	0.00
3. Agriculture	268.80	268.80	0.00	0.00	0.00	0.00
A. Enteric fermentation	0.00	0.00	0.00	0.00	0.00	0.00
B. Manure management	0.00	0.00	0.00	0.00	0.00	0.00
C. Rice cultivation	0.00	0.00	0.00	0.00	0.00	0.00
D. Agricultural soils	0.00	0.00	0.00	0.00	0.00	0.00
E. Prescribed burning of savannahs	0.00	0.00	0.00	0.00	0.00	0.00
F. Field burning of agricultural residues	0.00	0.00	0.00	0.00	0.00	0.00
G. Liming	120.75	120.75	0.00	0.00	0.00	0.00
H. Urea application	148.05	148.05	0.00	0.00	0.00	0.00
I. Other carbon-containing fertilizer	NO	NO	–	–	–	–
J. Other	NA	NA	–	–	–	–
4. Land use, land-use change and forestry (net)	-3577.92	-3788.75	-210.83	5.89	0.00	-0.21
A. Forestland	-2021.86	-2057.90	-36.04	1.78	0.00	-0.04
B. Cropland	33.37	91.66	58.28	174.66	0.00	0.06
C. Grassland	-633.56	-813.31	-179.75	28.37	0.00	-0.18
D. Wetlands	24.67	-15.22	-39.89	-161.68	0.00	-0.04
E. Settlements	267.57	252.01	-15.56	-5.82	0.00	-0.02
F. Other land	NA,NO	NA,NO	–	–	0.00	–
G. Harvested wood products	-1248.11	-1245.98	2.13	-0.17	0.00	0.00
H. Other	NO	NO	–	–	0.00	–
5. Waste	68.95	68.93	-0.02	-0.03	0.00	0.00
A. Solid waste disposal	0.00	0.00	0.00	0.00	0.00	0.00
B. Biological treatment of solid waste	0.00	0.00	0.00	0.00	0.00	0.00
C. Incineration and open burning of waste	68.95	68.93	-0.02	-0.03	0.00	0.00
D. Waste water treatment and discharge	0.00	0.00	0.00	0.00	0.00	0.00
E. Other	NO	NO	–	–	–	–
6. Other (As specified in summary 1.A)	NA	NA	–	–	–	–
Memo items:	NA	NA	NA	NA	NA	NA
International bunkers	1039.50	1039.50	0.00	0.00	0.00	0.00
Aviation	1039.50	1039.50	0.00	0.00	0.00	0.00
Navigation	NO	NO	–	–	–	–
Multilateral operations	NO	NO	–	–	–	–

CO_2 emissions from biomass	17851.13	18358.15	507.03	2.84	0.50	0.52
CO_2 captured	NO	NO	–	–	–	–
Long-term storage of C in waste disposal sites	51081.31	51081.80	0.49	0.00	0.00	0.00
Indirect N_2O	0.00	0.00	0.00	0.00	0.00	0.00
Indirect CO_2	430.84	421.35	-9.48	-2.20	-0.01	-0.01

Tab. 10-6 Implications of recalculations on CH_4 emission levels on example on 2023 emission levels

GREENHOUSE GAS SOURCE AND SINK CATEGORIES	Previous submission (CO_2-eq, kt)	Latest submission (CO_2-eq, kt)	Difference (CO_2-eq, kt)	Difference (%)	Impact of recalculation on total emissions excl. LULUCF (%)	Impact of recalculation on total emissions incl.LULUCF (%)
Total National Emissions and Removals	11283.10	11125.06	-158.04	-1.40	-0.16	-0.16
1. Energy	2014.70	1850.26	-164.45	-8.16	-0.16	-0.17
A. Fuel combustion activities	985.44	989.31	3.87	0.39	0.00	0.00
1. Energy industries	34.96	39.22	4.26	12.20	0.00	0.00
2. Manufacturing industries and construction	47.73	47.78	0.05	0.10	0.00	0.00
3. Transport	25.78	25.72	-0.06	-0.23	0.00	0.00
4. Other sectors	876.74	876.54	-0.19	-0.02	0.00	0.00
5. Other	0.23	0.05	-0.18	-79.85	0.00	0.00
B. Fugitive Emissions from Fuels	1029.27	860.95	-168.32	-16.35	-0.17	-0.17
1. Solid fuels	601.01	491.42	-109.59	-18.23	-0.11	-0.11
2. Oil and natural gas	428.26	369.52	-58.73	-13.71	-0.06	-0.06
C. CO_2 transport and storage	0.00	0.00	0.00	0.00	0.00	0.00
2. Industrial processes and product use	55.56	55.56	0.00	0.00	0.00	0.00
A. Mineral industry	NO	NO	–	–	–	–
B. Chemical industry	45.69	45.69	0.00	0.00	0.00	0.00
C. Metal industry	9.87	9.87	0.00	0.00	0.00	0.00
D. Non-energy products from fuels and solvent use	NA,NO	NA,NO	–	–	–	–
2.E. Electronics Industry	0.00	0.00	0.00	0.00	0.00	0.00
G. Other product manufacture and use	NO	NO	–	–	–	–
H. Other	NO	NO	–	–	–	–
3. Agriculture	3968.16	3968.90	0.74	0.02	0.00	0.00
A. Enteric fermentation	3613.58	3614.32	0.75	0.02	0.00	0.00
B. Manure management	354.58	354.57	-0.01	0.00	0.00	0.00
C. Rice cultivation	NO	NA,NO	–	–	–	–
D. Agricultural soils	NA	NA	–	–	–	–
E. Prescribed burning of savannahs	NA	NA	–	–	–	–
F. Field burning of agricultural residues	NO	NA,NO	–	–	–	–
G. Liming	0.00	0.00	0.00	0.00	0.00	0.00
H. Urea application	0.00	0.00	0.00	0.00	0.00	0.00
I. Other carbon-containing fertilizer	0.00	0.00	0.00	0.00	0.00	0.00
J. Other	NA	NA	–	–	–	–
4. Land use, land-use change and forestry (net)	4.41	10.07	5.67	128.59	0.00	0.01
A. Forestland	4.41	4.85	0.44	10.07	0.00	0.00
B. Cropland	NO	NO	–	–	0.00	–
C. Grassland	NO	5.22	–	–	0.00	–
D. Wetlands	NO	NO	–	–	0.00	–
E. Settlements	NO	NO	–	–	0.00	–
F. Other land	NO	NO	–	–	0.00	–
G. Harvested wood products	0.00	0.00	0.00	0.00	0.00	0.00
H. Other	NO	NO	–	–	0.00	–
5. Waste	5240.28	5240.28	0.00	0.00	0.00	0.00
A. Solid waste disposal	3813.68	3813.68	0.00	0.00	0.00	0.00
B. Biological treatment of solid waste	497.08	497.08	0.00	0.00	0.00	0.00
C. Incineration and open burning of waste	5.08	5.08	0.00	-0.01	0.00	0.00
D. Waste water treatment and discharge	924.44	924.44	0.00	0.00	0.00	0.00
E. Other	NO	NO	–	–	–	–
6. Other (As specified in summary 1.A)	NA	NA	–	–	–	–
Memo items:	NA	NA	NA	NA	NA	NA
International bunkers	0.20	0.20	0.00	0.00	0.00	0.00
Aviation	0.20	0.20	0.00	0.00	0.00	0.00
Navigation	NO	NO	–	–	–	–
Multilateral operations	NO	NO	–	–	–	–
CO_2 emissions from biomass	0.00	0.00	0.00	0.00	0.00	0.00
CO_2 captured	0.00	0.00	0.00	0.00	0.00	0.00
Long-term storage of C in waste disposal sites	0.00	0.00	0.00	0.00	0.00	0.00
Indirect N_2O	0.00	0.00	0.00	0.00	0.00	0.00
Indirect CO_2	0.00	0.00	0.00	0.00	0.00	0.00

Tab. 10-7 Implications of recalculations on N_2O emission levels on example on 2023 emission levels

GREENHOUSE GAS SOURCE AND SINK CATEGORIES	Previous submission (CO_2-eq, kt)	Latest submission (CO_2-eq, kt)	Difference (CO_2-eq, kt)	Difference (%)	Impact of recalculation on total emissions excl. LULUCF (%)	Impact of recalculation on total emissions incl.LULUCF (%)
Total National Emissions and Removals	3837.21	3754.35	-82.87	-2.16	-0.08	-0.08
1. Energy	521.20	698.45	177.26	34.01	0.17	0.18
A. Fuel combustion activities	521.18	698.44	177.26	34.01	0.17	0.18
1. Energy industries	159.67	165.06	5.39	3.37	0.01	0.01
2. Manufacturing industries and construction	61.45	61.51	0.07	0.11	0.00	0.00
3. Transport	186.76	328.05	141.29	75.65	0.14	0.14
4. Other sectors	110.46	136.12	25.65	23.22	0.03	0.03
5. Other	2.84	7.70	4.86	170.96	0.00	0.00
B. Fugitive Emissions from Fuels	0.01	0.01	0.00	0.00	0.00	0.00
1. Solid fuels	NA,NO	NA,NO	–	–	–	–
2. Oil and natural gas	0.01	0.01	0.00	0.00	0.00	0.00
C. CO_2 transport and storage	0.00	0.00	0.00	0.00	0.00	0.00
2. Industrial processes and product use	314.58	314.58	0.00	0.00	0.00	0.00
A. Mineral industry	NO	NO	–	–	–	–
B. Chemical industry	115.83	115.83	0.00	0.00	0.00	0.00
C. Metal industry	NA	NA	–	–	–	–
D. Non-energy products from fuels and solvent use	NA,NO	NA,NO	–	–	–	–
2.E. Electronics Industry	NO	NO	–	–	–	–
G. Other product manufacture and use	198.75	198.75	0.00	0.00	0.00	0.00
H. Other	NO	NO	–	–	–	–
3. Agriculture	2729.79	2453.88	-275.91	-10.11	-0.27	-0.28
A. Enteric fermentation	0.00	0.00	0.00	0.00	0.00	0.00
B. Manure management	378.09	378.59	0.50	0.13	0.00	0.00
C. Rice cultivation	0.00	0.00	0.00	0.00	0.00	0.00
D. Agricultural soils	2351.71	2075.29	-276.42	-11.75	-0.27	-0.28
E. Prescribed burning of savannahs	NA	NA	–	–	–	–
F. Field burning of agricultural residues	NO	NA,NO	–	–	–	–
G. Liming	0.00	0.00	0.00	0.00	0.00	0.00
H. Urea application	0.00	0.00	0.00	0.00	0.00	0.00
I. Other carbon-containing fertilizer	0.00	0.00	0.00	0.00	0.00	0.00
J. Other	NA	NA	–	–	–	–
4. Land use, land-use change and forestry (net)	5.09	22.20	17.11	336.09	0.00	0.02
A. Forestland	2.31	6.81	4.50	194.98	0.00	0.00
B. Cropland	2.78	9.29	6.51	233.93	0.00	0.01
C. Grassland	NO	NO	–	–	0.00	–
D. Wetlands	NA,NO	NA,NO	–	–	0.00	–
E. Settlements	NO	6.10	–	–	0.00	–
F. Other land	NO	NO	–	–	0.00	–
G. Harvested wood products	0.00	0.00	0.00	0.00	0.00	0.00
H. Other	0.00	NO	–	–	0.00	–
5. Waste	266.56	265.24	-1.32	-0.49	0.00	0.00
A. Solid waste disposal	0.00	0.00	0.00	0.00	0.00	0.00
B. Biological treatment of solid waste	62.28	62.28	0.00	0.00	0.00	0.00
C. Incineration and open burning of waste	4.22	2.90	-1.32	-31.23	0.00	0.00
D. Waste water treatment and discharge	200.06	200.06	0.00	0.00	0.00	0.00
E. Other	NO	NO	–	–	–	–
6. Other (As specified in summary 1.A)	NA	NA	–	–	–	–
Memo items:	NA	NA	NA	NA	NA	NA
International bunkers	7.49	7.49	0.00	0.00	0.00	0.00
Aviation	7.49	7.49	0.00	0.00	0.00	0.00
Navigation	NO	NO	–	–	–	–
Multilateral operations	NO	NO	–	–	–	–
CO_2 emissions from biomass	0.00	0.00	0.00	0.00	0.00	0.00
CO_2 captured	0.00	0.00	0.00	0.00	0.00	0.00
Long-term storage of C in waste disposal sites	0.00	0.00	0.00	0.00	0.00	0.00
Indirect N_2O	158.93	158.42	-0.51	-0.32	0.00	0.00
Indirect CO_2	0.00	0.00	0.00	0.00	0.00	0.00

Tab. 10-8 Implications of recalculations on F-gases emission levels on example on 2023 emission levels

GREENHOUSE GAS SOURCE AND SINK CATEGORIES	Gas (PFC, HFC, NF_3, SF_6, HFC-PFC Mix)	Previous submission (CO_2-eq, kt)	Latest submission (CO_2-eq, kt)	Difference (CO_2-eq, kt)	Difference %	Impact of recalculation on total emissions excluding LULUCF %	Impact of recalculation on total emissions including LULUCF %
F-gases: Total actual Emissions	PFC, HFC, NF_3, SF_6	3712.75	3711.97	-0.77	-0.02	0.00	0.00
2.B.9. Flurochemical production		NO	NO	NA	NA	NA	NA
2.B.10. Other		NO	NO	NA	NA	NA	NA
2.C.3. Aluminium production		NO	NO	NA	NA	NA	NA
2.C.4. Magnesium production		NO	NO	NA	NA	NA	NA
2.C.7. Other		NO	NO	NA	NA	NA	NA
2.E.1. Integrated circuit or semiconductor	PFC, NF_3, SF_6	70.56	70.56	NA	NA	NA	NA
2.E.2. TFT flat panel display		NO	NO	NA	NA	NA	NA
2.E.3. Photovoltaics		NO	NO	NA	NA	NA	NA
2.E.4. Heat transfer fluid		NO	NO	NA	NA	NA	NA
2.E.5. Other		NO	NO	NA	NA	NA	NA
2.F.1. Refrigeration and air conditioning	PFC, HFC	3532.31	3532.31	NA	NA	NA	NA
2.F.2. Foam blowing agents	HFC	2.67	2.67	NA	NA	NA	NA
2.F.3. Fire protection	PFC, HFC	32.49	32.49	NA	NA	NA	NA
2.F.4. Aerosols	HFC	2.84	2.84	NA	NA	NA	NA
2.F.5. Solvents		NO	NO	NA	NA	NA	NA
2.F.6. Other applications		NO	NO	NA	NA	NA	NA
2.G.1. Electrical equipment	SF_6	55.05	54.30	-0.75	-1.35	0.00	0.00
2.G.2. SF_6 and PFCs from other product use	SF_6	16.63	16.63	NA	NA	NA	NA
2.G.4. Other		NO	NO	NA	NA	NA	NA
2.H. Other	HFC	0.20	0.17	-0.03	-13.94	0.00	0.00

10.3 Implications for emission trends, including time-series consistency

10.3.1 Implications for emission trend and time-series consistency of CO_2

The influence of the recalculations for the emission trend of CO_2 are illustrated on Fig. 10-1. Both curves are following the same pattern. The CO_2 emission trend through the whole time period.



Fig. 10-1 Difference in trends of CO_2 emissions between the submissions 2025 and 2026, due to recalculations

10.3.1 Implications for emission trend and time-series consistency of CH_4

The influence of the recalculations for the emission trend of CH_4 are illustrated on Fig. 10-2. Both curves are following the same pattern, the CH_4 emission trend is lower in recent submission in average by 3%, through the whole time period.



Fig. 10-2 Difference in trends of CH4 emissions in index form, between the submissions 2025 and 2026, due to recalculations

10.3.2 Implications for emission trend and time-series consistency of N_2O

The influence of the recalculations for the emission trend of N_2O are illustrated on Fig. 10-3. Both curves are following the simmilar pattern, the N_2O emission trend is lower in recent submission in average by 5.4%, through the whole time period.



Fig. 10-3 Difference in trends of N_2O emissions, between the submissions 2025 and 2026, due to recalculations

10.3.3 Implications for emission trends and time-series consistency of F-gases and SF_6

The influence of the recalculations for the emission trend of HFCs are illustrated on Fig. 10-4. Both curves are following the same pattern.



Fig. 10-4 Difference in trends of HFCs emissions in index form, between submission 2025 and 2026, due to recalculations

The influence of the recalculations for the emission trend of PFCs are illustrated on Fig. 10-5. Both curves are following the same pattern.



Fig. 10-5 Difference in trends of PFCs emissions, between submission 2025 and 2026, due to recalculations

The influence of the recalculations for the emission trend of SF_6 are illustrated on Fig. 10-6. Both curves are following the same pattern with the exception of the last two years.



Fig. 10-6 Difference in trends of SF_6 emissions, between submission 2025 and 2026, due to recalculations

10.3.4 Implications for emission trends and time-series consistency of total emissions

The influence of the recalculations for the emission trend of total emissions, including LULUCF are illustrated on Fig. 10-7. Both curves are following the same pattern. The total emissions including LULUCF in trend is lower on average by 0.8% through the whole time period.



Fig. 10-7 Difference in trends of total emissions including LULUCF, between submission 2025 and 2026, due to recalculations

The influence of the recalculations for the emission trend of total emissions, excluding LULUCF are illustrated on Fig. 10-8. Both curves are following the same pattern. The total emissions excluding LULUCF in trend is lower on average by 0.5% through the whole time period.



Fig. 10-8 Difference in trends of total emissions excluding LULUCF, between submission 2025 and 2026, due to recalculations

10.4 Planned improvements, including in response to the review process

Each year, the Czech inventory team analyses the findings of ERT (the Expert Review Team) and attempts to improve the quality of the inventory by implementation of the relevant recommendations.

An overview of previous findings and the relevant follow up by the Czech Republic was given in the previous NIDs. In this report, attention is focused on the two last reviews.

In September 2022, the Czech Republic was subject to the centralized review conducted remotely. No 'potential problems' were formulated, thus no resubmission after the review was carried out. In May 2025 the Czech Republic was subjected to the EU Comprehensive Review. The review has resulted with one revised estimates in Energy sector and one in Agriculture sector and 1 technical correction in LULUCF sector, no resubmission was carried out.

10.4.1 Overview of implemented improvements in the 2026 submission

The following Tab. 10-9 summarises the main changes that were performed in 2026 submission in comparison with previous submissions.

Tab. 10-9 Table of implemented improvements in the 2026 submission

Topic/Category, gas	Description of the change	Reason (motive) of the change	Reference to NID or CRT Table
Sector: General issues			
Archiving	Expert judgement forms have been archived from sectors Energy, Agriculture, Transportation, Waste and IPPU.	Improvement suggested by the UNFCCC recommendation G.2/ FCCC/ARR/2022/CZE	**NID, chapter 1.3.3**
General	Likely level of significance rough estimate to justify NE added to table 9	Improvement suggested by the UNFCCC recommendation G.1/ FCCC/ARR/2022/CZE	**CRT table 9**
Key category analysis	KCA calculation sheet updated correctly, which is reflected in NID ch 1.5 KCA tables and text.	Improvement suggested by the UNFCCC recommendation G.5/ FCCC/ARR/2022/CZE	**NID, chapter 1.5**
Sector: Energy – emissions from combustion			
1.A	Comparison CRT and Eurostat data	ARR2019, E.9	**Annex 4**
1.B.1.a.1.ii	Apply new CS EF for CO_2	Energy team	**CRT, NID pp. 153**
1.B.2.b.iv	Added detailed decription of methodology applied, EF using in time	Improvement suggested by EU comprehensive review, CZ-1B2b-2025- 0002	**NID pp. 166-167**
1.B.2.b.v	Use of revised estimate	Improvement suggested by EU comprehensive review, CZ-1B2b-2025- 0001	**CRT, NID pp. 167 and 170**
1.A.4.c.ii	Change of the EF for the long time series	Energy team, correcting inaccurate reporting of emissions	**NID, 3.2.20.1**
1.A.5.b	Change of the EF for the long time series	Energy team, correcting inaccurate reporting of emissions	**NID, 3.3.21.1**
Sector: Industrial processes and Other Product Use			
	No change		
Sector: Agriculture			
3.D	Transition of the methodology to a higher level of estimation by introducing zoning of the territory according to climate	Improvement suggested by the UNFCCC recommendation and recommendation of TERT ID CZ-3D2-2025-0001,	**CRT 3.D**
3.D.1.f	Emissions from cultivation of drained organic soils (FOS) was included in actvity data	Technical correction prepared by the EU review team (LULUCF sector)	**CRT 3.D**
Sector: LULUCF			
4.A.1, 4.C.1	Emissions from drained organic soils	Technical correction prepared by the EU review team (CZ-4A1-2025-0002)	**NID, chapter 6.4.2.2, 6.6.2.1**
4.A.2, 4.B.2, 4.E.2	N_2O emissions for all land-use conversion types resulting in carbon loss in mineral soil	EU review CZ-4-2025-0002	**NID, chapter 6.4.2.3, 6.5.2.2, 6.8.2**
4.D.2	Mineral soils in wetlands are explicitly considered and accounted	EU review CZ-4D2-2024-0001	**NID, chapter 6.7.2**
Sector: Waste			

Topic/Category, gas	Description of the change	Reason (motive) of the change	Reference to NID or CRT Table
5.B.2	No change		

Tab. 10-10 Methodological descriptions in submission 2026

GREENHOUSE GAS SOURCE AND SINK CATEGORIES	DESCRIPTION OF METHODS	RECALCULATIONS	REFERENCE
Total (Net Emissions)			
1. Energy			
A. Fuel Combustion (Sectoral Approach)			
1. Energy Industries			
2. Manufacturing Industries and Construction			
3. Transport	✓	✓	NID 3.2.17.3, 10.1.1.2
4. Other Sectors	✓	✓	NID, 3.2.20.1
5. Other	✓	✓	NID, 3.2.21.1
B. Fugitive Emissions from Fuels			
1. Solid Fuels	✓	✓	NID, 3.3.1.2, pg. 143-144
2. Oil and Natural Gas and Other emissions from Energy Production	✓	✓	NID, 3.3.2.2.2, pg. 160-161
C. CO_2 transport and storage			
2. Industrial Processes			
A. Mineral Industry			
B. Chemical Industry			
C. Metal Industry			
D. Non-energy Products from Fuels and Solvent Use			
E. Electronics Industry			
F. Product Uses as Substitutes for ODS			
G. Other Product Manufacture and Use			
3. Agriculture			
A. Enteric Fermentation	√		NID 5.2.1
B. Manure Management	√		NID 5.2.2
C. Rice Cultivation			
D. Agricultural Soils	√	√	NID 5.4.2, Annex 3.8
E. Prescribed Burning of Savannas			
F. Field Burning of Agricultural Residues			
G. Liming			
H. Urea Application			
I. Other Carbon-containing Fertilizers			
J. Other			
4. Land Use, Land-Use Change and Forestry			
A. Forest Land	√	√	6.4.2.1, Annex 3.6
B. Cropland	√	√	6.5.2
C. Grassland	√	√	6.6.2
D. Wetlands	√	√	6.7.2
E. Settlements	√	√	6.8.2
F. Other Land			
G. Harvested Wood Products			
H. Other			
5. Waste			

GREENHOUSE GAS SOURCE AND SINK CATEGORIES	DESCRIPTION OF METHODS	RECALCULATIONS	REFERENCE
A. Solid Waste Disposal			
B. Biological treatment of solid waste			
C. Incineration and open burning of waste			
D. Wastewater treatment and discharge			
E. Other			
6. Other (as specified in Summary 1.A)			
Memo Items:			
International Bunkers			
Aviation			
Marine			
Multilateral Operations			
CO_2 Emissions from Biomass			
CO_2 Captured			
Long-term storage of C in waste disposal sites			
Indirect N_2O			
NID Chapter	**DESCRIPTION**		**REFERENCE**
	Please tick where the latest NID includes major changes		**If ticked please provide some more detailed information**
Chapter 1.2 Institutional arrangements	√		Since submission 2025 CHMI (Monika Filipenska) is the main body responsible for sector Waste. CENIA provides only activity data.
Chapter 1.6 QA/QC plan	√		Following the discussion during the in-country review 2026 te description of QA/QC Plan and QA/QC Manual were revised

10.4.2 Improvement plan

Improvement plan is in accordance with the recommendation of the international Technical Expert Review Team (TERT) and concentrates particularly on introduction the more sophisticated procedures of the higher Tiers. These procedures employ country-specific emission factors and other parameters required for determining greenhouse gas emissions. However, it is rather difficult to obtain the data required for these purposes, especially at the present time, when only limited funds are available for the national inventory. Thus, it is planned to introduce the procedures of the higher Tiers gradually, over a longer time interval. In accordance with the IPCC methodology, emphasis is simultaneously put on Key categories. The following table gives the anticipated timetable for introduction of these procedures. As announced in the last submission, the country-specific emission factor for estimating CO_2 emissions from combustion of Natural Gas has been determined (please see Annex 2). These factors were already employed in this submission (see Chapter 3).

In addition to the planned introduction of the procedures of the higher Tiers in the individual sectors, the Improvement plan also includes a more general aspect. For instance last year have been revised uncertainty estimates. A substantial improvement in this respect has already appeared in this submission (see Chapter 1).

Furthermore Improvement Plan also includes using of EU ETS data for the purposes of national inventory. Substantial effort is put into implementation of this issue. In this submission EU ETS data were used for emission estimates in some subcategories in 2.A Mineral Product (e.g. 2.A.1 Cement Production). EU ETS data would be useful tool for QA/QC procedures also in Energy sector.

Tab. 10-11 Plan of improvements for key categories

Sector	Key Categories (KC)	GHG	% *) GHG	Type of KC	Present situation	Planned improvement	For submission
3	3.B Manure management	CH_4	0.29	TA	Tier 1, Tier 2	MCF calculation update according IPCCC 2019 Guidelines	2028
5	5.D Wastewater Treatment and Discharge	CH_4 N_2O	0.88	LA, TA	Tier 1, CS, D	Review of biogas composition and used factors	2028

**) share in total GHG emissions excluding LULUCF*

11 Other Information

No other information submitted in 2026.

References

Adolt, R., Kohn, I., Kučera, M., Piškytlová, K., Kratěna, L., Fejfar, J., Závodský, J., Čech, Z. (2016). Výstupy národní inventarizace lesů uskutečněné v letech 2011-2015, 5. Mortalita kmenů. Lesnická práce 95(5) (in Czech)

Adolt, R., Hájek F., Kohn, I., Mlčoušek M., Kantorová M., Hejlová, V. a Hanáková, J. (2020), „Odhad zásoby dříví v převážně jehličnatých porostech do září 2019 nepoškozených kůrovcovou kalamitou," 13 3 2020. [Online]. Available: http://nil.uhul.cz/downloads/vysledky

Alfeld, K. (1998): Methane Emissions Produced by the Gas Industry Worldwide, IGU Study Group 8.1: Methane emissions, Essen

Anonymus (2020): Zpráva o stavu zemědělství v ČR v roce 2019. Ministerstvo zemědělství, Praha, 162 pp.

ARR 2017: Report of the individual review of the annual submission of the Czech Republic submitted in 2017 (FCCC/ARR/2017/CZE)

Audiowell (2020): How to Measure the Quality of AdBlue by Ultrasonic Sensor?, 29-10-2020 [Online]. Available: https://www.audiowellsensor.com/news/how-to-measure-the-quality-of-adblue-by-ultrasonic-sensor

Beranová, J., Joch, M., Fukalova, T. (2022a): Aktualizace metodiky odhadu emisí z enterické fermentace u skotu, zhodnocení možnosti využití národně specifických údajů pro odhad emisí z enterické fermentace (Updating the methodology for estimating emissions from enteric fermentation in cattle, evaluating the possibility of using nationally specific data for estimating emissions from enteric fermentation). Výstup V 23 projektu "Rozvoj metodik pro reporting emisí a propadů skleníkových plynů a jejich projekcí, včetně projekcí emisí tradičních polutantů (TK02010056), 36 stran. In Czech

Beranova, J. , Wollnerova, J., Klír J., Dědina, M. (2022b): Podmínky a důsledky implementace modelu dusíkové bilance při vykazování emisí skleníkových plynů ze zemědělských půd podle metodiky IPCC 2006 (Conditions and consequences of implementing the nitrogen balance model when reporting greenhouse gas emissions from agricultural land according to the IPCC 2006 methodology). Výstup V 21 projektu Rozvoj metodik pro reporting emisí a propadů skleníkových plynů a jejich projekcí, včetně projekcí emisí tradičních polutantů (TK02010056), 21 stran. In Czech.

Bernauer B., Markvart M. (1999, 2015): Emissions of GHG in chemical industry in the Czech Republic in years 2008 - 2013, Report for CHMI, Prague (in Czech)

Bernauer B., Markvart M. (2015): Balance of greenhouse gas emissions in selected technologies of Chemical Industry of the Czech Republic, Report for CHMI, Prague (in Czech)

Bláha J. (1986): Nutrition and Feeding of Farm Animals, p. 63-64. *(*in Czech)

Boudewyn, P., Song, X., Magnussen, S., Gillis, M.D., 2007. Model-Based, volume-to-biomass conversion for forested and vegetated land in Canada, Forestry. https://doi.org/Information Report – BC-X-411

Brich et al. (2014): Methodology of calculation of traffic performance using database of Technical Control. CDV. Brno. (in Czech)

Büntgen, U., Urban, O., Krusic, P. J., Rybníček, M., Kolář, T., Kyncl, T., Ač, A., Koňasová, E., Čáslavský, J., Esper, J., Wagner, S., Saurer, M., Tegel, W., Dobrovolný, P., Cherubini, P., Reinig, F., and Trnka, M. (2021): Recent European drought extremes beyond Common Era background variability. Nature Geoscience, 14(4), 190–196.

CENIA (2021): Národní metodika výpočtů emisí z kategorie 5.B.2 Anaerobní digesce odpadů – TK02010056-V16. Česká informační agentura životního prostřed. Prague. (in Czech)

Čapla, L., Havlát, M. (2006): Calculating the Carbon Dioxide Emission Factor for Natural Gas/Výpočet emisního faktoru pro zemní plyn, Plyn, Vol. 86, p. 62-65 (in Czech)

Carmona, M.R., Armesto, J.J., Aravena, J.C. & Perez, C.A.: Coarse woody debris biomass in successional and primary temperate forests in Chiloe Island, Chile. Forest Ecology and Management 164: 265-275, 2002.

Černý, J. (2018): Analysis of automobile fuels – calculation of country specific H:C and O:C ratios. Tribochem. Prague. 20 p. (in Czech)

Černý, M., Pařez, J., Malík, Z. (1996): Growth and yield tables for the main tree species of the Czech Republic. App. 3, Ministry of Agriculture, Czech Forestry Act 84/1996 (in Czech)

Černý, M., Cienciala, E., Russ, R. Methodology for Carbon Stock Monitoring (Ver. 3.2) (2002):. Report for the Face Foundation. IFER - Institute of Forest Ecosystem Research, Jílove u Prahy, Czech Republic, 70 pp

Černý, M., Pařez, J., Zatloukal, V. (2006): Growing stock estimated by FNI CR 2001-2004. Lesnická práce, 9 (85): 10-12

Černý, M. (1990): Biomass of Picea abies (L.) Karst. in Midwestern Bohemia. Scand.J.For.Res. 5, 83-95

Černý, M.: Use of the growth models of main tree species of the Czech Republic in combination with the data of the Czech National Forest Inventory. In: Neuhöferová P (ed) The growth functions in forestry. Korf´s growth function and its use in forestry and world reputation. Kostelec nad Černými lesy, Prague 2005 (in Czech).

Černý, M. (2009): Development of a Dynamic Observation Network Providing Information on the State and changes In Terrestrial Ecosystems and Land Use. Annual Report to the project CzechTerra - – Adaptation of Landscape Carbon Reservoirs in the Context Of Global Change, 2007-2011, Funded by the Ministry of Environment of the Czech Republic (SP/2d1/93/07). Jilove u Prahy, (in Czech).

Černý J., Balík J., Švehla P., Kulhánek M. (2009). Využití odpadů z ČOV jako sdroje organických látek a živin. Sborník KAVR, ČZU Praha, 151 stran.

Černý, M., Cienciala, E., Zatloukal, V. (2015). Inventarizace krajiny CzechTerra. Co ukazuje opakované šetření z let 2008/2009 a 2014/2015? Lesnická práce 10 (2015), 14–16 (In Czech).

Čermák a kol. (2008): Conventional and ecological feed, USB AFC Ceske Budejovice, ISBN 978-80-739-141-3, p.135-138 (In Czech, tables)¨

CHMI (2012): Development of the system of monitoring, inventories and projections of greenhouse gas in the Czech Republic. Task 5 - Proposal to improve the current state of the of greenhouse gas inventories

including uncertainty analysis. Project for the State Environmental Fund of the Czech Republic, Prague, November 2012 (In Czech).

CHMI (2018): National Greenhouse Gas Inventory Report, NIR (reported inventory 2016), CHMI Praha, 2018 (http://unfccc.int/national_reports)

CHMI (2022): National Greenhouse Gas Inventory Report, NIR (reported inventory 2020), CHMI Praha, 2018 (http://unfccc.int/national_reports)

CHMI (2023): National Greenhouse Gas Inventory Report, NIR (reported inventory 2021), CHMI Praha, 2018 (http://unfccc.int/national_reports)

Cienciala E. and Melichar J. (2024): Forest carbon stock development following extreme drought-induced dieback of coniferous stands in Central Europe: a CBM-CFS3 model application. Carbon Balance and Management, 19(1), 1-20.

Cienciala and Melichar (2022): Update on the impact of the calamity on the carbon balance
(Chapter in the report for MA). Report of IFER - Institute of Forest Ecosystem Research for Ministry of Agriculture, pp. 13 (in Czech).

Cienciala E. and Palán Š. (2014). Metodický podklad pro kvantifikaci emisí oxidu uhličitého vyplývajících ze změn zásobníku „výrobky ze dřeva“ (Harvested Wood Products). Report prepared for the Ministry of Environment, 26 pp. (in Czech).

Cienciala E., Cerny M., Tatarinov F., Apltauer A. and Exnerova Z. (2006b): Biomass functions applicable to Scots pine. Trees 20: 483-495

Cienciala E., Henžlík V., Zatloukal V. (2006a): Assessment of carbon stock change in forests – adopting IPCC LULUCF Good Practice Guidance in the Czech Republic. Forestry Journal (Zvolen), 52(1-2): 17-28

Cienciala E., Cerny M., Tatarinov F., Apltauer A. and Exnerova Z. (2006b): Biomass functions applicable to Scots pine. Trees 20: 483-495, 2006b.

Cienciala E., Apltauer J., Exnerova Z. and Tatarinov F. (2008a): Biomass functions applicable to oak trees grown in Central-European forestry. Journal of Forest Science 54, 109-120

Cienciala, E., Exnerova, Z. & Schelhaas, M.J. (2008b): Development of forest carbon stock and wood production in the Czech Republic until 2060. Annals of Forest Science 65: 603

Cienciala E. and Palán Š. (2014). Metodický podklad pro kvantifikaci emisí oxidu uhličitého vyplývajících ze změn zásobníku „výrobky ze dřeva“ (Harvested Wood Products). Report prepared for the Ministry of Environment, 26 pp. (in Czech).

Cienciala, E., Černý, M., Russ, R., Zatloukal, V. (2015): Inventarizace krajiny CzechTerra. Vybrané výsledky šetření z let 2008/2009 a 2014/2015. Příloha IFER v Lesnické práci 10/2015, 12 pp. (In Czech)

Cienciala, E., Russ, R., Šantrůčková, H., Altman, J., Kopáček, J., Hůnová, I., Štěpánek, P., Oulehle, F., Tumajer, J., Ståhl, G. (2016). Discerning environmental factors affecting current tree growth in Central Europe. Sci. Total Environ. 573, 541–554. doi:10.1016/j.scitotenv.2016.08.115

Cienciala, E., Tumajer, J., Zatloukal, V., Beranová, J., Holá, Š., Hůnová, I., Russ, R. (2017): Recent spruce decline with biotic pathogen infestation as a result of interacting climate, deposition and soil variables. Eur. J. For. Res. 136. doi:10.1007/s10342-017-1032-9

ČSN EN ISO 6976 (2006): Natural Gas – Calculation of gross calorific value, net calorific value, density, relative density and Wobbe number, Czech Standards Institute

ČSN EN ISO 4256 (1996): Liquefied petroleum gases – Determination of gauge vapour pressure – LPG method, Czech Standards Institute

CzSO (2004): Production, use and disposal of waste in year 2003, Czech Statistical Office, Prague 2004 (in Czech)

CzSO (2013, 2014): Energy Questionnaire - IEA - Eurostat – UNECE (CZECH_COAL, CZECH_OIL, CZECH_GAS, CZECH_REN, Prague 2013

CzSO (2013): Development of overall and specific consumption of fuels and energy in relation to product, Prague 2013

CzSO (2013): Statistical Yearbook of the Czech Republic 2012, Czech Statistical Office, Prague 2013

CzSO (2014): Statistical Yearbook of the Czech Republic 2013, Czech Statistical Office, Prague 2014

CzSO (2015): Statistical Yearbook of the Czech Republic 2014, Czech Statistical Office, Prague 2015

CzSO (2016): Statistical Yearbook of the Czech Republic 2015, Czech Statistical Office, Prague 2016

CzSO (2017): Statistical Yearbook of the Czech Republic 2016, Czech Statistical Office, Prague 2016

CzSO (2018): Statistical Yearbook of the Czech Republic 2017, Czech Statistical Office, Prague 2017

CzSO (2019): Statistical Yearbook of the Czech Republic 2019, Czech Statistical Office, Prague 2019

CzSO (2020): Statistical Yearbook of the Czech Republic 2020, Czech Statistical Office, Prague 2020

CzSO (2020b): Cross border movements of goods – methodology, Czech Statistical Office, Prague 2020

CzSO (2023): Statistical Yearbook of the Czech Republic 2022, Czech Statistical Office, Prague 2023

Daemmgen, U. et al (2012): Data sets to assess methane emissions from untreated cattle and pig slurry and solid manure storage systems in the German and Austrian emission inventories. Agriculture and Forestry Research 1-2, 62, p. 1-20.

Dedina, M. et al. (2023): Calculation of typical specific emissions of greenhouse gases from the cultivation and processing of agricultural raw materials to determine the value of their emission factors. VÚZTv.v.i., 2023, 64 pp. ISBN: 978-80-7569-015-9.

Dohányos M., Zábranská J. (2000): Proposals for refining the calculation of methane emissions from municipal and industrial wastewater; Report for CHMI, Prague (in Czech)

Dolejš (1994): Emissions of greenhouse gases in agriculture in the Czech Republic, Report for PROINCOM Pardubice, Research Institute of Animal Production, Uhříněves, Prague (in Czech)

Dufek, J. (2005): Verification and evaluation of weight criteria of available data sources N_2O from transportation, Report CDV Brno for CHMI, Brno (in Czech)

Dufek, J., Huzlík, J., Adamec, V. (2006): Methodology for determination of emission stress of air pollutants in the Czech Republic, CDV, Brno (in Czech)

Dvořák F., Novák M. (2010): Significant structural changes in selected branches of chemical industry in the Czech Republic/Významné strukturální změny ve vybraných oborech chemického průmyslu na území ČR, VŠCHT Praha (in Czech)

EEA (2019): EMEP/EEA air pollutant emission inventory guidebook 2019. Luxembourg: Publications Office of the European Union, 2019. ISBN 978-92-9480-098-5.

EEA (2025): Approximated estimates for the primary and final consumption of energy, Prod-ID: DAT-186-en, 26.11.2025. URL: https://www.eea.europa.eu/en/datahub/datahubitem-view/d4943227-c1c2-430d-8cb3-bebc2dd8666c.

European Commission (2016): Urban Waste Water Treatment: dissemination, https://uwwtd.eu/Czech-Republic/uwwtps/compliance

Exnerová Z., Cienciala E. (2009).: Greenhouse gas inventory of agriculture in the Czech Republic, Plant, Soil and Environment 55, 311-319

Edwards, R., O´Connell,A.,Padella, M, Giuntoli, J., Koeble, R., Bulgheroni, C., Marelli, L., Lonza, L. (2019): Definition of input data to assess GHG default emissions form biofuels in EU legislation, Version 1d – 2019, EUR 28349 EN, Publication Office of the EU, Luxembourg, 2019. JRC Science for Policy Report JRC115952. ISBN 978-92-76-02907-6, doi:10.2760/69179, ISSN 1831-9424

ETS (2011): Database of ETS installations – preliminary version for CHMI

FAOSTAT (2005): Food Balance Sheets, Food and agriculture organization, URL: http://faostat.fao.org/faostat/, 2005

FAOSTAT (2020): Suite of Food Security Indicators. Food and Agriculture Organization of the United Nations, http://www.fao.org/faostat/en/#data/FS , 2020

FAOSTAT (2021): Suite of Food Security Indicators. Food and Agriculture Organization of the United Nations, http://www.fao.org/faostat/en/#data/FS , 2021

Federální shromáždění České a Slovenské Federativní Republiky (1991): Zákon č. 238/1991 Sb., zákon o odpadech (https://www.psp.cz/sqw/sbirka.sqw?cz=238&r=1991)

FMI (2007): National Forest Inventory in the Czech Republic 2001-2004. Introduction, Methods, Results. 224 pp. Forest Management Institute, Brandýs n. Labem, 2007.

Fott, P., Vácha D., Neužil V., Bláha J. (2009): Reference approach for estimation of CO_2 emissions from fossil fuels and its significance for GHG inventories in the Czech Republic. Ochrana ovzduší 21 (No.1), 2009, p. 26 - 30 (in Czech)

Fott, P. (1999): Carbon emission factors of coal and lignite: Analysis of Czech coal data and comparison with European values. Environmental Science and Policy (Elsevier), 2, 1999, p. 347 - 354

Gas and the Environment, 21th World Gas Conference, Nice 2000.

Green C., Tobin B., O'Shea M., Farrell E., Byrne K. (2006): Above- and belowground biomass measurements in an unthinned stand of Sitka spruce (Picea sitchensis (Bong) Carr.). European Journal of Forest Research DOI 10.107/s10342-005-0093-3

Haenel H-D, Rösemann C, Dämmgen U, Döring U, Wulf S, Eurich-Menden B, Freibauer A, Döhler H, Schreiner C, Osterburg B, Fuß R (2020): Calculations of gaseous and particulate emissions from German agriculture 1990–2018 Report on methods and data (RMD) Submission 2020. Braunschweig: Johann Heinrich von Thünen-Insti tut, 448 p, Thünen Rep 77, DOI:10.3220/REP158436370800

Harmelen, A. K. van, & Koch, W. W. R. (2002). CO_2 emission factors for fuels in the Netherlands. TNO-report.

Havránek M. (2001): Emissions of greenhouse gases from the waste sector in CR, Thesis. Institute of the Environment, Faculty of Sciences, Charles University and CHMI, Prague (in Czech)

Havránek M. (2007): Emissions of methane from solid waste disposal sites in the Czech Republic during 1990-2005: Application of first order decay model, Charles University Environment Center Working Paper WP2007/02, Prague

Hok P. (2009): Special material for the purpose of solving GHG inventory of CH_4 emissions that are produced in OKD mines in 2000-2008 period, OKD Inc., Ostrava (in Czech)

Hons P., Mudřík Z. (2003): Czech country-specific data for estimation of methane emissions from enteric fermentation of cattle. AGROBIO report for CHMI, Prague (in Czech)

Hruška, J., Cienciala, E. (2003): Long-term acidification and nutrient degradation of forest soils - limiting factors of forestry today. Czech Ministry of the Environment, Prague, 165 pp (2nd edition).

Hůla J. a kol. (2010): Dopad netradičních technologií zpracování půdy na půdní prostředí. Uplatněná certifikovaná metodika. Vydal VÚZT, ISBN 978-80-86884-53-0, 60 pages (in Czech)

Ingr I. (2003): Processing of agricultural products. Brno: MZLU, 249 s., ISBN 8071575208 (in Czech)

Internal study material of Faculty of Agronomy, South Bohemia University. Clover/Jeteloviny. www.zf.jcu.cz, *opr.zf.jcu.cz/docs/predmety/-eb721c77ad.doc (*in Czech)

IPCC (1995): IPCC Guidelines for National Greenhouse Gas Inventories, Vol. 1-3, IPCC/OECD/IEA, 1995

IPCC (1997): Revised 1996 IPCC Guidelines for National Greenhouse Gas Inventories, Vol. 1-3, IPCC 1997

IPCC (1997b) Revised 1996 IPCC Guidelines for National Greenhouse Gas Inventories: Reference Manual, Chapter 4, Agriculture, p.140, IPCC 1997

IPCC (2000): Good Practice Guidance and Uncertainty Management in National GHG Inventories, IPCC 2000

IPCC (2003): Good Practice Guidance for Land Use, Land Use Change and Forestry, IPCC 2003

IPCC (2006): 2006 IPCC Guidelines for National Greenhouse Gas Inventories, Vol. 1-5, IPCC 2006.

IPCC (2014): IPCC Fifth Assessment Report: Climate Change 2014, Geneva (www.ipcc.ch)

IPCC (2014a): 2013 Revised Supplementary Methods and Good Practice Guidance Arising from the Kyoto Protocol. Hiraishi, T., Krug, T., Tanabe, K., Srivastava, N., Baasansuren, J., Fukuda, M. and Troxler, T.G. (eds). Published: IPCC, Switzerland

IPCC (2019): 2019 Refinement to the 2006 IPCC Guidelines for National Greenhouse Gas Inventories, Vol. 5 Waste. Intergovernmental Panel on Climate Change (IPCC).

IPCC (2022): IPCC Sixth Assessment Report: Climate Change 2022: Impacts, Adaptation, and Vulnerability. Contribution of Working Group II to the Sixth Assessment Report of the Intergovernmental Panel on Climate Change [H.-O. Pörtner, D.C. Roberts, M. Tignor, E.S. Poloczanska, K. Mintenbeck, A. Alegría, M. Craig, S. Langsdorf, S. Löschke, V. Möller, A. Okem, B. Rama (eds.)]. Cambridge University Press. Cambridge University Press, Cambridge, UK and New York, NY, USA, 3056 pp., doi:10.1017/9781009325844.

IPR (2012): Integrated Pollution Register, http://www.irz.cz/

Jančík, F., Homolka, P. & Koukolová, V. (2010): Prediction of parameters characterizing rumen degradation of dry matter in grass silage (certified methodology). ISBN 978-80-7403-054-3 (in Czech)

Jandová, V. et al. (2021): Studie o vývoji dopravy z hlediska životního prostředí v České republice za rok 2020. Brno: CDV, 194 s.

Jedlička J., Dufek J., Adamec V. (2005): Greenhouse gas emission balance, (In: 20th International Air Protection Conference p. 96-99, ISBN 80-969365-2-2, High Tatras - Štrbské Pleso (Slovakia), November 23 – 25

Jedlička J., Adamec, V., Dostál, I., Dufek, J., Effenberger, K., Cholava, R., Jandová, V., Špička, I. (2009): Study of transport trends from environmental viewpoint in the Czech Republic 2008, Transport Research Centre (CDV), Brno

Jedlička J., Jandová, V., Dostál, I., Špička, L., Tichý, J. (2012): Study on transport trends from environmental viewpoint in the Czech Republic 2011, Transport Research Centre (CDV), Brno

Jelínek A, Plíva P., Vostoupal B. (1996): Determining VOC emissions from agricultural activities in the Czech Republic, Report for CHMI, Research Institute of Agricultural Technology, Prague (in Czech)

Kačmárová, Z., Pelikán, L. (2024): Aktualizace metodiky pro odhad skleníkových plynů a znečišťujících látek z lodní dopravy. Brno: CDV, 32 p.

Karbanová L. (2008): Emission Inventory of HFCs, PFCs and SF_6 in exported and imported products, Thesis. Faculty of the Environment, Jan Evangelista Purkyně University in Ústí nad Labem, Ústí nad Labem (in Czech)

Karjalainen, T., Pussinen, A., Liski, J., Nabuurs, G.-J., Erhard, M., Eggers, T., Sonntag, M. & Mohren, G.M.J. (2002): An approach towards an estimate of the impact of forest management and climate change on the European forest sector carbon budget: Germany as a case study. Forest Ecology and Management 162(1):87-103

Klír, J., Dostál, J., Hajzlerova, L. (2011): Production of Manure in deferent Systems of Animal housing. Proceedings of the International Conference „Soil, Plant and Food Interactions“. Mendel University in Brno, 6-8. September 2011, 8 pages.

Klír, J., Haberle, J., Růžek, P., Šimon, T., Svoboda, P. (2018): Postupy hospodaření pro efektivní využití dusíku a snížení jeho ztrát/Farming practices fro efficient use of nitrogene and reduction of its losses. Methodology, Certified by Ministry of Agriculture, Prague 2018. ISBN 978-80-7427-273-8.

Klír, J. (2019): Bilance organických látek v rostlinné výrobě/The balance of Organic Substances in the Crop production. Proceedings of the International Conference. Czech University o Life Sciences Prague, 15. November 2019, 8 pages.

Klír, J., Wollnerová, J., Dědina M., Beranová, J. (2021): Bilancování dusíku v zemědělství. Certifikovaná metodika pro praxi (v procesu certifikace). Výzkumný ústav rostlinné výroby, v.v.i., 51 s.

Kolář F, Havlíková M., Fott P. (2004): Recalculation of emission series of methane from enteric fermentation of cattle. Report of CHMI, Prague (in Czech)

Koukolová V., Homolka P. (2008): Rating digestible neutral-detergent fiber in the diet of cattle. Methodology, 29 p., ISBN 978-80-7403-016-1 (in Czech)

Koukolová, V., Koukol O., Homolka P., Jančík F. (2010): Rumen degradability of neutral detergent fiber and organic matter digestibility of red clover (certified methodology), 25 p, ISBN 978-80-7403-041-3 (in Czech)

Koukolová V., Homolka P., Kudrna V. (2010): The Scientific Committee on Animal Nutrition, Effect of structural carbohydrates on rumen fermentation, animal health and milk quality. Research Institute of Animal Production Prague, ISBN 978-80-7403-066-6 (in Czech)

Krtková E., Fott P., Neužil V. (2014): Carbon dioxide emissions from natural gas combustion – country specific emission factors for the Czech Republic, Greenhouse Gas Measurement & Management, DOI:10.1080/20430779.2014.905244

Kubát, J., Cerhanová, D., Nováková, J., & Lipavský J.: Total organic carbon and its composition in long-term field experiments in the Czech Republic. Archives of Agronomy and Soil Science: 52, 495-505, 2006.

Kučera M., Adolt R. (eds.) (2019). Národní inventarizace lesů v České republice – výsledky druhého cyklu 2011-2015. Forest Management Institute, Brandýs and Labem, ISBN 978-80-88184-23-2, 439 pp. (In Czech).

Kull, S.J., Rampley, G.J., Morken, S., Metsaranta, J., Neilson, E.T., Kurz, W.A., 2019. Operational-scale carbon budget model of the Canadian forest sector (CBM-CFS3): version 1.2, user's guide. Canadian Forest Service, Northern Forestry Centre, Canada, 348 pp.

Kurz, W.A.A., Dymond, C.C.C., White, T.M.M., Stinson, G., Shaw, C.H.H., Rampley, G.J.J., Smyth, C., Simpson, B.N.N., Neilson, E.T.T., Trofymow, J.A.A., Metsaranta, J., Apps, M.J.J., (2009). CBM-CFS3: A model of carbon-dynamics in forestry and land-use change implementing IPCC standards. Ecol. Modell. 220, 480–504. https://doi.org/10.1016/j.ecolmodel.2008.10.018

Kvapilík J., Růžička Z., Bucek P. a kol. (2018): Annual report - Yearbook of cattle breeding in the Czech Republic in 2017 (in Czech). Praha, pp 89.

Lehtonen A., Cienciala E., Tatarinov F. and Mäkipää, R. (2007): Uncertainty estimation of biomass expansion factors for Norway spruce in the Czech Republic. Annals of Forest Science 64(2): 133-140, 2007.

Lehtonen A., Makipaa R., Heikkinen J., Sievanen R. and Liski J. (2004): Biomass expansion factors (BEFs) for Scots pine, Norway spruce and birch according to stand age for boreal forests. Forest Ecology and Management 188: 211-224

Liski, J., Nissinen, A., Erhard, M. & Taskinen, O. (2003): Climatic effects on litter decomposition from arctic tundra to tropical rainforest. Global Change Biology 9(4): 575-584. doi:10.1046/j.1365-2486.2003.00605.x

Liski, J., Palosuo, T., Peltoniemi, M. & Sievänen, R. (2005): Carbon and decomposition model Yasso for forest soils. Ecological Modelling 189(1-2): 168-182. doi:10.1016/j.ecolmodel.2005.03.005.

MAA (2015): Yearbook 2014 - Organic Farming in the Czech Republic. Published by Ministry of Agricuture, Prague 2015, ISBN 978-80-7434-250-9. pp.72.

MA (2025): Report about forest and forestry conditions in the Czech Republic 2024 (Green Report), Ministry of Agriculture, ISBN 978-80-7434-829-7, Prague 2024, pp. 128. (In Czech).

Macků, J., Sirota, I., Homolová, K. (2007): Carbon balance in forest topsoil of the Czech Republic. VaV 640/18/03 Czech Carbo – Study of carbon in terrestrial ecosystems of the Czech Republic - interim project report. Czech Carbo VaV/640/18/03. Prague (in Czech)

Marek V. (2002): Development of Land Resources in the Czech Republic. Proceedings of the Czech National Soil Conference, Prague (in Czech)

Marklund, L.G., (1988). Biomass functions for pine, spruce and birch in Sweden. Report 45, Dept. Forest Survey, Swedish University of Agricultural Sciences, Umea, pp. 1 73 (In Swedish)

Markvart M., Bernauer B. (2006): Dominant sources of GHG in chemical industry in the Czech Republic in years 2003 - 2005, Report for CHMI, Prague (in Czech)

Markvart M., Bernauer B. (2000): Emission trends in nitrous oxide from industrial processes in the nineties, Report for CHMI, Prague (in Czech)

Markvart M., Bernauer B. (2003): Nitrogen industry as a source of nitrous oxide emissions in the Czech Republic, Report for CHMI, Prague (in Czech)

Markvart M., Bernauer B. (2004): Emissions of nitrous oxide in the Czech Republic in years 2000 - 2003, Report for CHMI, Prague (in Czech)

Markvart M., Bernauer B. (2008): Emissions of GHG in chemical industry in the Czech Republic in years 2005 - 2007, Report for CHMI, Prague (in Czech)

Markvart M., Bernauer B. (2009): Emissions of GHG in chemical industry in the Czech Republic in years 2006 - 2008, Report for CHMI, Prague (in Czech)

Markvart M., Bernauer B. (2010): Emissions of GHG in chemical industry in the Czech Republic in years 2007 - 2009, Report for CHMI, Prague (in Czech)

Markvart M., Bernauer B. (2011): Emissions of GHG in chemical industry in the Czech Republic in years 2008 - 2010, Report for CHMI, Prague 2011 (in Czech)

Markvart M., Bernauer B. (2012): Emissions of GHG in chemical industry in the Czech Republic in years 2008 - 2011, Report for CHMI, Prague (in Czech)

Markvart M., Bernauer B. (2013): Emissions of GHG in chemical industry in the Czech Republic in years 2008 - 2012, Report for CHMI, Prague (in Czech)

Markvart M., Bernauer B. (2007): Emissions of N_2O and CO_2 in chemical industry in the Czech Republic in years 2004 - 2006, Report for CHMI, Prague (in Czech)

Marková, I., Janouš, D., Pavelka, M., Macků, J., Havránková, K., Rejšek, K., MV, M., 2016. Potential changes in Czech forest soil carbon stocks under different climate change scenarios. J. For. Sci. 62, 537–544.

Máslo, J., Adolt, R., Kučera, M., Kohn, I. (2023). 3. Změna zásoby dříví. Národní inventarizace lesů v České republice. Výsledky třetího cyklu. ÚHÚL, Brandýs n. Labem, 12 pp. (in Czech)

Menšík, L., Hlisnikovský, L. & Kunzová, E. (2019): The State of the Soil Organic Matter and Nutrients in the Long-Term Field Experiments with Application of Organic and Mineral Fertilizers in Different Soil-Climate Conditions in the View of Expecting Climate Change. In: Organic Fertilizers - History, Production and Applications (Eds Larramendy, M. & Soloneski, S.), p. 23-42.

Meyer, H., Kampues, J., Schneider, D., Leibetseder, J., Coenen, M., Iben, Ch., Kienzle, E., Manner, K., Wolf, P., Zentek, J.; Supplemente zu Vorlesungen und Ubungen in der Tierernahrung, Verlag M. and H. Schaper Alfeld-Hannover, 9. uberarbeitete Auflage, 1999, s. 322. ISBN: 3-7944-0189-1.

MA (2022): Situační zpráva o stavu zemědělství v roce 2022. Ministerstvo zemědělství, Praha 1922. 164 stran. Available online: https://eagri.cz/public/web/file/704653/Zemedelstvi_2021_web.pdf

MoE (1997): Second National Communication of the Czech Republic on the UN Framework Convention on Climate Change, MoE CR, Prague

MoE (2006): Czech Republic's Initial report under the Kyoto Protocol. Ministry of Environment of the Czech Republic, Prague

MoE (2009): Fifth National Communication of the Czech Republic on the UNFCCC, MoE CR Prague 2009 (www.mzp.cz)

MoE (2010): Statistical Environmental Yearbooks of the Czech Republic. Ministry of Environment of the Czech Republic, Prague 1995-2009

Mining Yearbooks, 1994 - 2015 (in Czech)

MIT (2008): RES in the Czech Republic 2008, Ministry of industry and trade, October 2009

MIT (2009): Statistics of waste energy use during 1905-2009: results of statistical survey, Ministry of industry and trade, March 2010

MIT (2021): Obnovitelné zdroje energie 2021, https://www.mpo.cz/assets/cz/energetika/statistika/obnovitelne-zdroje-energie/2022/11/Obnovitelne-zdroje-energie-2021.pdf.

MONTANEX (2008): Czech Mining Office and The Employers' Association of Mining and Oil Industries, Mining Yearbooks, Montanex Inc., 2005-2007

Mudřík Z., Hons, P. (2004): Vstupní zootechnické a provozní parametry pro zpřesnění inventarizace skleníkových plynů u hospodářských zvířat v ČR za období 19990-2003 – dotazník. CHMI, internal study, Praha, 20 pp.

Mudřík Z., Havránek F. (2006): Czech country-specific data for estimation of methane emissions from enteric fermentation of cattle- updated data (pers.communication, October, 2006)

MUŽÍK, O., KÁRA, J. Rozvoj bioplynových technologií v podmínkách ČR. [Development of biogas technologies in conditions of the Czech Republic]. *Farmář*, 2009, roč. 15, č. 11, s. 15-29

Nesňal, J. et al (2018): Možnosti diverzifikace zemědělské výroby do výroby energie z OZE a příprava aktualizace Akčního plánu pro biomasu. Zpráva TÚ 64, UZEI, 2018

Pelikán, L., Brich, M. (2017) Methodology for collecting and processing activity data on vehicle fleet in Czech Republic. DV. Brno. 73 p. (in Czech)

Pelikán, L., Brich, M. (2018): Introducing of COPERT 5 for calculating emissions from road transport in Czech Republic. CDV. Brno. 73 p. (in Czech)

Pelikán, L. et al. (2021): Pracovní postup výpočtu emisí z železniční dopravy. Brno: CDV, 47 p.

Perůtka, J. et al. (2020): Snížení emisí CO_2 vlivem modernizace vozového parku. Brno: CDV, 72 s.

Petrikovič P., Sommer A., Čerešňáková Z., Svetlanská M., Chrenková M., Chrastinová L., Poláčiková M., Bencová E., Dolešová P. (2000): The nutritive value of feeds. Research Institute of Animal Production Nitra: ISBN 80-88872-12-X, 320 s. (in Czech)

Petrikovič P., Sommer A. (2002): Nutrient requirements for beef cattle. Research Institute of Animal Production Nitra: ISBN 80-88872-21-9, 62 p. (in Czech)

Pilli, R., Grassi, G., Kurz, W.A., Smyth, C.E., Blujdea, V., 2013. Application of the CBM-CFS3 model to estimate Italy's forest carbon budget, 1995-2020. Ecol. Modell. 266, 144–171. https://doi.org/10.1016/j.ecolmodel.2013.07.007

PILLI, Roberto, Stephen KULL, Viorel BLUJDEA a Giacomo GRASSI, 2017. The EU Archive Index Database customised for the Carbon Budget Model (CBM-CFS3) [online]. [vid. 2019-12-16]. http://data.europa.eu/89h/jrc-cbm-eu-aidb

PILLI, Roberto, Stephen KULL, Blujdea VIOREL a Giacomo GRASSI, 2018. The Carbon Budget Model of the Canadian Forest Sector (CBM-CFS3): customization of the Archive Index Database for European Union countries. Annals of Forest Science [online]. 75. doi:10.1007/s13595-018-0743-5

Poustka J. (2007): The analysis of milk and milk products. Presentation on Institute of Chemical Technology (ICT) (in Czech)

Pozdíšek J., Ponížil A. (2010): Possibilities of using LOS for feeding ruminants, Presentation of Research Institute of cattle breeding Rapotín in Jihlava, 9.3.2010 (in Czech)

Prokop P. (2011): CO_2 emission factors and emissions from underground coal mining in the Ostrava-Karvina area, Technical University of Ostrava, Ostrava

Prokop P. (2015): Methodology for CO_2 and CH_4 emission estimation from abandoned mines, Ostrava 2015 (in Czech)

Reifová, B. (2012): Physical properties of the cow ´s milk. Bachelor thesis, Mendel University, Brno, 2012, 46 pp.

Repola, J., (2008): Biomass equations for birch in Finland. Silva Fenn. 42, 605–624. https://doi.org/10.14214/sf.236

Řeháček, V. (2017): Anthropogenic emissions of SF_6, CFCs and PFCs in the Czech Republic in 2013, Report for CHMI, Prague 2015 (in Czech)

Řeháček V., Michálek L. (2005): Information on emissions of greenhouse gases containing fluorine in CR in 2004, Report for CHMI, Prague (in Czech)

Saarikivi, R. (2023): Quality manual for the Czech greenhouse gas inventory. Version 1. Czech hydrometeorological institute, TD 000156.

Sálusová D., Kovář J. and Zavázal P. (2006): Czech agriculture by statistic view. CzSO Prague (in Czech)

Schieman, R., Nehring, K., Hoffman, L., Jentsch, W. & Chudy, A. (1971); Energetische Futterbewertung und Energienormen. VEB Deutscher Landwirtschafts verlag, Berlin, s. 75.

Schwappach A., Neumann J. (1923): Ertrags tafeln der Wichtigeren Holzarten, Neudamm 1923.

SDA (2021): Car Fleet Overview Dec 2021 [Online]. Available: https://portal.sda-cia.cz/stat.php?v#rok=2021&mesic=12&kat=stav&vyb=&upr=&obd=m&jine=false&lang=EN&str=vpp.

Sommer, A., Čerešňáková, Z., Frydrych, Z., Králík, O., Králíková, Z., Krása, A., Pajtáš, M., Petrikovič, P., Pozdíšek, J., Šimek, M., Třináctý, J., Vencl, B., Zeman, L. (1994): Nutrient requirements tables and nutritive value of feeds for ruminants. CAAS – commission nutrition of farm animals, Pohořelice, 196 p. ISBN 80-901598-1-8 (in Czech)

Šefrna, L., Janderková, J. (2007): Organic carbon content in soil associations of the map 1:500000, Agricultural soils. VaV 640/18/03 Czech Carbo – Study of carbon in terrestrial ecosystems of the Czech Republic – interim project report. Czech Carbo VaV/640/18/03. Prague (in Czech)

Šimon, T., Cerhanová, D., & Mikanová, O. (2011): The effect of site characteristics and farming practices on soil organic matter in long-term field experiments in the Czech Republic. Archives of Agronomy and Soil Science: 57, 693-704, 2011.

Straka, F. (2001): Calculation of emissions from landfills in CR, Institute for Research and Use of Fuels, Prague (in Czech)

Supply of Basic Final Refinery Products in the CR, Czech Statistical Office, Prague 1995 – 2005

Svoboda, P.(2016): The risk of contamination of ground waters by nitrtes form field deposits of manure (in Czech).Úroda 12/2016 Vědecká příloha časopisu, VÚRV Praha, pp 4.

Takla G., Nováček P. (1997): Emissions of mine gases in the Ostrava-Karviná coal-mining area and potential for minimization, Proceedings from the conference Emissions of Natural Gas – economic and environmental impacts, Czech Gas Association (in Czech)

Takla, G. (2002): Methane emissions from deep coal mining, national conference “Natural Gas Emissions – New Clean Air Act and international reliability of the methane emission inventory in the Czech Republic”, Czech Gas Association (in Czech)

Third National Communication of the Czech Republic on the UN Framework Convention on Climate Change, MoE CR, Prague 2001

Thomas, S.C., Martin, A.R., 2012. Carbon content of tree tissues: A synthesis. Forests 3, 332–352. https://doi.org/10.3390/f3020332

Tománková, O., Homolka, P., (2010): Prediction of intestinal digestibility of crude protein escaped degradation in the rumen of ruminants combined method (certified methodology). ISBN 978-80-7403-063-5 (in Czech)

Trnka, M., Brázdil, R., Možný, M., Štěpánek, P., Dobrovolný, P., Zahradníček, P., Balek, J., Semerádová, D., Dubrovský, M., Hlavinka, P., Eitzinger, J., Wardlow, B., Svoboda, M., Hayes, M., Žalud, Z. (2015). Soil moisture trends in the Czech Republic between 1961 and 2012. Int. J. Climatol. 35, 3733–3747. Doi:10.1002/joc.4242

Třináctý J. (2010): Animal nutrition and its impact on the performance and health of the animal (Research Institute of cattle breeding Rapotín). Conference on the "Application of new knowledge in the field of nutrition for livestock to common farming practice" within the Rural Development Programme of the Czech Republic (in Czech)

Turek B. (2000). Milk in human nutrition. National Institute of Public Health (NIPH) (in Czech)

UN ECE (1999): EMEP/CORINAIR Atmospheric Emission Inventory Guidebook, UN ECE – EMEP 1999

UNFCCC (2006): Updated UNFCCC reporting guidelines on annual inventories following incorporation of the provisions of decision 14/CP.11, FCCC/SBSTA/2006/9 (www.unfccc.int)

UNFCCC (2009): Annotated outline of the National Inventory Report including reporting elements under the Kyoto Protocol, UNFCCC, Bonn, 2009 (www.unfccc.int)

UNFCCC (2019): EMEP/EEA air pollutant emission inventory guidebook 2016. European Environment Agency. Luxemburg.

Vácha, D. (2004): Methodology for CO_2 emissions estimates for cement production and CO_2 emissions and removals form lime production and use, CHMI Report (in Czech)

Vacková. L.; Vácha, D. (2008): F-gases emissions form import and export of products; Air Protection 2008; Tatry – Štrbské pleso (in Czech)

Vonderach, C., Kändler, G., Dormann, C.F. (2018): Consistent set of additive biomass functions for eight tree species in Germany fit by nonlinear seemingly unrelated regression. Ann. For. Sci. 75, 49. https://doi.org/10.1007/s13595-018-0728-4

Vopravil, J & Khel T. (2020): Preparation and provision of a reference polygonal layer of the organic soil carbon stock in absolute units (t / ha, or kg / m2) on agricultural soils in the Czech Republic to a reference layer of 0–30 cm for the needs of the inventory of greenhouse gas emissions of the LULUCF sector. Expert Report, Research Institute for Soil and Water Conservation (In Czech).

Vopravil, J., Khel, T., Průková, D., Formánek, P., Veselý, A., & Duffek, P. (2024). Potenciál trvalých travních porostů (TTP) pro sekvestraci uhlíku. Výzkumný ústav monitoringu a ochrany půdy, v.v.i., Praha. MZe, smlouva o dílo č./DMS: 461-2024-14132 (In Czech).

Veselá A., Miklová B., Krtková E., Neužil V. (2020): Calculation of uncertainties in greenhouse gas inventories in the Energy sector, Meteorologické zprávy 73, 161-166 (in Czech)

Vyhláška Ministerstva životního prostředí o podrobnostech nakládání s odpady. 383/2001 Sb. (CZ). Available at: https://www.psp.cz/sqw/sbirka.sqw?cz=383&r=2001.

Vyhláška o podmínkách ukládání odpadů na skládky a jejich využívání na povrchu terénu a změně vyhlášky č. 383/2001 Sb., o podrobnostech nakládání s odpady 294/2005 Sb. (CZ). Available at: (https://www.psp.cz/sqw/sbirka.sqw?cz=294&r=2005)

Vyhláška o podrobnostech nakládání s odpady 273/2021 Sb. (CZ) Available at: https://www.psp.cz/sqw/sbirka.sqw?cz=273&r=2021.

Wikkerink J.B.W. (2006): Improvement in the determination of methane emissions from gas distribution in the Netherlands, 23rd World Gas Conference, Amsterdam 2006

Willey (2005): Ullmans's encyclopedia of Industrial Chemistry, Release 2005, 7th Edition, John Willey 2005

Wirth C., Schumacher J. and Schulze E.-D. (2004): Generic biomass functions for Norway spruce in Central Europe – a-meta-analysis approach toward prediction and uncertainty estimation. Tree Physiology 24, 121-139

Wutzler T., Wirth C. and Schumacher J. (2008): Generic biomass functions for Common beech (Fagus sylvatica L.) in Central Europe – predictions and components of uncertainty, Canadian Journal of Forest Research 38(6): 1661–1675

Zábranská J. (2004): Proposals for update of the calculation of methane emissions from municipal and industrial wastewater in 2002 – 2003; University of Chemical Technology, Report for CUEC, Prague (in Czech)

Zákon o odpadech 238/1991 Sb. (ČSFR). Available at: https://www.psp.cz/sqw/sbirka.sqw?cz=238&r=1991.

Zákon o odpadech 541/2020 Sb. (CZ). Available at: https://www.psp.cz/sqw/sbirka.sqw?cz=541&r=2020.

Zákon o odpadech a o změně některých dalších zákonů 185/2001 Sb. (CZ). Available at: https://www.psp.cz/sqw/sbirka.sqw?cz=185&r=2001.

Zanat, J.; Dorda, P.; Grezl, T. (1997): Conference Emissions of Natural Gas, economic and environmental issues, Czech Association of Gas, Prague

Zee, T. van der et al. (2019): Methodology for estimating emissions from agriculture in the Netherlands. Calculations of CH_4, NH3, N_2O, Nox, NMVOC, PM10, PM2.5 and CO_2 with the National Emission Model for Agriculture (NEMA) – update 2019. Wageningen, The Statutory Research Tasks Unit for Nature and the Environment. Wot-technical report 148, 215 p.; 6 Figs; 45 Tabs; 108 Refs; 12 Annexes

Zeman, L. (2006): Výživa a krmení hospodářských zvířat. Profi Press, Praha 360 stran, in Czech. ISBN: 80-86726-17-7.

Zeman, L., Beranová, J. (2021): Aktualizace výpočtu emisí metanu z enterické fermentace u skotu. Studie zpracovaná pro Ministerstvo zemědělství , Praha, 62 stran, in Czech.

Web pages (online status checked in March 2022)

http://www.suas.cz/

http://www.dpb.cz/

http://www.svcement.cz/

http://www.svvapno.cz/

http://www.eagri.cz

https://www.czso.cz

Abbreviations

AACLC	Aggregate areas of cadastral land categories
A/C	Air-conditioning
AD	Activity data
APL	Association of Industrial Distilleries (Asociace průmyslových lihovarů)
ARR	Annual Review Report
AVNH	Association of Coatings Producers (Asociace výrobců nátěrových hmot)
AWMS	Animal Waste Management System
BOD	Biochemical Oxygen Demand
CARC	Czech Agrifood Research Center
CBM	Carbon Budget Model of the Canadian Forest Sector (CBM-CFS3)
CCA	Czech Cement Association
CCR	Czech Car Registry
CDV	Transport Research Centre (Centrum dopravního výzkumu)
CENIA	Czech Environmental Information Agency
CHMI	Czech Hydrometeorological Institute
CLA	Czech Lime Association
CLRTAP	Convention on Long-Range Transboundary Air Pollution
CNG	Compressed Natural Gas
COD	Chemical Oxygen Demand
COP	Conference of Parties
COPERT	Computer Programme to calculate Emissions from Road Transport
COSMC	Czech Office for Surveying, Mapping and Cadastre
CRT	Common Reporting Format
CS	Country specific
CUEC	Charles University Environment Center
CULS	Czech University of Life Sciences
CzechTerra	Czech Landscape Inventory
CzSO	Czech Statistical Office
ČPS	Czech Gas Association (Český plynárenský svaz)
ČD	Czech Railways
DOC	Degradable Organic Carbon
DOM	Dead Organic Matter
EEA	European Environmental Agency
EF	Emission Factor
EIG	Emission Inventory Guidebook
EMEP/EEA	European Monitoring and Evaluation Programme/Environmetal Protection Agency
ERT	Expert Review Team
ETS	Emission Trading Scheme
ETBE	Ethyl Tertiary Butyl Ether
FAO	Food and Agriculture Organization
FAME	Fatty Acid Methyl Esters
FMP	Forest Management Plans
FOD (model)	First Order Decay (model)
GCRI	Global Change Research Institute of the Czech Academy of Sciences
GDP	Gross Domectic Product
GHG	Greenhouse Gas

HDV	Heavy Duty Vehicle
HWP	Harwested Wood Products
CHMI	Czech Hydrometeorological institute
IAEI	Institute of Agriculture Economics and Information
IEA	International Energy Agency
IEF	Implied emission factor
IFER	Institute of Forest Ecosystem Research (Ústav pro výzkum lesních ekosystémů)
IFR	Instrument flight rules
IGU	International Gas Union
IIR	Czech Informative Inventory Report
IPCC	Intergovernmental Panel of Climate Change
IPR	Integrated Pollution Register
ISOH/VISOH	Information system of waste management/Public information system of waste management
ISPOP	Integrated system of mandatory reporting (Integrovaný systém plnění ohlašovacích povinností)
IW	Industrial Waste
IWW	Industrial Wastewater
KC	Key Category
KP LULUCF	LULUCF activities under Kyoto Protocol
LA	Level Assessment
LDV	Light Duty Vehicle
LFG	Landfill Gas
LKD	Lime Kiln Dust
LPG	Liquid Petroleum Gas
LPIS	Land Parcel Identification System,
LTO	Landing/Taking-off
LULUCF	Land Use, Land-Use Change and Forestry
MA	Ministry of Agriculture
MCF	Methane Conversion Factor
MIT	Ministry of Industry and Trade
MoE	Ministry of Environment
MSW	Municipal Solid Waste
NACE	Nomenclature Classification of Economic Activities
NCV	Net Calorific Value
NEC	National Emission Ceilings
NFI	National Forest Inventory
NID	National Inventory Document
NIS	National Inventory System (National system under Kyoto protocol, Art. 5)
NLI	Czech Forestry Institute
NMVOC	Non-Methane Volatile Organic Compound
OECD	Organisation for Economic Co-operation and Development
OKD, a.s.	Ostrava – Karvina Mines (Ostravsko karvinské doly, a.s.)
OMD	Organic Matter Digestibility
OTE	Electricity Market Operator (Operátor trhu s elektřinou, a.s.)
PC	Passenger Car
QA/QC	Quality Assurance/Quality Control
R	Recovered methane
RA	Reference Approach
REZZO	Register of Emissions and Sources of Air Pollution (Registr emisí a zdrojů znečišťování ovzduší)
SA	Sectoral Approach

SCR	Selective catalytic reduction
SDA	Car Importers Association (Svaz dovozců automobilů)
STC	Technical control stations
SÚKL	State Institute for Drug Control (Státní ústav pro kontrolu léčiv)
SWDS	Solid Waste Disposal Sites
TA	Trend Assessment
TACR	Technological Agency of the Czech Republic
THC	Total Hydrocarbons
TOW	Total Organic Waste
TSC	Database of Technical Control Stations
ÚCL	Civil Aviation Authority
UNECE	United Nations Economic Commission for Europe
UNFCCC	United Nation Framework Convention on Climate Change
ÚVVP	Institute for Research and Use of Fuels (Ústav pro výzkum a využití paliv)
VFR	Visual flight rules
VŠCHT	University of Chemistry and Technology Prague (Vysoká škola chemicko technologická)
WA	Weighted average
WWTP	Wastewater Treatment Plant

List of figures

FIG. ES 1 SOURCES AND SINKS OF GREENHOUSE GASES IN 1990 (KT CO_2 EQ.) 11
FIG. ES 2 SOURCES AND SINKS OF GREENHOUSE GASES IN 2024 (KT CO_2 EQ.) 14

FIG. 1-1 INSTITUTIONAL ARRANGEMENTS OF NATIONAL INVENTORY SYSTEM IN THE CZECH REPUBLIC 21
FIG. 1-2 TIMESCHEDULE OF SUBMISSIONS AND QA/QC PRODEDURES 25
FIG. 2-1 TOTAL TREND OF GHG EMISSIONS, [KT CO_2 EQ.] 48
FIG. 2-2 TREND IN CO_2, CH_4 AND N_2O EMISSIONS 1990–2024 IN INDEX FORM (BASE YEAR = 100%) AND TREND IN HFCS, PFCS (1995–2024) AND SF_6 (1990–2024) ACTUAL EMISSIONS IN INDEX FORM (BASE YEAR = 100%) 50
FIG. 2-3 PERCENTUAL SHARE OF GHGS (Y-AXIS BEGINS AT 70% - PART OF CO_2 SHARE IS HIDDEN) 50
FIG. 2-4 EMISSION TRENDS IN 1990–2024 BY CATEGORIES IN INDEX FORM (BASE YEAR = 100) 52
FIG. 2-5 TRENDS IN ENERGY BY CATEGORIES 1990–2024 (MT CO_2 EQ.) 54
FIG. 2-6 TRENDS IN IPPU BY CATEGORIES 1990–2024 (MT CO_2 EQ.) 54
FIG. 2-7 TRENDS IN AGRICULTURE BY CATEGORIES 1990–2024 (MT CO_2 EQ.) 55
FIG. 2-8 TRENDS IN LULUCF BY SEPARATE SOURCE AND SINK CATEGORIES 1990–2024 (MT CO_2 EQ.) 56
FIG. 2-9 TRENDS IN WASTE BY CATEGORIES 1990–2024 (MT CO_2 EQ.) 57
FIG. 3-1 TREND TOTAL CO_2 (SECTORAL APPROACH) IN 1.A AND TREND OF CO_2 AND CH_4 FROM 1.B SECTOR IN PERIOD 1990 – 2024 ..60
FIG. 3-2 SHARE AND DEVELOPMENT OF CO_2 EMISSIONS FROM 1990–2024 IN INDIVIDUAL SUB-SECTORS; SHARE OF CO_2 EMISSIONS IN INDIVIDUAL SUBSECTORS IN 2024 [KT] 61
FIG. 3-3 CO_2 AND CH_4 TREND FROM THE SECTOR FUGITIVE EMISSIONS FROM SOLID FUELS AND FROM THE SECTOR FUGITIVE EMISSIONS FROM OIL AND NATURAL GAS. 62
FIG. 3-4 DEVELOPMENT OF CO_2 EMISSIONS IN 1.A.1.A CATEGORY 77
FIG. 3-5 TREND OF GHG EMISSIONS FROM WASTE INCINERATION FOR ENERGY PURPOSES 79
FIG. 3-6 THE RATIO BETWEEN THE TOTAL CONSUMPTION OF FUELS FROM THE HEAT SOURCES IN THE CATEGORY 1.A.1.A AND OVERALL ENERGY PRODUCTION 80
FIG. 3-7 DEVELOPMENT OF CO_2 EMISSIONS IN 1.A.1.B CATEGORY 82
FIG. 3-8 COMPARISON OF FUEL CONSUMPTION IN THE SECTOR 1.A.1.B AND AMOUNT OF CRUDE OIL PROCESSED 83
FIG. 3-9 DEVELOPMENT OF CO_2 EMISSIONS IN 1.A.1.C.I CATEGORY 85
FIG. 3-10 COMPARISON OF LIGNITE CONSUMPTION FOR STEAM PRODUCTION AND GASIFICATION 87
FIG. 3-11 DEVELOPMENT OF CO_2 EMISSIONS IN SOURCE CATEGORY 1.A.2.A 89
FIG. 3-12 THE TREND IN THE MANUFACTURE OF AGGLOMERATES OF IRON ORE AND IRON, IN COMPARISON WITH THE DEVELOPMENT OF FUEL CONSUMPTION IN THE SECTOR 1.A.2.A 90
FIG. 3-13 DEVELOPMENT OF CO_2 EMISSIONS IN SOURCE CATEGORY 1.A.2.B 92
FIG. 3-14 DEVELOPMENT OF CO_2 EMISSIONS IN SOURCE CATEGORY 1.A.2.C 94
FIG. 3-15 DEVELOPMENT OF CO_2 EMISSIONS IN SOURCE CATEGORY 1.A.2.D 97
FIG. 3-16 DEVELOPMENT OF CO_2 EMISSIONS FROM FOSSIL FUELS COMBUSTION IN SOURCE CATEGORY 1.A.2.E 99
FIG. 3-17 PRODUCTION OF THE MOST IMPORTANT MINERAL PRODUCTS 102
FIG. 3-18 DEVELOPMENT OF CO_2 EMISSIONS IN SOURCE CATEGORY 1.A.2.F 102
FIG. 3-19 TRENDS IN PRODUCTION OF MINERAL PRODUCTS COMPARED WITH THE DEVELOPMENT OF FUEL CONSUMPTION IN THE SECTOR 1.A.2.F 104
FIG. 3-20 DEVELOPMENT OF CO_2 EMISSIONS IN SOURCE CATEGORY 1.A.2.G 106
FIG. 3-21 ANNUAL FUEL CONSUMPTION BY MODE OF TRANSPORT 108
FIG. 3-22 ANNUAL JET KEROSENE CONSUMPTION IN AVIATION ACCORDING TO FLIGHT MODE 111
FIG. 3-23 EMISSIONS OF CO_2, CH_4 AND N_2O FROM AVIATION 112
FIG. 3-24 TREND OF FUEL CONSUMPTION ACCORDING TO VEHICLE CATEGORIES 114
FIG. 3-25 EMISSIONS OF CO_2 FROM ROAD TRANSPORT ACCORDING TO SUBCATEGORIES 117
FIG. 3-26 COMPARISON OF ENERGY CONSUMPTION AND CO_2 EMISSIONS FROM ROAD TRANSPORT 118
FIG. 3-27 EMISSIONS OF CH_4 FROM ROAD TRANSPORT ACCORDING TO SUBCATEGORIES 118
FIG. 3-28 COMPARISON OF ENERGY CONSUMPTION AND CH_4 EMISSIONS FROM ROAD TRANSPORT 119
FIG. 3-29 EMISSIONS OF N_2O FROM ROAD TRANSPORT ACCORDING TO SUBCATEGORIES 119
FIG. 3-30 COMPARISON OF ENERGY CONSUMPTION AND N_2O EMISSIONS FROM ROAD TRANSPORT 120
FIG. 3-31 TREND IN EMISSIONS OF CO_2, CH_4 AND N_2O FROM RAILWAYS 122
FIG. 3-32 TREND IN EMISSIONS OF CO_2, CH_4 AND N_2O FROM DOMESTIC NAVIGATION 124
FIG. 3-33 DEVELOPMENT OF CO_2 EMISSIONS IN SOURCE CATEGORY 1.A.4.A 128

FIG. 3-34 DEVELOPMENT OF CO_2 EMISSIONS IN SOURCE CATEGORY 1.A.4.B 131
FIG. 3-35 DEVELOPMENT OF CO_2 EMISSIONS IN SOURCE CATEGORY 1.A.4.C 133
FIG. 3-36 DEVELOPMENT OF CO_2 EMISSIONS IN SOURCE CATEGORY 1.A.4.C.I 133
FIG. 3-37 DEVELOPMENT OF CO_2 EMISSIONS IN SOURCE CATEGORY 1.A.4.C.II 134
FIG. 3-38 DEVELOPMENT OF CO_2 EMISSIONS IN SOURCE CATEGORY 1.A.5.B. 138
FIG. 3-39 GHG EMISSIONS TRENDS FROM FUGITIVE EMISSIONS FROM FUELS [KT/YEAR] 141
FIG. 3-40 THE SHARE OF INDIVIDUAL GHG EMISSIONS FROM THE TOTAL EMISSIONS, EXPRESSED AS CO_2 EQ. (1.B.) 142
FIG. 3-41 THE TREND OF GHG EMISSIONS AND THE RELATIONSHIP BETWEEN EMISSIONS OF CO_2 AND CH_4 (1.B.1) 144
FIG. 3-42 THE RATIO OF METHANE EMISSIONS FROM UNDERGROUND MINES AND SURFACE MINES AND THE CORRESPONDING DEVELOPMENT OF MINING OF HARD COAL AND LIGNITE (1.B.1) 144
FIG. 3-44 THE TREND OF GHG EMISSIONS AND THE RELATIONSHIP BETWEEN CO_2 AND CH_4 EMISSIONS (1.B.2) 159
FIG. 3-44B THE RATIO OF METHANE EMISSIONS FROM SUBSECTOR OIL (1.B.2.A) AND NATURAL GAS (1.B.2.B) 159
FIG. 3-45 CRUDE OIL PRODUCTION AND IMPORT IN THE CZ IN 1990–2024 160
FIG. 3-46 CRUDE OIL PRODUCTION IN THE CZ IN 1990–2024 160
FIG. 3-47 NATURAL GAS PRODUCTION AND IMPORT IN THE CZ IN 1990–2024 161
FIG. 3-48 NATURAL GAS PRODUCTION IN THE AREA OF CZ IN 1990 – 2024 162
FIG. 3-49 CORRELATION BETWEEN EF FOR NMVOC AND CH_4 EMISSIONS 166
FIG. 4-1 TREND OF EMISSIONS FROM IPPU [KT CO_2 EQ.] 174
FIG. 4-2 EMISSIONS FROM PRINCIPAL SUBCATEGORIES OF IPPU [KT CO_2 EQ.] 174
FIG. 4-3 TREND OF EMISSIONS FROM 2.A MINERAL INDUSTRY AND SHARE OF SPECIFIC SUBCATEGORIES [KT CO_2] 175
FIG. 4-4 FINAL EMISSION VALUES [KT CO_2] WITH APPLIED EF 0.7332 AND 0.7884 [T CO_2/T LIME] COMPARED TO EU ETS DATA 180
FIG. 4-5 TREND OF EMISSIONS FROM 2.B CHEMICAL INDUSTRY AND SHARE OF SPECIFIC SUBCATEGORIES [KT CO_2 EQ.] 188
FIG. 4-6 TREND OF CO_2 EMISSIONS IN 2.C.1, 1990–2024 [KT CO_2] 204
FIG. 4-7 THE SHARE OF INDIVIDUAL SUBCATEGORIES FOR CO_2 EMISSIONS IN 2.D IN 2024 [KT CO_2 EQ.] 210
FIG. 4-8 IMPACT OF THE RECALCULATIONS OF UREA USED AS A CATALYST. 214
FIG. 4-9 TREND OF EMISSIONS FROM 2.E ELECTRONICS INDUSTRY [KT CO_2 EQ.] 215
FIG. 4-10 TREND OF EMISSIONS FROM 2.F PRODUCT USES AS SUBSTITUTES FOR OZONE DEPLETING SUBSTANCES AND SHARE OF SPECIFIC SUBCATEGORIES [KT CO_2 EQ.] 218
FIG. 4-11 TREND OF EMISSIONS FROM 2.F.1 REFRIGERATION AND AIR CONDITIONING AND SHARE OF SPECIFIC SUBCATEGORIES [KT CO_2 EQ.] 220
FIG. 4-12 TREND OF EMISSIONS FROM 2.G OTHER PRODUCT MANUFACTURE AND USE AND SHARE OF SPECIFIC SUBCATEGORIES [KT CO_2 EQ.] 231
FIG. 5-1 TREND OF EMISSIONS FROM AGRICULTURAL SECTOR [KT CO_2 EQ.], 1990–2024 242
FIG. 5-2 ANIMAL WASTE MANAGEMENT SYSTEMS DISTRIBUTION, ALL LIVESTOCK, 1990–2024 259
FIG. 5-3 TREND IN METHANE EMISSIONS FROM MANURE MANAGEMENT, 1990–2024 262
FIG. 5-4 N_2O EMISSIONS FROM AGRICULTURAL SOILS BY INDIVIDUAL SUB-CATEGORIES [KT N_2O], 1990–2024 277
FIG. 5-5 CONSUMPTION OF NITROGEN FROM SYNTHETIC FERTILIZERS [KT N], 1990–2024 280
FIG. 5-6 TREND OF TOTAL AMOUNT OF NITROGEN EXCRETION FROM AWMS AND NITROGEN EXCRETION FROM PASTURE, 1990–2024 282
FIG. 5-7 COMPARISON OF N_2O EMISSION ESTIMATES (SUBMISSION 2025 AND RECALCULATED DATA / SUBMISSION 2026) FROM LEACHING AND RUNOFF FROM MANAGED AGRICULTURAL SOILS [KT CO_2 EQ.], 1990-2024 289
FIG. 5-8 COMPARISON OF N_2O EMISSION ESTIMATES (SUBMISSION 2025 AND RECALCULATED DATA / SUBMISSION 2026) FROM PASTURE, RANGE AND PADDOCK CATEGORY FROM HORSES [KT CO_2 EQ.], 1990-2024 291
FIG. 6-1 CURRENTLY REPORTED ESTIMATES OF EMISSIONS FOR THE LULUCF SECTOR. THE NEGATIVE VALUES CORRESPOND TO NET REMOVALS OF GREEN-HOUSE GASES. THE POSITIVE VALUES ARE NET EMISSIONS OF GREEN-HOUSE GASES REPORTED FOR THE YEARS 2019–2022, WHEN THE EMISSION BALANCE TURNED TEMPORARILY POSITIVE DUE TO THE DEVELOPMENT IN THE FORESTRY SECTOR. 298
FIG. 6-2 CADASTRAL UNITS (GREY LINES; N = 13 074 IN 2024) AND DISTRICTS (BLACK LINES; N=77), THE BASIS OF THE CZECH LAND USE REPRESENTATION AND LAND USE CHANGE IDENTIFICATION SYSTEM. 302
FIG. 6-3 EXAMPLE OF LAND-USED CHANGE IDENTIFICATION FOR 2011 AND THE CADASTRAL UNIT 661635 (KÁCOV) – TOTAL DIFFERENCE BETWEEN YEARS FOR ALL LAND-USE CATEGORIES AS WELL AS THE SPECIFIC CONVERSIONS BETWEEN CONCRETE LAND USE CATEGORIES AS PROVIDED BY COSMC. THE SPATIAL UNIT IS M^2. NOT OCCURRING (NO) NOTED FOR OTHER LAND. 304
FIG. 6-4 TRENDS IN AREAS OF THE SIX MAJOR LAND-USE CATEGORIES IN THE CZECH REPUBLIC BETWEEN 1970 AND 2024 (BASED ON INFORMATION FROM THE CZECH OFFICE FOR SURVEYING, MAPPING AND CADASTRE). 4.F OTHER LAND (IE) IS INCLUDED WITHIN 4.E. 305
FIG. 6-5 FOREST LAND IN THE CZECH REPUBLIC – DISTRIBUTION CALCULATED AS A SPATIAL SHARE OF THE CATEGORY WITHIN INDIVIDUAL CADASTRAL UNITS (AS OF 2024) 307

FIG. 6-6 ACTIVITY DATA – AREA FOR THE FOUR MAJOR TREE SPECIES GROUPS AND CLEAR-CUT AREA DURING 1990 TO 2024 (TOTAL AREA OF FOREST LAND SHOWN) 309
FIG. 6-7 ACTIVITY DATA – MEAN GROWING STOCK VOLUME AGAINST STAND AGE FOR THE FOUR MAJOR GROUPS OF SPECIES DURING 1990 TO 2024; EACH LINE CORRESPONDS TO AN INDIVIDUAL INVENTORY YEAR. THE SYMBOLS IDENTIFY ONLY THE SITUATION IN 1990 AND 2024. 309
FIG. 6-8 ILLUSTRATION OF BASE HARVEST (LEFT) AND ADDITIONAL (EXTRA) HARVEST (RIGHT) VOLUME AS REPORTED BY CSSO AND USED AS ACTIVITY DATA AS DESCRIBED IN THE TEXT. 311
FIG. 6-9 THE APPLICABLE TOTAL ANNUAL HARVEST FOR CONIFEROUS (CONIF.) AND BROADLEAVED (BROADL.) TREE SPECIES, WHICH INCLUDES BOTH THE REPORTED QUANTITIES OF MERCHANTABLE WOOD FOR THE TWO CATEGORIES (CONIF. MERCH, BROADL. MERCH.) AND THE ESTIMATED/REPORTED ADDITIONAL HARVEST DRAIN (CONIF. EXTRA, BROADL. EXTRA) FOR THE ENTIRE REPORTING PERIOD OF 1990 TO 2024. 311
FIG. 6-10 CONCEPTUAL DIAGRAM OF CBM (TAKEN FROM KURZ ET AL. 2009) SHOWING THE INDIVIDUAL BIOMASS AND DEAD ORGANIC MATTER (DOM) CARBON POOLS AND KEY GOVERNING SIMULATED PROCESSES (IN OVALS) AND TRANSFERS IN FOREST ECOSYSTEM CARBON BALANCE. 314
FIG. 6-11 CURRENT ANNUAL INCREMENT (INCREMENT, MIL. M^3 UNDER BARK) BY THE INDIVIDUAL TREE SPECIES GROUPS AS USED IN THE REPORTING PERIOD 1990 TO 2024 (SOURCE DATA CFI). 316
FIG. 6-12 HARVEST OF MERCHANTABLE VOLUME (MILL. M^3) BY SPECIES GROUPS (BEECH, OAK, PINE, SPRUCE) AND TYPE OF HARVEST INCLUDING THINNING, SALVAGE FELLING WITH (A) OR WITHOUT (B) CLEARCUT AND THE PLANNED FINAL CUT FOR THE REPORTING PERIOD 1990 TO 2024, SERVING AS THE PRESCRIBED MANAGEMENT/DISTURBANCE INPUTS IN CBM (CONVERTED TO CARBON UNITS). 317
FIG. 6-13 CARBON STOCK CHANGES ESTIMATED FOR THE CATEGORY 4.A.1 FOREST LAND REMAINING FOREST LAND BY MAJOR POOLS, NAMELY LIVING BIOMASS, DEAD ORGANIC MATTER (LITTER INCLUDING ORGANIC SOIL LAYERS, AND DEADWOOD) AND MINERAL SOIL (0 TO 30 CM DEPTH). 319
FIG. 6-14 MAP OF ORGANIC SOILS INCLUDING THEIR ATTRIBUTION TO FOREST LAND AND GRASSLAND. 319
FIG. 6-15 WILDFIRES ON FOREST LAND SINCE 1990 – ANNUAL AREA (HA; LEFT; BARS) AND NUMBER OF FIRES PER YEAR (N; RIGHT; FILLED SYMBOLS). 322
FIG. 6-16 MEAN CARBON STOCK (T C/HA) OF DOM COMPONENTS LITTER (INCL. SOIL ORGANIC LAYER) AND DEADWOOD FOR THE REPORTING PERIOD. 323
FIG. 6-17 TOP - TOPSOIL (30 CM) ORGANIC CARBON CONTENT MAP ADAPTED FROM FORCARBO PROJECT (2025), VOPRAVIL AND KHEL (2025) ESTIMATED AS CADASTRAL UNIT MEANS FROM THE SOURCE MAPS {BOTTOM] –TOPSOIL CARBON CONTENT FOR AGRICULTURAL (LEFT) AND FOREST (RIGHT). THE UNIT (T/HA) AND UNIT CATEGORIES ARE IDENTICAL FOR ALL THE MAPS 324
FIG. 6-18 CARBON STOCK CHANGES ESTIMATED FOR THE CATEGORY 4.A.2 LAND CONVERTED TO FOREST LAND BY MAJOR POOLS, NAMELY LIVING BIOMASS, DEAD ORGANIC MATTER (LITTER AND DEADWOOD) AND MINERAL SOIL. 325
FIG. 6-19 ESTIMATED EMISSIONS FOR CATEGORY 4.A FOREST LAND – THE CURRENT (NID 2026) AND PREVIOUS (NID 2025) INVENTORY SUBMISSION. 328
FIG. 6-20 CROPLAND IN THE CZECH REPUBLIC – DISTRIBUTION CALCULATED AS A SPATIAL SHARE OF THE CATEGORY WITHIN INDIVIDUAL CADASTRAL UNITS (AS OF 2024) 331
FIG. 6-21 TREND IN PERENNIAL CROPLAND AREA IN THE CZECH REPUBLIC FOR THE PERIOD 1970 TO 2024 332
FIG. 6-22 MEAN CARBON STOCK (T C/HA) OF DOM COMPONENTS LITTER AND ABOVEGROUND (AG) DEADWOOD FOR THE REPORTING PERIOD. 335
FIG. 6-23 ESTIMATED EMISSIONS FOR CATEGORY 4.B CROPLAND – THE CURRENT (NID 2026) AND PREVIOUS (NID 2025) INVENTORY SUBMISSION. 336
FIG. 6-24 GRASSLAND IN THE CZECH REPUBLIC – DISTRIBUTION CALCULATED AS A SPATIAL SHARE OF THE CATEGORY WITHIN INDIVIDUAL CADASTRAL UNITS (AS OF 2024) 338
FIG. 6-25 ESTIMATED EMISSIONS FOR CATEGORY 4.C GRASSLAND – THE CURRENT (NID 2026) AND PREVIOUS (NID 2025) INVENTORY SUBMISSION. 342
FIG. 6-26 WETLANDS – DISTRIBUTION CALCULATED AS A SPATIAL SHARE OF THE CATEGORY WITHIN INDIVIDUAL CADASTRAL UNITS (AS OF 2024) 343
FIG. 6-27 ESTIMATED EMISSIONS FOR CATEGORY 4.D WETLANDS – THE CURRENT (NID 2026) AND PREVIOUS (NID 2025) INVENTORY SUBMISSION. 345
FIG. 6-28 SETTLEMENTS, INCL. OTHER LAND – DISTRIBUTION CALCULATED AS A SPATIAL SHARE OF THE CATEGORY WITHIN INDIVIDUAL CADASTRAL UNITS (AS OF 2024) 346
FIG. 6-29 ESTIMATED EMISSIONS FOR CATEGORY 4.E SETTLEMENTS– THE CURRENT (NID 2026) AND PREVIOUS (NID 2025) INVENTORY SUBMISSION. 349
FIG. 6-30 ESTIMATED EMISSIONS FOR CATEGORY 4.G HWP – THE CURRENT (NID 2026) AND PREVIOUS (NID 2025) INVENTORY SUBMISSION. 353
FIG. 7-1 THE DEVELOPMENT OF GAS EMISSIONS FROM THE WASTE SECTOR, 1990-2024 354

FIG. 7-2 DEVELOPMENT OF EMISSIONS FROM SWDS AND TOTAL AMOUNT OF WASTE DISPOSED TO SWDS 1990–2024 356
FIG. 7-3 DISPOSAL OF MUNICIPAL SOLID WASTE (MSW) TO SWDS AND GDP, CZECH REPUBLIC, 1950–1990 356
FIG. 7-4 AMOUNT OF WASTE PRODUCED IN THE CZECH REPUBLIC - COMPARISON OF DATA FROM EUROSTAT AND ISOH, 2010–2018 . 357
FIG. 7-5 AMOUNT OF WASTE DISPOSED TO SWDS IN THE CZECH REPUBLIC - COMPARISON OF DATA FROM EUROSTAT AND ISOH, 2010-2018 358
FIG. 7-6 THE DEVELOPMENT OF EMISSIONS FROM BIOLOGICAL TREATMENT OF SOLID WASTE, 2003–2024 (2003 AND 2004 ONLY ANAEROBIC DIGESTION) 363
FIG. 7-7 DEVELOPMENT OF EMISSIONS FROM WASTE INCINERATION, 1990–2024 368
FIG. 7-8 DEVELOPMENT OF GHG EMISSIONS FROM WASTEWATER TREATMENT AND DISCHARGE. 1990–2024 377
FIG. 7-9 DEVELOPMENT OF 5.D.1 EMISSION OF CH_4 BY TYPES OF TREATMENT, 1990–2024 377
FIG. 7-10 THE SCHEME OF TOTAL ORGANIC WASTE FLOW IN 5.D.1 378
FIG. 7-11 DEVELOPMENT OF EMISSIONS FROM 5.D.2 BY TYPES OF EMISSION SOURCES 383
FIG. 7-12 THE OUTLINE OF THE TOTAL ORGANIC WASTE FLOW IN 5.D.2 385
FIG. 7-13 MAXIMUM UNCERTAINTY RANGE FOR 5.D.2, 1990–2024 (LOG SCALE) 386
FIG. 9-1 INDEXED EMISSIONS OF PRECURSOR GASES FOR 1990–2024 (1990 =100%), [%] (LEFT); OVERALL TREND IN PERCENTAGE SHARE OF PRECURSOR GASES (RIGHT) 391
FIG. 9-2 INDIRECT N_2O EMISSIONS FROM NO_X EMISSIONS IN 2024 393
FIG. 9-3 INDIRECT N_2O EMISSIONS FROM NH_3 EMISSIONS IN 2024 393
FIG. 9-4 INDIRECT CO_2 EMISSIONS FROM CO EMISSIONS IN 2024 394
FIG. 9-5 INDIRECT CO_2 EMISSIONS FROM NMVOC EMISSIONS IN 2024 394
FIG. 9-6 INDIRECT CO_2 EMISSIONS FROM 2.D NON-ENERGY PRODUCTS FROM FUELS AND SOLVENT USE IN 2024 395
FIG. 9-7 INDIRECT CO_2 EMISSIONS FROM METHANE IN 2024 395
FIG. 9-8 DIVISION OF INDIRECT EMISSION OF CO_2 (LEFT) AND N_2O (RIGHT) BETWEEN THE PRODUCING SECTORS FOR 2024 (IN %) 397
FIG. 10-1 DIFFERENCE IN TRENDS OF CO_2 EMISSIONS BETWEEN THE SUBMISSIONS 2025 AND 2026, DUE TO RECALCULATIONS 414
FIG. 10-2 DIFFERENCE IN TRENDS OF CH4 EMISSIONS IN INDEX FORM, BETWEEN THE SUBMISSIONS 2025 AND 2026, DUE TO RECALCULATIONS 414
FIG. 10-3 DIFFERENCE IN TRENDS OF N_2O EMISSIONS, BETWEEN THE SUBMISSIONS 2025 AND 2026, DUE TO RECALCULATIONS 415
FIG. 10-4 DIFFERENCE IN TRENDS OF HFCS EMISSIONS IN INDEX FORM, BETWEEN SUBMISSION 2025 AND 2026, DUE TO RECALCULATIONS 415
FIG. 10-5 DIFFERENCE IN TRENDS OF PFCS EMISSIONS, BETWEEN SUBMISSION 2025 AND 2026, DUE TO RECALCULATIONS 416
FIG. 10-6 DIFFERENCE IN TRENDS OF SF_6 EMISSIONS, BETWEEN SUBMISSION 2025 AND 2026, DUE TO RECALCULATIONS 416
FIG. 10-7 DIFFERENCE IN TRENDS OF TOTAL EMISSIONS INCLUDING LULUCF, BETWEEN SUBMISSION 2025 AND 2026, DUE TO RECALCULATIONS 417
FIG. 10-8 DIFFERENCE IN TRENDS OF TOTAL EMISSIONS EXCLUDING LULUCF, BETWEEN SUBMISSION 2025 AND 2026, DUE TO RECALCULATIONS 417

List of tables

TAB. ES 1 GHG EMISSION/REMOVAL OVERALL TRENDS 10
TAB. ES 2 OVERVIEW OF GHG EMISSION/REMOVAL TRENDS BY CRT CATEGORIES 12
TAB. ES 3 OTHER GASES TOTALS FOR NO_x, CO, NMVOC, SO_x AND NH_3 FROM 1990 TO 2024 [KT] 15

TAB. 1-1 CHMI STAFF FOR QA/QC COORDINATION 24
TAB. 1-2 THE SCHEDULE OF QC ACTIVITIES – TIER 1 OF THE DATA OUTPUT FOR EU (OUTPUT DEADLINE 15 JANUARY). THE OUTPUT FOR EU, AFTER FURTHER CONTROLS (SEE BELOW) AND POSSIBLE UPDATES IS USED AS THE OUTPUT FOR UNFCCC (DEADLINE 15 SEPTEMBER) 28
TAB. 1-3 QA/QC STAFF MEMBERS FOR ENERGY – STATIONARY SOURCES 32
TAB. 1-4 QA/QC STAFF MEMBERS FOR ENERGY – MOBILE SOURCES 33
TAB. 1-5 QA/QC STAFF MEMBERS FOR ENERGY – FUGITIVE EMISSIONS 34
TAB. 1-6 QA/QC STAFF MEMBERS FOR INDUSTRIAL PROCESSES AND SOLVENT AND OTHER PRODUCT USE 35
TAB. 1-7 QA/QC STAFF MEMBERS FOR AGRICULTURE 36
TAB. 1-8 QA/QC STAFF MEMBERS FOR LULUCF 37
TAB. 1-9 QA/QC STAFF MEMBERS FOR WASTE 38
TAB. 1-10 IDENTIFICATION OF KEY CATEGORIES BY LEVEL ASSESSMENT (LA) AND TREND ASSESSMENT (TA) FOR 2024 EVALUATED WITH LULUCF (APPROACH 2) 42
TAB. 1-11 IDENTIFICATION OF KEY CATEGORIES BY LEVEL ASSESSMENT (LA) AND TREND ASSESSMENT (TA) FOR 2024 EVALUATED WITHOUT LULUCF (APPROACH 2) 42
TAB. 1-12 IDENTIFICATION OF KEY CATEGORIES BY LEVEL ASSESSMENT (LA) AND TREND ASSESSMENT (TA) FOR 2024 EVALUATED WITH LULUCF (APPROACH 1) 43
TAB. 1-13 IDENTIFICATION OF KEY CATEGORIES BY LEVEL ASSESSMENT (LA) AND TREND ASSESSMENT (TA) FOR 2024 EVALUATED WITHOUT LULUCF (APPROACH 1) 44
TAB. 1-14 FIGURES FOR KEY CATEGORIES ASSESSED 44
TAB. 2-1 GHG EMISSIONS FROM 1990–2024 EXCL. BUNKERS [KT CO_2 EQ.] 47
TAB. 2-2 SUMMARY OF GHG EMISSIONS BY CATEGORY 1990–2024 [KT CO_2 EQ.] 52
TAB. 2-3 OVERVIEW OF TRENDS IN CATEGORIES AND SUBCATEGORIES [KT CO_2 EQ.] 53
TAB. 3-1 OVERVIEW OF KEY CATEGORIES IN 1 ENERGY (2024) 59
TAB. 3-2 EMISSIONS OF GREENHOUSE GASES AND THEIR TREND FROM 1990–2024 FROM IPCC CATEGORY 1 ENERGY 60
TAB. 3-3 TOTAL GHG EMISSIONS IN [KT CO_2 EQUIVALENT] FROM 1990–2024 BY SUBCATEGORIES OF ENERGY 62
TAB. 3-4 PRODUCTS USED AS FEEDSTOCKS, REDUCTANTS, AND FOR NON-ENERGY PRODUCTS (IPCC, 2006) 63
TAB. 3-5 ACTIVITY DATA IN ENERGY UNITS [TJ], USED IN REFERENCE AND SECTORAL APPROACH FOR BASIC GROUPS OF FOSSIL FUELS 64
TAB. 3-6 RESULTS FOR CO_2 EMISSIONS (KT) ACCORDING TO REFERENCE APPROACH AND COMPARISON WITH SECTORAL APPROACH 65
TAB. 3-7 APPARENT CONSUMPTION IN ENERGY UNITS (PJ) USED IN REFERENCE AND SECTORAL APPROACH FOR ALL FOSSIL FUELS AND CORRESPONDING RESULTS FOR CO_2 EMISSIONS (KT) 66
TAB. 3-8 EXPLANATION OF HIGH DIFFERECE BETWEEN REFERENCE AND SECTORAL APPROACH 67
TAB. 3-9 KEROSENE JET FUEL IN INTERNATIONAL BUNKERS 67
TAB. 3-10 NET CALORIFIC VALUES AND EMISSION FACTORS OF FEEDSTOCKS 69
TAB. 3-11 NET CALORIFIC VALUES (NCV), CO_2 EMISSION FACTORS AND OXIDATION FACTORS USED IN THE SUBMISSION 2026 72
TAB. 3-12 CAPACITY OF MUNICIPAL WASTE INCINERATION PLANTS IN THE CZECH REPUBLIC, 2023 79
TAB. 3-13 CHANGES AFTER RECALCULATION IN 1.A.1.A FOR WASTE 80
TAB. 3-14 CHANGES AFTER RECALCULATION IN 1.A.1.A FOR BIOMASS. 81
TAB. 3-15 CONSUMPTION OF LIGNITE FOR PRODUCTION OF TECHNOLOGICAL STEAM IN FUEL COMBINE VŘESOVÁ 1995–2023 86
TAB. 3-16 CHANGES AFTER RECALCULATION IN 1.A.1.C.I FOR SOLID FUELS. 87
TAB. 3-17 CHANGES AFTER RECALCULATION IN 1.A.2.A FOR SOLID FUELS. 90
TAB. 3-18 CHANGES AFTER RECALCULATION IN 1.A.2.B FOR SOLID FUELS. 93
TAB. 3-19 CHANGES AFTER RECALCULATION IN 1.A.2.C FOR SOLID FUELS 95
TAB. 3-20 CHANGES AFTER RECALCULATION IN 1.A.2.D FOR SOLID FUELS 97
TAB. 3-21 CHANGES AFTER RECALCULATION IN 1.A.2.E FOR SOLID FUELS 100
TAB. 3-22 CONSUMPTION OF ALTERNATIVE FUELS IN SECTOR 1.A.2.F 103
TAB. 3-23 CO_2 EMISSION FACTORS USED IN THE CONSUMPTION OF ALTERNATIVE FUELS IN SECTOR 1.A.2.F 103
TAB. 3-24 EMISSION FACTORS FOR CH_4 AND N_2O EMISSIONS USED IN THE CONSUMPTION OF ALTERNATIVE FUELS SECTOR 1.A.2.F 103
TAB. 3-25 CHANGES AFTER RECALCULATION IN 1.A.2.F FOR SOLID FUELS 104

TAB. 3-26 CHANGES AFTER RECALCULATION IN 1.A.2.G FOR SOLID FUELS. 107
TAB. 3-27 CALORIFIC VALUES OF FUELS IN [MJ/KG] (SOURCE: CZSO) 109
TAB. 3-28 ANNUAL FUEL CONSUMPTION BY MODE OF TRANSPORT 109
TAB. 3-29 RATIO OF FUEL USAGE BETWEEN LTO AND CRUISE FLIGHT MODE IN 2024 111
TAB. 3-30 EMISSION FACTORS FOR CO_2, CH_4 AND N_2O FOR AVIATION IN [$G.KG^{-1}$] OF FUEL IN 2024 112
TAB. 3-31 FUEL CONSUMPTION IN ROAD TRANSPORT IN THE CZECH REPUBLIC 115
TAB. 3-32 IMPLIED EFS FOR CO_2 FOR ROAD TRANSPORT 116
TAB. 3-33 IMPLIED EFS FOR CH_4 FOR ROAD TRANSPORT 116
TAB. 3-34 IMPLIED EFS FOR N_2O FOR ROAD TRANSPORT 117
TAB. 3-35 FUEL CONSUMPTION BY RAILWAYS 121
TAB. 3-36 EMISSION FACTORS FOR CO_2, CH_4 AND N_2O FOR RAILWAYS IN [$G.KG^{-1}$] OF FUEL IN 2024 122
TAB. 3-37 FUEL CONSUMPTION BY DOMESTIC NAVIGATION 123
TAB. 3-38 EMISSION FACTORS OF CO_2, CH_4 AND N_2O FOR DOMESTIC NAVIGATION IN [$G.KG^{-1}$] OF FUEL IN 2024 124
TAB. 3-39 UNCERTAINTY DATA FOR TRANSPORT FROM UNCERTAINTY ANALYSIS 125
TAB. 3-40 QUANTITIES OF FUELS USED IN THE SECTOR TRANSPORT IN STATIONARY SOURCES 129
TAB. 3-41 CHANGES AFTER RECALCULATION IN 1.A.4.B FOR BIOMASS 131
TAB. 3-42 CHANGES AFTER RECALCULATION IN 1.A.4.C.II FOR GASOLINE 136
TAB. 3-43 CHANGES AFTER RECALCULATION IN 1.A.4.C.II FOR DIESEL OIL 136
TAB. 3-44 CHANGES AFTER RECALCULATION OF FUEL CONSUMPTION IN 1.A.5.B LIQUID FUELS 139
TAB. 3-45 CHANGES AFTER RECALCULATION IN 1.A.5.B 140
TAB. 3-46 CH_4 EMISSIONS FROM CHARCOAL PRODUCTION 147
TAB. 3-47 COAL MINING AND CH_4 EMISSIONS IN THE OSTRAVA - KARVINA COAL-MINING AREA 148
TAB. 3-48 METHANE PRODUCTION FROM GAS ABSORPTION OF MINES AND ITS USE 148
TAB. 3-49 CALCULATION OF EMISSION FACTORS FROM OKD MINES FOR PERIOD 2000 ONWARDS 149
TAB. 3-50 EMISSION FACTORS AND EMISSIONS FROM UNDERGROUND MINING OF HARD COAL 149
TAB. 3-51 USED EMISSIONS FACTORS AND CALCULATION OF CH_4 EMISSIONS FROM UNDERGROUND COAL MINING – POST MINES OPERATIONS IN PERIOD 1990–2024 150
TAB. 3-52 USED EMISSIONS FACTORS AND CALCULATION OF CH_4 EMISSIONS FROM UNDERGROUND COAL MINING – IN PERIOD 2002–2016. 151
TAB. 3-53 EMISSION OF CH_4 ON ABANDONED MINES 152
TAB. 3-54 USED ACTIVITY DATA, EMISSIONS FACTORS AND CALCULATION OF CH_4 EMISSIONS FROM SURFACE COAL MINING AND POST MINES OPERATIONS IN PERIOD 1990-2024 153
TAB. 3-55 CHANGES AFTER RECALCULATION IN CH_4 EMISSIONS 1.B.1.A.I.1. UNDERGROUND MINES, MINING ACTIVITY 156
TAB. 3-56 CHANGES AFTER RECALCULATION IN CH_4 EMISSIONS IN 1.B.1.A.I.2. UNDERGROUND MINES, POST - MINING ACTIVITIES 156
TAB. 3-57 CHANGES AFTER RECALCULATION IN CO_2 EMISSIONS IN 1.B.1.A.I.2. SURFACE MINES, MINING ACTIVITIES 156
TAB. 3-58 EMISSIONS OF CH_4, CO_2 AND N_2O FROM VENTING AND FLARING IN 1990–2024 163
TAB. 3-59 EMISSION FACTORS AND CH_4 EMISSIONS FOR TRANSMISSION 168
TAB. 3-60 MODEL CALCULATION OF CH_4 EMISSIONS IN THE NATURAL GAS SECTOR (2023) 169
TAB. 3-61 RECAPITULATION OF METHANE EMISSIONS IN 1.B.2.B – GAS. 169
TAB. 3-62 CHANGES AFTER RECALCULATION IN CH_4 EMISSIONS IN 1.B.2.A.IV. OIL – REFINING/STORAGE 171
TAB. 3-63 CHANGES AFTER RECALCULATION IN CO_2 AND CH_4 EMISSIONS IN 1.B.2.B.V. DISTRIBUTION 171
TAB. 4-1 OVERVIEW OF KEY CATEGORIES IN SECTOR INDUSTRIAL PROCESSES (2024) 173
TAB. 4-2 OVERVIEW OF CATEGORIES IN SECTOR INDUSTRIAL PROCESSES AND PRODUCT USE (2024) 175
TAB. 4-3 CO_2 EMISSIONS IN INDIVIDUAL SUBCATEGORIES IN 2.A MINERAL PRODUCTS CATEGORY IN 1990–2024 175
TAB. 4-4 CO_2 EMISSION FACTORS AND METHODOLOGY USED FOR COMPUTATIONS OF 2024 EMISSIONS AND REMOVALS IN CATEGORY 2.A 176
TAB. 4-5 ACTIVITY DATA, CO_2 EMISSION FACTOR AND CO_2 EMISSIONS IN 2.A.1 CEMENT PRODUCTION CATEGORY IN 1990–2024 178
TAB. 4-6 ACTIVITY DATA, CO_2 EMISSION FACTOR AND CO_2 EMISSIONS IN 2.A.2 LIME PRODUCTION CATEGORY IN 1990–2024 180
TAB. 4-7 ACTIVITY DATA, CO_2 EMISSION FACTOR AND CO_2 EMISSIONS IN 2.A.3 GLASS PRODUCTION CATEGORY IN 1990–2024 182
TAB. 4-8 CO_2 EMISSIONS AND REMOVALS IN INDIVIDUAL SUBCATEGORIES IN 2.A.4 OTHER PROCESS USES OF CARBONATES CATEGORY IN 1990–2024 186
TAB. 4-9 CO_2 EQ. EMISSIONS IN INDIVIDUAL SUBCATEGORIES IN 2.B CHEMICAL INDUSTRY CATEGORY IN 1990–2024 188
TAB. 4-10 EMISSION FACTORS USED FOR COMPUTATIONS OF 2024 EMISSIONS IN CATEGORY 2.B 189
TAB. 4-11 CHEMICAL PRODUCTION IN THE CZECH REPUBLIC WITH NUMBER OF MANUFACTURERS 190
TAB. 4-12 ACTIVITY DATA AND CO_2 EMISSIONS FROM AMMONIA PRODUCTION IN 1990–2024 191
TAB. 4-13 PRESSURE LEVEL AND REMOVAL TECHNOLOGY USED BY UNIT IN THE CZECH REPUBLIC 193
TAB. 4-14 EMISSION FACTORS FOR N_2O RECOMMENDED BY (MARKVART AND BERNAUER, 2000. 2003) FOR 1990–2003 193

TAB. 4-15 EMISSION FACTORS FOR N_2O RECOMMENDED BY MARKVART AND BERNAUER, FOR 2004 AND THEREAFTER 194
TAB. 4-16 DECREASE IN THE EMISSION FACTOR FOR 0.7 MPA TECHNOLOGY DUE TO INSTALLATION OF THE N_2O MITIGATION UNIT 194
TAB. 4-17 EMISSION TRENDS FOR HNO_3 PRODUCTION AND N_2O EMISSIONS IN 1990–2024 194
TAB. 4-18 EMISSION TRENDS FROM CO_2 AND CH_4 EMISSIONS FROM PRODUCTION OF ETHYLENE IN 1990–2024 199
TAB. 4-19 EMISSION TRENDS FOR CATEGORY 2.B.10 OTHER IN 2008–2024 202
TAB. 4-20 THE ACTIVITY DATA AND CO2 EMISSIONS IN 1990–2024 205
TAB. 4-21 EVALUATION OF EMISSION FACTORS USED FOR 2.C.2 EMISSION ESTIMATES 207
TAB. 4-22 EMISSIONS FROM CATEGORY 2.E. ELECTRONICS INDUSTRY IN TIME PERIOD 1997–2024 215
TAB. 4-23 TYPE OF CO_2 EMISSIONS FACTORS USED FOR COMPUTATIONS OF 2024 EMISSIONS IN CATEGORY 2.E ELECTRONICS INDUSTRY 216
TAB. 4-24 EMISSIONS FACTORS USED FOR COMPUTATIONS OF 2024 EMISSIONS FROM 2.E.1 INTEGRATED CIRCUIT OR SEMICONDUCTOR 216
TAB. 4-25 ACTUAL EMISSIONS OF HFCS AND PFCS IN 1995–2024 [KT CO_2 EQ.] 218
TAB. 4-26 TYPE OF EMISSIONS FACTORS USED FOR COMPUTATIONS OF 2024 EMISSIONS IN CATEGORY 2.F 219
TAB. 4-27 AN OVERVIEW OF THE F-GASES REPORTED UNDER SUBCATEGORY 2.F.1 220
TAB. 4-28 PARAMETERS USED FOR EMISSION CALCULATIONS FOR CATEGORY 2.F.1 IN CALCULATION MODEL 221
TAB. 4-29 DISTRIBUTION OF HFCS AND PFCS USE BY APPLICATION AREA USED FOR EMISSION CALCULATIONS IN 2024 222
TAB. 4-30 EMISSIONS OF HFCS AND PFCS FROM SUBCATEGORIES UNDER 2.F.1 IN 2024 – COMPARISON TO LEVELS OF EMISSIONS IN 2024 AND 1995 222
TAB. 4-31 SUBCATEGORIES IN WHICH IS USED NOTATION KEY NE FOR GASES HFC-134A AND HFC-32 WITH RELATED YEAR 223
TAB. 4-32 PARAMETERS USED FOR EMISSION CALCULATIONS FOR SUBCATEGORY 2.F.1.E 223
TAB. 4-33 NUMBER OF VEHICLES PRODUCED IN THE CZECH REPUBLIC IN THE YEAR 2024 224
TAB. 4-34 INFORMATION ABOUT VEHICLES FLEET OF THE CZECH REPUBLIC OBTAINED FROM COPERT 225
TAB. 4-35 AC SHARES AND TYPE OF REFRIGERANT IN EURO STANDARD 226
TAB. 4-36 EMISSIONS OF HFCS AND PFCS FROM 2.F.1.E IN 2024 – COMPARISON TO EMISSION LEVELS IN 2023 AND 1995 227
TAB. 4-37 CO_2 EQ. EMISSIONS IN INDIVIDUAL SUBCATEGORIES IN 2.G OTHER PRODUCT MANUFACTURE AND USE CATEGORY IN 1990–2024 231
TAB. 4-38 TYPE OF EMISSIONS FACTORS USED FOR COMPUTATIONS OF 2024 EMISSIONS IN CATEGORY 2.G OTHER PRODUCT MANUFACTURE AND USE 232
TAB. 5-1 OVERVIEW OF SIGNIFICANT SOURCE CATEGORIES IN AGRICULTURE (SUBMISSION 2026), ASSESSED WITH AND WITHOUT CONSIDERING LULUCF 241
TAB. 5-2 EMISSIONS FROM AGRICULTURE, SORTED BY SOURCE CATEGORIES, 1990–2024 241
TAB. 5-3 EMISSION CATEGORIES EXPRESSED IN RELATIVE SHARES COMPARED TO 1990 (YEAR 1990 IS STATED AS 100%) 243
TAB. 5-4 TRENDS IN LIVESTOCK POPULATIONS [1 000 HEADS], 1990–2024 (CZSO 2025) 245
TAB. 5-5 WEIGHT OF AN INDIVIDUAL IN CATTLE CATEGORIES [KG], 1990–2024 247
TAB. 5-6 ACTIVITY COEFFICIENT (ADJUSTED IN COMPLIANCE WITH IPCC 2019 GL.) AND THE CORRESPONDING VALUES FOR THE PRODUCTION SYSTEM (ZEMAN, 2006) 248
TAB. 5-7 THE UPDATE OF ACTIVITY COEFFICIENT ESTIMATION BY USING THE BREEDING COEFFICIENT; DAIRY CATTLE, SUCKLER COWS AND NON-DAIRY CATTLE AS A SUMMARIZED CATEGORY 248
TAB. 5-8 DAILY MILK PRODUCTION OF DAIRY COWS AND FAT CONTENT IN MILK, 1990–2024 249
TAB. 5-9 WEIGHT GAIN DEVELOPMENT OVERVIEW [KG PER LIVESTOCK CATEGORIES]; DAIRY AND SUCKLER COW WEIGHT GAINS ARE ASSUMED TO BE ZERO AND ARE NOT LISTED IN THE TABLE, 1990–2024 (SOURCE: KOLÁŘ ET AL. 2004, ZEMAN ET AL. 2021, BERANOVA ET AL. 2022A). WEIGHT 249
TAB. 5-10 DIGESTIBILITY (DE) OF DAIRY AND NON-DAIRY CATTLE: VALUES DEVELOPMENT IN NID (FORMER NIR) OF THE CZECH REPUBLIC, 1991–2024 (CHMI 2025, BERANOVA ET AL. 2022A) 250
TAB. 5-11 DEVELOPMENT OF METHANE CONVERSION FACTOR (Y_M) VALUES IN 1990–2024 (BERANOVA ET AL. 2024) 250
TAB. 5-12 ACTIVITY DATA AND INPUT DATA USED FOR ESTIMATING GROSS ENERGY INTAKE (GE) AND EMISSION FACTORS FOR ALL AGE CATEGORIES OF CATTLE, ACTUAL DATA FOR 2024 251
TAB. 5-13 CALCULATED VALUES USED FOR ESTIMATING METHANE EMISSIONS FROM ENTERIC FERMENTATION FOR ALL AGE CATEGORIES OF CATTLE, ACTUAL DATA FOR 2024 252
TAB. 5-14 ACTIVITY DATA AND METHANE EMISSIONS FROM ENTERIC FERMENTATION OF DAIRY AND NON-DAIRY CATTLE, TIER 2, 1990–2024 252
TAB. 5-15 METHANE EMISSIONS FROM ENTERIC FERMENTATION OF OTHER LIVESTOCK, TIER 1, 1990–2024 253
TAB. 5-16 COMPARISON OF DIGESTIBILITY VALUES DERIVED FROM THE CALCULATION OF DMI FROM GE VALUES, CALCULATION RECOMMENDED BY IPCC GUIDELINES 2019 (DATA 2024), DMI VALUES ARE FROM CZECH FEEDING RATIO STANDARDS. 256

TAB. 5-17 COMPARISON OF EMISSIONS FACTORS FOR METHANE EMISSIONS FROM ENTERIC FERMENTATION OF DAIRY AND NON-DAIRY CATTLE, FACTORS RECOMMENDED BY IPCC 2006 GL. FOR WESTERN EUROPE, IPCC 2019 GL. FOR WESTERN EUROPE AND DATA CALCULATED FOR SUBMISSION 2026 256
TAB. 5-18 COMPARISON OF TWO DIFFERENT ESTIMATIONS OF EMISSION FACTORS FOR METHANE EMISSIONS FROM ENTERIC FERMENTATION OF DAIRY AND NON-DAIRY CATTLE, INPUT DATA 2023-2024 (SUBMISSION 2025 AND 2026) 256
TAB. 5-19 OVERVIEW OF EMISSIONS FROM MANURE MANAGEMENT [KT CO_2 EQ.], 1990–2024 258
TAB. 5-20 INCREASE IN THE NUMBER OF BIOGAS STATIONS, ESTIMATION OF TOTAL DIGESTATES PRODUCTION AND AMOUNT OF NITROGEN IN DIGESTATE, 2001–2024 (CARC) 259
TAB. 5-21 OVERVIEW OF CZECH COUNTRY-SPECIFIC AWMS: DAIRY AND NON-DAIRY CATTLE, FRACTIONS OF INDIVIDUAL MANURE MANAGEMENT SYSTEMS [%], 1990–2024 260
TAB. 5-22 OVERVIEW OF THE CZECH COUNTRY-SPECIFIC AWMS: SWINE AND POULTRY, FRACTIONS OF INDIVIDUAL MANURE MANAGEMENT SYSTEMS [%], 1990–2024 260
TAB. 5-23 OVERVIEW OF THE CZECH COUNTRY-SPECIFIC AWMS SYSTEMS: SHEEP, HORSES AND GOATS, FRACTIONS OF INDIVIDUAL MANURE MANAGEMENT SYSTEMS [%], 1990–2024 261
TAB. 5-24 GROSS ENERGY (GE) FOR DAIRY AND NON-DAIRY CATTLE [MJ/HEAD/DAY], REPORTED PERIOD 1990–2024 262
TAB. 5-25 ACTIVITY DATA, INPUT DATA AND CALCULATED DATA USED FOR ESTIMATING METHANE EMISSION FACTORS FOR MANURE MANAGEMENT FOR ALL AGE CATTLE CATEGORIES, CURRENT DATA (2024) 263
TAB. 5-26 LIST OF PARAMETERS FOR METHANE EMISSION FACTOR ESTIMATION FROM MANURE MANAGEMENT IN THE CZECH CONDITIONS, MCF VALUES [%] 263
TAB. 5-27 OVERVIEW OF VS [KG DRY MATTER/HEAD/DAY], EF [KG CH_4/HEAD/YEAR] AND METHANE EMISSIONS [KT] FROM MANURE MANAGEMENT, DAIRY AND NON-DAIRY CATEGORY, 1990–2024 264
TAB. 5-28 LIST OF PARAMETERS FOR ESTIMATING METHANE EMISSIONS FROM MANURE MANAGEMENT OF SWINE IN THE CZECH CONDITIONS, DATA 2024 264
TAB. 5-29 LIST OF PARAMETERS FOR ESTIMATING METHANE EMISSIONS FROM MANURE MANAGEMENT OF SWINE IN THE CZECH CONDITIONS, MCF VALUES [%], DATA 2024 265
TAB. 5-30 ACTIVITY DATA FOR ESTIMATING METHANE EMISSIONS FROM MANURE MANAGEMENT OF SWINE IN THE CZECH CONDITIONS, 1990–2024 * 265
TAB. 5-31 DEFAULT METHANE EMISSION FACTORS USED FOR ESTIMATING CH_4 EMISSIONS FROM MANURE MANAGEMENT (TABLE 10.15 AND 10.14 IPCC 2006 GL.) 265
TAB. 5-32 ACTIVITY DATA, DEFAULT EMISSIONS FACTORS (TABLE 10.15 IPCC 2006 GL.) AND EMISSIONS ESTIMATED FOR POULTRY POPULATION 266
TAB. 5-33 OVERVIEW OF INPUT DATA FOR NITROGEN EXCRETION CALCULATION 267
TAB. 5-34 NEX RATE VALUES USED FOR ESTIMATING NITROUS EMISSIONS, DATA 1990–2024 268
TAB. 5-35 SOURCE DATA FOR CALCULATION OF NITROGEN EXCRETION RATE FOR DAIRY CATTLE, 1990–2024 268
TAB. 5-36 ACTIVITY DATA, INPUT DATA AND CALCULATED DATA USED FOR ESTIMATION OF ANNUAL NITROGEN EXCRETION RATE FOR ALL ANIMAL CATEGORIES, CURRENT DATA (2024) 269
TAB. 5-37 DEFAULT IPCC EMISSION FACTORS FOR DIRECT N_2O EMISSIONS USED FOR DIFFERENT AWMS (T.10.21, IPCC 2006) 270
TAB. 5-38 NITROGEN PRODUCTION OF MANURE DISTRIBUTED IN INDIVIDUAL AWMS [KG N/YR], DATA 2010–2024 270
TAB. 5-39 INDIRECT AND DIRECT N_2O EMISSIONS FROM MANURE MANAGEMENT [KT N_2O/YEAR], 1990–2024 271
TAB. 5-40 EXAMPLE OF THE DERIVED VALUES OF NEX FOR SWINE WITH SUPPORT OF DATA FROM DECREE NO. 377/2013 COLL., DATA FOR 2024 272
TAB. 5-41 COMPARISON OF METHANE EMISSION FACTORS FOR MANURE MANAGEMENT, IPCC 2006 GL. DEFAULT AND COUNTRY-SPECIFIC VALUES (SUBMISSION 2026) 273
TAB. 5-42 OVERVIEW OF N RATE VALUES, IPCC 2006 DEFAULT AND COUNTRY-SPECIFIC VALUES (LONG-TERM AVERAGE AND SUBMISSION 2026 VALUES) 273
TAB. 5-43 OVERVIEW OF DAILY VOLATILE SOLID EXCRETED VALUES, IPCC 2006 DEFAULT AND COUNTRY-SPECIFIC VALUES (LONG-TERM AVERAGE AND SUBMISSION 2026 VALUES) 273
TAB. 5-44 SHARE OF AWMS IN 2024, RESULTS OF CARC SURVEY AMONG AGRICULTURAL HOLDINGS IN CZECH REPUBLIC (CARC, 2025) 274
TAB. 5-45 DIRECT AND INDIRECT N_2O EMISSIONS FROM AGRICULTURAL SOILS [KT N_2O], 1990–2024 276
TAB. 5-46 EMISSION FACTORS FOR ESTIMATING DIRECT EMISSIONS FROM MANAGED SOILS (TABLE 11.1, IPCC 2019). 278
TAB. 5-47 ACTIVITY DATA INPUTS TO CALCULATION OF F_{ON}: ANNUAL AMOUNT OF ANIMAL MANURE N (FAM), ANNUAL AMOUNT OF SEWAGE SLUDGE N (F_{SEW}) AND ANNUAL AMOUNT OF DIGESTATED N AND COMPOST N (F_{OOA}) [T N/YEAR], 1990–2024 280
TAB. 5-48 DEVELOPMENT OF THE AMOUNT OF N AND EMISSIONS FROM URINE AND DUNG FROM GRAZING ANIMALS, 1990–2024 281
TAB. 5-49 IPCC DEFAULT EMISSION FACTORS FOR ANIMAL WASTE MANAGEMENT SYSTEM: PASTURE, RANGE AND PADDOCK (PRP), (T 11.1, IPCC 2019) 282
TAB. 5-50 ANNUAL YIELD OF AGRICULTURAL PRODUCTS, 1990–2024 283

TAB. 5-51 ANNUAL YIELD OF FODDER [T/HA] INCLUDING TOTAL CROP AREA, 1990–2024 283
TAB. 5-52 DEFAULT VALUES OF INPUT FACTORS USED FOR ESTIMATING F_{CR} (TABLE 11.2, IPCC 2006 AND 2019), CALCULATED DATA (SUBMISSION 2026) 284
TAB. 5-53 DEFAULT VALUE OF INPUT FACTORS USED IN ESTIMATION OF FODDER (TABLE 11.2, IPCC 2006), CALCULATED DATA (FODER DRY MATTER 2014, SILAGE MAIZE AND PERENNIAL AND ANNUAL FODDER, SUBMISSION 2026) 284
TAB. 5-54 OVERVIEW OF ACTIVITY DATA AND N_2O EMISSIONS FROM LOSS OF SOIL ORGANIC MATTER (F_{SOM}) 285
TAB. 5-55 DIRECT EMISSIONS FROM CULTIVATION OF ORGANIC SOILS (F_{OS}) 1990-2024 286
TAB. 5-56 IPCC DEFAULT PARAMETERS/FRACTIONS USED FOR ESTIMATING INDIRECT EMISSIONS (TABLE 11.3, IPCC 2019, METHODS IN ANNEX 11A.9.) 286
TAB. 5-57 EMISSION FACTORS (EFS) USED FOR ESTIMATING INDIRECT EMISSIONS (T 11.3, IPCC 2019) 286
TAB. 5-58 OVERVIEW OF $FRAC_{LEACH-(H)}$ VALUES CONSIDERING THE CLIMATIC ZONATION, 1990-2024 289
TAB. 5-59 AMOUNT OF LIMESTONE AND DOLOMITE APPLIED TO MANAGED SOILS [1 000 TONS] 293
TAB. 5-60 ESTIMATED CONSUMPTION OF UREA AND UREA IN DAM (IPPU) APPLIED TO MANAGED SOILS IN THE CZECH REPUBLIC DURING REPORTING PERIOD (MA, 2025) AND ESTIMATED EMISSIONS [KT CO_2 EQ.] 294
TAB. 6-1 GHG ESTIMATES IN SECTOR 4 (LULUCF) AND ITS CATEGORIES IN 1990 (BASE YEAR) AND 2024 298
TAB. 6-2 ESTIMATED EMISSIONS AND REMOVALS FOR THE MAJOR LAND-USE CATEGORIES AND HWP CONTRIBUTION FOR THE ENTIRE REPORTING PERIOD 1990 TO 2024 BY 5-YEAR INTERVALS AND ANNUALLY SINCE 2020. IE FOR 4.F OTHER LAND – INCLUDED WITHIN 4.E SETTLEMENTS. 299
TAB. 6-3 KEY CATEGORIES OF THE LULUCF SECTOR (2024) 299
TAB. 6-4 CARBON POOLS IN LULUCF AND IN THEIR FINER RESOLUTION UNDER THE FORMER KP LULUCF REPORTING 300
TAB. 6-5 LINKING THE CZECH NATIONAL CADASTRAL (COSMC) LAND-USE CATEGORIES TO THE IPCC LAND-USE CATEGORIES. COSMC CODES IN PARENTHESIS COMBINE TYPES OF PROPERTIES AND THEIR DOMINANT USE. 302
TAB. 6-6 LAND-USE MATRICES DESCRIBING ANNUAL INITIAL AND FINAL AREAS OF PARTICULAR LAND-USE CATEGORIES AND THE IDENTIFIED ANNUAL LAND-USE CONVERSIONS AMONG THESE CATEGORIES, SHOWN FOR 1990 AND 2024 305
TAB. 6-7 THE REPORTED HARVEST, TOTAL SHARE OF SALVAGE LOGGING IN THE REPORTED HARVEST, QUANTITY OF SALVAGE LOGGING BY DISTURBANCE TYPE (SOURCE DATA CZSO) AND TOTAL APPLICABLE ADDITIONAL HARVEST EXTRACTION (SOURCE INFORMATION IFER, CZSO) 312
TAB. 6-8 METHODOLOGICAL TIER INDICATING USE OF CBM IN ESTIMATION CARBON POOLS FOR THE CONCERNED LAND USE CATEGORIES AND THE FORMER KP LULUCF ACTIVITIES. *CARBON STOCK CHANGE IN ORGANIC SOIL IS NOT INCLUDED IN THIS TABLE, BUT IT IS ESTIMATED USING T1/T2 METHODOLOGIES. 313
TAB. 6-9 SPECIFIC INPUT DATA AND FACTORS USED TO ESTIMATE EMISSIONS OF N_2O AND CH_4 FROM PRESCRIBED BURNING IN FORESTS (1990 AND 2024 SHOWN) ACCORDING TO EQ. (1) 321
TAB. 6-10 CATEGORIES OF MANAGEMENT ACTIVITIES BY VEGETATION CATEGORY ON CROPLAND REMAINING CROPLAND, ATTRIBUTED LAND USE, TILLAGE (MANAGEMENT) AND INPUT FACTORS AND CORRESPONDING AREAS (1990 AND 2024 SHOWN) 333
TAB. 6-11 CATEGORIES OF MANAGEMENT ACTIVITIES BY VEGETATION CATEGORY ON GRASSLAND REMAINING GRASSLAND, ATTRIBUTED LAND USE, TILLAGE (MANAGEMENT) AND INPUT FACTORS AND CORRESPONDING AREAS (1990 AND 2024 SHOWN) – RELEVANT FOR MINERAL SOIL 339
TAB. 6-12 THE COUNTRY-SPECIFIC SHARES APPLICABLE FOR THE HWP QUANTITIES GIVEN FOR THE FORMER CZECHOSLOVAKIA IN THE FAO DATABASE, DERIVED FROM THE PERIOD 1993–1997 351
TAB. 7-1 THE OVERVIEW OF SIGNIFICANT SOURCE CATEGORIES IN THE WASTE SECTOR (2024) 355
TAB. 7-2 MSW AND IW (MUNICIPAL SOLID WASTE + INDUSTRIAL WASTE) DISPOSAL TO SWDS IN THE CZECH REPUBLIC [KT], 1990–2024 357
TAB. 7-3 MSW COMPOSITION FOR THE CZECH REPUBLIC USED IN THE QUANTIFICATION (FRACTIONS OF TOTAL, 1950–2024) 359
TAB. 7-4 METHANE CORRECTION FACTOR VALUES (IPCC, 2006) 360
TAB. 7-5 MCF VALUES EMPLOYED, 1950–2024 360
TAB. 7-6 METHANE FROM SWDS [KT], 1990–2024 361
TAB. 7-7 UNCERTAINTY ESTIMATES FOR 5.A CATEGORY 362
TAB. 7-8 EMISSIONS OF GHG (AND RELATED PARAMETERS) FROM COMPOSTING, 2005–2024 364
TAB. 7-9 EMISSIONS AND RELATED PARAMETERS FROM ANAEROBIC DIGESTION FACILITIES, 2003–2024 366
TAB. 7-10 UNCERTAINITY ESTIMATES FOR 5.B CATEGORY 366
TAB. 7-11 PARAMETERS OF INCINERATION USED FOR EACH TYPE OF WASTE AND THEIR ORIGIN 369
TAB. 7-12 WASTE INCINERATED [KT] BY TYPES 1990–2024 (2005–2024 DATA FROM ISOH, PRIOR TO 2005 EXTRAPOLATION) 370
TAB. 7-13 GHG EMISSIONS FROM WASTE INCINERATION FOR EACH TYPE OF WASTE 1990–2024 370
TAB. 7-14 UNCERTAINTY ESTIMATES FOR 5.C.1 CATEGORY 373
TAB. 7-15 EMISSION FACTORS FOR OPEN BURNING OF WASTE FOR EACH YEAR 375
TAB. 7-16 AMOUNT OF WASTE OPEN BURNED AND GENERATED EMISSIONS 2010–2024 375
TAB. 7-17 UNCERTAINTY ESTIMATES FOR 5.C.2 CATEGORY 376

TAB. 7-18 ACTIVITY DATA USED FOR 5.D.1 CATEGORY, 1990–2024 379
TAB. 7-19 PARAMETERS USED FOR 5.D.1 CATEGORY, 1990–2024 379
TAB. 7-20 METHANE EMISSIONS FROM 5.D.1 CATEGORY, 1990–2024 379
TAB. 7-21 INDIRECT N_2O EMISSIONS [KT] FROM 5.D.1 AND 5.D.2, 1990–2024 380
TAB. 7-22 UNCERTAINTY ESTIMATES FOR 5.D.1 CATEGORY 382
TAB. 7-23 INDUSTRIAL PRODUCTION DATA AND USED WATER GENERATION AND COD CONTENT FACTORS, 1990–2024 383
TAB. 7-24 USED MCF FOR INDUSTRIAL WASTE WATER TREATMENT 385
TAB. 7-25 EMISSIONS OF CH_4 [KT] FROM 5.D.2, 1990–2024 385
TAB. 7-26 UNCERTAINTY ESTIMATES FOR 5.D.2 CATEGORY 386
TAB. 7-27 LONG-TERM STORED CARBON, 1990–2024, CZECH REPUBLIC 387
TAB. 9-1 THE TOTAL OTHER EMISSIONS AND THEIR TRENDS FROM 1990–2024 390
TAB. 9-2 THE TOTAL OTHER EMISSIONS IN SECTORS OF ORIGIN FOR 2024 391
TAB. 9-3 TIME SERIES AND TREND OF INDIRECT EMISSIONS PER SECTOR AND TOTAL 1990–2024 396
TAB. 9-4 RECALCULATION OF INDIRECT CO_2 AND N_2O TOTAL EMISSIONS BETWEEN 1990–2024 400
TAB. 10-1 THE RECALCULATION IN ACTIVITY DATA WILL BE AS FOLLOWS. 401
TAB. 10-2 UPDATED ACTIVITY DATA DUE TO THE IMPROVEMENT PLAN 402
TAB. 10-3 RECALCULATIONS DUE TO THE UPDATED ACTIVITY DATA 402
TAB. 10-4 HOT N_2O EMISSION FACTORS OF EURO VI DIESEL HDVS IN COPERT 403
TAB. 10-5 IMPLICATIONS OF RECALCULATIONS ON CO_2 EMISSION LEVELS ON EXAMPLE ON 2023 EMISSION LEVELS 409
TAB. 10-6 IMPLICATIONS OF RECALCULATIONS ON CH_4 EMISSION LEVELS ON EXAMPLE ON 2023 EMISSION LEVELS 411
TAB. 10-7 IMPLICATIONS OF RECALCULATIONS ON N_2O EMISSION LEVELS ON EXAMPLE ON 2023 EMISSION LEVELS 412
TAB. 10-8 IMPLICATIONS OF RECALCULATIONS ON F-GASES EMISSION LEVELS ON EXAMPLE ON 2023 EMISSION LEVELS 413
TAB. 10-9 TABLE OF IMPLEMENTED IMPROVEMENTS IN THE 2026 SUBMISSION 418
TAB. 10-10 METHODOLOGICAL DESCRIPTIONS IN SUBMISSION 2026 419
TAB. 10-11 PLAN OF IMPROVEMENTS FOR KEY CATEGORIES 421

Annexes to the National Inventory Document

Annex 1 Key Categories

Key Categories were estimated using IPCC 2006 Gl. approach 1 including and excluding LULUCF. Tab. A1 1 till Tab. A1 4 followed the approach in Tables 4.2 and 4.3 of the IPCC 2006 Gl.

Tab. A1 1 Spreadsheet for Approach 1 KC IPCC 2006 Gl., 2024 – Level Assessment including LULUCF

IPCC Source Categories	GHG	Latest Year Emission or Removal Estimate (kt CO_2 eq.)	ABS Latest Year Emission or Removal Estimate (kt CO_2 eq.)	LA, %	Cumulative Total (LA, %)
1.A.1 Energy industries - Solid Fuels	CO_2	28240.73	28240.73	27.75	27.75
1.A.3.b Road Transportation	CO_2	20152.39	20152.39	19.80	47.55
1.A.4 Other Sectors - Gaseous Fuels	CO_2	5703.74	5703.74	5.60	53.15
1.A.2 Manufacturing Industries and Construction - Gaseous Fuels	CO_2	4586.76	4586.76	4.51	57.66
5.A Solid Waste Disposal	CH_4	3824.24	3824.24	3.76	61.42
3.A Enteric Fermentation	CH_4	3697.98	3697.98	3.63	65.05
2.F.1 Refrigeration and Air conditioning	F-gases	3450.95	3450.95	3.39	68.44
1.A.2 Manufacturing Industries and Construction - Solid Fuels	CO_2	3114.68	3114.68	3.06	71.50
2.C.1 Iron and Steel Production	CO_2	3025.57	3025.57	2.97	74.48
1.A.1 Energy industries - Gaseous Fuels	CO_2	2774.98	2774.98	2.73	77.20
4.A.1 Forest Land remaining Forest Land	CO_2	-2282.12	2282.12	2.24	79.45
3.D.1 Direct N_2O Emissions From Managed Soils	N_2O	2084.17	2084.17	2.05	81.49
1.A.4 Other Sectors - Solid Fuels	CO_2	1547.36	1547.36	1.52	83.01
2.A.1 Cement Production	CO_2	1449.97	1449.97	1.42	84.44
1.A.4 Other Sectors - Liquid Fuels	CO_2	1289.15	1289.15	1.27	85.70
4.G Harvested wood products	CO_2	-1285.43	1285.43	1.26	86.97
2.B.8 Petrochemical and Carbon Black Production	CO_2	922.85	922.85	0.91	87.87
5.D Wastewater treatment and discharge	CH_4	855.98	855.98	0.84	88.72
1.A.4 Other Sectors - Biomass	CH_4	644.08	644.08	0.63	89.35
4.A.2 Land converted to Forest Land	CO_2	-633.08	633.08	0.62	89.97
3.D.2 Indirect N_2O Emissions From Managed Soils	N_2O	579.50	579.50	0.57	90.54
1.A.2 Manufacturing Industries and Construction - Liquid Fuels	CO_2	577.96	577.96	0.57	91.11
5.B Biological treatment of solid waste	CH_4	499.57	499.57	0.49	91.60
2.A.4 Other Process Uses of Carbonates	CO_2	496.06	496.06	0.49	92.09
1.A.2 Manufacturing Industries and Construction - Other Fossil Fuels	CO_2	481.38	481.38	0.47	92.56
1.B.1.a Coal Mining and Handling	CH_4	474.57	474.57	0.47	93.03
2.B.1 Ammonia Production	CO_2	430.96	430.96	0.42	93.45
4.C.2 Land converted to Grassland	CO_2	-415.52	415.52	0.41	93.86
4.C.1 Grassland remaining Grassland	CO_2	-407.71	407.71	0.40	94.26
2.A.2 Lime Production	CO_2	397.91	397.91	0.39	94.65
3.B Manure Management	N_2O	390.50	390.50	0.38	95.03
3.B Manure Management	CH_4	371.21	371.21	0.36	95.40
1.A.1 Energy industries - Liquid Fuels	CO_2	359.48	359.48	0.35	95.75
1.B.2.b Fugitive Emissions from Fuels - Oil and Natural Gas - Natural Gas	CH_4	350.63	350.63	0.34	96.10
1.A.3.b Road Transportation	N_2O	335.89	335.89	0.33	96.43
1.A.1 Energy industries - Other Fossil Fuels	CO_2	320.00	320.00	0.31	96.74
4.E.2 Land converted to Settlements	CO_2	263.22	263.22	0.26	97.00

1.A.5.b Other mobile - Liquid Fuels	CO_2	242.25	242.25	0.24	97.24
1.A.3.c Railways	CO_2	215.90	215.90	0.21	97.45
5.D Wastewater treatment and discharge	N_2O	200.22	200.22	0.20	97.65
2.G Other Product Manufacture and Use	N_2O	198.75	198.75	0.20	97.84
3.H Urea application	CO_2	191.47	191.47	0.19	98.03
2.B.10 Other	CO_2	145.35	145.35	0.14	98.17
1.A.4 Other Sectors - Solid Fuels	CH_4	133.66	133.66	0.13	98.30
3.G Liming	CO_2	132.49	132.49	0.13	98.43
2.A.3 Glass Production	CO_2	131.66	131.66	0.13	98.56
4.B.2 Land converted to Cropland	CO_2	113.86	113.86	0.11	98.67
1.A.1 Energy industries - Solid Fuels	N_2O	112.63	112.63	0.11	98.78
1. Energy (indirect CO_2 emissions)	CO_2	93.02	93.02	0.09	98.88
2.B.2 Nitric Acid Production	N_2O	87.45	87.45	0.09	98.96
2.D.1 Lubricant Use	CO_2	84.30	84.30	0.08	99.04
1.A.4 Other Sectors - Biomass	N_2O	81.15	81.15	0.08	99.12
5.C Incineration and open burning of waste	CO_2	70.53	70.53	0.07	99.19
2.G Other Product Manufacture and Use	F-gases	65.28	65.28	0.06	99.26
5.B Biological treatment of solid waste	N_2O	63.22	63.22	0.06	99.32
1.B.1.a Coal Mining and Handling	CO_2	60.98	60.98	0.06	99.38
2.B.8 Petrochemical and Carbon Black Production	CH_4	51.89	51.89	0.05	99.43
2.E Electronics industry	F-gases	41.51	41.51	0.04	99.47
1.A.4 Other Sectors - Liquid Fuels	N_2O	38.22	38.22	0.04	99.51
1.A.2 Manufacturing Industries and Construction - Biomass	N_2O	36.85	36.85	0.04	99.55
1.A.1 Energy industries - Biomass	N_2O	34.76	34.76	0.03	99.58
2.F.3 Fire Protection	F-gases	33.79	33.79	0.03	99.61
1.A.2 Manufacturing Industries and Construction - Biomass	CH_4	29.32	29.32	0.03	99.64
1.A.1 Energy industries - Biomass	CH_4	27.56	27.56	0.03	99.67
1.A.3.b Road Transportation	CH_4	26.80	26.80	0.03	99.70
2.B.4 Caprolactam, glyoxal and glyoxylic acid production	N_2O	26.50	26.50	0.03	99.72
4.B.1 Cropland remaining Cropland	CO_2	-26.11	26.11	0.03	99.75
2.D.3 Other non-energy products from fuels and solvent use	CO_2	26.00	26.00	0.03	99.77
1.B.2.c Fugitive Emissions from Fuels - Venting and flaring	CH_4	19.37	19.37	0.02	99.79
1.A.3.a Domestic Aviation	CO_2	15.55	15.55	0.02	99.81
1.A.4 Other Sectors - Gaseous Fuels	CH_4	14.24	14.24	0.01	99.82
1.A.2 Manufacturing Industries and Construction - Solid Fuels	N_2O	12.17	12.17	0.01	99.83
4.D.2. Land converted to Wetlands	CO_2	11.65	11.65	0.01	99.84
2.C.5 Lead Production	CO_2	10.30	10.30	0.01	99.85
4.B.2. Land converted to Cropland	N_2O	9.77	9.77	0.01	99.86
1.A.3.d Transport - Domestic navigation	CO_2	9.44	9.44	0.01	99.87
1.A.2 Manufacturing Industries and Construction - Solid Fuels	CH_4	8.59	8.59	0.01	99.88
2.D.2 Paraffin Wax Use	CO_2	8.25	8.25	0.01	99.89
1.A.1 Energy industries - Solid Fuels	CH_4	8.12	8.12	0.01	99.90
1.A.5.b Other mobile - Liquid Fuels	N_2O	7.90	7.90	0.01	99.91
1.A.4 Other Sectors - Solid Fuels	N_2O	6.48	6.48	0.01	99.91
1.A.2 Manufacturing Industries and Construction - Other Fossil Fuels	N_2O	6.28	6.28	0.01	99.92
4.E.2 Land converted to Settlements	N_2O	5.96	5.96	0.01	99.92
4.C.1 Grassland remaining Grassland	CH_4	5.22	5.22	0.01	99.93
2.C.1 Iron and Steel Production	CH_4	5.12	5.12	0.01	99.93
1.A.2 Manufacturing Industries and Construction - Other Fossil Fuels	CH_4	4.98	4.98	0.00	99.94
5.C Incineration and open burning of waste	CH_4	4.97	4.97	0.00	99.94
4.A.1 Forest Land remaining Forest Land	N_2O	4.13	4.13	0.00	99.95
1.B.2.a Fugitive Emissions from Fuels - Oil and Natural Gas - Oil	CH_4	3.99	3.99	0.00	99.95
2.F.2 Foam Blowing Agents	F-gases	3.89	3.89	0.00	99.96

4.A.1 Forest Land remaining Forest Land	CH_4	3.73	3.73	0.00	99.96
1.A.1 Energy industries - Other Fossil Fuels	N_2O	3.70	3.70	0.00	99.96
2.C.2 Ferroalloys Production	CH_4	3.37	3.37	0.00	99.97
1.B.1.b Solid Fuel Transformation	CH_4	3.36	3.36	0.00	99.97
1.A.1 Energy industries - Other Fossil Fuels	CH_4	2.93	2.93	0.00	99.97
2.F.4 Aerosols	F-gases	2.91	2.91	0.00	99.98
5.C Incineration and open burning of waste	N_2O	2.87	2.87	0.00	99.98
1.B.2.c Fugitive Emissions from Fuels - Venting and flaring	CO_2	2.84	2.84	0.00	99.98
1.A.4 Other Sectors - Gaseous Fuels	N_2O	2.70	2.70	0.00	99.98
1.A.2 Manufacturing Industries and Construction - Gaseous Fuels	CH_4	2.29	2.29	0.00	99.99
1.A.2 Manufacturing Industries and Construction - Gaseous Fuels	N_2O	2.17	2.17	0.00	99.99
4.A.2 Land converted to Forest Land	N_2O	1.99	1.99	0.00	99.99
1.A.1 Energy industries - Gaseous Fuels	CH_4	1.39	1.39	0.00	99.99
1.A.1 Energy industries - Gaseous Fuels	N_2O	1.31	1.31	0.00	99.99
1.A.3.c Railways	CH_4	1.11	1.11	0.00	99.99
1.A.4 Other Sectors - Liquid Fuels	CH_4	1.05	1.05	0.00	99.99
1.A.3.e Other Transportation	CO_2	0.97	0.97	0.00	100.00
2.H Other	CO_2	0.94	0.94	0.00	100.00
1.A.2 Manufacturing Industries and Construction - Liquid Fuels	N_2O	0.92	0.92	0.00	100.00
1.A.2 Manufacturing Industries and Construction - Liquid Fuels	CH_4	0.53	0.53	0.00	100.00
1.A.3.c Railways	N_2O	0.47	0.47	0.00	100.00
2.C.2 Ferroalloys Production	CO_2	0.43	0.43	0.00	100.00
2.C.6 Zinc Production	CO_2	0.25	0.25	0.00	100.00
1.A.1 Energy industries - Liquid Fuels	N_2O	0.23	0.23	0.00	100.00
1.A.1 Energy industries - Liquid Fuels	CH_4	0.20	0.20	0.00	100.00
2.H Other	F-gases	0.18	0.18	0.00	100.00
1.A.3.a Domestic Aviation	N_2O	0.11	0.11	0.00	100.00
1.A.3.d Transport - Domestic navigation	N_2O	0.07	0.07	0.00	100.00
1.B.2.b Fugitive Emissions from Fuels - Oil and Natural Gas - Natural Gas	CO_2	0.05	0.05	0.00	100.00
1.A.5.b Other mobile - Liquid Fuels	CH_4	0.04	0.04	0.00	100.00
1.B.2.a Fugitive Emissions from Fuels - Oil and Natural Gas - Oil	CO_2	0.03	0.03	0.00	100.00
1.A.3.d Transport - Domestic navigation	CH_4	0.03	0.03	0.00	100.00
1.B.2.c Fugitive Emissions from Fuels - Venting and flaring	N_2O	0.01	0.01	0.00	100.00
1.A.3.a Domestic Aviation	CH_4	0.00	0.00	0.00	100.00

Tab. A1 2 Spreadsheet for Approach 1 KC IPCC 2006 Gl., 2024 – Trend Assessment including LULUCF

IPCC Source Categories	GHG	Base Year Estimate	Current Year Estimate	Trend Assessment	% contribution to Trend	Cumulative total of contribution to trend
1.A.3.b Road Transportation	CO_2	10251.31	20152.39	0.07	17.42	17.42
1.A.2 Manufacturing Industries and Construction - Solid Fuels	CO_2	35635.57	3114.68	0.07	16.84	34.27
1.A.4 Other Sectors - Solid Fuels	CO_2	24005.03	1547.36	0.05	11.98	46.25
4.A.1 Forest Land remaining Forest Land	CO_2	-8191.21	-2282.12	0.05	11.60	57.85
1.B.1.a Coal Mining and Handling	CH_4	8620.61	474.57	0.02	4.40	62.25
1.A.4 Other Sectors - Gaseous Fuels	CO_2	4173.90	5703.74	0.02	4.20	66.45
2.F.1 Refrigeration and Air conditioning	F-gases	0.00	3450.95	0.02	3.99	70.44
5.A Solid Waste Disposal	CH_4	2007.82	3824.24	0.01	3.27	73.71

1.A.2 Manufacturing Industries and Construction - Liquid Fuels	CO_2	5502.33	577.96	0.01	2.49	76.20
1.A.1 Energy industries - Gaseous Fuels	CO_2	1336.03	2774.98	0.01	2.44	78.64
2.C.1 Iron and Steel Production	CO_2	9782.03	3025.57	0.01	2.11	80.76
1.A.2 Manufacturing Industries and Construction - Gaseous Fuels	CO_2	5685.63	4586.76	0.01	2.04	82.80
1.A.1 Energy industries - Solid Fuels	CO_2	53719.76	28240.73	0.01	1.83	84.63
4.G Harvested wood products	CO_2	-1680.47	-1285.43	0.01	1.44	86.07
3.D.1 Direct N_2O Emissions From Managed Soils	N_2O	2192.74	2084.17	0.00	1.15	87.22
1.A.4 Other Sectors - Solid Fuels	CH_4	1491.69	133.66	0.00	0.70	87.92
1.A.4 Other Sectors - Liquid Fuels	CO_2	3775.90	1289.15	0.00	0.68	88.60
2.B.8 Petrochemical and Carbon Black Production	CO_2	792.47	922.85	0.00	0.61	89.21
5.B Biological treatment of solid waste	CH_4	0.00	499.57	0.00	0.58	89.79
1.A.2 Manufacturing Industries and Construction - Other Fossil Fuels	CO_2	0.00	481.38	0.00	0.56	90.34
3.G Liming	CO_2	1236.71	132.49	0.00	0.56	90.90
1.A.4 Other Sectors - Biomass	CH_4	363.17	644.08	0.00	0.54	91.44
3.A Enteric Fermentation	CH_4	6523.38	3697.98	0.00	0.53	91.97
2.A.4 Other Process Uses of Carbonates	CO_2	113.86	496.06	0.00	0.51	92.48
4.C.1 Grassland remaining Grassland	CO_2	59.69	-407.71	0.00	0.51	92.98
1. Energy (indirect CO_2 emissions)	CO_2	1020.18	93.02	0.00	0.48	93.46
3.B Manure Management	CH_4	1539.13	371.21	0.00	0.45	93.91
1.A.1 Energy industries - Liquid Fuels	CO_2	1514.04	359.48	0.00	0.45	94.37
2.B.2 Nitric Acid Production	N_2O	932.80	87.45	0.00	0.43	94.80
3.D.2 Indirect N_2O Emissions From Managed Soils	N_2O	437.48	579.50	0.00	0.42	95.22
4.A.2 Land converted to Forest Land	CO_2	-208.35	-633.08	0.00	0.37	95.59
5.D Wastewater treatment and discharge	CH_4	1082.93	855.98	0.00	0.37	95.96
1.A.1 Energy industries - Other Fossil Fuels	CO_2	24.04	320.00	0.00	0.36	96.31
1.A.3.b Road Transportation	N_2O	100.51	335.89	0.00	0.33	96.65
2.A.2 Lime Production	CO_2	1336.65	397.91	0.00	0.31	96.95
1.B.2.b Fugitive Emissions from Fuels - Oil and Natural Gas - Natural Gas	CH_4	1170.32	350.63	0.00	0.27	97.22
2.A.1 Cement Production	CO_2	2489.18	1449.97	0.00	0.25	97.47
1.B.1.a Coal Mining and Handling	CO_2	542.38	60.98	0.00	0.24	97.71
1.A.3.c Railways	CO_2	767.62	215.90	0.00	0.19	97.90
1.A.5.b Other mobile - Liquid Fuels	CO_2	191.93	242.25	0.00	0.17	98.07
2.B.10 Other	CO_2	0.00	145.35	0.00	0.17	98.24
3.H Urea application	CO_2	108.53	191.47	0.00	0.16	98.40
2.G Other Product Manufacture and Use	N_2O	183.38	198.75	0.00	0.12	98.52
5.D Wastewater treatment and discharge	N_2O	208.25	200.22	0.00	0.11	98.63
3.B Manure Management	N_2O	975.60	390.50	0.00	0.11	98.74
5.B Biological treatment of solid waste	N_2O	0.00	63.22	0.00	0.07	98.81
2.A.3 Glass Production	CO_2	142.75	131.66	0.00	0.07	98.88
2.B.1 Ammonia Production	CO_2	990.80	430.96	0.00	0.07	98.95
5.C Incineration and open burning of waste	CO_2	19.97	70.53	0.00	0.07	99.02
1.A.4 Other Sectors - Biomass	N_2O	45.79	81.15	0.00	0.07	99.09

1.A.2 Manufacturing Industries and Construction - Solid Fuels	N_2O	135.94	12.17	0.00	0.06	99.16
2.E Electronics industry	F-gases	0.00	41.51	0.00	0.05	99.20
1.A.4 Other Sectors - Solid Fuels	N_2O	91.86	6.48	0.00	0.05	99.25
1.A.2 Manufacturing Industries and Construction - Solid Fuels	CH_4	96.04	8.59	0.00	0.05	99.29
1.A.1 Energy industries - Biomass	N_2O	0.43	34.76	0.00	0.04	99.33
4.C.2 Land converted to Grassland	CO_2	-253.50	-415.52	0.00	0.04	99.37
2.F.3 Fire Protection	F-gases	0.00	33.79	0.00	0.04	99.41
4.D.2. Land converted to Wetlands	CO_2	-14.55	11.65	0.00	0.04	99.45
2.B.8 Petrochemical and Carbon Black Production	CH_4	40.51	51.89	0.00	0.04	99.49
4.E.2 Land converted to Settlements	CO_2	469.70	263.22	0.00	0.03	99.52
1.A.2 Manufacturing Industries and Construction - Biomass	N_2O	14.76	36.85	0.00	0.03	99.56
1.A.4 Other Sectors - Liquid Fuels	N_2O	17.79	38.22	0.00	0.03	99.59
1.A.1 Energy industries - Biomass	CH_4	0.34	27.56	0.00	0.03	99.62
2.D.1 Lubricant Use	CO_2	116.13	84.30	0.00	0.03	99.65
2.D.3 Other non-energy products from fuels and solvent use	CO_2	0.00	26.00	0.00	0.03	99.68
1.A.2 Manufacturing Industries and Construction - Biomass	CH_4	11.70	29.32	0.00	0.03	99.71
2.G Other Product Manufacture and Use	F-gases	86.57	65.28	0.00	0.03	99.74
4.B.2 Land converted to Cropland	CO_2	268.29	113.86	0.00	0.02	99.76
1.A.3.b Road Transportation	CH_4	88.66	26.80	0.00	0.02	99.78
1.A.3.d Transport - Domestic navigation	CO_2	53.48	9.44	0.00	0.02	99.80
1.A.3.a Domestic Aviation	CO_2	0.00	15.55	0.00	0.02	99.82
1.B.2.c Fugitive Emissions from Fuels - Venting and flaring	CH_4	13.76	19.37	0.00	0.01	99.83
1.A.4 Other Sectors - Gaseous Fuels	CH_4	10.72	14.24	0.00	0.01	99.84
2.C.5 Lead Production	CO_2	4.04	10.30	0.00	0.01	99.85
2.B.4 Caprolactam, glyoxal and glyoxylic acid production	N_2O	68.82	26.50	0.00	0.01	99.86
4.E.2 Land converted to Settlements	N_2O	26.94	5.96	0.00	0.01	99.87
4.B.1 Cropland remaining Cropland	CO_2	-12.68	-26.11	0.00	0.01	99.88
1.A.5.b Other mobile - Liquid Fuels	N_2O	1.74	7.90	0.00	0.01	99.88
1.A.1 Energy industries - Solid Fuels	N_2O	213.31	112.63	0.00	0.01	99.89
1.A.2 Manufacturing Industries and Construction - Other Fossil Fuels	N_2O	0.00	6.28	0.00	0.01	99.90
4.A.1 Forest Land remaining Forest Land	CH_4	19.77	3.73	0.00	0.01	99.91
1.A.4 Other Sectors - Liquid Fuels	CH_4	13.04	1.05	0.00	0.01	99.91
1.A.2 Manufacturing Industries and Construction - Other Fossil Fuels	CH_4	0.00	4.98	0.00	0.01	99.92
5.C Incineration and open burning of waste	CH_4	0.00	4.97	0.00	0.01	99.92
4.B.2. Land converted to Cropland	N_2O	29.32	9.77	0.00	0.01	99.93
1.A.2 Manufacturing Industries and Construction - Liquid Fuels	N_2O	11.42	0.92	0.00	0.01	99.94
2.C.6 Zinc Production	CO_2	8.70	0.25	0.00	0.00	99.94
2.F.2 Foam Blowing Agents	F-gases	0.00	3.89	0.00	0.00	99.94
2.D.2 Paraffin Wax Use	CO_2	9.43	8.25	0.00	0.00	99.95
1.A.1 Energy industries - Other Fossil Fuels	N_2O	0.28	3.70	0.00	0.00	99.95

2.C.2 Ferroalloys Production	CH_4	0.20	3.37	0.00	0.00	99.96
2.C.1 Iron and Steel Production	CH_4	16.62	5.12	0.00	0.00	99.96
1.B.1.b Solid Fuel Transformation	CH_4	0.84	3.36	0.00	0.00	99.96
2.F.4 Aerosols	F-gases	0.00	2.91	0.00	0.00	99.97
1.A.1 Energy industries - Other Fossil Fuels	CH_4	0.22	2.93	0.00	0.00	99.97
5.C Incineration and open burning of waste	N_2O	0.46	2.87	0.00	0.00	99.97
4.C.1 Grassland remaining Grassland	CH_4	5.22	5.22	0.00	0.00	99.98
1.A.2 Manufacturing Industries and Construction - Liquid Fuels	CH_4	6.03	0.53	0.00	0.00	99.98
4.A.1 Forest Land remaining Forest Land	N_2O	12.31	4.13	0.00	0.00	99.98
1.B.2.c Fugitive Emissions from Fuels - Venting and flaring	CO_2	2.02	2.84	0.00	0.00	99.98
1.A.3.e Other Transportation	CO_2	5.42	0.97	0.00	0.00	99.99
1.A.4 Other Sectors - Gaseous Fuels	N_2O	2.03	2.70	0.00	0.00	99.99
1.B.2.a Fugitive Emissions from Fuels - Oil and Natural Gas - Oil	CH_4	11.38	3.99	0.00	0.00	99.99
1.A.1 Energy industries - Liquid Fuels	N_2O	2.94	0.23	0.00	0.00	99.99
1.A.1 Energy industries - Gaseous Fuels	CH_4	0.69	1.39	0.00	0.00	99.99
1.A.1 Energy industries - Gaseous Fuels	N_2O	0.65	1.31	0.00	0.00	99.99
2.H Other	CO_2	0.00	0.94	0.00	0.00	99.99
1.A.2 Manufacturing Industries and Construction - Gaseous Fuels	CH_4	2.92	2.29	0.00	0.00	100.00
1.A.2 Manufacturing Industries and Construction - Gaseous Fuels	N_2O	2.76	2.17	0.00	0.00	100.00
1.A.1 Energy industries - Liquid Fuels	CH_4	1.59	0.20	0.00	0.00	100.00
1.A.3.c Railways	CH_4	1.23	1.11	0.00	0.00	100.00
2.C.2 Ferroalloys Production	CO_2	0.03	0.43	0.00	0.00	100.00
1.A.1 Energy industries - Solid Fuels	CH_4	15.72	8.12	0.00	0.00	100.00
1.A.3.c Railways	N_2O	1.55	0.47	0.00	0.00	100.00
1.A.5.b Other mobile - Liquid Fuels	CH_4	0.64	0.04	0.00	0.00	100.00
2.H Other	F-gases	0.00	0.18	0.00	0.00	100.00
1.A.3.d Transport - Domestic navigation	N_2O	0.38	0.07	0.00	0.00	100.00
1.A.3.a Domestic Aviation	N_2O	0.00	0.11	0.00	0.00	100.00
1.A.3.d Transport - Domestic navigation	CH_4	0.14	0.03	0.00	0.00	100.00
1.B.2.b Fugitive Emissions from Fuels - Oil and Natural Gas - Natural Gas	CO_2	0.17	0.05	0.00	0.00	100.00
1.B.2.a Fugitive Emissions from Fuels - Oil and Natural Gas - Oil	CO_2	0.02	0.03	0.00	0.00	100.00
1.B.2.c Fugitive Emissions from Fuels - Venting and flaring	N_2O	0.01	0.01	0.00	0.00	100.00
4.A.2 Land converted to Forest Land	N_2O	4.02	1.99	0.00	0.00	100.00
1.A.3.a Domestic Aviation	CH_4	0.00	0.00	0.00	0.00	100.00

Tab. A1 3 Spreadsheet for Approach 1 KC IPCC 2006 Gl., 2024 – Level Assessment excluding LULUCF

IPCC Source Categories	GHG	Latest Year Emission or Removal Estimate (kt CO_2 eq.)	ABS Latest Year Emission or Removal Estimate (kt CO_2 eq.)	LA, %	Cumulative Total (LA, %)
1.A.1 Energy industries - Solid Fuels	CO_2	28240.73	28240.73	29.32	29.32

1.A.3.b Road Transportation	CO_2	20152.39	20152.39	20.93	50.25
1.A.4 Other Sectors - Gaseous Fuels	CO_2	5703.74	5703.74	5.92	56.17
1.A.2 Manufacturing Industries and Construction - Gaseous Fuels	CO_2	4586.76	4586.76	4.76	60.94
5.A Solid Waste Disposal	CH_4	3824.24	3824.24	3.97	64.91
3.A Enteric Fermentation	CH_4	3697.98	3697.98	3.84	68.75
2.F.1 Refrigeration and Air conditioning	F-gases	3450.95	3450.95	3.58	72.33
1.A.2 Manufacturing Industries and Construction - Solid Fuels	CO_2	3114.68	3114.68	3.23	75.56
2.C.1 Iron and Steel Production	CO_2	3025.57	3025.57	3.14	78.71
1.A.1 Energy industries - Gaseous Fuels	CO_2	2774.98	2774.98	2.88	81.59
3.D.1 Direct N2O Emissions From Managed Soils	N_2O	2084.17	2084.17	2.16	83.75
1.A.4 Other Sectors - Solid Fuels	CO_2	1547.36	1547.36	1.61	85.36
2.A.1 Cement Production	CO_2	1449.97	1449.97	1.51	86.86
1.A.4 Other Sectors - Liquid Fuels	CO_2	1289.15	1289.15	1.34	88.20
2.B.8 Petrochemical and Carbon Black Production	CO_2	922.85	922.85	0.96	89.16
5.D Wastewater treatment and discharge	CH_4	855.98	855.98	0.89	90.05
1.A.4 Other Sectors - Biomass	CH_4	644.08	644.08	0.67	90.72
3.D.2 Indirect N_2O Emissions From Managed Soils	N_2O	579.50	579.50	0.60	91.32
1.A.2 Manufacturing Industries and Construction - Liquid Fuels	CO_2	577.96	577.96	0.60	91.92
5.B Biological treatment of solid waste	CH_4	499.57	499.57	0.52	92.44
2.A.4 Other Process Uses of Carbonates	CO_2	496.06	496.06	0.52	92.95
1.A.2 Manufacturing Industries and Construction - Other Fossil Fuels	CO_2	481.38	481.38	0.50	93.45
1.B.1.a Coal Mining and Handling	CH_4	474.57	474.57	0.49	93.95
2.B.1 Ammonia Production	CO_2	430.96	430.96	0.45	94.39
2.A.2 Lime Production	CO_2	397.91	397.91	0.41	94.81
3.B Manure Management	N_2O	390.50	390.50	0.41	95.21
3.B Manure Management	CH_4	371.21	371.21	0.39	95.60
1.A.1 Energy industries - Liquid Fuels	CO_2	359.48	359.48	0.37	95.97
1.B.2.b Fugitive Emissions from Fuels - Oil and Natural Gas - Natural Gas	CH_4	350.63	350.63	0.36	96.34
1.A.3.b Road Transportation	N_2O	335.89	335.89	0.35	96.68
1.A.1 Energy industries - Other Fossil Fuels	CO_2	320.00	320.00	0.33	97.02
1.A.5.b Other mobile - Liquid Fuels	CO_2	242.25	242.25	0.25	97.27
1.A.3.c Railways	CO_2	215.90	215.90	0.22	97.49
5.D Wastewater treatment and discharge	N_2O	200.22	200.22	0.21	97.70
2.G Other Product Manufacture and Use	N_2O	198.75	198.75	0.21	97.91
3.H Urea application	CO_2	191.47	191.47	0.20	98.11
2.B.10 Other	CO_2	145.35	145.35	0.15	98.26
1.A.4 Other Sectors - Solid Fuels	CH_4	133.66	133.66	0.14	98.40
3.G Liming	CO_2	132.49	132.49	0.14	98.53
2.A.3 Glass Production	CO_2	131.66	131.66	0.14	98.67
1.A.1 Energy industries - Solid Fuels	N_2O	112.63	112.63	0.12	98.79
1. Energy (indirect CO_2 emissions)	CO_2	93.02	93.02	0.10	98.88
2.B.2 Nitric Acid Production	N_2O	87.45	87.45	0.09	98.97

2.D.1 Lubricant Use	CO_2	84.30	84.30	0.09	99.06
1.A.4 Other Sectors - Biomass	N_2O	81.15	81.15	0.08	99.15
5.C Incineration and open burning of waste	CO_2	70.53	70.53	0.07	99.22
2.G Other Product Manufacture and Use	F-gases	65.28	65.28	0.07	99.29
5.B Biological treatment of solid waste	N_2O	63.22	63.22	0.07	99.35
1.B.1.a Coal Mining and Handling	CO_2	60.98	60.98	0.06	99.42
2.B.8 Petrochemical and Carbon Black Production	CH_4	51.89	51.89	0.05	99.47
2.E Electronics industry	F-gases	41.51	41.51	0.04	99.51
1.A.4 Other Sectors - Liquid Fuels	N_2O	38.22	38.22	0.04	99.55
1.A.2 Manufacturing Industries and Construction - Biomass	N_2O	36.85	36.85	0.04	99.59
1.A.1 Energy industries - Biomass	N_2O	34.76	34.76	0.04	99.63
2.F.3 Fire Protection	F-gases	33.79	33.79	0.04	99.66
1.A.2 Manufacturing Industries and Construction - Biomass	CH_4	29.32	29.32	0.03	99.69
1.A.1 Energy industries - Biomass	CH_4	27.56	27.56	0.03	99.72
1.A.3.b Road Transportation	CH_4	26.80	26.80	0.03	99.75
2.B.4 Caprolactam, glyoxal and glyoxylic acid production	N_2O	26.50	26.50	0.03	99.78
2.D.3 Other non-energy products from fuels and solvent use	CO_2	26.00	26.00	0.03	99.80
1.B.2.c Fugitive Emissions from Fuels - Venting and flaring	CH_4	19.37	19.37	0.02	99.82
1.A.3.a Domestic Aviation	CO_2	15.55	15.55	0.02	99.84
1.A.4 Other Sectors - Gaseous Fuels	CH_4	14.24	14.24	0.01	99.85
1.A.2 Manufacturing Industries and Construction - Solid Fuels	N_2O	12.17	12.17	0.01	99.87
2.C.5 Lead Production	CO_2	10.30	10.30	0.01	99.88
1.A.3.d Transport - Domestic navigation	CO_2	9.44	9.44	0.01	99.89
1.A.2 Manufacturing Industries and Construction - Solid Fuels	CH_4	8.59	8.59	0.01	99.90
1.A.1 Energy industries - Solid Fuels	CH_4	8.12	8.12	0.01	99.91
1.A.5.b Other mobile - Liquid Fuels	N_2O	7.90	7.90	0.01	99.92
1.A.4 Other Sectors - Solid Fuels	N_2O	6.48	6.48	0.01	99.93
1.A.2 Manufacturing Industries and Construction - Other Fossil Fuels	N_2O	6.28	6.28	0.01	99.94
2.C.1 Iron and Steel Production	CH_4	5.12	5.12	0.01	99.94
1.A.2 Manufacturing Industries and Construction - Other Fossil Fuels	CH_4	4.98	4.98	0.01	99.95
5.C Incineration and open burning of waste	CH_4	4.97	4.97	0.01	99.95
1.B.2.a Fugitive Emissions from Fuels - Oil and Natural Gas - Oil	CH_4	3.99	3.99	0.00	99.96
2.F.2 Foam Blowing Agents	F-gases	3.89	3.89	0.00	99.96
1.A.1 Energy industries - Other Fossil Fuels	N_2O	3.70	3.70	0.00	99.96
2.C.2 Ferroalloys Production	CH_4	3.37	3.37	0.00	99.97
1.B.1.b Solid Fuel Transformation	CH_4	3.36	3.36	0.00	99.97
1.A.1 Energy industries - Other Fossil Fuels	CH_4	2.93	2.93	0.00	99.97
2.F.4 Aerosols	F-gases	2.91	2.91	0.00	99.98
5.C Incineration and open burning of waste	N_2O	2.87	2.87	0.00	99.98
1.B.2.c Fugitive Emissions from Fuels - Venting and flaring	CO_2	2.84	2.84	0.00	99.98

1.A.4 Other Sectors - Gaseous Fuels	N_2O	2.70	2.70	0.00	99.98
1.A.2 Manufacturing Industries and Construction - Gaseous Fuels	CH_4	2.29	2.29	0.00	99.99
1.A.2 Manufacturing Industries and Construction - Gaseous Fuels	N_2O	2.17	2.17	0.00	99.99
1.A.1 Energy industries - Gaseous Fuels	CH_4	1.39	1.39	0.00	99.99
1.A.1 Energy industries - Gaseous Fuels	N_2O	1.31	1.31	0.00	99.99
1.A.3.c Railways	CH_4	1.11	1.11	0.00	99.99
1.A.4 Other Sectors - Liquid Fuels	CH_4	1.05	1.05	0.00	99.99
1.A.3.e Other Transportation	CO_2	0.97	0.97	0.00	100.00
2.H Other	CO_2	0.94	0.94	0.00	100.00
1.A.2 Manufacturing Industries and Construction - Liquid Fuels	N_2O	0.92	0.92	0.00	100.00
1.A.2 Manufacturing Industries and Construction - Liquid Fuels	CH_4	0.53	0.53	0.00	100.00
1.A.3.c Railways	N_2O	0.47	0.47	0.00	100.00
2.C.2 Ferroalloys Production	CO_2	0.43	0.43	0.00	100.00
2.C.6 Zinc Production	CO_2	0.25	0.25	0.00	100.00
1.A.1 Energy industries - Liquid Fuels	N_2O	0.23	0.23	0.00	100.00
1.A.1 Energy industries - Liquid Fuels	CH_4	0.20	0.20	0.00	100.00
2.H Other	F-gases	0.18	0.18	0.00	100.00
1.A.3.a Domestic Aviation	N_2O	0.11	0.11	0.00	100.00
1.A.3.d Transport - Domestic navigation	N_2O	0.07	0.07	0.00	100.00
1.B.2.b Fugitive Emissions from Fuels - Oil and Natural Gas - Natural Gas	CO_2	0.05	0.05	0.00	100.00
1.A.5.b Other mobile - Liquid Fuels	CH_4	0.04	0.04	0.00	100.00
1.B.2.a Fugitive Emissions from Fuels - Oil and Natural Gas - Oil	CO_2	0.03	0.03	0.00	100.00
1.A.3.d Transport - Domestic navigation	CH_4	0.03	0.03	0.00	100.00
1.B.2.c Fugitive Emissions from Fuels - Venting and flaring	N_2O	0.01	0.01	0.00	100.00
1.A.3.a Domestic Aviation	CH_4	0.00	0.00	0.00	100.00
1.A.3.e Other Transportation	CH_4	0.00	0.00	0.00	100.00
1.A.3.e Other Transportation	N_2O	0.00	0.00	0.00	100.00
2.F.5 Solvents	F-gases	0.00	0.00	0.00	100.00

Tab. A1 4 Spreadsheet for Approach 1 KC IPCC 2006 Gl., 2024 – Trend Assessment excluding LULUCF

IPCC Source Categories	GHG	Base Year Estimate	Current Year Estimate	Trend Assessment	% contribution to Trend	Cumulative total of contribution to trend
1.A.3.b Road Transportation	CO_2	10251.31	20152.39	0.08	20.28	20.28
1.A.2 Manufacturing Industries and Construction - Solid Fuels	CO_2	35635.57	3114.68	0.07	19.59	39.87
1.A.4 Other Sectors - Solid Fuels	CO_2	24005.03	1547.36	0.05	13.94	53.81
1.B.1.a Coal Mining and Handling	CH_4	8620.61	474.57	0.02	5.11	58.93
1.A.4 Other Sectors - Gaseous Fuels	CO_2	4173.90	5703.74	0.02	4.89	63.82
2.F.1 Refrigeration and Air conditioning	F-gases	0.00	3450.95	0.02	4.64	68.46
5.A Solid Waste Disposal	CH_4	2007.82	3824.24	0.01	3.81	72.27

1.A.2 Manufacturing Industries and Construction - Liquid Fuels	CO_2	5502.33	577.96	0.01	2.89	75.16
1.A.1 Energy industries - Gaseous Fuels	CO_2	1336.03	2774.98	0.01	2.84	78.01
2.C.1 Iron and Steel Production	CO_2	9782.03	3025.57	0.01	2.46	80.46
1.A.2 Manufacturing Industries and Construction - Gaseous Fuels	CO_2	5685.63	4586.76	0.01	2.38	82.84
1.A.1 Energy industries - Solid Fuels	CO_2	53719.76	28240.73	0.01	2.16	85.00
3.D.1 Direct N2O Emissions From Managed Soils	N_2O	2192.74	2084.17	0.01	1.34	86.34
1.A.4 Other Sectors - Solid Fuels	CH_4	1491.69	133.66	0.00	0.82	87.16
1.A.4 Other Sectors - Liquid Fuels	CO_2	3775.90	1289.15	0.00	0.78	87.94
2.B.8 Petrochemical and Carbon Black Production	CO_2	792.47	922.85	0.00	0.71	88.66
5.B Biological treatment of solid waste	CH_4	0.00	499.57	0.00	0.67	89.33
1.A.2 Manufacturing Industries and Construction - Other Fossil Fuels	CO_2	0.00	481.38	0.00	0.65	89.98
3.G Liming	CO_2	1236.71	132.49	0.00	0.65	90.62
1.A.4 Other Sectors - Biomass	CH_4	363.17	644.08	0.00	0.62	91.25
3.A Enteric Fermentation	CH_4	6523.38	3697.98	0.00	0.62	91.87
2.A.4 Other Process Uses of Carbonates	CO_2	113.86	496.06	0.00	0.59	92.46
1. Energy (indirect CO_2 emissions)	CO_2	1020.18	93.02	0.00	0.56	93.02
3.B Manure Management	CH_4	1539.13	371.21	0.00	0.53	93.55
1.A.1 Energy industries - Liquid Fuels	CO_2	1514.04	359.48	0.00	0.53	94.07
2.B.2 Nitric Acid Production	N_2O	932.80	87.45	0.00	0.50	94.58
3.D.2 Indirect N_2O Emissions From Managed Soils	N_2O	437.48	579.50	0.00	0.49	95.07
5.D Wastewater treatment and discharge	CH_4	1082.93	855.98	0.00	0.43	95.50
1.A.1 Energy industries - Other Fossil Fuels	CO_2	24.04	320.00	0.00	0.41	95.91
1.A.3.b Road Transportation	N_2O	100.51	335.89	0.00	0.39	96.29
2.A.2 Lime Production	CO_2	1336.65	397.91	0.00	0.36	96.65
1.B.2.b Fugitive Emissions from Fuels - Oil and Natural Gas - Natural Gas	CH_4	1170.32	350.63	0.00	0.31	96.96
2.A.1 Cement Production	CO_2	2489.18	1449.97	0.00	0.29	97.25
1.B.1.a Coal Mining and Handling	CO_2	542.38	60.98	0.00	0.28	97.53
1.A.3.c Railways	CO_2	767.62	215.90	0.00	0.22	97.75
1.A.5.b Other mobile - Liquid Fuels	CO_2	191.93	242.25	0.00	0.20	97.95
2.B.10 Other	CO_2	0.00	145.35	0.00	0.20	98.15
3.H Urea application	CO_2	108.53	191.47	0.00	0.19	98.33
2.G Other Product Manufacture and Use	N_2O	183.38	198.75	0.00	0.15	98.48
5.D Wastewater treatment and discharge	N_2O	208.25	200.22	0.00	0.13	98.61
3.B Manure Management	N_2O	975.60	390.50	0.00	0.13	98.73
5.B Biological treatment of solid waste	N_2O	0.00	63.22	0.00	0.09	98.82
2.A.3 Glass Production	CO_2	142.75	131.66	0.00	0.08	98.90
5.C Incineration and open burning of waste	CO_2	19.97	70.53	0.00	0.08	98.98
2.B.1 Ammonia Production	CO_2	990.80	430.96	0.00	0.08	99.06
1.A.4 Other Sectors - Biomass	N_2O	45.79	81.15	0.00	0.08	99.14
1.A.2 Manufacturing Industries and Construction - Solid Fuels	N_2O	135.94	12.17	0.00	0.07	99.22
2.E Electronics industry	F-gases	0.00	41.51	0.00	0.06	99.27

1.A.4 Other Sectors - Solid Fuels	N_2O	91.86	6.48	0.00	0.05	99.32
1.A.2 Manufacturing Industries and Construction - Solid Fuels	CH_4	96.04	8.59	0.00	0.05	99.38
1.A.1 Energy industries - Biomass	N_2O	0.43	34.76	0.00	0.05	99.42
2.F.3 Fire Protection	F-gases	0.00	33.79	0.00	0.05	99.47
2.B.8 Petrochemical and Carbon Black Production	CH_4	40.51	51.89	0.00	0.04	99.51
1.A.2 Manufacturing Industries and Construction - Biomass	N_2O	14.76	36.85	0.00	0.04	99.55
1.A.4 Other Sectors - Liquid Fuels	N_2O	17.79	38.22	0.00	0.04	99.59
1.A.1 Energy industries - Biomass	CH_4	0.34	27.56	0.00	0.04	99.63
2.D.1 Lubricant Use	CO_2	116.13	84.30	0.00	0.04	99.66
2.D.3 Other non-energy products from fuels and solvent use	CO_2	0.00	26.00	0.00	0.03	99.70
1.A.2 Manufacturing Industries and Construction - Biomass	CH_4	11.70	29.32	0.00	0.03	99.73
2.G Other Product Manufacture and Use	F-gases	86.57	65.28	0.00	0.03	99.76
1.A.3.b Road Transportation	CH_4	88.66	26.80	0.00	0.02	99.78
1.A.3.d Transport - Domestic navigation	CO_2	53.48	9.44	0.00	0.02	99.81
1.A.3.a Domestic Aviation	CO_2	0.00	15.55	0.00	0.02	99.83
1.B.2.c Fugitive Emissions from Fuels - Venting and flaring	CH_4	13.76	19.37	0.00	0.02	99.84
1.A.4 Other Sectors - Gaseous Fuels	CH_4	10.72	14.24	0.00	0.01	99.86
2.C.5 Lead Production	CO_2	4.04	10.30	0.00	0.01	99.87
2.B.4 Caprolactam, glyoxal and glyoxylic acid production	N_2O	68.82	26.50	0.00	0.01	99.88
1.A.5.b Other mobile - Liquid Fuels	N_2O	1.74	7.90	0.00	0.01	99.89
1.A.1 Energy industries - Solid Fuels	N_2O	213.31	112.63	0.00	0.01	99.90
1.A.2 Manufacturing Industries and Construction - Other Fossil Fuels	N_2O	0.00	6.28	0.00	0.01	99.90
1.A.4 Other Sectors - Liquid Fuels	CH_4	13.04	1.05	0.00	0.01	99.91
1.A.2 Manufacturing Industries and Construction - Other Fossil Fuels	CH_4	0.00	4.98	0.00	0.01	99.92
5.C Incineration and open burning of waste	CH_4	0.00	4.97	0.00	0.01	99.93
1.A.2 Manufacturing Industries and Construction - Liquid Fuels	N_2O	11.42	0.92	0.00	0.01	99.93
2.C.6 Zinc Production	CO_2	8.70	0.25	0.00	0.01	99.94
2.F.2 Foam Blowing Agents	F-gases	0.00	3.89	0.00	0.01	99.94
2.D.2 Paraffin Wax Use	CO_2	9.43	8.25	0.00	0.00	99.95
1.A.1 Energy industries - Other Fossil Fuels	N_2O	0.28	3.70	0.00	0.00	99.95
2.C.2 Ferroalloys Production	CH_4	0.20	3.37	0.00	0.00	99.96
2.C.1 Iron and Steel Production	CH_4	16.62	5.12	0.00	0.00	99.96
1.B.1.b Solid Fuel Transformation	CH_4	0.84	3.36	0.00	0.00	99.96
2.F.4 Aerosols	F-gases	0.00	2.91	0.00	0.00	99.97
1.A.1 Energy industries - Other Fossil Fuels	CH_4	0.22	2.93	0.00	0.00	99.97
5.C Incineration and open burning of waste	N_2O	0.46	2.87	0.00	0.00	99.98
1.A.2 Manufacturing Industries and Construction - Liquid Fuels	CH_4	6.03	0.53	0.00	0.00	99.98
1.B.2.c Fugitive Emissions from Fuels - Venting and flaring	CO_2	2.02	2.84	0.00	0.00	99.98
1.A.3.e Other Transportation	CO_2	5.42	0.97	0.00	0.00	99.98

1.A.4 Other Sectors - Gaseous Fuels	N_2O	2.03	2.70	0.00	0.00	99.99
1.B.2.a Fugitive Emissions from Fuels - Oil and Natural Gas - Oil	CH_4	11.38	3.99	0.00	0.00	99.99
1.A.1 Energy industries - Liquid Fuels	N_2O	2.94	0.23	0.00	0.00	99.99
1.A.1 Energy industries - Gaseous Fuels	CH_4	0.69	1.39	0.00	0.00	99.99
1.A.1 Energy industries - Gaseous Fuels	N_2O	0.65	1.31	0.00	0.00	99.99
2.H Other	CO_2	0.00	0.94	0.00	0.00	99.99
1.A.2 Manufacturing Industries and Construction - Gaseous Fuels	CH_4	2.92	2.29	0.00	0.00	99.99
1.A.2 Manufacturing Industries and Construction - Gaseous Fuels	N_2O	2.76	2.17	0.00	0.00	100.00
1.A.1 Energy industries - Liquid Fuels	CH_4	1.59	0.20	0.00	0.00	100.00
1.A.3.c Railways	CH_4	1.23	1.11	0.00	0.00	100.00
2.C.2 Ferroalloys Production	CO_2	0.03	0.43	0.00	0.00	100.00
1.A.1 Energy industries - Solid Fuels	CH_4	15.72	8.12	0.00	0.00	100.00
1.A.3.c Railways	N_2O	1.55	0.47	0.00	0.00	100.00
1.A.5.b Other mobile - Liquid Fuels	CH_4	0.64	0.04	0.00	0.00	100.00
2.H Other	F-gases	0.00	0.18	0.00	0.00	100.00
1.A.3.d Transport - Domestic navigation	N_2O	0.38	0.07	0.00	0.00	100.00
1.A.3.a Domestic Aviation	N_2O	0.00	0.11	0.00	0.00	100.00
1.A.3.d Transport - Domestic navigation	CH_4	0.14	0.03	0.00	0.00	100.00
1.B.2.b Fugitive Emissions from Fuels - Oil and Natural Gas - Natural Gas	CO_2	0.17	0.05	0.00	0.00	100.00
1.B.2.a Fugitive Emissions from Fuels - Oil and Natural Gas - Oil	CO_2	0.02	0.03	0.00	0.00	100.00
1.B.2.c Fugitive Emissions from Fuels - Venting and flaring	N_2O	0.01	0.01	0.00	0.00	100.00
1.A.3.a Domestic Aviation	CH_4	0.00	0.00	0.00	0.00	100.00
1.A.3.e Other Transportation	CH_4	0.00	0.00	0.00	0.00	100.00
1.A.3.e Other Transportation	N_2O	0.00	0.00	0.00	0.00	100.00

Tab. A1 5 Spreadsheet for Approach 1 KC IPCC 2006 Gl., 1990 – Level Assessment including LULUCF

IPCC Source Categories	GHG	Base Year Estimate	Base Year Estimate (Abs)	Level Assessment	Cumulative Total (LA)
1.A.1 Energy industries - Solid Fuels	CO_2	53719.76	53719.76	26.14	26.14
1.A.2 Manufacturing Industries and Construction - Solid Fuels	CO_2	35635.57	35635.57	17.34	43.49
1.A.4 Other Sectors - Solid Fuels	CO_2	24005.03	24005.03	11.68	55.17
1.A.3.b Road Transportation	CO_2	10251.31	10251.31	4.99	60.16
2.C.1 Iron and Steel Production	CO_2	9782.03	9782.03	4.76	64.92
1.B.1.a Coal Mining and Handling	CH_4	8620.61	8620.61	4.20	69.11
4.A.1 Forest Land remaining Forest Land	CO_2	-8191.21	8191.21	3.99	73.10
3.A Enteric Fermentation	CH_4	6523.38	6523.38	3.17	76.28
1.A.2 Manufacturing Industries and Construction - Gaseous Fuels	CO_2	5685.63	5685.63	2.77	79.04
1.A.2 Manufacturing Industries and Construction - Liquid Fuels	CO_2	5502.33	5502.33	2.68	81.72
1.A.4 Other Sectors - Gaseous Fuels	CO_2	4173.90	4173.90	2.03	83.75
1.A.4 Other Sectors - Liquid Fuels	CO_2	3775.90	3775.90	1.84	85.59

2.A.1 Cement Production	CO_2	2489.18	2489.18	1.21	86.80
3.D.1 Direct N2O Emissions From Managed Soils	N_2O	2192.74	2192.74	1.07	87.87
5.A Solid Waste Disposal	CH_4	2007.82	2007.82	0.98	88.85
4.G Harvested wood products	CO_2	-1680.47	1680.47	0.82	89.66
3.B Manure Management	CH_4	1539.13	1539.13	0.75	90.41
1.A.1 Energy industries - Liquid Fuels	CO_2	1514.04	1514.04	0.74	91.15
1.A.4 Other Sectors - Solid Fuels	CH_4	1491.69	1491.69	0.73	91.88
2.A.2 Lime Production	CO_2	1336.65	1336.65	0.65	92.53
1.A.1 Energy industries - Gaseous Fuels	CO_2	1336.03	1336.03	0.65	93.18
3.G Liming	CO_2	1236.71	1236.71	0.60	93.78
1.B.2.b Fugitive Emissions from Fuels - Oil and Natural Gas - Natural Gas	CH_4	1170.32	1170.32	0.57	94.35
5.D Wastewater treatment and discharge	CH_4	1082.93	1082.93	0.53	94.87
1. Energy (indirect CO_2 emissions)	CO_2	1020.18	1020.18	0.50	95.37
2.B.1 Ammonia Production	CO_2	990.80	990.80	0.48	95.85
3.B Manure Management	N_2O	975.60	975.60	0.47	96.33
2.B.2 Nitric Acid Production	N_2O	932.80	932.80	0.45	96.78
2.B.8 Petrochemical and Carbon Black Production	CO_2	792.47	792.47	0.39	97.17
1.A.3.c Railways	CO_2	767.62	767.62	0.37	97.54
1.B.1.a Coal Mining and Handling	CO_2	542.38	542.38	0.26	97.81
4.E.2 Land converted to Settlements	CO_2	469.70	469.70	0.23	98.03
3.D.2 Indirect N_2O Emissions From Managed Soils	N_2O	437.48	437.48	0.21	98.25
1.A.4 Other Sectors - Biomass	CH_4	363.17	363.17	0.18	98.42
4.B.2 Land converted to Cropland	CO_2	268.29	268.29	0.13	98.55
4.C.2 Land converted to Grassland	CO_2	-253.50	253.50	0.12	98.68
1.A.1 Energy industries - Solid Fuels	N_2O	213.31	213.31	0.10	98.78
4.A.2 Land converted to Forest Land	CO_2	-208.35	208.35	0.10	98.88
5.D Wastewater treatment and discharge	N_2O	208.25	208.25	0.10	98.98
1.A.5.b Other mobile - Liquid Fuels	CO_2	191.93	191.93	0.09	99.08
2.G Other Product Manufacture and Use	N_2O	183.38	183.38	0.09	99.17
2.A.3 Glass Production	CO_2	142.75	142.75	0.07	99.24
1.A.2 Manufacturing Industries and Construction - Solid Fuels	N_2O	135.94	135.94	0.07	99.30
2.D.1 Lubricant Use	CO_2	116.13	116.13	0.06	99.36
2.A.4 Other Process Uses of Carbonates	CO_2	113.86	113.86	0.06	99.41
3.H Urea application	CO_2	108.53	108.53	0.05	99.47
1.A.3.b Road Transportation	N_2O	100.51	100.51	0.05	99.52
1.A.2 Manufacturing Industries and Construction - Solid Fuels	CH_4	96.04	96.04	0.05	99.56
1.A.4 Other Sectors - Solid Fuels	N_2O	91.86	91.86	0.04	99.61
1.A.3.b Road Transportation	CH_4	88.66	88.66	0.04	99.65
2.G Other Product Manufacture and Use	F-gases	86.57	86.57	0.04	99.69
2.B.4 Caprolactam, glyoxal and glyoxylic acid production	N_2O	68.82	68.82	0.03	99.73
4.C.1 Grassland remaining Grassland	CO_2	59.69	59.69	0.03	99.76
1.A.3.d Transport - Domestic navigation	CO_2	53.48	53.48	0.03	99.78
1.A.4 Other Sectors - Biomass	N_2O	45.79	45.79	0.02	99.80
2.B.8 Petrochemical and Carbon Black Production	CH_4	40.51	40.51	0.02	99.82

4.B.2. Land converted to Cropland	N_2O	29.32	29.32	0.01	99.84
4.E.2 Land converted to Settlements	N_2O	26.94	26.94	0.01	99.85
1.A.1 Energy industries - Other Fossil Fuels	CO_2	24.04	24.04	0.01	99.86
5.C Incineration and open burning of waste	CO_2	19.97	19.97	0.01	99.87
4.A.1 Forest Land remaining Forest Land	CH_4	19.77	19.77	0.01	99.88
1.A.4 Other Sectors - Liquid Fuels	N_2O	17.79	17.79	0.01	99.89
2.C.1 Iron and Steel Production	CH_4	16.62	16.62	0.01	99.90
1.A.1 Energy industries - Solid Fuels	CH_4	15.72	15.72	0.01	99.91
1.A.2 Manufacturing Industries and Construction - Biomass	N_2O	14.76	14.76	0.01	99.91
4.D.2. Land converted to Wetlands	CO_2	-14.55	14.55	0.01	99.92
1.B.2.c Fugitive Emissions from Fuels - Venting and flaring	CH_4	13.76	13.76	0.01	99.93
1.A.4 Other Sectors - Liquid Fuels	CH_4	13.04	13.04	0.01	99.93
4.B.1 Cropland remaining Cropland	CO_2	-12.68	12.68	0.01	99.94
4.A.1 Forest Land remaining Forest Land	N_2O	12.31	12.31	0.01	99.95
1.A.2 Manufacturing Industries and Construction - Biomass	CH_4	11.70	11.70	0.01	99.95
1.A.2 Manufacturing Industries and Construction - Liquid Fuels	N_2O	11.42	11.42	0.01	99.96
1.B.2.a Fugitive Emissions from Fuels - Oil and Natural Gas - Oil	CH_4	11.38	11.38	0.01	99.96
1.A.4 Other Sectors - Gaseous Fuels	CH_4	10.72	10.72	0.01	99.97
2.D.2 Paraffin Wax Use	CO_2	9.43	9.43	0.00	99.97
2.C.6 Zinc Production	CO_2	8.70	8.70	0.00	99.98
1.A.2 Manufacturing Industries and Construction - Liquid Fuels	CH_4	6.03	6.03	0.00	99.98
1.A.3.e Other Transportation	CO_2	5.42	5.42	0.00	99.98
4.C.1 Grassland remaining Grassland	CH_4	5.22	5.22	0.00	99.98
2.C.5 Lead Production	CO_2	4.04	4.04	0.00	99.99
4.A.2 Land converted to Forest Land	N_2O	4.02	4.02	0.00	99.99
1.A.1 Energy industries - Liquid Fuels	N_2O	2.94	2.94	0.00	99.99
1.A.2 Manufacturing Industries and Construction - Gaseous Fuels	CH_4	2.92	2.92	0.00	99.99
1.A.2 Manufacturing Industries and Construction - Gaseous Fuels	N_2O	2.76	2.76	0.00	99.99
1.A.4 Other Sectors - Gaseous Fuels	N_2O	2.03	2.03	0.00	99.99
1.B.2.c Fugitive Emissions from Fuels - Venting and flaring	CO_2	2.02	2.02	0.00	99.99
1.A.5.b Other mobile - Liquid Fuels	N_2O	1.74	1.74	0.00	100.00
1.A.1 Energy industries - Liquid Fuels	CH_4	1.59	1.59	0.00	100.00
1.A.3.c Railways	N_2O	1.55	1.55	0.00	100.00
1.A.3.c Railways	CH_4	1.23	1.23	0.00	100.00
1.B.1.b Solid Fuel Transformation	CH_4	0.84	0.84	0.00	100.00
1.A.1 Energy industries - Gaseous Fuels	CH_4	0.69	0.69	0.00	100.00
1.A.1 Energy industries - Gaseous Fuels	N_2O	0.65	0.65	0.00	100.00
1.A.5.b Other mobile - Liquid Fuels	CH_4	0.64	0.64	0.00	100.00
5.C Incineration and open burning of waste	N_2O	0.46	0.46	0.00	100.00
1.A.1 Energy industries - Biomass	N_2O	0.43	0.43	0.00	100.00
1.A.3.d Transport - Domestic navigation	N_2O	0.38	0.38	0.00	100.00
1.A.1 Energy industries - Biomass	CH_4	0.34	0.34	0.00	100.00
1.A.1 Energy industries - Other Fossil Fuels	N_2O	0.28	0.28	0.00	100.00
1.A.1 Energy industries - Other Fossil Fuels	CH_4	0.22	0.22	0.00	100.00

2.C.2 Ferroalloys Production	CH_4	0.20	0.20	0.00	100.00
1.B.2.b Fugitive Emissions from Fuels - Oil and Natural Gas - Natural Gas	CO_2	0.17	0.17	0.00	100.00
1.A.3.d Transport - Domestic navigation	CH_4	0.14	0.14	0.00	100.00
2.C.2 Ferroalloys Production	CO_2	0.03	0.03	0.00	100.00
1.B.2.a Fugitive Emissions from Fuels - Oil and Natural Gas - Oil	CO_2	0.02	0.02	0.00	100.00
1.B.2.c Fugitive Emissions from Fuels - Venting and flaring	N_2O	0.01	0.01	0.00	100.00
1.A.3.e Other Transportation	CH_4	0.00	0.00	0.00	100.00
1.A.3.e Other Transportation	N_2O	0.00	0.00	0.00	100.00
5.C Incineration and open burning of waste	CH_4	0.00	0.00	0.00	100.00
1.A.2 Manufacturing Industries and Construction - Other Fossil Fuels	CO_2	0.00	0.00	0.00	100.00
1.A.2 Manufacturing Industries and Construction - Other Fossil Fuels	CH_4	0.00	0.00	0.00	100.00
1.A.2 Manufacturing Industries and Construction - Other Fossil Fuels	N_2O	0.00	0.00	0.00	100.00
1.A.3.a Domestic Aviation	CO_2	0.00	0.00	0.00	100.00
1.A.3.a Domestic Aviation	CH_4	0.00	0.00	0.00	100.00
1.A.3.a Domestic Aviation	N_2O	0.00	0.00	0.00	100.00
2.B.10 Other	CO_2	0.00	0.00	0.00	100.00
2.D.3 Other non-energy products from fuels and solvent use	CO_2	0.00	0.00	0.00	100.00
2.E Electronics industry	F-gases	0.00	0.00	0.00	100.00
2.F.1 Refrigeration and Air conditioning	F-gases	0.00	0.00	0.00	100.00
2.F.2 Foam Blowing Agents	F-gases	0.00	0.00	0.00	100.00
2.F.3 Fire Protection	F-gases	0.00	0.00	0.00	100.00
2.F.4 Aerosols	F-gases	0.00	0.00	0.00	100.00
2.F.5 Solvents	F-gases	0.00	0.00	0.00	100.00
2.H Other	CO_2	0.00	0.00	0.00	100.00

Tab. A1 6 Spreadsheet for Approach 1 KC IPCC 2006 Gl., 1990 – Level Assessment excluding LULUCF

IPCC Source Categories	GHG	Base Year Estimate	Base Year Estimate (Abs)	Level Assessment	Cumulative Total (LA)
1.A.1 Energy industries - Solid Fuels	CO_2	53719.76	53719.76	26.81	26.81
1.A.2 Manufacturing Industries and Construction - Solid Fuels	CO_2	35635.57	35635.57	17.78	44.59
1.A.4 Other Sectors - Solid Fuels	CO_2	24005.03	24005.03	11.98	56.57
1.A.3.b Road Transportation	CO_2	10251.31	10251.31	5.12	61.68
2.C.1 Iron and Steel Production	CO_2	9782.03	9782.03	4.88	66.56
1.B.1.a Coal Mining and Handling	CH_4	8620.61	8620.61	4.30	70.86
4.A.1 Forest Land remaining Forest Land	CO_2	-8191.21	8191.21	4.09	74.95
3.A Enteric Fermentation	CH_4	6523.38	6523.38	3.26	78.21
1.A.2 Manufacturing Industries and Construction - Gaseous Fuels	CO_2	5685.63	5685.63	2.84	81.04
1.A.2 Manufacturing Industries and Construction - Liquid Fuels	CO_2	5502.33	5502.33	2.75	83.79
1.A.4 Other Sectors - Gaseous Fuels	CO_2	4173.90	4173.90	2.08	85.87
1.A.4 Other Sectors - Liquid Fuels	CO_2	3775.90	3775.90	1.88	87.76
2.A.1 Cement Production	CO_2	2489.18	2489.18	1.24	89.00

3.D.1 Direct N_2O Emissions From Managed Soils	N_2O	2192.74	2192.74	1.09	90.09
3.B Manure Management	CH_4	1539.13	1539.13	0.77	90.86
1.A.1 Energy industries - Liquid Fuels	CO_2	1514.04	1514.04	0.76	91.62
1.A.4 Other Sectors - Solid Fuels	CH_4	1491.69	1491.69	0.74	92.36
2.A.2 Lime Production	CO_2	1336.65	1336.65	0.67	93.03
1.A.1 Energy industries - Gaseous Fuels	CO_2	1336.03	1336.03	0.67	93.69
3.G Liming	CO_2	1236.71	1236.71	0.62	94.31
1.B.2.b Fugitive Emissions from Fuels - Oil and Natural Gas - Natural Gas	CH_4	1170.32	1170.32	0.58	94.89
5.D Wastewater treatment and discharge	CH_4	1082.93	1082.93	0.54	95.43
1. Energy (indirect CO_2 emissions)	CO_2	1020.18	1020.18	0.51	95.94
2.B.1 Ammonia Production	CO_2	990.80	990.80	0.49	96.44
3.B Manure Management	N_2O	975.60	975.60	0.49	96.93
2.B.2 Nitric Acid Production	N_2O	932.80	932.80	0.47	97.39
2.B.8 Petrochemical and Carbon Black Production	CO_2	792.47	792.47	0.40	97.79
1.A.3.c Railways	CO_2	767.62	767.62	0.38	98.17
1.B.1.a Coal Mining and Handling	CO_2	542.38	542.38	0.27	98.44
3.D.2 Indirect N_2O Emissions From Managed Soils	N_2O	437.48	437.48	0.22	98.66
1.A.4 Other Sectors - Biomass	CH_4	363.17	363.17	0.18	98.84
1.A.1 Energy industries - Solid Fuels	N_2O	213.31	213.31	0.11	98.95
5.D Wastewater treatment and discharge	N_2O	208.25	208.25	0.10	99.05
1.A.5.b Other mobile - Liquid Fuels	CO_2	191.93	191.93	0.10	99.15
2.G Other Product Manufacture and Use	N_2O	183.38	183.38	0.09	99.24
2.A.3 Glass Production	CO_2	142.75	142.75	0.07	99.31
1.A.2 Manufacturing Industries and Construction - Solid Fuels	N_2O	135.94	135.94	0.07	99.38
2.D.1 Lubricant Use	CO_2	116.13	116.13	0.06	99.43
2.A.4 Other Process Uses of Carbonates	CO_2	113.86	113.86	0.06	99.49
3.H Urea application	CO_2	108.53	108.53	0.05	99.54
1.A.3.b Road Transportation	N_2O	100.51	100.51	0.05	99.59
1.A.2 Manufacturing Industries and Construction - Solid Fuels	CH_4	96.04	96.04	0.05	99.64
1.A.4 Other Sectors - Solid Fuels	N_2O	91.86	91.86	0.05	99.69
1.A.3.b Road Transportation	CH_4	88.66	88.66	0.04	99.73
2.G Other Product Manufacture and Use	F-gases	86.57	86.57	0.04	99.78
2.B.4 Caprolactam, glyoxal and glyoxylic acid production	N_2O	68.82	68.82	0.03	99.81
1.A.3.d Transport - Domestic navigation	CO_2	53.48	53.48	0.03	99.84
1.A.4 Other Sectors - Biomass	N_2O	45.79	45.79	0.02	99.86
2.B.8 Petrochemical and Carbon Black Production	CH_4	40.51	40.51	0.02	99.88
1.A.1 Energy industries - Other Fossil Fuels	CO_2	24.04	24.04	0.01	99.89
4.A.1 Forest Land remaining Forest Land	CH_4	19.77	19.77	0.01	99.90
1.A.4 Other Sectors - Liquid Fuels	N_2O	17.79	17.79	0.01	99.91
2.C.1 Iron and Steel Production	CH_4	16.62	16.62	0.01	99.92
1.A.1 Energy industries - Solid Fuels	CH_4	15.72	15.72	0.01	99.93
1.A.2 Manufacturing Industries and Construction - Biomass	N_2O	14.76	14.76	0.01	99.93
1.B.2.c Fugitive Emissions from Fuels - Venting and flaring	CH_4	13.76	13.76	0.01	99.94
1.A.4 Other Sectors - Liquid Fuels	CH_4	13.04	13.04	0.01	99.95

4.A.1 Forest Land remaining Forest Land	N_2O	12.31	12.31	0.01	99.95
1.A.2 Manufacturing Industries and Construction - Biomass	CH_4	11.70	11.70	0.01	99.96
1.A.2 Manufacturing Industries and Construction - Liquid Fuels	N_2O	11.42	11.42	0.01	99.97
1.B.2.a Fugitive Emissions from Fuels - Oil and Natural Gas - Oil	CH_4	11.38	11.38	0.01	99.97
1.A.4 Other Sectors - Gaseous Fuels	CH_4	10.72	10.72	0.01	99.98
2.C.6 Zinc Production	CO_2	8.70	8.70	0.00	99.98
1.A.2 Manufacturing Industries and Construction - Liquid Fuels	CH_4	6.03	6.03	0.00	99.98
1.A.3.e Other Transportation	CO_2	5.42	5.42	0.00	99.99
2.C.5 Lead Production	CO_2	4.04	4.04	0.00	99.99
1.A.2 Manufacturing Industries and Construction - Gaseous Fuels	CH_4	2.92	2.92	0.00	99.99
1.A.2 Manufacturing Industries and Construction - Gaseous Fuels	N_2O	2.76	2.76	0.00	99.99
1.A.4 Other Sectors - Gaseous Fuels	N_2O	2.03	2.03	0.00	99.99
1.B.2.c Fugitive Emissions from Fuels - Venting and flaring	CO_2	2.02	2.02	0.00	99.99
1.A.5.b Other mobile - Liquid Fuels	N_2O	1.74	1.74	0.00	100.00
1.A.1 Energy industries - Liquid Fuels	CH_4	1.59	1.59	0.00	100.00
1.A.3.c Railways	N_2O	1.55	1.55	0.00	100.00
1.A.3.c Railways	CH_4	1.23	1.23	0.00	100.00
1.A.1 Energy industries - Gaseous Fuels	CH_4	0.69	0.69	0.00	100.00
1.A.1 Energy industries - Gaseous Fuels	N_2O	0.65	0.65	0.00	100.00
1.A.5.b Other mobile - Liquid Fuels	CH_4	0.64	0.64	0.00	100.00
1.A.1 Energy industries - Biomass	N_2O	0.43	0.43	0.00	100.00
1.A.3.d Transport - Domestic navigation	N_2O	0.38	0.38	0.00	100.00
1.A.1 Energy industries - Biomass	CH_4	0.34	0.34	0.00	100.00
1.A.1 Energy industries - Other Fossil Fuels	N_2O	0.28	0.28	0.00	100.00
1.A.1 Energy industries - Other Fossil Fuels	CH_4	0.22	0.22	0.00	100.00
2.C.2 Ferroalloys Production	CH_4	0.20	0.20	0.00	100.00
1.B.2.b Fugitive Emissions from Fuels - Oil and Natural Gas - Natural Gas	CO_2	0.17	0.17	0.00	100.00
1.A.3.d Transport - Domestic navigation	CH_4	0.14	0.14	0.00	100.00
2.C.2 Ferroalloys Production	CO_2	0.03	0.03	0.00	100.00
1.B.2.a Fugitive Emissions from Fuels - Oil and Natural Gas - Oil	CO_2	0.02	0.02	0.00	100.00
1.B.2.c Fugitive Emissions from Fuels - Venting and flaring	N_2O	0.01	0.01	0.00	100.00
1.A.3.e Other Transportation	CH_4	0.00	0.00	0.00	100.00
1.A.3.e Other Transportation	N_2O	0.00	0.00	0.00	100.00
1.A.2 Manufacturing Industries and Construction - Other Fossil Fuels	CO_2	0.00	0.00	0.00	100.00
1.A.2 Manufacturing Industries and Construction - Other Fossil Fuels	CH_4	0.00	0.00	0.00	100.00
1.A.2 Manufacturing Industries and Construction - Other Fossil Fuels	N_2O	0.00	0.00	0.00	100.00
1.A.3.a Domestic Aviation	CO_2	0.00	0.00	0.00	100.00
1.A.3.a Domestic Aviation	CH_4	0.00	0.00	0.00	100.00
1.A.3.a Domestic Aviation	N_2O	0.00	0.00	0.00	100.00
2.B.10 Other	CO_2	0.00	0.00	0.00	100.00
2.E Electronics industry	F-gases	0.00	0.00	0.00	100.00
2.F.1 Refrigeration and Air conditioning	F-gases	0.00	0.00	0.00	100.00

2.F.2 Foam Blowing Agents	F-gases	0.00	0.00	0.00	100.00
2.F.3 Fire Protection	F-gases	0.00	0.00	0.00	100.00
2.F.4 Aerosols	F-gases	0.00	0.00	0.00	100.00
2.F.5 Solvents	F-gases	0.00	0.00	0.00	100.00
2.H Other	CO_2	0.00	0.00	0.00	100.00
2.H Other	F-gases	0.00	0.00	0.00	100.00
4.A.2 Land converted to Forest Land	CO_2	0.00	0.00	0.00	100.00
4.B.1 Cropland remaining Cropland	CO_2	0.00	0.00	0.00	100.00
4.B.2 Land converted to Cropland	CO_2	0.00	0.00	0.00	100.00

Tab. A1 7 Spreadsheet for Approach 2 KC IPCC 2006 Gl., 2024 – Level Assessment including LULUCF

IPCC Source Categories	GHG	Latest Year Estimate	Latest Year Estimate (Abs)	Combined Uncertainty	LA for category	L*U (unc.amount)	LA_A2	Cumulative fraction of total emissions	Cumulative fraction of uncertainty	Cumulative Total (LA)
5.A Solid Waste Disposal	CH_4	3824.24	3824.24	63.70	3.76	239.36	16.52	3.76	1.02	16.52
2.F.1 Refrigeration and Air conditioning	F-gases	3450.95	3450.95	43.57	3.39	147.72	10.20	3.39	0.70	26.72
4.A.1 Forest Land remaining Forest Land	CO_2	-2282.12	2282.12	42.54	2.24	95.39	6.58	2.24	0.68	33.30
1.A.1 Energy industries - Solid Fuels	CO_2	28240.73	28240.73	3.28	27.75	90.89	6.27	27.75	0.05	39.58
4.G Harvested wood products	CO_2	-1285.43	1285.43	62.00	1.26	78.31	5.41	1.26	0.99	44.98
1.A.3.b Road Transportation	CO_2	20152.39	20152.39	3.69	19.80	73.06	5.04	19.80	0.06	50.02
1.A.3.b Road Transportation	N_2O	335.89	335.89	180.40	0.33	59.54	4.11	0.33	2.90	54.13
3.A Enteric Fermentation	CH_4	3697.98	3697.98	15.81	3.63	57.45	3.97	3.63	0.25	58.10
5.D Wastewater treatment and discharge	CH_4	855.98	855.98	58.38	0.84	49.10	3.39	0.84	0.94	61.49
5.B Biological treatment of solid waste	CH_4	499.57	499.57	91.29	0.49	44.81	3.09	0.49	1.46	64.58
3.D.1 Direct N2O Emissions From Managed Soils	N_2O	2084.17	2084.17	20.62	2.05	42.22	2.91	2.05	0.33	67.50
2.B.8 Petrochemical and Carbon Black Production	CO_2	922.85	922.85	40.31	0.91	36.55	2.52	0.91	0.65	70.02
2.C.1 Iron and Steel Production	CO_2	3025.57	3025.57	12.21	2.97	36.29	2.50	2.97	0.20	72.52
1.A.4 Other Sectors - Biomass	CH_4	644.08	644.08	52.07	0.63	32.95	2.27	0.63	0.84	74.80
1.A.2 Manufacturing Industries and Construction - Other Fossil Fuels	CO_2	481.38	481.38	60.70	0.47	28.71	1.98	0.47	0.97	76.78
1.A.4 Other Sectors - Gaseous Fuels	CO_2	5703.74	5703.74	4.79	5.60	26.84	1.85	5.60	0.08	78.63
1.B.1.a Coal Mining and Handling	CH_4	474.57	474.57	38.22	0.47	17.82	1.23	0.47	0.61	79.86

4.C.2 Land converted to Grassland	CO_2	-415.52	415.52	42.78	0.41	17.47	1.21	0.41	0.69	81.07
3.D.2 Indirect N_2O Emissions From Managed Soils	N_2O	579.50	579.50	30.41	0.57	17.32	1.20	0.57	0.49	82.26
1.B.2.b Fugitive Emissions from Fuels - Oil and Natural Gas - Natural Gas	CH_4	350.63	350.63	49.74	0.34	17.14	1.18	0.34	0.80	83.45
3.B Manure Management	N_2O	390.50	390.50	40.31	0.38	15.47	1.07	0.38	0.65	84.51
1.A.4 Other Sectors - Solid Fuels	CO_2	1547.36	1547.36	9.96	1.52	15.15	1.05	1.52	0.16	85.56
4.C.1 Grassland remaining Grassland	CO_2	-407.71	407.71	34.78	0.40	13.93	0.96	0.40	0.56	86.52
4.A.2 Land converted to Forest Land	CO_2	-633.08	633.08	20.68	0.62	12.86	0.89	0.62	0.33	87.41
5.D Wastewater treatment and discharge	N_2O	200.22	200.22	56.36	0.20	11.09	0.77	0.20	0.90	88.17
1.A.2 Manufacturing Industries and Construction - Gaseous Fuels	CO_2	4586.76	4586.76	2.25	4.51	10.13	0.70	4.51	0.04	88.87
4.E.2 Land converted to Settlements	CO_2	263.22	263.22	38.49	0.26	9.95	0.69	0.26	0.62	89.56
3.H Urea application	CO_2	191.47	191.47	52.20	0.19	9.82	0.68	0.19	0.84	90.24
1.A.2 Manufacturing Industries and Construction - Solid Fuels	CO_2	3114.68	3114.68	2.83	3.06	8.66	0.60	3.06	0.05	90.84
2.G Other Product Manufacture and Use	N_2O	198.75	198.75	43.57	0.20	8.51	0.59	0.20	0.70	91.42
3.B Manure Management	CH_4	371.21	371.21	22.36	0.36	8.16	0.56	0.36	0.36	91.99
1.A.1 Energy industries - Solid Fuels	N_2O	112.63	112.63	70.05	0.11	7.75	0.54	0.11	1.12	92.52
1.A.4 Other Sectors - Liquid Fuels	CO_2	1289.15	1289.15	6.12	1.27	7.75	0.54	1.27	0.10	93.06
1.A.4 Other Sectors - Solid Fuels	CH_4	133.66	133.66	55.87	0.13	7.34	0.51	0.13	0.90	93.56
1.A.4 Other Sectors - Biomass	N_2O	81.15	81.15	71.49	0.08	5.70	0.39	0.08	1.15	93.96
2.A.4 Other Process Uses of Carbonates	CO_2	496.06	496.06	11.18	0.49	5.45	0.38	0.49	0.18	94.33
1.A.1 Energy industries - Other Fossil Fuels	CO_2	320.00	320.00	17.29	0.31	5.44	0.38	0.31	0.28	94.71
1.A.3.b Road Transportation	CH_4	26.80	26.80	199.45	0.03	5.25	0.36	0.03	3.20	95.07
1.A.1 Energy industries - Gaseous Fuels	CO_2	2774.98	2774.98	1.90	2.73	5.18	0.36	2.73	0.03	95.43
2.D.1 Lubricant Use	CO_2	84.30	84.30	50.25	0.08	4.16	0.29	0.08	0.81	95.72
2.A.1 Cement Production	CO_2	1449.97	1449.97	2.83	1.42	4.03	0.28	1.42	0.05	95.99
3.G Liming	CO_2	132.49	132.49	30.41	0.13	3.96	0.27	0.13	0.49	96.27
2.B.1 Ammonia Production	CO_2	430.96	430.96	8.60	0.42	3.64	0.25	0.42	0.14	96.52
2.G Other Product Manufacture and Use	F-gases	65.28	65.28	43.57	0.06	2.79	0.19	0.06	0.70	96.71
1.A.4 Other Sectors - Liquid Fuels	N_2O	38.22	38.22	70.21	0.04	2.64	0.18	0.04	1.13	96.89

1.A.2 Manufacturing Industries and Construction - Biomass	N_2O	36.85	36.85	70.36	0.04	2.55	0.18	0.04	1.13	97.07
1.A.1 Energy industries - Biomass	N_2O	34.76	34.76	70.29	0.03	2.40	0.17	0.03	1.13	97.23
4.B.2. Land converted to Cropland	N_2O	9.77	9.77	250.00	0.01	2.40	0.17	0.01	4.01	97.40
1.A.2 Manufacturing Industries and Construction - Liquid Fuels	CO_2	577.96	577.96	4.13	0.57	2.35	0.16	0.57	0.07	97.56
4.B.2 Land converted to Cropland	CO_2	113.86	113.86	19.93	0.11	2.23	0.15	0.11	0.32	97.72
2.B.8 Petrochemical and Carbon Black Production	CH_4	51.89	51.89	40.31	0.05	2.06	0.14	0.05	0.65	97.86
4.E.2 Land converted to Settlements	N_2O	5.96	5.96	250.00	0.01	1.46	0.10	0.01	4.01	97.96
1.A.2 Manufacturing Industries and Construction - Biomass	CH_4	29.32	29.32	50.50	0.03	1.45	0.10	0.03	0.81	98.06
1.B.2.c Fugitive Emissions from Fuels - Venting and flaring	CH_4	19.37	19.37	74.33	0.02	1.42	0.10	0.02	1.19	98.16
2.F.3 Fire Protection	F-gases	33.79	33.79	41.88	0.03	1.39	0.10	0.03	0.67	98.25
1.A.1 Energy industries - Biomass	CH_4	27.56	27.56	50.40	0.03	1.36	0.09	0.03	0.81	98.35
2.B.2 Nitric Acid Production	N_2O	87.45	87.45	15.52	0.09	1.33	0.09	0.09	0.25	98.44
1. Energy (indirect CO2 emissions)	CO_2	93.02	93.02	14.14	0.09	1.29	0.09	0.09	0.23	98.53
1.A.5.b Other mobile - Liquid Fuels	CO_2	242.25	242.25	4.89	0.24	1.16	0.08	0.24	0.08	98.61
1.A.1 Energy industries - Liquid Fuels	CO_2	359.48	359.48	3.25	0.35	1.15	0.08	0.35	0.05	98.69
1.A.3.c Railways	CO_2	215.90	215.90	5.24	0.21	1.11	0.08	0.21	0.08	98.77
2.A.2 Lime Production	CO_2	397.91	397.91	2.83	0.39	1.11	0.08	0.39	0.05	98.84
5.C Incineration and open burning of waste	CO_2	70.53	70.53	15.81	0.07	1.10	0.08	0.07	0.25	98.92
2.B.4 Caprolactam, glyoxal and glyoxylic acid production	N_2O	26.50	26.50	40.31	0.03	1.05	0.07	0.03	0.65	98.99
4.D.2. Land converted to Wetlands	CO_2	11.65	11.65	80.85	0.01	0.93	0.06	0.01	1.30	99.05
4.B.1 Cropland remaining Cropland	CO_2	-26.11	26.11	34.58	0.03	0.89	0.06	0.03	0.55	99.11
1.B.1.a Coal Mining and Handling	CO_2	60.98	60.98	14.23	0.06	0.85	0.06	0.06	0.23	99.17
1.A.2 Manufacturing Industries and Construction - Solid Fuels	N_2O	12.17	12.17	70.03	0.01	0.84	0.06	0.01	1.12	99.23
2.A.3 Glass Production	CO_2	131.66	131.66	5.39	0.13	0.70	0.05	0.13	0.09	99.28
2.E Electronics industry	F-gases	41.51	41.51	15.30	0.04	0.62	0.04	0.04	0.25	99.32
1.A.4 Other Sectors - Gaseous Fuels	CH_4	14.24	14.24	41.94	0.01	0.59	0.04	0.01	0.67	99.36
2.B.10 Other	CO_2	145.35	145.35	3.91	0.14	0.56	0.04	0.14	0.06	99.40

1.A.2 Manufacturing Industries and Construction - Solid Fuels	CH_4	8.59	8.59	65.04	0.01	0.55	0.04	0.01	1.04	99.44
1.A.5.b Other mobile - Liquid Fuels	N_2O	7.90	7.90	70.12	0.01	0.54	0.04	0.01	1.13	99.48
1.A.1 Energy industries - Solid Fuels	CH_4	8.12	8.12	65.06	0.01	0.52	0.04	0.01	1.04	99.51
2.C.5 Lead Production	CO_2	10.30	10.30	50.99	0.01	0.52	0.04	0.01	0.82	99.55
1.A.2 Manufacturing Industries and Construction - Other Fossil Fuels	N_2O	6.28	6.28	80.52	0.01	0.50	0.03	0.01	1.29	99.58
4.A.2 Land converted to Forest Land	N_2O	1.99	1.99	250.00	0.00	0.49	0.03	0.00	4.01	99.62
1.A.4 Other Sectors - Solid Fuels	N_2O	6.48	6.48	70.68	0.01	0.45	0.03	0.01	1.13	99.65
4.C.1 Grassland remaining Grassland	CH_4	5.22	5.22	81.00	0.01	0.42	0.03	0.01	1.30	99.68
2.D.2 Paraffin Wax Use	CO_2	8.25	8.25	50.25	0.01	0.41	0.03	0.01	0.81	99.70
5.C Incineration and open burning of waste	CH_4	4.97	4.97	82.46	0.00	0.40	0.03	0.00	1.32	99.73
5.B Biological treatment of solid waste	N_2O	63.22	63.22	5.04	0.06	0.31	0.02	0.06	0.08	99.75
1.A.2 Manufacturing Industries and Construction - Other Fossil Fuels	CH_4	4.98	4.98	60.70	0.00	0.30	0.02	0.00	0.97	99.77
1.A.1 Energy industries - Other Fossil Fuels	N_2O	3.70	3.70	80.37	0.00	0.29	0.02	0.00	1.29	99.79
1.B.2.a Fugitive Emissions from Fuels - Oil and Natural Gas - Oil	CH_4	3.99	3.99	63.12	0.00	0.25	0.02	0.00	1.01	99.81
5.C Incineration and open burning of waste	N_2O	2.87	2.87	72.80	0.00	0.21	0.01	0.00	1.17	99.83
2.D.3 Other non-energy products from fuels and solvent use	CO_2	26.00	26.00	7.07	0.03	0.18	0.01	0.03	0.11	99.84
1.A.1 Energy industries - Other Fossil Fuels	CH_4	2.93	2.93	60.49	0.00	0.17	0.01	0.00	0.97	99.85
1.B.1.b Solid Fuel Transformation	CH_4	3.36	3.36	48.54	0.00	0.16	0.01	0.00	0.78	99.86
2.F.2 Foam Blowing Agents	F-gases	3.89	3.89	41.88	0.00	0.16	0.01	0.00	0.67	99.87
1.B.2.c Fugitive Emissions from Fuels - Venting and flaring	CO_2	2.84	2.84	57.03	0.00	0.16	0.01	0.00	0.92	99.88
4.A.1 Forest Land remaining Forest Land	N_2O	4.13	4.13	38.84	0.00	0.16	0.01	0.00	0.62	99.89
2.C.1 Iron and Steel Production	CH_4	5.12	5.12	30.81	0.01	0.16	0.01	0.01	0.49	99.90
4.A.1 Forest Land remaining Forest Land	CH_4	3.73	3.73	38.84	0.00	0.14	0.01	0.00	0.62	99.91
1.A.4 Other Sectors - Gaseous Fuels	N_2O	2.70	2.70	53.55	0.00	0.14	0.01	0.00	0.86	99.92
1.A.3.c Railways	CH_4	1.11	1.11	125.67	0.00	0.14	0.01	0.00	2.02	99.93
2.F.4 Aerosols	F-gases	2.91	2.91	41.88	0.00	0.12	0.01	0.00	0.67	99.94

1.A.2 Manufacturing Industries and Construction - Gaseous Fuels	N_2O	2.17	2.17	53.38	0.00	0.11	0.01	0.00	0.86	99.95
1.A.2 Manufacturing Industries and Construction - Gaseous Fuels	CH_4	2.29	2.29	41.72	0.00	0.09	0.01	0.00	0.67	99.96
2.C.2 Ferroalloys Production	CH_4	3.37	3.37	25.50	0.00	0.08	0.01	0.00	0.41	99.96
1.A.3.a Domestic Aviation	CO_2	15.55	15.55	5.36	0.02	0.08	0.01	0.02	0.09	99.97
1.A.1 Energy industries - Gaseous Fuels	N_2O	1.31	1.31	53.36	0.00	0.07	0.00	0.00	0.86	99.97
1.A.2 Manufacturing Industries and Construction - Liquid Fuels	N_2O	0.92	0.92	70.07	0.00	0.06	0.00	0.00	1.12	99.98
1.A.3.c Railways	N_2O	0.47	0.47	125.40	0.00	0.06	0.00	0.00	2.01	99.98
1.A.4 Other Sectors - Liquid Fuels	CH_4	1.05	1.05	55.27	0.00	0.06	0.00	0.00	0.89	99.98
1.A.1 Energy industries - Gaseous Fuels	CH_4	1.39	1.39	41.71	0.00	0.06	0.00	0.00	0.67	99.99
1.A.3.d Transport - Domestic navigation	CO_2	9.44	9.44	5.00	0.01	0.05	0.00	0.01	0.08	99.99
1.A.2 Manufacturing Industries and Construction - Liquid Fuels	CH_4	0.53	0.53	55.09	0.00	0.03	0.00	0.00	0.88	99.99
1.A.1 Energy industries - Liquid Fuels	N_2O	0.23	0.23	70.02	0.00	0.02	0.00	0.00	1.12	100.00
2.C.6 Zinc Production	CO_2	0.25	0.25	50.99	0.00	0.01	0.00	0.00	0.82	100.00
1.A.3.a Domestic Aviation	N_2O	0.11	0.11	110.07	0.00	0.01	0.00	0.00	1.77	100.00
1.A.1 Energy industries - Liquid Fuels	CH_4	0.20	0.20	55.03	0.00	0.01	0.00	0.00	0.88	100.00
2.C.2 Ferroalloys Production	CO_2	0.43	0.43	25.50	0.00	0.01	0.00	0.00	0.41	100.00
2.H Other	F-gases	0.18	0.18	43.57	0.00	0.01	0.00	0.00	0.70	100.00
2.H Other	CO_2	0.94	0.94	5.39	0.00	0.00	0.00	0.00	0.09	100.00
1.A.3.e Other Transportation	CO_2	0.97	0.97	5.00	0.00	0.00	0.00	0.00	0.08	100.00
1.B.2.b Fugitive Emissions from Fuels - Oil and Natural Gas - Natural Gas	CO_2	0.05	0.05	50.29	0.00	0.00	0.00	0.00	0.81	100.00
1.A.5.b Other mobile - Liquid Fuels	CH_4	0.04	0.04	55.15	0.00	0.00	0.00	0.00	0.89	100.00
1.B.2.a Fugitive Emissions from Fuels - Oil and Natural Gas - Oil	CO_2	0.03	0.03	50.42	0.00	0.00	0.00	0.00	0.81	100.00
1.B.2.c Fugitive Emissions from Fuels - Venting and flaring	N_2O	0.01	0.01	74.33	0.00	0.00	0.00	0.00	1.19	100.00
1.A.3.d Transport - Domestic navigation	N_2O	0.07	0.07	5.18	0.00	0.00	0.00	0.00	0.08	100.00
1.A.3.a Domestic Aviation	CH_4	0.00	0.00	78.60	0.00	0.00	0.00	0.00	1.26	100.00

1.A.3.d Transport - Domestic navigation	CH_4	0.03	0.03	5.10	0.00	0.00	0.00	0.00	0.08	100.00
1.A.3.e Other Transportation	N_2O	0.00	0.00	60.13	0.00	0.00	0.00	0.00	0.97	100.00

Tab. A1 8 Spreadsheet for Approach 2 KC IPCC 2006 Gl., 2024 – Level Assessment excluding LULUCF

IPCC Source Categories	GHG	Latest Year Estimate	Latest Year Estimate (Abs)	Combined Uncertainty	LA for category	L*U (unc.amount)	LA_A2	Cumulative fraction of	Cumulative fraction of	Cumulative Total (LA)
2.F.1 Refrigeration and Air conditioning	F-gases	3450.95	3450.95	41.88	3.58	150.08	13.33	3.58	0.71	13.33
2.C.1 Iron and Steel Production	CO_2	3025.57	3025.57	30.81	3.14	96.78	8.60	3.14	0.52	21.93
1.A.1 Energy industries - Solid Fuels	CO_2	28240.73	28240.73	3.28	29.32	96.06	8.53	29.32	0.06	30.47
3.A Enteric Fermentation	CH_4	3697.98	3697.98	22.36	3.84	85.86	7.63	3.84	0.38	38.10
1.A.3.b Road Transportation	CO_2	20152.39	20152.39	3.69	20.93	77.21	6.86	20.93	0.06	44.96
3.D.1 Direct N_2O Emissions From Managed Soils	N_2O	2084.17	2084.17	30.41	2.16	65.82	5.85	2.16	0.52	50.80
1.A.3.b Road Transportation	N_2O	335.89	335.89	180.40	0.35	62.92	5.59	0.35	3.05	56.39
5.A Solid Waste Disposal	CH_4	3824.24	3824.24	15.81	3.97	62.79	5.58	3.97	0.27	61.97
5.B Biological treatment of solid waste	CH_4	499.57	499.57	82.46	0.52	42.78	3.80	0.52	1.40	65.77
2.B.8 Petrochemical and Carbon Black Production	CO_2	922.85	922.85	40.31	0.96	38.63	3.43	0.96	0.68	69.20
1.A.4 Other Sectors - Biomass	CH_4	644.08	644.08	52.07	0.67	34.82	3.09	0.67	0.88	72.30
1.A.2 Manufacturing Industries and Construction - Other Fossil Fuels	CO_2	481.38	481.38	60.70	0.50	30.34	2.70	0.50	1.03	74.99
1.A.4 Other Sectors - Gaseous Fuels	CO_2	5703.74	5703.74	4.79	5.92	28.37	2.52	5.92	0.08	77.51
1.B.1.a Coal Mining and Handling	CH_4	474.57	474.57	38.22	0.49	18.83	1.67	0.49	0.65	79.19
3.D.2 Indirect N_2O Emissions From Managed Soils	N_2O	579.50	579.50	30.41	0.60	18.30	1.63	0.60	0.52	80.81
1.B.2.b Fugitive Emissions from Fuels - Oil and Natural Gas - Natural Gas	CH_4	350.63	350.63	49.74	0.36	18.11	1.61	0.36	0.84	82.42
1.A.4 Other Sectors - Solid Fuels	CO_2	1547.36	1547.36	9.96	1.61	16.01	1.42	1.61	0.17	83.84
3.B Manure Management	CH_4	371.21	371.21	40.31	0.39	15.54	1.38	0.39	0.68	85.23
1.A.2 Manufacturing Industries and Construction - Gaseous Fuels	CO_2	4586.76	4586.76	2.25	4.76	10.71	0.95	4.76	0.04	86.18
1.A.2 Manufacturing Industries and Construction - Solid Fuels	CO_2	3114.68	3114.68	2.83	3.23	9.15	0.81	3.23	0.05	86.99
3.H Urea application	CO_2	191.47	191.47	42.54	0.20	8.46	0.75	0.20	0.72	87.74
3.B Manure Management	N_2O	390.50	390.50	20.62	0.41	8.36	0.74	0.41	0.35	88.48
1.A.1 Energy industries - Solid Fuels	N_2O	112.63	112.63	70.05	0.12	8.19	0.73	0.12	1.19	89.21
1.A.4 Other Sectors - Liquid Fuels	CO_2	1289.15	1289.15	6.12	1.34	8.19	0.73	1.34	0.10	89.94
1.A.4 Other Sectors - Solid Fuels	CH_4	133.66	133.66	55.87	0.14	7.75	0.69	0.14	0.95	90.63
3.G Liming	CO_2	132.49	132.49	52.20	0.14	7.18	0.64	0.14	0.88	91.27
2.B.1 Ammonia Production	CO_2	430.96	430.96	15.52	0.45	6.95	0.62	0.45	0.26	91.88
1.A.4 Other Sectors - Biomass	N_2O	81.15	81.15	71.49	0.08	6.02	0.54	0.08	1.21	92.42
1.A.1 Energy industries - Other Fossil Fuels	CO_2	320.00	320.00	17.29	0.33	5.75	0.51	0.33	0.29	92.93
1.A.3.b Road Transportation	CH_4	26.80	26.80	199.45	0.03	5.55	0.49	0.03	3.38	93.42
1.A.1 Energy industries - Gaseous Fuels	CO_2	2774.98	2774.98	1.90	2.88	5.48	0.49	2.88	0.03	93.91

5.B Biological treatment of solid waste	N_2O	63.22	63.22	72.80	0.07	4.78	0.42	0.07	1.23	94.33
2.A.4 Other Process Uses of Carbonates	CO_2	496.06	496.06	8.60	0.52	4.43	0.39	0.52	0.15	94.73
2.D.1 Lubricant Use	CO_2	84.30	84.30	50.25	0.09	4.40	0.39	0.09	0.85	95.12
5.C Incineration and open burning of waste	CO_2	70.53	70.53	58.38	0.07	4.28	0.38	0.07	0.99	95.50
2.A.1 Cement Production	CO_2	1449.97	1449.97	2.83	1.51	4.26	0.38	1.51	0.05	95.88
2.B.2 Nitric Acid Production	N_2O	87.45	87.45	40.31	0.09	3.66	0.33	0.09	0.68	96.20
2.G Other Product Manufacture and Use	F-gases	65.28	65.28	43.57	0.07	2.95	0.26	0.07	0.74	96.46
1.A.4 Other Sectors - Liquid Fuels	N_2O	38.22	38.22	70.21	0.04	2.79	0.25	0.04	1.19	96.71
1.A.2 Manufacturing Industries and Construction - Biomass	N_2O	36.85	36.85	70.36	0.04	2.69	0.24	0.04	1.19	96.95
1.A.1 Energy industries - Biomass	N_2O	34.76	34.76	70.29	0.04	2.54	0.23	0.04	1.19	97.18
1.A.2 Manufacturing Industries and Construction - Liquid Fuels	CO_2	577.96	577.96	4.13	0.60	2.48	0.22	0.60	0.07	97.40
2.A.2 Lime Production	CO_2	397.91	397.91	5.39	0.41	2.23	0.20	0.41	0.09	97.59
2.E Electronics industry	F-gases	41.51	41.51	43.57	0.04	1.88	0.17	0.04	0.74	97.76
2.B.10 Other	CO_2	145.35	145.35	12.21	0.15	1.84	0.16	0.15	0.21	97.92
1.A.2 Manufacturing Industries and Construction - Biomass	CH_4	29.32	29.32	50.50	0.03	1.54	0.14	0.03	0.86	98.06
2.A.3 Glass Production	CO_2	131.66	131.66	11.18	0.14	1.53	0.14	0.14	0.19	98.20
1.B.2.c Fugitive Emissions from Fuels - Venting and flaring	CH_4	19.37	19.37	74.33	0.02	1.50	0.13	0.02	1.26	98.33
2.F.3 Fire Protection	F-gases	33.79	33.79	41.88	0.04	1.47	0.13	0.04	0.71	98.46
1.A.1 Energy industries - Biomass	CH_4	27.56	27.56	50.40	0.03	1.44	0.13	0.03	0.85	98.59
1.A.5.b Other mobile - Liquid Fuels	CO_2	242.25	242.25	4.89	0.25	1.23	0.11	0.25	0.08	98.70
1.A.1 Energy industries - Liquid Fuels	CO_2	359.48	359.48	3.25	0.37	1.21	0.11	0.37	0.06	98.81
1.A.3.c Railways	CO_2	215.90	215.90	5.24	0.22	1.17	0.10	0.22	0.09	98.91
2.G Other Product Manufacture and Use	N_2O	198.75	198.75	5.39	0.21	1.11	0.10	0.21	0.09	99.01
2.B.4 Caprolactam, glyoxal and glyoxylic acid production	N_2O	26.50	26.50	40.31	0.03	1.11	0.10	0.03	0.68	99.11
1.B.1.a Coal Mining and Handling	CO_2	60.98	60.98	14.23	0.06	0.90	0.08	0.06	0.24	99.19
1.A.2 Manufacturing Industries and Construction - Solid Fuels	N_2O	12.17	12.17	70.03	0.01	0.88	0.08	0.01	1.19	99.27
1.A.4 Other Sectors - Gaseous Fuels	CH_4	14.24	14.24	41.94	0.01	0.62	0.06	0.01	0.71	99.32
1.A.2 Manufacturing Industries and Construction - Solid Fuels	CH_4	8.59	8.59	65.04	0.01	0.58	0.05	0.01	1.10	99.37
1.A.5.b Other mobile - Liquid Fuels	N_2O	7.90	7.90	70.12	0.01	0.57	0.05	0.01	1.19	99.42
1.A.1 Energy industries - Solid Fuels	CH_4	8.12	8.12	65.06	0.01	0.55	0.05	0.01	1.10	99.47
2.C.5 Lead Production	CO_2	10.30	10.30	50.99	0.01	0.55	0.05	0.01	0.86	99.52
1.A.2 Manufacturing Industries and Construction - Other Fossil Fuels	N_2O	6.28	6.28	80.52	0.01	0.53	0.05	0.01	1.36	99.57
1.A.4 Other Sectors - Solid Fuels	N_2O	6.48	6.48	70.68	0.01	0.48	0.04	0.01	1.20	99.61
2.D.3 Other non-energy products from fuels and solvent use	CO_2	26.00	26.00	15.30	0.03	0.41	0.04	0.03	0.26	99.65
1.A.2 Manufacturing Industries and Construction - Other Fossil Fuels	CH_4	4.98	4.98	60.70	0.01	0.31	0.03	0.01	1.03	99.67
1.A.1 Energy industries - Other Fossil Fuels	N_2O	3.70	3.70	80.37	0.00	0.31	0.03	0.00	1.36	99.70
5.C Incineration and open burning of waste	CH_4	4.97	4.97	56.36	0.01	0.29	0.03	0.01	0.95	99.73
1. Energy (indirect CO_2 emissions)	CO_2	93.02	93.02	2.83	0.10	0.27	0.02	0.10	0.05	99.75

1.B.2.a Fugitive Emissions from Fuels - Oil and Natural Gas - Oil	CH_4	3.99	3.99	63.12	0.00	0.26	0.02	0.00	1.07	99.78
2.B.8 Petrochemical and Carbon Black Production	CH_4	51.89	51.89	3.91	0.05	0.21	0.02	0.05	0.07	99.79
1.A.1 Energy industries - Other Fossil Fuels	CH_4	2.93	2.93	60.49	0.00	0.18	0.02	0.00	1.02	99.81
2.C.2 Ferroalloys Production	CH_4	3.37	3.37	50.99	0.00	0.18	0.02	0.00	0.86	99.83
1.B.1.b Solid Fuel Transformation	CH_4	3.36	3.36	48.54	0.00	0.17	0.02	0.00	0.82	99.84
2.F.2 Foam Blowing Agents	F-gases	3.89	3.89	41.88	0.00	0.17	0.02	0.00	0.71	99.86
1.B.2.c Fugitive Emissions from Fuels - Venting and flaring	CO_2	2.84	2.84	57.03	0.00	0.17	0.01	0.00	0.97	99.87
1.A.4 Other Sectors - Gaseous Fuels	N_2O	2.70	2.70	53.55	0.00	0.15	0.01	0.00	0.91	99.88
1.A.3.c Railways	CH_4	1.11	1.11	125.67	0.00	0.14	0.01	0.00	2.13	99.90
2.C.1 Iron and Steel Production	CH_4	5.12	5.12	25.50	0.01	0.14	0.01	0.01	0.43	99.91
2.F.4 Aerosols	F-gases	2.91	2.91	41.88	0.00	0.13	0.01	0.00	0.71	99.92
1.A.2 Manufacturing Industries and Construction - Gaseous Fuels	N_2O	2.17	2.17	53.38	0.00	0.12	0.01	0.00	0.90	99.93
1.A.2 Manufacturing Industries and Construction - Gaseous Fuels	CH_4	2.29	2.29	41.72	0.00	0.10	0.01	0.00	0.71	99.94
1.A.3.a Domestic Aviation	CO_2	15.55	15.55	5.36	0.02	0.09	0.01	0.02	0.09	99.95
1.A.1 Energy industries - Gaseous Fuels	N_2O	1.31	1.31	53.36	0.00	0.07	0.01	0.00	0.90	99.95
1.A.2 Manufacturing Industries and Construction - Liquid Fuels	N_2O	0.92	0.92	70.07	0.00	0.07	0.01	0.00	1.19	99.96
1.A.3.c Railways	N_2O	0.47	0.47	125.40	0.00	0.06	0.01	0.00	2.12	99.97
2.D.2 Paraffin Wax Use	CO_2	8.25	8.25	7.07	0.01	0.06	0.01	0.01	0.12	99.97
1.A.4 Other Sectors - Liquid Fuels	CH_4	1.05	1.05	55.27	0.00	0.06	0.01	0.00	0.94	99.98
1.A.1 Energy industries - Gaseous Fuels	CH_4	1.39	1.39	41.71	0.00	0.06	0.01	0.00	0.71	99.98
1.A.3.d Transport - Domestic navigation	CO_2	9.44	9.44	5.00	0.01	0.05	0.00	0.01	0.08	99.99
2.H Other	CO_2	0.94	0.94	43.57	0.00	0.04	0.00	0.00	0.74	99.99
1.A.2 Manufacturing Industries and Construction - Liquid Fuels	CH_4	0.53	0.53	55.09	0.00	0.03	0.00	0.00	0.93	99.99
1.A.1 Energy industries - Liquid Fuels	N_2O	0.23	0.23	70.02	0.00	0.02	0.00	0.00	1.19	99.99
2.C.6 Zinc Production	CO_2	0.25	0.25	50.25	0.00	0.01	0.00	0.00	0.85	100.00
1.A.3.a Domestic Aviation	N_2O	0.11	0.11	110.07	0.00	0.01	0.00	0.00	1.86	100.00
1.A.1 Energy industries - Liquid Fuels	CH_4	0.20	0.20	55.03	0.00	0.01	0.00	0.00	0.93	100.00
2.C.2 Ferroalloys Production	CO_2	0.43	0.43	25.50	0.00	0.01	0.00	0.00	0.43	100.00
1.A.3.e Other Transportation	CO_2	0.97	0.97	5.00	0.00	0.01	0.00	0.00	0.08	100.00
2.H Other	F-gases	0.18	0.18	15.81	0.00	0.00	0.00	0.00	0.27	100.00
1.B.2.b Fugitive Emissions from Fuels - Oil and Natural Gas - Natural Gas	CO_2	0.05	0.05	50.29	0.00	0.00	0.00	0.00	0.85	100.00
1.A.5.b Other mobile - Liquid Fuels	CH_4	0.04	0.04	55.15	0.00	0.00	0.00	0.00	0.93	100.00
1.B.2.a Fugitive Emissions from Fuels - Oil and Natural Gas - Oil	CO_2	0.03	0.03	50.42	0.00	0.00	0.00	0.00	0.85	100.00
1.B.2.c Fugitive Emissions from Fuels - Venting and flaring	N_2O	0.01	0.01	74.33	0.00	0.00	0.00	0.00	1.26	100.00
1.A.3.d Transport - Domestic navigation	N_2O	0.07	0.07	5.18	0.00	0.00	0.00	0.00	0.09	100.00
1.A.3.a Domestic Aviation	CH_4	0.00	0.00	78.60	0.00	0.00	0.00	0.00	1.33	100.00
1.A.3.d Transport - Domestic navigation	CH_4	0.03	0.03	5.10	0.00	0.00	0.00	0.00	0.09	100.00
1.A.3.e Other Transportation	N_2O	0.00	0.00	60.13	0.00	0.00	0.00	0.00	1.02	100.00
1.A.3.e Other Transportation	CH_4	0.00	0.00	50.16	0.00	0.00	0.00	0.00	0.85	100.00
2.F.5 Solvents	F-gases	0.00	0.00	43.57	0.00	0.00	0.00	0.00	0.74	100.00

4.A.1 Forest Land remaining Forest Land	CO_2	0.00	0.00	38.84	0.00	0.00	0.00	0.00	0.66	100.00
4.A.1 Forest Land remaining Forest Land	CH_4	0.00	0.00	38.84	0.00	0.00	0.00	0.00	0.66	100.00

Tab. A1 9 Spreadsheet for Approach 2 KC IPCC 2006 Gl., 2024 – Trend Assessment including LULUCF

IPCC Source Categories	GHG	Base Year Estimate (Abs)	Current Year Estimate (Abs)	Combined Uncertainty	TA_A1	Uncertain ammount BY	Uncertain ammount CY	BY uncertain total	CY uncertain total	Level A 2 assessment	Trend A2 Assessment	% contribution to Trend	Cumulative fraction of uncertainty (BY)	Cumulative Total (TA)
4.A.1 Forest Land remaining Forest Land	CO_2	-8191	-2282	43	12	-3484	-971	-11676	-3253	-3	494	26	-9.43	25.61
5.A Solid Waste Disposal	CH_4	2008	3824	64	3	1279	2436	3287	6260	6	208	11	23.67	36.42
2.F.1 Refrigeration and Air conditioning	F-gases	0	3451	44	4	0	1503	0	4954	5	174	9	14.61	45.44
1.B.1.a Coal Mining and Handling	CH_4	8621	475	38	4	3295	181	11915	656	1	168	9	1.76	54.16
1.A.4 Other Sectors - Solid Fuels	CO_2	24005	1547	10	12	2392	154	26397	1702	2	119	6	1.50	60.35
4.G Harvested wood products	CO_2	-1680	-1285	62	1	-1042	-797	-2722	-2082	-2	89	5	-7.75	64.97
1.A.3.b Road Transportation	CO_2	10251	20152	4	17	378	744	10630	20896	20	64	3	7.23	68.31
1.A.3.b Road Transportation	N_2O	101	336	180	0	181	606	282	942	1	60	3	5.89	71.40
5.B Biological treatment of solid waste	CH_4	0	500	91	1	0	456	0	956	1	53	3	4.43	74.14
1.A.2 Manufacturing Industries and Construction - Solid Fuels	CO_2	35636	3115	3	17	1008	88	36644	3203	3	48	2	0.86	76.61
1.A.4 Other Sectors - Solid Fuels	CH_4	1492	134	56	1	833	75	2325	208	0	39	2	0.73	78.64
1.A.2 Manufacturing Industries and Construction - Other Fossil Fuels	CO_2	0	481	61	1	0	292	0	774	1	34	2	2.84	80.40
1.A.4 Other Sectors - Biomass	CH_4	363	644	52	1	189	335	552	979	1	28	1	3.26	81.85
2.C.1 Iron and Steel Production	CO_2	9782	3026	12	2	1194	369	10976	3395	3	26	1	3.59	83.18
2.B.8 Petrochemical and Carbon Black Production	CO_2	792	923	40	1	319	372	1112	1295	1	25	1	3.62	84.47
3.D.1 Direct N_2O Emissions From Managed Soils	N_2O	2193	2084	21	1	452	430	2645	2514	2	24	1	4.18	85.70
5.D Wastewater treatment and discharge	CH_4	1083	856	58	0	632	500	1715	1356	1	22	1	4.86	86.81
1.A.4 Other Sectors - Gaseous Fuels	CO_2	4174	5704	5	4	200	273	4374	5977	6	20	1	2.65	87.86
4.C.1 Grassland remaining Grassland	CO_2	60	-408	35	1	21	-142	80	-549	-1	18	1	-1.38	88.77
3.G Liming	CO_2	1237	132	30	1	376	40	1613	173	0	17	1	0.39	89.65
1.B.2.b Fugitive Emissions from Fuels - Oil and Natural Gas - Natural Gas	CH_4	1170	351	50	0	582	174	1752	525	1	13	1	1.69	90.33

3.D.2 Indirect N_2O Emissions From Managed Soils	N_2O	437	580	30	0	133	176	571	756	1	13	1	1.71	91.00
1.A.2 Manufacturing Industries and Construction - Liquid Fuels	CO_2	5502	578	4	2	227	24	5730	602	1	10	1	0.23	91.53
3.B Manure Management	CH_4	1539	371	22	0	344	83	1883	454	0	10	1	0.81	92.06
3.A Enteric Fermentation	CH_4	6523	3698	16	1	1031	585	7555	4283	4	8	0	5.68	92.49
3.H Urea application	CO_2	109	191	52	0	57	100	165	291	0	8	0	0.97	92.92
4.A.2 Land converted to Forest Land	CO_2	-208	-633	21	0	-43	-131	-251	-764	-1	8	0	-1.27	93.32
1. Energy (indirect CO_2 emissions)	CO_2	1020	93	14	0	144	13	1164	106	0	7	0	0.13	93.67
2.B.2 Nitric Acid Production	N_2O	933	87	16	0	145	14	1078	101	0	7	0	0.13	94.02
5.D Wastewater treatment and discharge	N_2O	208	200	56	0	117	113	326	313	0	6	0	1.10	94.35
1.A.1 Energy industries - Other Fossil Fuels	CO_2	24	320	17	0	4	55	28	375	0	6	0	0.54	94.67
1.A.1 Energy industries - Solid Fuels	CO_2	53720	28241	3	2	1760	925	55479	29166	29	6	0	8.99	94.98
2.A.4 Other Process Uses of Carbonates	CO_2	114	496	11	1	13	55	127	552	1	6	0	0.54	95.27
2.G Other Product Manufacture and Use	N_2O	183	199	44	0	80	87	263	285	0	5	0	0.84	95.56
1.A.4 Other Sectors - Biomass	N_2O	46	81	71	0	33	58	79	139	0	5	0	0.56	95.81
1.A.1 Energy industries - Gaseous Fuels	CO_2	1336	2775	2	2	25	53	1361	2828	3	5	0	0.51	96.05
1.A.2 Manufacturing Industries and Construction - Gaseous Fuels	CO_2	5686	4587	2	2	128	103	5813	4690	5	5	0	1.00	96.29
1.A.2 Manufacturing Industries and Construction - Solid Fuels	N_2O	136	12	70	0	95	9	231	21	0	4	0	0.08	96.52
3.B Manure Management	N_2O	976	390	40	0	393	157	1369	548	1	4	0	1.53	96.74
1.A.4 Other Sectors - Liquid Fuels	CO_2	3776	1289	6	1	231	79	4007	1368	1	4	0	0.77	96.96
1.A.3.b Road Transportation	CH_4	89	27	199	0	177	53	265	80	0	4	0	0.52	97.16
1.B.1.a Coal Mining and Handling	CO_2	542	61	14	0	77	9	620	70	0	3	0	0.08	97.34
1.A.4 Other Sectors - Solid Fuels	N_2O	92	6	71	0	65	5	157	11	0	3	0	0.04	97.51
4.D.2. Land converted to Wetlands	CO_2	-15	12	81	0	-12	9	-26	21	0	3	0	0.09	97.67
1.A.2 Manufacturing Industries and Construction - Solid Fuels	CH_4	96	9	65	0	62	6	158	14	0	3	0	0.05	97.82
1.A.1 Energy industries - Biomass	N_2O	0	35	70	0	0	24	1	59	0	3	0	0.24	97.97
1.A.2 Manufacturing Industries and Construction - Biomass	N_2O	15	37	70	0	10	26	25	63	0	2	0	0.25	98.09
1.A.4 Other Sectors - Liquid Fuels	N_2O	18	38	70	0	12	27	30	65	0	2	0	0.26	98.22
4.E.2 Land converted to Settlements	N_2O	27	6	250	0	67	15	94	21	0	2	0	0.14	98.33

4.C.2 Land converted to Grassland	CO_2	-253	-416	43	0	-108	-178	-362	-593	-1	2	0	-1.73	98.42
2.F.3 Fire Protection	F-gases	0	34	42	0	0	14	0	48	0	2	0	0.14	98.50
1.A.1 Energy industries - Biomass	CH_4	0	28	50	0	0	14	1	41	0	2	0	0.13	98.58
2.D.1 Lubricant Use	CO_2	116	84	50	0	58	42	174	127	0	2	0	0.41	98.66
2.B.8 Petrochemical and Carbon Black Production	CH_4	41	52	40	0	16	21	57	73	0	1	0	0.20	98.74
1.A.1 Energy industries - Liquid Fuels	CO_2	1514	359	3	0	49	12	1563	371	0	1	0	0.11	98.82
4.B.2. Land converted to Cropland	N_2O	29	10	250	0	73	24	103	34	0	1	0	0.24	98.89
1.A.2 Manufacturing Industries and Construction - Biomass	CH_4	12	29	51	0	6	15	18	44	0	1	0	0.14	98.96
4.E.2 Land converted to Settlements	CO_2	470	263	38	0	181	101	650	365	0	1	0	0.98	99.03
2.G Other Product Manufacture and Use	F-gases	87	65	44	0	38	28	124	94	0	1	0	0.28	99.09
5.C Incineration and open burning of waste	CO_2	20	71	16	0	3	11	23	82	0	1	0	0.11	99.15
1.B.2.c Fugitive Emissions from Fuels - Venting and flaring	CH_4	14	19	74	0	10	14	24	34	0	1	0	0.14	99.20
1.A.3.c Railways	CO_2	768	216	5	0	40	11	808	227	0	1	0	0.11	99.25
2.A.2 Lime Production	CO_2	1337	398	3	0	38	11	1374	409	0	1	0	0.11	99.30
1.A.5.b Other mobile - Liquid Fuels	CO_2	192	242	5	0	9	12	201	254	0	1	0	0.12	99.34
2.E Electronics industry	F-gases	0	42	15	0	0	6	0	48	0	1	0	0.06	99.38
2.A.1 Cement Production	CO_2	2489	1450	3	0	70	41	2560	1491	1	1	0	0.40	99.42
2.B.10 Other	CO_2	0	145	4	0	0	6	0	151	0	1	0	0.06	99.45
2.B.1 Ammonia Production	CO_2	991	431	9	0	85	37	1076	468	0	1	0	0.36	99.48
1.A.2 Manufacturing Industries and Construction - Other Fossil Fuels	N_2O	0	6	81	0	0	5	0	11	0	1	0	0.05	99.51
1.A.5.b Other mobile - Liquid Fuels	N_2O	2	8	70	0	1	6	3	13	0	1	0	0.05	99.54
1.A.1 Energy industries - Solid Fuels	N_2O	213	113	70	0	149	79	363	192	0	1	0	0.77	99.57
2.C.5 Lead Production	CO_2	4	10	51	0	2	5	6	16	0	0	0	0.05	99.60
5.C Incineration and open burning of waste	CH_4	0	5	82	0	0	4	0	9	0	0	0	0.04	99.62
4.B.2 Land converted to Cropland	CO_2	268	114	20	0	53	23	322	137	0	0	0	0.22	99.64
1.A.4 Other Sectors - Gaseous Fuels	CH_4	11	14	42	0	4	6	15	20	0	0	0	0.06	99.67
1.A.2 Manufacturing Industries and Construction - Liquid Fuels	N_2O	11	1	70	0	8	1	19	2	0	0	0	0.01	99.69
2.A.3 Glass Production	CO_2	143	132	5	0	8	7	150	139	0	0	0	0.07	99.71
5.B Biological treatment of solid waste	N_2O	0	63	5	0	0	3	0	66	0	0	0	0.03	99.72
2.B.4 Caprolactam, glyoxal and glyoxylic acid production	N_2O	69	27	40	0	28	11	97	37	0	0	0	0.10	99.74
1.A.2 Manufacturing Industries and	CH_4	0	5	61	0	0	3	0	8	0	0	0	0.03	99.76

Construction - Other Fossil Fuels														
1.A.4 Other Sectors - Liquid Fuels	CH_4	13	1	55	0	7	1	20	2	0	0	0	0.01	99.78
1.A.1 Energy industries - Other Fossil Fuels	N_2O	0	4	80	0	0	3	1	7	0	0	0	0.03	99.80
4.B.1 Cropland remaining Cropland	CO_2	-13	-26	35	0	-4	-9	-17	-35	0	0	0	-0.09	99.81
4.A.1 Forest Land remaining Forest Land	CH_4	20	4	39	0	8	1	27	5	0	0	0	0.01	99.83
4.C.1 Grassland remaining Grassland	CH_4	5	5	81	0	4	4	9	9	0	0	0	0.04	99.84
2.C.6 Zinc Production	CO_2	9	0	51	0	4	0	13	0	0	0	0	0.00	99.85
5.C Incineration and open burning of waste	N_2O	0	3	73	0	0	2	1	5	0	0	0	0.02	99.86
2.D.3 Other non-energy products from fuels and solvent use	CO_2	0	26	7	0	0	2	0	28	0	0	0	0.02	99.87
2.D.2 Paraffin Wax Use	CO_2	9	8	50	0	5	4	14	12	0	0	0	0.04	99.88
1.A.1 Energy industries - Other Fossil Fuels	CH_4	0	3	60	0	0	2	0	5	0	0	0	0.02	99.89
2.F.2 Foam Blowing Agents	F-gases	0	4	42	0	0	2	0	6	0	0	0	0.02	99.90
1.B.1.b Solid Fuel Transformation	CH_4	1	3	49	0	0	2	1	5	0	0	0	0.02	99.91
1.A.2 Manufacturing Industries and Construction - Liquid Fuels	CH_4	6	1	55	0	3	0	9	1	0	0	0	0.00	99.92
2.F.4 Aerosols	F-gases	0	3	42	0	0	1	0	4	0	0	0	0.01	99.93
1.B.2.c Fugitive Emissions from Fuels - Venting and flaring	CO_2	2	3	57	0	1	2	3	4	0	0	0	0.02	99.93
1.B.2.a Fugitive Emissions from Fuels - Oil and Natural Gas - Oil	CH_4	11	4	63	0	7	3	19	7	0	0	0	0.02	99.94
2.C.1 Iron and Steel Production	CH_4	17	5	31	0	5	2	22	7	0	0	0	0.02	99.95
1.A.4 Other Sectors - Gaseous Fuels	N_2O	2	3	54	0	1	1	3	4	0	0	0	0.01	99.95
1.A.1 Energy industries - Liquid Fuels	N_2O	3	0	70	0	2	0	5	0	0	0	0	0.00	99.96
1.A.3.d Transport - Domestic navigation	CO_2	53	9	5	0	3	0	56	10	0	0	0	0.00	99.96
1.A.3.a Domestic Aviation	CO_2	0	16	5	0	0	1	0	16	0	0	0	0.01	99.97
2.C.2 Ferroalloys Production	CH_4	0	3	25	0	0	1	0	4	0	0	0	0.01	99.97
4.A.1 Forest Land remaining Forest Land	N_2O	12	4	39	0	5	2	17	6	0	0	0	0.02	99.98
1.A.3.c Railways	CH_4	1	1	126	0	2	1	3	3	0	0	0	0.01	99.98
1.A.1 Energy industries - Gaseous Fuels	N_2O	1	1	53	0	0	1	1	2	0	0	0	0.01	99.98
1.A.1 Energy industries - Gaseous Fuels	CH_4	1	1	42	0	0	1	1	2	0	0	0	0.01	99.99
1.A.2 Manufacturing Industries and Construction - Gaseous Fuels	N_2O	3	2	53	0	1	1	4	3	0	0	0	0.01	99.99
1.A.3.c Railways	N_2O	2	0	125	0	2	1	3	1	0	0	0	0.01	99.99
1.A.2 Manufacturing Industries and	CH_4	3	2	42	0	1	1	4	3	0	0	0	0.01	99.99

Construction - Gaseous Fuels														
1.A.1 Energy industries - Liquid Fuels	CH_4	2	0	55	0	1	0	2	0	0	0	0	0.00	99.99
1.A.1 Energy industries - Solid Fuels	CH_4	16	8	65	0	10	5	26	13	0	0	0	0.05	100.00
1.A.5.b Other mobile - Liquid Fuels	CH_4	1	0	55	0	0	0	1	0	0	0	0	0.00	100.00
1.A.3.a Domestic Aviation	N_2O	0	0	110	0	0	0	0	0	0	0	0	0.00	100.00
2.C.2 Ferroalloys Production	CO_2	0	0	25	0	0	0	0	1	0	0	0	0.00	100.00
1.A.3.e Other Transportation	CO_2	5	1	5	0	0	0	6	1	0	0	0	0.00	100.00
2.H Other	F-gases	0	0	44	0	0	0	0	0	0	0	0	0.00	100.00
2.H Other	CO_2	0	1	5	0	0	0	0	1	0	0	0	0.00	100.00
4.A.2 Land converted to Forest Land	N_2O	4	2	250	0	10	5	14	7	0	0	0	0.05	100.00
1.B.2.b Fugitive Emissions from Fuels - Oil and Natural Gas - Natural Gas	CO_2	0	0	50	0	0	0	0	0	0	0	0	0.00	100.00
1.B.2.a Fugitive Emissions from Fuels - Oil and Natural Gas - Oil	CO_2	0	0	50	0	0	0	0	0	0	0	0	0.00	100.00
1.A.3.d Transport - Domestic navigation	N_2O	0	0	5	0	0	0	0	0	0	0	0	0.00	100.00
1.B.2.c Fugitive Emissions from Fuels - Venting and flaring	N_2O	0	0	74	0	0	0	0	0	0	0	0	0.00	100.00
1.A.3.a Domestic Aviation	CH_4	0	0	79	0	0	0	0	0	0	0	0	0.00	100.00
1.A.3.d Transport - Domestic navigation	CH_4	0	0	5	0	0	0	0	0	0	0	0	0.00	100.00

Tab. A1 10 Spreadsheet for Approach 2 KC IPCC 2006 Gl., 2024 – Trend Assessment excluding LULUCF

IPCC Source Categories	GHG	Base Year Estimate (Abs)	Current Year Estimate (Abs)	Combined Uncertainty	TA_A1	Uncertain ammount BY	Uncertain ammount CY	BY uncertain total	CY uncertain total	Level A 2 assessment	Trend A2 Assessment	% contribution to Trend	Cumulative fraction of uncertainty (BY)	Cumulative Total (TA)
1.B.1.a Coal Mining and Handling	CH_4	8621	475	38	5	3295	181	11915	656	1	195	14	1.67	14.08
2.F.1 Refrigeration and Air conditioning	F-gases	0	3451	42	5	0	1445	0	4896	5	195	14	15.01	28.09
1.A.4 Other Sectors - Solid Fuels	CO_2	24005	1547	10	14	2392	154	26397	1702	2	139	10	1.42	38.09
2.C.1 Iron and Steel Production	CO_2	9782	3026	31	2	3013	932	12795	3958	4	76	5	10.02	43.54
1.A.3.b Road Transportation	CO_2	10251	20152	4	20	378	744	10630	20896	20	75	5	16.88	48.93
1.A.3.b Road Transportation	N_2O	101	336	180	0	181	606	282	942	1	69	5	22.47	53.94
5.A Solid Waste Disposal	CH_4	2008	3824	16	4	317	605	2325	4429	4	60	4	28.05	58.27
5.B Biological treatment of solid waste	CH_4	0	500	82	1	0	412	0	912	1	55	4	31.85	62.27

1.A.2 Manufacturing Industries and Construction - Solid Fuels	CO_2	35636	3115	3	20	1008	88	36644	3203	3	55	4	0.81	66.26
1.A.4 Other Sectors - Solid Fuels	CH_4	1492	134	56	1	833	75	2325	208	0	46	3	1.50	69.54
3.D.1 Direct N2O Emissions From Managed Soils	N_2O	2193	2084	30	1	667	634	2860	2718	3	41	3	7.35	72.48
1.A.2 Manufacturing Industries and Construction - Other Fossil Fuels	CO_2	0	481	61	1	0	292	0	774	1	39	3	10.05	75.31
3.G Liming	CO_2	1237	132	52	1	646	69	1882	202	0	34	2	10.68	77.75
1.A.4 Other Sectors - Biomass	CH_4	363	644	52	1	189	335	552	979	1	33	2	13.78	80.09
2.B.8 Petrochemical and Carbon Black Production	CO_2	792	923	40	1	319	372	1112	1295	1	29	2	17.21	82.16
1.A.4 Other Sectors - Gaseous Fuels	CO_2	4174	5704	5	5	200	273	4374	5977	6	23	2	19.73	83.85
3.B Manure Management	CH_4	1539	371	40	1	620	150	2160	521	0	21	2	21.11	85.38
2.B.2 Nitric Acid Production	N_2O	933	87	40	1	376	35	1309	123	0	20	1	21.44	86.84
1.B.2.b Fugitive Emissions from Fuels - Oil and Natural Gas - Natural Gas	CH_4	1170	351	50	0	582	174	1752	525	0	15	1	23.04	87.95
3.D.2 Indirect N_2O Emissions From Managed Soils	N_2O	437	580	30	0	133	176	571	756	1	15	1	24.67	89.02
3.A Enteric Fermentation	CH_4	6523	3698	22	1	1459	827	7982	4525	4	14	1	32.30	90.03
1.A.2 Manufacturing Industries and Construction - Liquid Fuels	CO_2	5502	578	4	3	227	24	5730	602	1	12	1	32.52	90.89
3.H Urea application	CO_2	109	191	43	0	46	81	155	273	0	8	1	33.27	91.45
1.A.1 Energy industries - Other Fossil Fuels	CO_2	24	320	17	0	4	55	28	375	0	7	1	0.51	91.97
1.A.1 Energy industries - Solid Fuels	CO_2	53720	28241	3	2	1760	925	55479	29166	27	7	1	8.53	92.48
5.B Biological treatment of solid waste	N_2O	0	63	73	0	0	46	0	109	0	6	0	8.96	92.93
1.A.4 Other Sectors - Biomass	N_2O	46	81	71	0	33	58	79	139	0	6	0	9.49	93.33
1.A.1 Energy industries - Gaseous Fuels	CO_2	1336	2775	2	3	25	53	1361	2828	3	5	0	0.49	93.72
1.A.2 Manufacturing Industries and Construction - Gaseous Fuels	CO_2	5686	4587	2	2	128	103	5813	4690	4	5	0	1.44	94.11
1.A.2 Manufacturing Industries and Construction - Solid Fuels	N_2O	136	12	70	0	95	9	231	21	0	5	0	1.52	94.48
2.A.4 Other Process Uses of Carbonates	CO_2	114	496	9	1	10	43	124	539	1	5	0	1.91	94.85
1.A.4 Other Sectors - Liquid Fuels	CO_2	3776	1289	6	1	231	79	4007	1368	1	5	0	2.64	95.19
5.C Incineration and open burning of waste	CO_2	20	71	58	0	12	41	32	112	0	5	0	3.02	95.54
1.A.3.b Road Transportation	CH_4	89	27	199	0	177	53	265	80	0	5	0	3.51	95.87
1.B.1.a Coal Mining and Handling	CO_2	542	61	14	0	77	9	620	70	0	4	0	0.08	96.16
1.A.4 Other Sectors - Solid Fuels	N_2O	92	6	71	0	65	5	157	11	0	4	0	0.12	96.42
1.A.2 Manufacturing Industries and Construction - Solid Fuels	CH_4	96	9	65	0	62	6	158	14	0	3	0	0.17	96.67
1.A.1 Energy industries - Biomass	N_2O	0	35	70	0	0	24	1	59	0	3	0	0.23	96.90

1.A.2 Manufacturing Industries and Construction - Biomass	N_2O	15	37	70	0	10	26	25	63	0	3	0	0.46	97.11
1.A.4 Other Sectors - Liquid Fuels	N_2O	18	38	70	0	12	27	30	65	0	3	0	0.71	97.31
3.B Manure Management	N_2O	976	390	21	0	201	81	1177	471	0	3	0	1.45	97.49
2.E Electronics industry	F-gases	0	42	44	0	0	18	0	60	0	2	0	0.17	97.67
2.B.10 Other	CO_2	0	145	12	0	0	18	0	163	0	2	0	0.33	97.84
2.A.2 Lime Production	CO_2	1337	398	5	0	72	21	1409	419	0	2	0	0.53	97.98
2.F.3 Fire Protection	F-gases	0	34	42	0	0	14	0	48	0	2	0	0.66	98.12
1.A.1 Energy industries - Biomass	CH_4	0	28	50	0	0	14	1	41	0	2	0	0.13	98.25
2.D.1 Lubricant Use	CO_2	116	84	50	0	58	42	174	127	0	2	0	0.52	98.38
1.A.1 Energy industries - Liquid Fuels	CO_2	1514	359	3	1	49	12	1563	371	0	2	0	0.11	98.50
1.A.2 Manufacturing Industries and Construction - Biomass	CH_4	12	29	51	0	6	15	18	44	0	2	0	0.24	98.62
1. Energy (indirect CO_2 emissions)	CO_2	1020	93	3	1	29	3	1049	96	0	2	0	0.27	98.73
2.G Other Product Manufacture and Use	F-gases	87	65	44	0	38	28	124	94	0	1	0	0.53	98.83
2.B.1 Ammonia Production	CO_2	991	431	16	0	154	67	1145	498	0	1	0	1.15	98.92
1.B.2.c Fugitive Emissions from Fuels - Venting and flaring	CH_4	14	19	74	0	10	14	24	34	0	1	0	1.28	99.01
1.A.3.c Railways	CO_2	768	216	5	0	40	11	808	227	0	1	0	1.39	99.09
1.A.5.b Other mobile - Liquid Fuels	CO_2	192	242	5	0	9	12	201	254	0	1	0	1.49	99.16
2.A.3 Glass Production	CO_2	143	132	11	0	16	15	159	146	0	1	0	1.63	99.23
2.A.1 Cement Production	CO_2	2489	1450	3	0	70	41	2560	1491	1	1	0	2.01	99.29
2.G Other Product Manufacture and Use	N_2O	183	199	5	0	10	11	193	209	0	1	0	2.11	99.34
1.A.2 Manufacturing Industries and Construction - Other Fossil Fuels	N_2O	0	6	81	0	0	5	0	11	0	1	0	2.15	99.39
1.A.5.b Other mobile - Liquid Fuels	N_2O	2	8	70	0	1	6	3	13	0	1	0	2.21	99.44
1.A.1 Energy industries - Solid Fuels	N_2O	213	113	70	0	149	79	363	192	0	1	0	0.73	99.48
2.C.5 Lead Production	CO_2	4	10	51	0	2	5	6	16	0	1	0	0.78	99.53
2.D.3 Other non-energy products from fuels and solvent use	CO_2	0	26	15	0	0	4	0	30	0	1	0	0.81	99.56
1.A.4 Other Sectors - Gaseous Fuels	CH_4	11	14	42	0	4	6	15	20	0	1	0	0.87	99.60
1.A.2 Manufacturing Industries and Construction - Liquid Fuels	N_2O	11	1	70	0	8	1	19	2	0	0	0	0.87	99.63
2.B.4 Caprolactam, glyoxal and glyoxylic acid production	N_2O	69	27	40	0	28	11	97	37	0	0	0	0.97	99.66
1.A.2 Manufacturing Industries and Construction - Other Fossil Fuels	CH_4	0	5	61	0	0	3	0	8	0	0	0	1.00	99.69
1.A.4 Other Sectors - Liquid Fuels	CH_4	13	1	55	0	7	1	20	2	0	0	0	1.01	99.72
1.A.1 Energy industries - Other Fossil Fuels	N_2O	0	4	80	0	0	3	1	7	0	0	0	0.03	99.75

5.C Incineration and open burning of waste	CH_4	0	5	56	0	0	3	0	8	0	0	0	0.05	99.78
2.C.6 Zinc Production	CO_2	9	0	50	0	4	0	13	0	0	0	0	0.05	99.80
1.A.1 Energy industries - Other Fossil Fuels	CH_4	0	3	60	0	0	2	0	5	0	0	0	0.02	99.81
2.C.2 Ferroalloys Production	CH_4	0	3	51	0	0	2	0	5	0	0	0	0.03	99.83
2.F.2 Foam Blowing Agents	F-gases	0	4	42	0	0	2	0	6	0	0	0	0.05	99.84
1.B.1.b Solid Fuel Transformation	CH_4	1	3	49	0	0	2	1	5	0	0	0	0.06	99.86
1.A.2 Manufacturing Industries and Construction - Liquid Fuels	CH_4	6	1	55	0	3	0	9	1	0	0	0	0.06	99.87
2.B.8 Petrochemical and Carbon Black Production	CH_4	41	52	4	0	2	2	42	54	0	0	0	0.08	99.88
2.F.4 Aerosols	F-gases	0	3	42	0	0	1	0	4	0	0	0	0.09	99.90
1.B.2.c Fugitive Emissions from Fuels - Venting and flaring	CO_2	2	3	57	0	1	2	3	4	0	0	0	0.11	99.91
1.B.2.a Fugitive Emissions from Fuels - Oil and Natural Gas - Oil	CH_4	11	4	63	0	7	3	19	7	0	0	0	0.13	99.92
1.A.4 Other Sectors - Gaseous Fuels	N_2O	2	3	54	0	1	1	3	4	0	0	0	0.15	99.92
1.A.1 Energy industries - Liquid Fuels	N_2O	3	0	70	0	2	0	5	0	0	0	0	0.00	99.93
1.A.3.d Transport - Domestic navigation	CO_2	53	9	5	0	3	0	56	10	0	0	0	0.01	99.94
1.A.3.a Domestic Aviation	CO_2	0	16	5	0	0	1	0	16	0	0	0	0.01	99.95
2.C.1 Iron and Steel Production	CH_4	17	5	25	0	4	1	21	6	0	0	0	0.03	99.96
1.A.3.c Railways	CH_4	1	1	126	0	2	1	3	3	0	0	0	0.04	99.96
1.A.1 Energy industries - Gaseous Fuels	N_2O	1	1	53	0	0	1	1	2	0	0	0	0.01	99.97
1.A.1 Energy industries - Gaseous Fuels	CH_4	1	1	42	0	0	1	1	2	0	0	0	0.01	99.97
1.A.2 Manufacturing Industries and Construction - Gaseous Fuels	N_2O	3	2	53	0	1	1	4	3	0	0	0	0.02	99.98
2.H Other	CO_2	0	1	44	0	0	0	0	1	0	0	0	0.02	99.98
1.A.3.c Railways	N_2O	2	0	125	0	2	1	3	1	0	0	0	0.03	99.98
1.A.2 Manufacturing Industries and Construction - Gaseous Fuels	CH_4	3	2	42	0	1	1	4	3	0	0	0	0.03	99.99
1.A.1 Energy industries - Liquid Fuels	CH_4	2	0	55	0	1	0	2	0	0	0	0	0.00	99.99
2.D.2 Paraffin Wax Use	CO_2	9	8	7	0	1	1	10	9	0	0	0	0.01	99.99
1.A.1 Energy industries - Solid Fuels	CH_4	16	8	65	0	10	5	26	13	0	0	0	0.05	99.99
1.A.5.b Other mobile - Liquid Fuels	CH_4	1	0	55	0	0	0	1	0	0	0	0	0.05	100.00
1.A.3.a Domestic Aviation	N_2O	0	0	110	0	0	0	0	0	0	0	0	0.05	100.00
2.C.2 Ferroalloys Production	CO_2	0	0	25	0	0	0	0	1	0	0	0	0.05	100.00
1.A.3.e Other Transportation	CO_2	5	1	5	0	0	0	6	1	0	0	0	0.05	100.00
2.H Other	F-gases	0	0	16	0	0	0	0	0	0	0	0	0.05	100.00
1.B.2.b Fugitive Emissions from Fuels - Oil and Natural Gas - Natural Gas	CO_2	0	0	50	0	0	0	0	0	0	0	0	0.05	100.00

1.B.2.a Fugitive Emissions from Fuels - Oil and Natural Gas - Oil	CO_2	0	0	50	0	0	0	0	0	0	0	0	0.05	100.00
1.A.3.d Transport - Domestic navigation	N_2O	0	0	5	0	0	0	0	0	0	0	0	0.05	100.00
1.B.2.c Fugitive Emissions from Fuels - Venting and flaring	N_2O	0	0	74	0	0	0	0	0	0	0	0	0.05	100.00
1.A.3.a Domestic Aviation	CH_4	0	0	79	0	0	0	0	0	0	0	0	0.05	100.00
1.A.3.d Transport - Domestic navigation	CH_4	0	0	5	0	0	0	0	0	0	0	0	0.05	100.00
1.A.3.e Other Transportation	N_2O	0	0	60	0	0	0	0	0	0	0	0	0.05	100.00
1.A.3.e Other Transportation	CH_4	0	0	50	0	0	0	0	0	0	0	0	0.05	100.00
2.F.5 Solvents	F-gases	0	0	44	0	0	0	0	0	0	0	0	0.05	100.00
4.A.1 Forest Land remaining Forest Land	CO_2	0	0	39	0	0	0	0	0	0	0	0	0.00	100.00
4.A.1 Forest Land remaining Forest Land	CH_4	0	0	39	0	0	0	0	0	0	0	0	0.00	100.00

Annex 2 Assessment of uncertainty

Tab. A2 1 Uncertainty analysis (Tier 1), first part of Table 3.3 of IPCC 2006 Gl. incl. LULUCF

Input DATA					
IPCC Source Category	Gas	Base year emissions (1990) abs	Latest year (t) emissions abs	Activity data uncertainty	Emission factor uncertainty
1.A.1 Energy industries - Solid Fuels	CO_2	53719.76	28240.73	2.72	1.83
1.A.1 Energy industries - Solid Fuels	CH_4	15.72	8.12	2.72	65.00
1.A.1 Energy industries - Solid Fuels	N_2O	213.31	112.63	2.72	70.00
1.A.1 Energy industries - Liquid Fuels	CO_2	1514.04	359.48	1.76	2.74
1.A.1 Energy industries - Liquid Fuels	CH_4	1.59	0.20	1.76	55.00
1.A.1 Energy industries - Liquid Fuels	N_2O	2.94	0.23	1.76	70.00
1.A.1 Energy industries - Gaseous Fuels	CO_2	1336.03	2774.98	1.83	0.50
1.A.1 Energy industries - Gaseous Fuels	CH_4	0.69	1.39	1.83	41.67
1.A.1 Energy industries - Gaseous Fuels	N_2O	0.65	1.31	1.83	53.33
1.A.1 Energy industries - Biomass	CH_4	0.34	27.56	6.33	50.00
1.A.1 Energy industries - Biomass	N_2O	0.43	34.76	6.33	70.00
1.A.1 Energy industries - Other Fossil Fuels	CO_2	24.04	320.00	7.70	15.48
1.A.1 Energy industries - Other Fossil Fuels	CH_4	0.22	2.93	7.70	60.00
1.A.1 Energy industries - Other Fossil Fuels	N_2O	0.28	3.70	7.70	80.00
1.A.2 Manufacturing Industries and Construction - Solid Fuels	CO_2	35635.57	3114.68	2.16	1.83
1.A.2 Manufacturing Industries and Construction - Solid Fuels	CH_4	96.04	8.59	2.16	65.00
1.A.2 Manufacturing Industries and Construction - Solid Fuels	N_2O	135.94	12.17	2.16	70.00
1.A.2 Manufacturing Industries and Construction - Liquid Fuels	CO_2	5502.33	577.96	3.10	2.74
1.A.2 Manufacturing Industries and Construction - Liquid Fuels	CH_4	6.03	0.53	3.10	55.00
1.A.2 Manufacturing Industries and Construction - Liquid Fuels	N_2O	11.42	0.92	3.10	70.00
1.A.2 Manufacturing Industries and Construction - Gaseous Fuels	CO_2	5685.63	4586.76	2.19	0.50
1.A.2 Manufacturing Industries and Construction - Gaseous Fuels	CH_4	2.92	2.29	2.19	41.67
1.A.2 Manufacturing Industries and Construction - Gaseous Fuels	N_2O	2.76	2.17	2.19	53.33
1.A.2 Manufacturing Industries and Construction - Biomass	CH_4	11.70	29.32	7.12	50.00
1.A.2 Manufacturing Industries and Construction - Biomass	N_2O	14.76	36.85	7.12	70.00
1.A.2 Manufacturing Industries and Construction - Other Fossil Fuels	CO_2	0.00	481.38	9.17	60.00
1.A.2 Manufacturing Industries and Construction - Other Fossil Fuels	CH_4	0.00	4.98	9.17	60.00
1.A.2 Manufacturing Industries and Construction - Other Fossil Fuels	N_2O	0.00	6.28	9.17	80.00
1.A.3.a Domestic Aviation	CO_2	0.00	15.55	4.00	3.57
1.A.3.a Domestic Aviation	CH_4	0.00	0.00	4.00	78.50
1.A.3.a Domestic Aviation	N_2O	0.00	0.11	4.00	110.00
1.A.3.b Road Transportation	CO_2	10251.31	20152.39	3.00	2.15
1.A.3.b Road Transportation	CH_4	88.66	26.80	3.00	199.42
1.A.3.b Road Transportation	N_2O	100.51	335.89	3.00	180.37
1.A.3.c Railways	CO_2	767.62	215.90	5.00	1.56
1.A.3.c Railways	CH_4	1.23	1.11	5.00	125.57
1.A.3.c Railways	N_2O	1.55	0.47	5.00	125.30
1.A.3.d Transport - Domestic navigation	CO_2	53.48	9.44	5.00	0.01
1.A.3.d Transport - Domestic navigation	CH_4	0.14	0.03	5.00	1.01
1.A.3.d Transport - Domestic navigation	N_2O	0.38	0.07	5.00	1.37

Input DATA					
IPCC Source Category	Gas	Base year emissions (1990) abs	Latest year (t) emissions abs	Activity data uncertainty	Emission factor uncertainty
1.A.3.e Other Transportation	CO_2	5.42	0.97	4.00	3.00
1.A.3.e Other Transportation	CH_4	0.00	0.00	4.00	50.00
1.A.3.e Other Transportation	N_2O	0.00	0.00	4.00	60.00
1.A.4 Other Sectors - Solid Fuels	CO_2	24005.03	1547.36	9.80	1.83
1.A.4 Other Sectors - Solid Fuels	CH_4	1491.69	133.66	9.80	55.00
1.A.4 Other Sectors - Solid Fuels	N_2O	91.86	6.48	9.80	70.00
1.A.4 Other Sectors - Liquid Fuels	CO_2	3775.90	1289.15	5.47	2.74
1.A.4 Other Sectors - Liquid Fuels	CH_4	13.04	1.05	5.47	55.00
1.A.4 Other Sectors - Liquid Fuels	N_2O	17.79	38.22	5.47	70.00
1.A.4 Other Sectors - Gaseous Fuels	CO_2	4173.90	5703.74	4.76	0.50
1.A.4 Other Sectors - Gaseous Fuels	CH_4	10.72	14.24	4.76	41.67
1.A.4 Other Sectors - Gaseous Fuels	N_2O	2.03	2.70	4.76	53.33
1.A.4 Other Sectors - Biomass	CH_4	363.17	644.08	14.53	50.00
1.A.4 Other Sectors - Biomass	N_2O	45.79	81.15	14.53	70.00
1.A.5.b Other mobile - Liquid Fuels	CO_2	191.93	242.25	4.05	2.74
1.A.5.b Other mobile - Liquid Fuels	CH_4	0.64	0.04	4.05	55.00
1.A.5.b Other mobile - Liquid Fuels	N_2O	1.74	7.90	4.05	70.00
1.B.1.a Coal Mining and Handling	CO_2	542.38	60.98	7.38	12.17
1.B.1.a Coal Mining and Handling	CH_4	8620.61	474.57	7.38	37.50
1.B.1.b Solid Fuel Transformation	CH_4	0.84	3.36	10.00	47.50
1.B.2.a Fugitive Emissions from Fuels - Oil and Natural Gas - Oil	CO_2	0.02	0.03	6.49	50.00
1.B.2.a Fugitive Emissions from Fuels - Oil and Natural Gas - Oil	CH_4	11.38	3.99	6.49	62.78
1.B.2.b Fugitive Emissions from Fuels - Oil and Natural Gas - Natural Gas	CO_2	0.17	0.05	5.44	50.00
1.B.2.b Fugitive Emissions from Fuels - Oil and Natural Gas - Natural Gas	CH_4	1170.32	350.63	5.44	49.44
1.B.2.c Fugitive Emissions from Fuels - Venting and flaring	CO_2	2.02	2.84	25.00	51.26
1.B.2.c Fugitive Emissions from Fuels - Venting and flaring	CH_4	13.76	19.37	25.00	70.00
1.B.2.c Fugitive Emissions from Fuels - Venting and flaring	N_2O	0.01	0.01	25.00	70.00
1. Energy (indirect CO_2 emissions)	CO_2	1020.18	93.02	10.00	10.00
2.A.1 Cement Production	CO_2	2489.18	1449.97	2.00	2.00
2.A.2 Lime Production	CO_2	1336.65	397.91	2.00	2.00
2.A.3 Glass Production	CO_2	142.75	131.66	5.00	2.00
2.A.4 Other Process Uses of Carbonates	CO_2	113.86	496.06	5.00	10.00
2.B.1 Ammonia Production	CO_2	990.80	430.96	5.00	7.00
2.B.2 Nitric Acid Production	N_2O	932.80	87.45	4.00	15.00
2.B.4 Caprolactam, glyoxal and glyoxylic acid production	N_2O	68.82	26.50	5.00	40.00
2.B.8 Petrochemical and Carbon Black Production	CO_2	792.47	922.85	5.00	40.00
2.B.8 Petrochemical and Carbon Black Production	CH_4	40.51	51.89	5.00	40.00
2.B.10 Other	CO_2	0.00	145.35	3.00	2.50
2.C.1 Iron and Steel Production	CO_2	9782.03	3025.57	7.00	10.00
2.C.1 Iron and Steel Production	CH_4	16.62	5.12	7.00	30.00
2.C.2 Ferroalloys Production	CO_2	0.03	0.43	5.00	25.00
2.C.2 Ferroalloys Production	CH_4	0.20	3.37	5.00	25.00
2.C.5 Lead Production	CO_2	4.04	10.30	10.00	50.00
2.C.6 Zinc Production	CO_2	8.70	0.25	10.00	50.00
2.D.1 Lubricant Use	CO_2	116.13	84.30	5.00	50.00
2.D.2 Paraffin Wax Use	CO_2	9.43	8.25	5.00	50.00
2.D.3 Other non-energy products from fuels and solvent use	CO_2	0.00	26.00	5.00	5.00
2.E Electronics industry	F-gases	0.00	41.51	3.00	15.00
2.F.1 Refrigeration and Air conditioning	F-gases	0.00	3450.95	37.00	23.00
2.F.2 Foam Blowing Agents	F-gases	0.00	3.89	35.00	23.00
2.F.3 Fire Protection	F-gases	0.00	33.79	35.00	23.00
2.F.4 Aerosols	F-gases	0.00	2.91	35.00	23.00
2.F.5 Solvents	F-gases	0.00	0.00	35.00	23.00

Input DATA					
IPCC Source Category	Gas	Base year emissions (1990) abs	Latest year (t) emissions abs	Activity data uncertainty	Emission factor uncertainty
2.G Other Product Manufacture and Use	F-gases	86.57	65.28	37.00	23.00
2.G Other Product Manufacture and Use	N_2O	183.38	198.75	37.00	23.00
2.H Other	CO_2	0.00	0.94	5.00	2.00
2.H Other	F-gases	0.00	0.18	37.00	23.00
3.A Enteric Fermentation	CH_4	6523.38	3697.98	5.00	15.00
3.B Manure Management	CH_4	1539.13	371.21	10.00	20.00
3.B Manure Management	N_2O	975.60	390.50	5.00	40.00
3.D.1 Direct N_2O Emissions From Managed Soils	N_2O	2192.74	2084.17	5.00	20.00
3.D.2 Indirect N_2O Emissions From Managed Soils	N_2O	437.48	579.50	5.00	30.00
3.G Liming	CO_2	1236.71	132.49	5.00	30.00
3.H Urea application	CO_2	108.53	191.47	15.00	50.00
4.A.1 Forest Land remaining Forest Land	CO_2	8191.21	2282.12	20.00	37.54
4.A.1 Forest Land remaining Forest Land	CH_4	19.77	3.73	20.00	33.29
4.A.1 Forest Land remaining Forest Land	N_2O	12.31	4.13	20.00	33.29
4.A.2 Land converted to Forest Land	CO_2	208.35	633.08	0.00	20.68
4.A.2 Land converted to Forest Land	N_2O	4.02	1.99	0.00	250.00
4.B.1 Cropland remaining Cropland	CO_2	12.68	26.11	0.00	34.58
4.B.2 Land converted to Cropland	CO_2	268.29	113.86	0.00	19.93
4.B.2. Land converted to Cropland	N_2O	29.32	9.77	0.00	250.00
4.C.1 Grassland remaining Grassland	CO_2	59.69	407.71	0.00	34.78
4.C.1 Grassland remaining Grassland	CH_4	5.22	5.22	0.00	81.00
4.C.2 Land converted to Grassland	CO_2	253.50	415.52	0.00	42.78
4.D.2. Land converted to Wetlands	CO_2	14.55	11.65	0.00	80.85
4.E.2 Land converted to Settlements	CO_2	469.70	263.22	0.00	38.49
4.E.2 Land converted to Settlements	N_2O	26.94	5.96	0.00	250.00
4.G Harvested wood products	CO_2	1680.47	1285.43	0.00	62.00
5.A Solid Waste Disposal	CH_4	2007.82	3824.24	0.00	63.70
5.B Biological treatment of solid waste	CH_4	0.00	499.57	5.00	91.15
5.B Biological treatment of solid waste	N_2O	0.00	63.22	5.00	0.60
5.C Incineration and open burning of waste	CO_2	19.97	70.53	15.00	5.00
5.C Incineration and open burning of waste	CH_4	0.00	4.97	20.00	80.00
5.C Incineration and open burning of waste	N_2O	0.46	2.87	20.00	70.00
5.D Wastewater treatment and discharge	CH_4	1082.93	855.98	30.14	50.00
5.D Wastewater treatment and discharge	N_2O	208.25	200.22	26.00	50.00

Tab. A2 2 Uncertainty analysis (Tier 1), second part of Table 3.3 of IPCC 2006 Gl. incl. LULUCF

	Uncertainty of Emissions			
IPCC Source Category	Gas	Combined uncertainty	Contribution to variance by category in year x	Contribution to variance by category in year x
1.A.1 Energy industries - Solid Fuels	CO_2	3.28	0.83	0.826152
1.A.1 Energy industries - Solid Fuels	CH_4	65.06	0.00	0.000027
1.A.1 Energy industries - Solid Fuels	N_2O	70.05	0.01	0.006010
1.A.1 Energy industries - Liquid Fuels	CO_2	3.25	0.00	0.000132
1.A.1 Energy industries - Liquid Fuels	CH_4	55.03	0.00	0.000000
1.A.1 Energy industries - Liquid Fuels	N_2O	70.02	0.00	0.000000
1.A.1 Energy industries - Gaseous Fuels	CO_2	1.90	0.00	0.002686
1.A.1 Energy industries - Gaseous Fuels	CH_4	41.71	0.00	0.000000
1.A.1 Energy industries - Gaseous Fuels	N_2O	53.36	0.00	0.000000
1.A.1 Energy industries - Biomass	CH_4	50.40	0.00	0.000186
1.A.1 Energy industries - Biomass	N_2O	70.29	0.00	0.000576
1.A.1 Energy industries - Other Fossil Fuels	CO_2	17.29	0.00	0.002956
1.A.1 Energy industries - Other Fossil Fuels	CH_4	60.49	0.00	0.000003
1.A.1 Energy industries - Other Fossil Fuels	N_2O	80.37	0.00	0.000009

	Uncertainty of Emissions			
IPCC Source Category	**Gas**	**Combined uncertainty**	**Contribution to variance by category in year x**	**Contribution to variance by category in year x**
1.A.2 Manufacturing Industries and Construction - Solid Fuels	CO_2	2.83	0.01	0.007497
1.A.2 Manufacturing Industries and Construction - Solid Fuels	CH_4	65.04	0.00	0.000030
1.A.2 Manufacturing Industries and Construction - Solid Fuels	N_2O	70.03	0.00	0.000070
1.A.2 Manufacturing Industries and Construction - Liquid Fuels	CO_2	4.13	0.00	0.000551
1.A.2 Manufacturing Industries and Construction - Liquid Fuels	CH_4	55.09	0.00	0.000000
1.A.2 Manufacturing Industries and Construction - Liquid Fuels	N_2O	70.07	0.00	0.000000
1.A.2 Manufacturing Industries and Construction - Gaseous Fuels	CO_2	2.25	0.01	0.010269
1.A.2 Manufacturing Industries and Construction - Gaseous Fuels	CH_4	41.72	0.00	0.000001
1.A.2 Manufacturing Industries and Construction - Gaseous Fuels	N_2O	53.38	0.00	0.000001
1.A.2 Manufacturing Industries and Construction - Biomass	CH_4	50.50	0.00	0.000212
1.A.2 Manufacturing Industries and Construction - Biomass	N_2O	70.36	0.00	0.000649
1.A.2 Manufacturing Industries and Construction - Other Fossil Fuels	CO_2	60.70	0.08	0.082420
1.A.2 Manufacturing Industries and Construction - Other Fossil Fuels	CH_4	60.70	0.00	0.000009
1.A.2 Manufacturing Industries and Construction - Other Fossil Fuels	N_2O	80.52	0.00	0.000025
1.A.3.a Domestic Aviation	CO_2	5.36	0.00	0.000001
1.A.3.a Domestic Aviation	CH_4	78.60	0.00	0.000000
1.A.3.a Domestic Aviation	N_2O	110.07	0.00	0.000000
1.A.3.b Road Transportation	CO_2	3.69	0.53	0.533767
1.A.3.b Road Transportation	CH_4	199.45	0.00	0.002758
1.A.3.b Road Transportation	N_2O	180.40	0.35	0.354461
1.A.3.c Railways	CO_2	5.24	0.00	0.000123
1.A.3.c Railways	CH_4	125.67	0.00	0.000002
1.A.3.c Railways	N_2O	125.40	0.00	0.000000
1.A.3.d Transport - Domestic navigation	CO_2	5.00	0.00	0.000000
1.A.3.d Transport - Domestic navigation	CH_4	5.10	0.00	0.000000
1.A.3.d Transport - Domestic navigation	N_2O	5.18	0.00	0.000000
1.A.3.e Other Transportation	CO_2	5.00	0.00	0.000000
1.A.3.e Other Transportation	CH_4	50.16	0.00	0.000000
1.A.3.e Other Transportation	N_2O	60.13	0.00	0.000000
1.A.4 Other Sectors - Solid Fuels	CO_2	9.96	0.02	0.022954
1.A.4 Other Sectors - Solid Fuels	CH_4	55.87	0.01	0.005383
1.A.4 Other Sectors - Solid Fuels	N_2O	70.68	0.00	0.000020
1.A.4 Other Sectors - Liquid Fuels	CO_2	6.12	0.01	0.006009
1.A.4 Other Sectors - Liquid Fuels	CH_4	55.27	0.00	0.000000
1.A.4 Other Sectors - Liquid Fuels	N_2O	70.21	0.00	0.000695
1.A.4 Other Sectors - Gaseous Fuels	CO_2	4.79	0.07	0.072042
1.A.4 Other Sectors - Gaseous Fuels	CH_4	41.94	0.00	0.000034
1.A.4 Other Sectors - Gaseous Fuels	N_2O	53.55	0.00	0.000002
1.A.4 Other Sectors - Biomass	CH_4	52.07	0.11	0.108589
1.A.4 Other Sectors - Biomass	N_2O	71.49	0.00	0.003250
1.A.5.b Other mobile - Liquid Fuels	CO_2	4.89	0.00	0.000135

	Uncertainty of Emissions			
IPCC Source Category	**Gas**	**Combined uncertainty**	**Contribution to variance by category in year x**	**Contribution to variance by category in year x**
1.A.5.b Other mobile - Liquid Fuels	CH_4	55.15	0.00	0.000000
1.A.5.b Other mobile - Liquid Fuels	N_2O	70.12	0.00	0.000030
1.B.1.a Coal Mining and Handling	CO_2	14.23	0.00	0.000073
1.B.1.a Coal Mining and Handling	CH_4	38.22	0.03	0.031760
1.B.1.b Solid Fuel Transformation	CH_4	48.54	0.00	0.000003
1.B.2.a Fugitive Emissions from Fuels - Oil and Natural Gas - Oil	CO_2	50.42	0.00	0.000000
1.B.2.a Fugitive Emissions from Fuels - Oil and Natural Gas - Oil	CH_4	63.12	0.00	0.000006
1.B.2.b Fugitive Emissions from Fuels - Oil and Natural Gas - Natural Gas	CO_2	50.29	0.00	0.000000
1.B.2.b Fugitive Emissions from Fuels - Oil and Natural Gas - Natural Gas	CH_4	49.74	0.03	0.029363
1.B.2.c Fugitive Emissions from Fuels - Venting and flaring	CO_2	57.03	0.00	0.000003
1.B.2.c Fugitive Emissions from Fuels - Venting and flaring	CH_4	74.33	0.00	0.000200
1.B.2.c Fugitive Emissions from Fuels - Venting and flaring	N_2O	74.33	0.00	0.000000
1. Energy (indirect CO_2 emissions)	CO_2	14.14	0.00	0.000167
2.A.1 Cement Production	CO_2	2.83	0.00	0.001624
2.A.2 Lime Production	CO_2	2.83	0.00	0.000122
2.A.3 Glass Production	CO_2	5.39	0.00	0.000049
2.A.4 Other Process Uses of Carbonates	CO_2	11.18	0.00	0.002970
2.B.1 Ammonia Production	CO_2	8.60	0.00	0.001327
2.B.2 Nitric Acid Production	N_2O	15.52	0.00	0.000178
2.B.4 Caprolactam, glyoxal and glyoxylic acid production	N_2O	40.31	0.00	0.000110
2.B.8 Petrochemical and Carbon Black Production	CO_2	40.31	0.13	0.133612
2.B.8 Petrochemical and Carbon Black Production	CH_4	40.31	0.00	0.000422
2.B.10 Other	CO_2	3.91	0.00	0.000031
2.C.1 Iron and Steel Production	CO_2	12.21	0.13	0.131684
2.C.1 Iron and Steel Production	CH_4	30.81	0.00	0.000002
2.C.2 Ferroalloys Production	CO_2	25.50	0.00	0.000000
2.C.2 Ferroalloys Production	CH_4	25.50	0.00	0.000001
2.C.5 Lead Production	CO_2	50.99	0.00	0.000027
2.C.6 Zinc Production	CO_2	50.99	0.00	0.000000
2.D.1 Lubricant Use	CO_2	50.25	0.00	0.001732
2.D.2 Paraffin Wax Use	CO_2	50.25	0.00	0.000017
2.D.3 Other non-energy products from fuels and solvent use	CO_2	7.07	0.00	0.000003
2.E Electronics industry	F-gases	15.30	0.00	0.000039
2.F.1 Refrigeration and Air conditioning	F-gases	43.57	2.18	2.182263
2.F.2 Foam Blowing Agents	F-gases	41.88	0.00	0.000003
2.F.3 Fire Protection	F-gases	41.88	0.00	0.000193
2.F.4 Aerosols	F-gases	41.88	0.00	0.000001
2.F.5 Solvents	F-gases	41.88	0.00	0.000000
2.G Other Product Manufacture and Use	F-gases	43.57	0.00	0.000781
2.G Other Product Manufacture and Use	N_2O	43.57	0.01	0.007238
2.H Other	CO_2	5.39	0.00	0.000000
2.H Other	F-gases	43.57	0.00	0.000000
3.A Enteric Fermentation	CH_4	15.81	0.33	0.330067
3.B Manure Management	CH_4	22.36	0.01	0.006652

	Uncertainty of Emissions			
IPCC Source Category	**Gas**	**Combined uncertainty**	**Contribution to variance by category in year x**	**Contribution to variance by category in year x**
3.B Manure Management	N_2O	40.31	0.02	0.023924
3.D.1 Direct N_2O Emissions From Managed Soils	N_2O	20.62	0.18	0.178233
3.D.2 Indirect N_2O Emissions From Managed Soils	N_2O	30.41	0.03	0.029991
3.G Liming	CO_2	30.41	0.00	0.001568
3.H Urea application	CO_2	52.20	0.01	0.009645
4.A.1 Forest Land remaining Forest Land	CO_2	42.54	0.91	0.909883
4.A.1 Forest Land remaining Forest Land	CH_4	38.84	0.00	0.000002
4.A.1 Forest Land remaining Forest Land	N_2O	38.84	0.00	0.000002
4.A.2 Land converted to Forest Land	CO_2	20.68	0.02	0.016542
4.A.2 Land converted to Forest Land	N_2O	250.00	0.00	0.000024
4.B.1 Cropland remaining Cropland	CO_2	34.58	0.00	0.000079
4.B.2 Land converted to Cropland	CO_2	19.93	0.00	0.000497
4.B.2. Land converted to Cropland	N_2O	250.00	0.00	0.000575
4.C.1 Grassland remaining Grassland	CO_2	34.78	0.02	0.019409
4.C.1 Grassland remaining Grassland	CH_4	81.00	0.00	0.000017
4.C.2 Land converted to Grassland	CO_2	42.78	0.03	0.030514
4.D.2. Land converted to Wetlands	CO_2	80.85	0.00	0.000086
4.E.2 Land converted to Settlements	CO_2	38.49	0.01	0.009908
4.E.2 Land converted to Settlements	N_2O	250.00	0.00	0.000214
4.G Harvested wood products	CO_2	62.00	0.61	0.613218
5.A Solid Waste Disposal	CH_4	63.70	5.73	5.729164
5.B Biological treatment of solid waste	CH_4	91.29	0.20	0.200795
5.B Biological treatment of solid waste	N_2O	5.04	0.00	0.000010
5.C Incineration and open burning of waste	CO_2	15.81	0.00	0.000120
5.C Incineration and open burning of waste	CH_4	82.46	0.00	0.000016
5.C Incineration and open burning of waste	N_2O	72.80	0.00	0.000004
5.D Wastewater treatment and discharge	CH_4	58.38	0.24	0.241123
5.D Wastewater treatment and discharge	N_2O	56.36	0.01	0.012292
	Level uncertainty =		3.60	

Tab. A2 3 Uncertainty analysis (Tier 1), third part of Table 3.3 of IPCC 2006 Gl. incl. LULUCF

		Uncertainty of Trend				
IPCC Source Category	**Gas**	**Type A sensitivity**	**Type B sensitivity**	**Uncertainty in trend in national emissions introduced by EF uncertainty**	**Uncertainty in trend in national emissions introduced by AD uncertainty**	**Uncertainty introduced into the trend in total national emissions**
1.A.1 Energy industries - Solid Fuels	CO_2	0.0079	0.1374	0.0145	0.5279	0.2789
1.A.1 Energy industries - Solid Fuels	CH_4	0.0000	0.0000	0.0001	0.0002	0.0000
1.A.1 Energy industries - Solid Fuels	N_2O	0.0000	0.0005	0.0024	0.0021	0.0000
1.A.1 Energy industries - Liquid Fuels	CO_2	-0.0019	0.0017	-0.0052	0.0044	0.0000
1.A.1 Energy industries - Liquid Fuels	CH_4	0.0000	0.0000	-0.0002	0.0000	0.0000
1.A.1 Energy industries - Liquid Fuels	N_2O	0.0000	0.0000	-0.0004	0.0000	0.0000
1.A.1 Energy industries - Gaseous Fuels	CO_2	0.0103	0.0135	0.0051	0.0350	0.0013

		Uncertainty of Trend				
IPCC Source Category	**Gas**	**Type A sensitivity**	**Type B sensitivity**	**Uncertainty in trend in national emissions introduced by EF uncertainty**	**Uncertainty in trend in national emissions introduced by AD uncertainty**	**Uncertainty introduced into the trend in total national emissions**
1.A.1 Energy industries - Gaseous Fuels	CH_4	0.0000	0.0000	0.0002	0.0000	0.0000
1.A.1 Energy industries - Gaseous Fuels	N_2O	0.0000	0.0000	0.0003	0.0000	0.0000
1.A.1 Energy industries - Biomass	CH_4	0.0001	0.0001	0.0067	0.0012	0.0000
1.A.1 Energy industries - Biomass	N_2O	0.0002	0.0002	0.0118	0.0015	0.0001
1.A.1 Energy industries - Other Fossil Fuels	CO_2	0.0015	0.0016	0.0232	0.0170	0.0008
1.A.1 Energy industries - Other Fossil Fuels	CH_4	0.0000	0.0000	0.0008	0.0002	0.0000
1.A.1 Energy industries - Other Fossil Fuels	N_2O	0.0000	0.0000	0.0014	0.0002	0.0000
1.A.2 Manufacturing Industries and Construction - Solid Fuels	CO_2	-0.0706	0.0152	-0.1293	0.0462	0.0189
1.A.2 Manufacturing Industries and Construction - Solid Fuels	CH_4	-0.0002	0.0000	-0.0123	0.0001	0.0002
1.A.2 Manufacturing Industries and Construction - Solid Fuels	N_2O	-0.0003	0.0001	-0.0188	0.0002	0.0004
1.A.2 Manufacturing Industries and Construction - Liquid Fuels	CO_2	-0.0104	0.0028	-0.0286	0.0123	0.0010
1.A.2 Manufacturing Industries and Construction - Liquid Fuels	CH_4	0.0000	0.0000	-0.0007	0.0000	0.0000
1.A.2 Manufacturing Industries and Construction - Liquid Fuels	N_2O	0.0000	0.0000	-0.0016	0.0000	0.0000
1.A.2 Manufacturing Industries and Construction - Gaseous Fuels	CO_2	0.0086	0.0223	0.0043	0.0692	0.0048
1.A.2 Manufacturing Industries and Construction - Gaseous Fuels	CH_4	0.0000	0.0000	0.0002	0.0000	0.0000
1.A.2 Manufacturing Industries and Construction - Gaseous Fuels	N_2O	0.0000	0.0000	0.0002	0.0000	0.0000
1.A.2 Manufacturing Industries and Construction - Biomass	CH_4	0.0001	0.0001	0.0057	0.0014	0.0000
1.A.2 Manufacturing Industries and Construction - Biomass	N_2O	0.0001	0.0002	0.0101	0.0018	0.0001
1.A.2 Manufacturing Industries and Construction - Other Fossil Fuels	CO_2	0.0023	0.0023	0.1406	0.0304	0.0207
1.A.2 Manufacturing Industries and Construction - Other Fossil Fuels	CH_4	0.0000	0.0000	0.0015	0.0003	0.0000
1.A.2 Manufacturing Industries and Construction - Other Fossil Fuels	N_2O	0.0000	0.0000	0.0024	0.0004	0.0000
1.A.3.a Domestic Aviation	CO_2	0.0001	0.0001	0.0003	0.0004	0.0000
1.A.3.a Domestic Aviation	CH_4	0.0000	0.0000	0.0000	0.0000	0.0000
1.A.3.a Domestic Aviation	N_2O	0.0000	0.0000	0.0001	0.0000	0.0000
1.A.3.b Road Transportation	CO_2	0.0733	0.0981	0.1575	0.4161	0.1979
1.A.3.b Road Transportation	CH_4	-0.0001	0.0001	-0.0166	0.0006	0.0003
1.A.3.b Road Transportation	N_2O	0.0014	0.0016	0.2511	0.0069	0.0631
1.A.3.c Railways	CO_2	-0.0008	0.0011	-0.0012	0.0074	0.0001
1.A.3.c Railways	CH_4	0.0000	0.0000	0.0003	0.0000	0.0000
1.A.3.c Railways	N_2O	0.0000	0.0000	-0.0002	0.0000	0.0000
1.A.3.d Transport - Domestic navigation	CO_2	-0.0001	0.0000	0.0000	0.0003	0.0000
1.A.3.d Transport - Domestic navigation	CH_4	0.0000	0.0000	0.0000	0.0000	0.0000

		Uncertainty of Trend				
IPCC Source Category	**Gas**	**Type A sensitivity**	**Type B sensitivity**	**Uncertainty in trend in national emissions introduced by EF uncertainty**	**Uncertainty in trend in national emissions introduced by AD uncertainty**	**Uncertainty introduced into the trend in total national emissions**
1.A.3.d Transport - Domestic navigation	N_2O	0.0000	0.0000	0.0000	0.0000	0.0000
1.A.3.e Other Transportation	CO_2	0.0000	0.0000	0.0000	0.0000	0.0000
1.A.3.e Other Transportation	CH_4	0.0000	0.0000	0.0000	0.0000	0.0000
1.A.3.e Other Transportation	N_2O	0.0000	0.0000	0.0000	0.0000	0.0000
1.A.4 Other Sectors - Solid Fuels	CO_2	-0.0503	0.0075	-0.0921	0.1043	0.0194
1.A.4 Other Sectors - Solid Fuels	CH_4	-0.0029	0.0007	-0.1620	0.0090	0.0263
1.A.4 Other Sectors - Solid Fuels	N_2O	-0.0002	0.0000	-0.0133	0.0004	0.0002
1.A.4 Other Sectors - Liquid Fuels	CO_2	-0.0028	0.0063	-0.0077	0.0486	0.0024
1.A.4 Other Sectors - Liquid Fuels	CH_4	0.0000	0.0000	-0.0014	0.0000	0.0000
1.A.4 Other Sectors - Liquid Fuels	N_2O	0.0001	0.0002	0.0100	0.0014	0.0001
1.A.4 Other Sectors - Gaseous Fuels	CO_2	0.0177	0.0278	0.0088	0.1870	0.0350
1.A.4 Other Sectors - Gaseous Fuels	CH_4	0.0000	0.0001	0.0018	0.0005	0.0000
1.A.4 Other Sectors - Gaseous Fuels	N_2O	0.0000	0.0000	0.0004	0.0001	0.0000
1.A.4 Other Sectors - Biomass	CH_4	0.0023	0.0031	0.1130	0.0644	0.0169
1.A.4 Other Sectors - Biomass	N_2O	0.0003	0.0004	0.0199	0.0081	0.0005
1.A.5.b Other mobile - Liquid Fuels	CO_2	0.0007	0.0012	0.0020	0.0068	0.0000
1.A.5.b Other mobile - Liquid Fuels	CH_4	0.0000	0.0000	-0.0001	0.0000	0.0000
1.A.5.b Other mobile - Liquid Fuels	N_2O	0.0000	0.0000	0.0024	0.0002	0.0000
1.B.1.a Coal Mining and Handling	CO_2	-0.0010	0.0003	-0.0123	0.0031	0.0002
1.B.1.a Coal Mining and Handling	CH_4	-0.0185	0.0023	-0.6924	0.0241	0.4799
1.B.1.b Solid Fuel Transformation	CH_4	0.0000	0.0000	0.0007	0.0002	0.0000
1.B.2.a Fugitive Emissions from Fuels - Oil and Natural Gas - Oil	CO_2	0.0000	0.0000	0.0000	0.0000	0.0000
1.B.2.a Fugitive Emissions from Fuels - Oil and Natural Gas - Oil	CH_4	0.0000	0.0000	-0.0005	0.0002	0.0000
1.B.2.b Fugitive Emissions from Fuels - Oil and Natural Gas - Natural Gas	CO_2	0.0000	0.0000	0.0000	0.0000	0.0000
1.B.2.b Fugitive Emissions from Fuels - Oil and Natural Gas - Natural Gas	CH_4	-0.0011	0.0017	-0.0551	0.0131	0.0032
1.B.2.c Fugitive Emissions from Fuels - Venting and flaring	CO_2	0.0000	0.0000	0.0005	0.0005	0.0000
1.B.2.c Fugitive Emissions from Fuels - Venting and flaring	CH_4	0.0001	0.0001	0.0043	0.0033	0.0000
1.B.2.c Fugitive Emissions from Fuels - Venting and flaring	N_2O	0.0000	0.0000	0.0000	0.0000	0.0000
1. Energy (indirect CO_2 emissions)	CO_2	-0.0020	0.0005	-0.0201	0.0064	0.0004
2.A.1 Cement Production	CO_2	0.0011	0.0071	0.0021	0.0200	0.0004
2.A.2 Lime Production	CO_2	-0.0013	0.0019	-0.0026	0.0055	0.0000
2.A.3 Glass Production	CO_2	0.0003	0.0006	0.0006	0.0045	0.0000
2.A.4 Other Process Uses of Carbonates	CO_2	0.0021	0.0024	0.0214	0.0171	0.0007
2.B.1 Ammonia Production	CO_2	-0.0003	0.0021	-0.0020	0.0148	0.0002
2.B.2 Nitric Acid Production	N_2O	-0.0018	0.0004	-0.0273	0.0024	0.0008
2.B.4 Caprolactam, glyoxal and glyoxylic acid production	N_2O	0.0000	0.0001	-0.0015	0.0009	0.0000
2.B.8 Petrochemical and Carbon Black Production	CO_2	0.0026	0.0045	0.1032	0.0318	0.0117
2.B.8 Petrochemical and Carbon Black Production	CH_4	0.0002	0.0003	0.0062	0.0018	0.0000
2.B.10 Other	CO_2	0.0007	0.0007	0.0018	0.0030	0.0000
2.C.1 Iron and Steel Production	CO_2	-0.0089	0.0147	-0.0885	0.1458	0.0291
2.C.1 Iron and Steel Production	CH_4	0.0000	0.0000	-0.0005	0.0002	0.0000

		Uncertainty of Trend				
IPCC Source Category	**Gas**	**Type A sensitivity**	**Type B sensitivity**	**Uncertainty in trend in national emissions introduced by EF uncertainty**	**Uncertainty in trend in national emissions introduced by AD uncertainty**	**Uncertainty introduced into the trend in total national emissions**
2.C.2 Ferroalloys Production	CO_2	0.0000	0.0000	0.0001	0.0000	0.0000
2.C.2 Ferroalloys Production	CH_4	0.0000	0.0000	0.0004	0.0001	0.0000
2.C.5 Lead Production	CO_2	0.0000	0.0001	0.0020	0.0007	0.0000
2.C.6 Zinc Production	CO_2	0.0000	0.0000	-0.0010	0.0000	0.0000
2.D.1 Lubricant Use	CO_2	0.0001	0.0004	0.0065	0.0029	0.0001
2.D.2 Paraffin Wax Use	CO_2	0.0000	0.0000	0.0009	0.0003	0.0000
2.D.3 Other non-energy products from fuels and solvent use	CO_2	0.0001	0.0001	0.0006	0.0009	0.0000
2.E Electronics industry	F-gases	0.0002	0.0002	0.0030	0.0009	0.0000
2.F.1 Refrigeration and Air conditioning	F-gases	0.0168	0.0168	0.3863	0.8788	0.9215
2.F.2 Foam Blowing Agents	F-gases	0.0000	0.0000	0.0004	0.0009	0.0000
2.F.3 Fire Protection	F-gases	0.0002	0.0002	0.0038	0.0081	0.0001
2.F.4 Aerosols	F-gases	0.0000	0.0000	0.0003	0.0007	0.0000
2.F.5 Solvents	F-gases	0.0000	0.0000	0.0000	0.0000	0.0000
2.G Other Product Manufacture and Use	F-gases	0.0001	0.0003	0.0025	0.0166	0.0003
2.G Other Product Manufacture and Use	N_2O	0.0005	0.0010	0.0121	0.0506	0.0027
2.H Other	CO_2	0.0000	0.0000	0.0000	0.0000	0.0000
2.H Other	F-gases	0.0000	0.0000	0.0000	0.0000	0.0000
3.A Enteric Fermentation	CH_4	0.0023	0.0180	0.0341	0.1273	0.0174
3.B Manure Management	CH_4	-0.0019	0.0018	-0.0381	0.0255	0.0021
3.B Manure Management	N_2O	-0.0005	0.0019	-0.0180	0.0134	0.0005
3.D.1 Direct N_2O Emissions From Managed Soils	N_2O	0.0049	0.0101	0.0971	0.0717	0.0146
3.D.2 Indirect N_2O Emissions From Managed Soils	N_2O	0.0018	0.0028	0.0530	0.0199	0.0032
3.G Liming	CO_2	-0.0023	0.0006	-0.0701	0.0046	0.0049
3.H Urea application	CO_2	0.0007	0.0009	0.0335	0.0198	0.0015
4.A.1 Forest Land remaining Forest Land	CO_2	-0.0086	0.0111	-0.3242	0.3141	0.2038
4.A.1 Forest Land remaining Forest Land	CH_4	0.0000	0.0000	-0.0010	0.0005	0.0000
4.A.1 Forest Land remaining Forest Land	N_2O	0.0000	0.0000	-0.0003	0.0006	0.0000
4.A.2 Land converted to Forest Land	CO_2	0.0026	0.0031	0.0533	0.0000	0.0028
4.A.2 Land converted to Forest Land	N_2O	0.0000	0.0000	0.0000	0.0000	0.0000
4.B.1 Cropland remaining Cropland	CO_2	0.0001	0.0001	0.0033	0.0000	0.0000
4.B.2 Land converted to Cropland	CO_2	-0.0001	0.0006	-0.0018	0.0000	0.0000
4.B.2. Land converted to Cropland	N_2O	0.0000	0.0000	-0.0058	0.0000	0.0000
4.C.1 Grassland remaining Grassland	CO_2	0.0018	0.0020	0.0640	0.0000	0.0041
4.C.1 Grassland remaining Grassland	CH_4	0.0000	0.0000	0.0010	0.0000	0.0000
4.C.2 Land converted to Grassland	CO_2	0.0014	0.0020	0.0604	0.0000	0.0036
4.D.2. Land converted to Wetlands	CO_2	0.0000	0.0001	0.0018	0.0000	0.0000
4.E.2 Land converted to Settlements	CO_2	0.0001	0.0013	0.0057	0.0000	0.0000
4.E.2 Land converted to Settlements	N_2O	0.0000	0.0000	-0.0090	0.0000	0.0001
4.G Harvested wood products	CO_2	0.0022	0.0063	0.1367	0.0000	0.0187
5.A Solid Waste Disposal	CH_4	0.0138	0.0186	0.8772	0.0000	0.7694
5.B Biological treatment of solid waste	CH_4	0.0024	0.0024	0.2216	0.0172	0.0494
5.B Biological treatment of solid waste	N_2O	0.0003	0.0003	0.0002	0.0022	0.0000

		Uncertainty of Trend				
IPCC Source Category	**Gas**	**Type A sensitivity**	**Type B sensitivity**	**Uncertainty in trend in national emissions introduced by EF uncertainty**	**Uncertainty in trend in national emissions introduced by AD uncertainty**	**Uncertainty introduced into the trend in total national emissions**
5.C Incineration and open burning of waste	CO_2	0.0003	0.0003	0.0015	0.0073	0.0001
5.C Incineration and open burning of waste	CH_4	0.0000	0.0000	0.0019	0.0007	0.0000
5.C Incineration and open burning of waste	N_2O	0.0000	0.0000	0.0009	0.0004	0.0000
5.D Wastewater treatment and discharge	CH_4	0.0016	0.0042	0.0778	0.1776	0.0376
5.D Wastewater treatment and discharge	N_2O	0.0005	0.0010	0.0236	0.0358	0.0018
					Trend uncertainty =	1.81

Tab. A2 4 Uncertainty analysis (Tier 1), second part of Table 3.3 of IPCC 2006 Gl. excl. LULUCF

		Uncertainty of Emissions	
IPCC Source Category	**Gas**	**Combined uncertainty**	**Contribution to variance by category in year x**
1.A.1 Energy industries - Solid Fuels	CO_2	3.28	0.92
1.A.1 Energy industries - Solid Fuels	CH_4	65.06	0.00
1.A.1 Energy industries - Solid Fuels	N_2O	70.05	0.01
1.A.1 Energy industries - Liquid Fuels	CO_2	3.25	0.00
1.A.1 Energy industries - Liquid Fuels	CH_4	55.03	0.00
1.A.1 Energy industries - Liquid Fuels	N_2O	70.02	0.00
1.A.1 Energy industries - Gaseous Fuels	CO_2	1.90	0.00
1.A.1 Energy industries - Gaseous Fuels	CH_4	41.71	0.00
1.A.1 Energy industries - Gaseous Fuels	N_2O	53.36	0.00
1.A.1 Energy industries - Biomass	CH_4	50.40	0.00
1.A.1 Energy industries - Biomass	N_2O	70.29	0.00
1.A.1 Energy industries - Other Fossil Fuels	CO_2	17.29	0.00
1.A.1 Energy industries - Other Fossil Fuels	CH_4	60.49	0.00
1.A.1 Energy industries - Other Fossil Fuels	N_2O	80.37	0.00
1.A.2 Manufacturing Industries and Construction - Solid Fuels	CO_2	2.83	0.01
1.A.2 Manufacturing Industries and Construction - Solid Fuels	CH_4	65.04	0.00
1.A.2 Manufacturing Industries and Construction - Solid Fuels	N_2O	70.03	0.00
1.A.2 Manufacturing Industries and Construction - Liquid Fuels	CO_2	4.13	0.00
1.A.2 Manufacturing Industries and Construction - Liquid Fuels	CH_4	55.09	0.00
1.A.2 Manufacturing Industries and Construction - Liquid Fuels	N_2O	70.07	0.00
1.A.2 Manufacturing Industries and Construction - Gaseous Fuels	CO_2	2.25	0.01
1.A.2 Manufacturing Industries and Construction - Gaseous Fuels	CH_4	41.72	0.00
1.A.2 Manufacturing Industries and Construction - Gaseous Fuels	N_2O	53.38	0.00

	Uncertainty of Emissions		
IPCC Source Category	Gas	Combined uncertainty	Contribution to variance by category in year x
1.A.2 Manufacturing Industries and Construction - Biomass	CH_4	50.50	0.00
1.A.2 Manufacturing Industries and Construction - Biomass	N_2O	70.36	0.00
1.A.2 Manufacturing Industries and Construction - Other Fossil Fuels	CO_2	60.70	0.09
1.A.2 Manufacturing Industries and Construction - Other Fossil Fuels	CH_4	60.70	0.00
1.A.2 Manufacturing Industries and Construction - Other Fossil Fuels	N_2O	80.52	0.00
1.A.3.a Domestic Aviation	CO_2	5.36	0.00
1.A.3.a Domestic Aviation	CH_4	78.60	0.00
1.A.3.a Domestic Aviation	N_2O	110.07	0.00
1.A.3.b Road Transportation	CO_2	3.69	0.60
1.A.3.b Road Transportation	CH_4	199.45	0.00
1.A.3.b Road Transportation	N_2O	180.40	0.40
1.A.3.c Railways	CO_2	5.24	0.00
1.A.3.c Railways	CH_4	125.67	0.00
1.A.3.c Railways	N_2O	125.40	0.00
1.A.3.d Transport - Domestic navigation	CO_2	5.00	0.00
1.A.3.d Transport - Domestic navigation	CH_4	5.10	0.00
1.A.3.d Transport - Domestic navigation	N_2O	5.18	0.00
1.A.3.e Other Transportation	CO_2	5.00	0.00
1.A.3.e Other Transportation	CH_4	50.16	0.00
1.A.3.e Other Transportation	N_2O	60.13	0.00
1.A.4 Other Sectors - Solid Fuels	CO_2	9.96	0.03
1.A.4 Other Sectors - Solid Fuels	CH_4	55.87	0.01
1.A.4 Other Sectors - Solid Fuels	N_2O	70.68	0.00
1.A.4 Other Sectors - Liquid Fuels	CO_2	6.12	0.01
1.A.4 Other Sectors - Liquid Fuels	CH_4	55.27	0.00
1.A.4 Other Sectors - Liquid Fuels	N_2O	70.21	0.00
1.A.4 Other Sectors - Gaseous Fuels	CO_2	4.79	0.08
1.A.4 Other Sectors - Gaseous Fuels	CH_4	41.94	0.00
1.A.4 Other Sectors - Gaseous Fuels	N_2O	53.55	0.00
1.A.4 Other Sectors - Biomass	CH_4	52.07	0.12
1.A.4 Other Sectors - Biomass	N_2O	71.49	0.00
1.A.5.b Other mobile - Liquid Fuels	CO_2	4.89	0.00
1.A.5.b Other mobile - Liquid Fuels	CH_4	55.15	0.00
1.A.5.b Other mobile - Liquid Fuels	N_2O	70.12	0.00
1.B.1.a Coal Mining and Handling	CO_2	14.23	0.00
1.B.1.a Coal Mining and Handling	CH_4	38.22	0.04
1.B.1.b Solid Fuel Transformation	CH_4	48.54	0.00
1.B.2.a Fugitive Emissions from Fuels - Oil and Natural Gas - Oil	CO_2	50.42	0.00
1.B.2.a Fugitive Emissions from Fuels - Oil and Natural Gas - Oil	CH_4	63.12	0.00
1.B.2.b Fugitive Emissions from Fuels - Oil and Natural Gas - Natural Gas	CO_2	50.29	0.00
1.B.2.b Fugitive Emissions from Fuels - Oil and Natural Gas - Natural Gas	CH_4	49.74	0.03
1.B.2.c Fugitive Emissions from Fuels - Venting and flaring	CO_2	57.03	0.00
1.B.2.c Fugitive Emissions from Fuels - Venting and flaring	CH_4	74.33	0.00

	Uncertainty of Emissions		
IPCC Source Category	**Gas**	**Combined uncertainty**	**Contribution to variance by category in year x**
1.B.2.c Fugitive Emissions from Fuels - Venting and flaring	N_2O	74.33	0.00
1. Energy (indirect CO_2 emissions)	CO_2	2.83	0.00
2.A.1 Cement Production	CO_2	2.83	0.00
2.A.2 Lime Production	CO_2	5.39	0.00
2.A.3 Glass Production	CO_2	11.18	0.00
2.A.4 Other Process Uses of Carbonates	CO_2	8.60	0.00
2.B.1 Ammonia Production	CO_2	15.52	0.00
2.B.2 Nitric Acid Production	N_2O	40.31	0.00
2.B.4 Caprolactam, glyoxal and glyoxylic acid production	N_2O	40.31	0.00
2.B.8 Petrochemical and Carbon Black Production	CO_2	40.31	0.15
2.B.8 Petrochemical and Carbon Black Production	CH_4	3.91	0.00
2.B.10 Other	CO_2	12.21	0.00
2.C.1 Iron and Steel Production	CO_2	30.81	0.94
2.C.1 Iron and Steel Production	CH_4	25.50	0.00
2.C.2 Ferroalloys Production	CO_2	25.50	0.00
2.C.2 Ferroalloys Production	CH_4	50.99	0.00
2.C.5 Lead Production	CO_2	50.99	0.00
2.C.6 Zinc Production	CO_2	50.25	0.00
2.D.1 Lubricant Use	CO_2	50.25	0.00
2.D.2 Paraffin Wax Use	CO_2	7.07	0.00
2.D.3 Other non-energy products from fuels and solvent use	CO_2	15.30	0.00
2.E Electronics industry	F-gases	43.57	0.00
2.F.1 Refrigeration and Air conditioning	F-gases	41.88	2.25
2.F.2 Foam Blowing Agents	F-gases	41.88	0.00
2.F.3 Fire Protection	F-gases	41.88	0.00
2.F.4 Aerosols	F-gases	41.88	0.00
2.F.5 Solvents	F-gases	43.57	0.00
2.G Other Product Manufacture and Use	F-gases	43.57	0.00
2.G Other Product Manufacture and Use	N_2O	5.39	0.00
2.H Other	CO_2	43.57	0.00
2.H Other	F-gases	15.81	0.00
3.A Enteric Fermentation	CH_4	22.36	0.74
3.B Manure Management	CH_4	40.31	0.02
3.B Manure Management	N_2O	20.62	0.01
3.D.1 Direct N_2O Emissions From Managed Soils	N_2O	30.41	0.43
3.D.2 Indirect N_2O Emissions From Managed Soils	N_2O	30.41	0.03
3.G Liming	CO_2	52.20	0.01
3.H Urea application	CO_2	42.54	0.01
5.A Solid Waste Disposal	CH_4	15.81	0.39
5.B Biological treatment of solid waste	CH_4	82.46	0.18
5.B Biological treatment of solid waste	N_2O	72.80	0.00
5.C Incineration and open burning of waste	CO_2	58.38	0.00
5.C Incineration and open burning of waste	CH_4	56.36	0.00
5.C Incineration and open burning of waste	N_2O	0.00	0.00
5.D Wastewater treatment and discharge	CH_4	0.00	0.00
5.D Wastewater treatment and discharge	N_2O	0.00	0.00
		Level uncertainty =	2.75

Tab. A2 5 Uncertainty analysis (Tier 1), third part of Table 3.3 of IPCC 2006 Gl. excl. LULUCF

		Uncertainty of Trend				
IPCC Source Category	Gas	Type A sensitivity	Type B sensitivity	Uncertainty in trend in national emissions introduced by EF uncertainty	Uncertainty in trend in national emissions introduced by AD uncertainty	Uncertainty introduced into the trend in total national emissions
1.A.1 Energy industries - Solid Fuels	CO_2	0.0082	0.1454	0.0151	0.5585	0.3121
1.A.1 Energy industries - Solid Fuels	CH_4	0.0000	0.0000	0.0001	0.0002	0.0000
1.A.1 Energy industries - Solid Fuels	N_2O	0.0000	0.0006	0.0025	0.0022	0.0000
1.A.1 Energy industries - Liquid Fuels	CO_2	-0.0020	0.0019	-0.0055	0.0046	0.0001
1.A.1 Energy industries - Liquid Fuels	CH_4	0.0000	0.0000	-0.0002	0.0000	0.0000
1.A.1 Energy industries - Liquid Fuels	N_2O	0.0000	0.0000	-0.0004	0.0000	0.0000
1.A.1 Energy industries - Gaseous Fuels	CO_2	0.0109	0.0143	0.0054	0.0371	0.0014
1.A.1 Energy industries - Gaseous Fuels	CH_4	0.0000	0.0000	0.0002	0.0000	0.0000
1.A.1 Energy industries - Gaseous Fuels	N_2O	0.0000	0.0000	0.0003	0.0000	0.0000
1.A.1 Energy industries - Biomass	CH_4	0.0001	0.0001	0.0071	0.0013	0.0001
1.A.1 Energy industries - Biomass	N_2O	0.0002	0.0002	0.0125	0.0016	0.0002
1.A.1 Energy industries - Other Fossil Fuels	CO_2	0.0016	0.0016	0.0246	0.0179	0.0009
1.A.1 Energy industries - Other Fossil Fuels	CH_4	0.0000	0.0000	0.0009	0.0002	0.0000
1.A.1 Energy industries - Other Fossil Fuels	N_2O	0.0000	0.0000	0.0015	0.0002	0.0000
1.A.2 Manufacturing Industries and Construction - Solid Fuels	CO_2	-0.0748	0.0160	-0.1370	0.0489	0.0212
1.A.2 Manufacturing Industries and Construction - Solid Fuels	CH_4	-0.0002	0.0000	-0.0131	0.0001	0.0002
1.A.2 Manufacturing Industries and Construction - Solid Fuels	N_2O	-0.0003	0.0001	-0.0199	0.0002	0.0004
1.A.2 Manufacturing Industries and Construction - Liquid Fuels	CO_2	-0.0111	0.0030	-0.0303	0.0130	0.0011
1.A.2 Manufacturing Industries and Construction - Liquid Fuels	CH_4	0.0000	0.0000	-0.0007	0.0000	0.0000
1.A.2 Manufacturing Industries and Construction - Liquid Fuels	N_2O	0.0000	0.0000	-0.0017	0.0000	0.0000
1.A.2 Manufacturing Industries and Construction - Gaseous Fuels	CO_2	0.0091	0.0236	0.0045	0.0732	0.0054
1.A.2 Manufacturing Industries and Construction - Gaseous Fuels	CH_4	0.0000	0.0000	0.0002	0.0000	0.0000
1.A.2 Manufacturing Industries and Construction - Gaseous Fuels	N_2O	0.0000	0.0000	0.0002	0.0000	0.0000
1.A.2 Manufacturing Industries and Construction - Biomass	CH_4	0.0001	0.0002	0.0061	0.0015	0.0000
1.A.2 Manufacturing Industries and Construction - Biomass	N_2O	0.0002	0.0002	0.0106	0.0019	0.0001
1.A.2 Manufacturing Industries and Construction - Other Fossil Fuels	CO_2	0.0025	0.0025	0.1487	0.0321	0.0231
1.A.2 Manufacturing Industries and Construction - Other Fossil Fuels	CH_4	0.0000	0.0000	0.0015	0.0003	0.0000
1.A.2 Manufacturing Industries and Construction - Other Fossil Fuels	N_2O	0.0000	0.0000	0.0026	0.0004	0.0000
1.A.3.a Domestic Aviation	CO_2	0.0001	0.0001	0.0003	0.0005	0.0000
1.A.3.a Domestic Aviation	CH_4	0.0000	0.0000	0.0000	0.0000	0.0000

		Uncertainty of Trend				
IPCC Source Category	Gas	Type A sensitivity	Type B sensitivity	Uncertainty in trend in national emissions introduced by EF uncertainty	Uncertainty in trend in national emissions introduced by AD uncertainty	Uncertainty introduced into the trend in total national emissions
1.A.3.a Domestic Aviation	N_2O	0.0000	0.0000	0.0001	0.0000	0.0000
1.A.3.b Road Transportation	CO_2	0.0775	0.1038	0.1666	0.4402	0.2215
1.A.3.b Road Transportation	CH_4	-0.0001	0.0001	-0.0176	0.0006	0.0003
1.A.3.b Road Transportation	N_2O	0.0015	0.0017	0.2656	0.0073	0.0706
1.A.3.c Railways	CO_2	-0.0008	0.0011	-0.0013	0.0079	0.0001
1.A.3.c Railways	CH_4	0.0000	0.0000	0.0003	0.0000	0.0000
1.A.3.c Railways	N_2O	0.0000	0.0000	-0.0002	0.0000	0.0000
1.A.3.d Transport - Domestic navigation	CO_2	-0.0001	0.0000	0.0000	0.0003	0.0000
1.A.3.d Transport - Domestic navigation	CH_4	0.0000	0.0000	0.0000	0.0000	0.0000
1.A.3.d Transport - Domestic navigation	N_2O	0.0000	0.0000	0.0000	0.0000	0.0000
1.A.3.e Other Transportation	CO_2	0.0000	0.0000	0.0000	0.0000	0.0000
1.A.3.e Other Transportation	CH_4	0.0000	0.0000	0.0000	0.0000	0.0000
1.A.3.e Other Transportation	N_2O	0.0000	0.0000	0.0000	0.0000	0.0000
1.A.4 Other Sectors - Solid Fuels	CO_2	-0.0533	0.0080	-0.0975	0.1104	0.0217
1.A.4 Other Sectors - Solid Fuels	CH_4	-0.0031	0.0007	-0.1716	0.0095	0.0295
1.A.4 Other Sectors - Solid Fuels	N_2O	-0.0002	0.0000	-0.0141	0.0005	0.0002
1.A.4 Other Sectors - Liquid Fuels	CO_2	-0.0030	0.0066	-0.0082	0.0514	0.0027
1.A.4 Other Sectors - Liquid Fuels	CH_4	0.0000	0.0000	-0.0015	0.0000	0.0000
1.A.4 Other Sectors - Liquid Fuels	N_2O	0.0002	0.0002	0.0106	0.0015	0.0001
1.A.4 Other Sectors - Gaseous Fuels	CO_2	0.0187	0.0294	0.0094	0.1978	0.0392
1.A.4 Other Sectors - Gaseous Fuels	CH_4	0.0000	0.0001	0.0019	0.0005	0.0000
1.A.4 Other Sectors - Gaseous Fuels	N_2O	0.0000	0.0000	0.0005	0.0001	0.0000
1.A.4 Other Sectors - Biomass	CH_4	0.0024	0.0033	0.1195	0.0682	0.0189
1.A.4 Other Sectors - Biomass	N_2O	0.0003	0.0004	0.0211	0.0086	0.0005
1.A.5.b Other mobile - Liquid Fuels	CO_2	0.0008	0.0012	0.0021	0.0071	0.0001
1.A.5.b Other mobile - Liquid Fuels	CH_4	0.0000	0.0000	-0.0001	0.0000	0.0000
1.A.5.b Other mobile - Liquid Fuels	N_2O	0.0000	0.0000	0.0025	0.0002	0.0000
1.B.1.a Coal Mining and Handling	CO_2	-0.0011	0.0003	-0.0130	0.0033	0.0002
1.B.1.a Coal Mining and Handling	CH_4	-0.0196	0.0024	-0.7334	0.0255	0.5385
1.B.1.b Solid Fuel Transformation	CH_4	0.0000	0.0000	0.0007	0.0002	0.0000
1.B.2.a Fugitive Emissions from Fuels - Oil and Natural Gas - Oil	CO_2	0.0000	0.0000	0.0000	0.0000	0.0000
1.B.2.a Fugitive Emissions from Fuels - Oil and Natural Gas - Oil	CH_4	0.0000	0.0000	-0.0005	0.0002	0.0000
1.B.2.b Fugitive Emissions from Fuels - Oil and Natural Gas - Natural Gas	CO_2	0.0000	0.0000	0.0000	0.0000	0.0000
1.B.2.b Fugitive Emissions from Fuels - Oil and Natural Gas - Natural Gas	CH_4	-0.0012	0.0018	-0.0585	0.0139	0.0036
1.B.2.c Fugitive Emissions from Fuels - Venting and flaring	CO_2	0.0000	0.0000	0.0005	0.0005	0.0000
1.B.2.c Fugitive Emissions from Fuels - Venting and flaring	CH_4	0.0001	0.0001	0.0045	0.0035	0.0000
1.B.2.c Fugitive Emissions from Fuels - Venting and flaring	N_2O	0.0000	0.0000	0.0000	0.0000	0.0000
1. Energy (indirect CO_2 emissions)	CO_2	-0.0021	0.0005	-0.0043	0.0014	0.0000
2.A.1 Cement Production	CO_2	0.0011	0.0075	0.0022	0.0211	0.0005
2.A.2 Lime Production	CO_2	-0.0014	0.0020	-0.0027	0.0145	0.0002
2.A.3 Glass Production	CO_2	0.0003	0.0007	0.0031	0.0048	0.0000

		Uncertainty of Trend				
IPCC Source Category	Gas	Type A sensitivity	Type B sensitivity	Uncertainty in trend in national emissions introduced by EF uncertainty	Uncertainty in trend in national emissions introduced by AD uncertainty	Uncertainty introduced into the trend in total national emissions
2.A.4 Other Process Uses of Carbonates	CO_2	0.0023	0.0026	0.0158	0.0181	0.0006
2.B.1 Ammonia Production	CO_2	-0.0003	0.0022	-0.0047	0.0126	0.0002
2.B.2 Nitric Acid Production	N_2O	-0.0019	0.0005	-0.0772	0.0032	0.0060
2.B.4 Caprolactam, glyoxal and glyoxylic acid production	N_2O	0.0000	0.0001	-0.0016	0.0010	0.0000
2.B.8 Petrochemical and Carbon Black Production	CO_2	0.0027	0.0048	0.1091	0.0336	0.0130
2.B.8 Petrochemical and Carbon Black Production	CH_4	0.0002	0.0003	0.0004	0.0011	0.0000
2.B.10 Other	CO_2	0.0007	0.0007	0.0075	0.0074	0.0001
2.C.1 Iron and Steel Production	CO_2	-0.0094	0.0156	-0.2817	0.1542	0.1032
2.C.1 Iron and Steel Production	CH_4	0.0000	0.0000	-0.0004	0.0002	0.0000
2.C.2 Ferroalloys Production	CO_2	0.0000	0.0000	0.0001	0.0000	0.0000
2.C.2 Ferroalloys Production	CH_4	0.0000	0.0000	0.0008	0.0002	0.0000
2.C.5 Lead Production	CO_2	0.0000	0.0001	0.0021	0.0007	0.0000
2.C.6 Zinc Production	CO_2	0.0000	0.0000	-0.0010	0.0000	0.0000
2.D.1 Lubricant Use	CO_2	0.0001	0.0004	0.0069	0.0031	0.0001
2.D.2 Paraffin Wax Use	CO_2	0.0000	0.0000	0.0001	0.0003	0.0000
2.D.3 Other non-energy products from fuels and solvent use	CO_2	0.0001	0.0001	0.0020	0.0006	0.0000
2.E Electronics industry	F-gases	0.0002	0.0002	0.0049	0.0112	0.0001
2.F.1 Refrigeration and Air conditioning	F-gases	0.0178	0.0178	0.4087	0.8795	0.9405
2.F.2 Foam Blowing Agents	F-gases	0.0000	0.0000	0.0005	0.0010	0.0000
2.F.3 Fire Protection	F-gases	0.0002	0.0002	0.0040	0.0086	0.0001
2.F.4 Aerosols	F-gases	0.0000	0.0000	0.0003	0.0007	0.0000
2.F.5 Solvents	F-gases	0.0000	0.0000	0.0000	0.0000	0.0000
2.G Other Product Manufacture and Use	F-gases	0.0001	0.0003	0.0026	0.0176	0.0003
2.G Other Product Manufacture and Use	N_2O	0.0006	0.0010	0.0011	0.0072	0.0001
2.H Other	CO_2	0.0000	0.0000	0.0001	0.0003	0.0000
2.H Other	F-gases	0.0000	0.0000	0.0000	0.0000	0.0000
3.A Enteric Fermentation	CH_4	0.0024	0.0190	0.0477	0.2693	0.0748
3.B Manure Management	CH_4	-0.0020	0.0019	-0.0807	0.0135	0.0067
3.B Manure Management	N_2O	-0.0005	0.0020	-0.0096	0.0142	0.0003
3.D.1 Direct N_2O Emissions From Managed Soils	N_2O	0.0051	0.0107	0.1540	0.0759	0.0295
3.D.2 Indirect N_2O Emissions From Managed Soils	N_2O	0.0019	0.0030	0.0560	0.0211	0.0036
3.G Liming	CO_2	-0.0025	0.0007	-0.1238	0.0145	0.0155
3.H Urea application	CO_2	0.0007	0.0010	0.0266	0.0279	0.0015
5.A Solid Waste Disposal	CH_4	0.0146	0.0197	0.0728	0.4177	0.1798
5.B Biological treatment of solid waste	CH_4	0.0026	0.0026	0.2058	0.0728	0.0476
5.B Biological treatment of solid waste	N_2O	0.0003	0.0003	0.0228	0.0092	0.0006
5.C Incineration and open burning of waste	CO_2	0.0003	0.0004	0.0156	0.0155	0.0005
5.C Incineration and open burning of waste	CH_4	0.0000	0.0000	0.0013	0.0009	0.0000
5.C Incineration and open burning of waste	N_2O	0.0000	0.0000	0.0000	0.0000	0.0000

		Uncertainty of Trend				
IPCC Source Category	**Gas**	**Type A sensitivity**	**Type B sensitivity**	**Uncertainty in trend in national emissions introduced by EF uncertainty**	**Uncertainty in trend in national emissions introduced by AD uncertainty**	**Uncertainty introduced into the trend in total national emissions**
5.D Wastewater treatment and discharge	CH_4	0.0016	0.0044	0.0000	0.0000	0.0000
5.D Wastewater treatment and discharge	N_2O	0.0005	0.0010	0.0000	0.0000	0.0000
					Trend uncertainty =	1.66

Annex 3 Detailed methodological descriptions for individual sources or sink categories

A 3.1 Updates of the country specific emission and oxidation factors for determination of CO_2 emissions from combustion of bituminous coal and lignite (brown coal) in the Czech Republic

A 3.1.1 Introduction

Emissions of CO_2, produced during the combustion of solid fuels, have in the Czech Republic a very significant contribution to the overall emissions of greenhouse gases. Emissions of CO_2 are according to the IPCC methodology determined as a product of the consumption of fuels, expressed as amount of energy contained in the fuels determined on the basis of net calorific value (TJ), emission factor for CO_2 (t CO_2/TJ) and oxidation factor. In the methodology for GHG inventory, IPCC provides default emission factors for CO_2, for the individual types of fuels (IPCC, 1997 and 2006).

The default emission factors, tabulated in IPCC methodology were determined as middle values based on many calorimetric and analytical tests of individual types of fuels. It is necessary to remember that the used data for determination of this emission factors has predominantly American origin and further comes from the 80s. For the needs of current national inventory, where the nature of the various types of fuels may be different, the default emission factors are not necessary sufficiently satisfactory.

Hence, the new versions of the IPCC methodology (IPCC, 2000 and 2006) recommend to all countries, where emissions of CO_2 from combustion of solid fuels is a so-called key category, to check and update the emission factors of CO_2 for calculation of emissions of CO_2 on the basis of national data. In the Czech Republic, where the main part of the CO_2 emissions from solid fuels comes from the combustion of lignite (brown coal) and bituminous coal, it is significant to determine country specific emission factors for these two types of fuels.

The default emission factors for lignite (brown coal) and bituminous coal, provided in the older and newer version of the IPCC methodology, practically do not differ. In the recommended values for oxidation factor, however a substantial change appeared: while the older version (IPCC, 1997) reported default value of oxidation factor 0.98, new version (IPCC, 2006) provides default value of 1, which is the maximum possible and considering the solid fuels, in practice unreachable. In the IPCC methodology this change was introduced, because the authors of the new version were aware that these values are for solid fuels so geographically and technologically specific, that it could be difficult to generalize them. Default value of 1 was chosen as a conservative estimate, preventing possible underestimation of emission determination. Therefore, a country which wants to prevent possible overestimation of the emissions of CO_2 from combustion of solid fuels, has to determine representative country specific values of oxidation factor for individual types of solid fuels, on the basis of local data.

For determination of the country specific emission factors, it is necessary to obtain data about the carbon content in given type of fuel and its net calorific value.

The factor for the carbon content (CC) is for the individual types of solid fuels defined as the ratio of weight of the carbon and the amount of energy in this fuel of the mass m

$$CC = m \cdot \frac{w_c}{m} \cdot Q_i = \frac{w_c}{Q_i} \quad \text{(A3-1)}$$

where wc is the fraction of mass of carbon in the fuel and Q_i is its net calorific value. It is important to notice, that all variables in the equation (A3-1) are related to the fuel (carbon) with its current water content in the supplied fuel, i.e. in the state, when it is determined the quantity (i.e. mass): raw - index ^{r}.

As the calorific value is expressed in MJ/kg (=TJ/kt), carbon content in% mass ($C^r = 100*w_C$) and CC in t C/TJ, it is possible to rewrite the previous equation to:

$$CC\left[t\frac{C}{TJ}\right] = \frac{10 \cdot C^r[\%]}{Q_i^r\left[\frac{MJ}{kg}\right]} \quad \text{(A3-2)}$$

The emission factor for CO_2 (t CO_2/TJ) is obtained by multiplying by the ratio of the molar weight of carbon dioxide and carbon

$$EF(CO_2) = CC \cdot 3.664 \quad \text{(A3-3)}$$

IPCC methodology provides the following default factors for carbon content CC:

Lignite (brown coal): 27.6 (t C/TJ)

Bituminous coal: 25.8 (t C/TJ)

In the Czech national inventory these emission factors were used until 2006. On the basis of the recommendation of international expert review team (ERT) of UNFCCC, during the review conducted in February 2007, it was decided to use for lignite (brown coal) and bituminous coal factors for CC values 25.43 and 27.27 (t C/TJ), which can be found in the national study from 1999 (Fott, 1999) and are pertaining to the state of the coal in the Czech Republic in the 90s. For determination of the oxidation factor the necessary data was not available, therefore for all solid fuels was used the default value of 0.98 from 1996 Guidelines, for the whole time series from 1990 to 2012 (2006 Guidelines come into force from the current year 2013).

In the last years related to the implementation of the emission trading within EU ETS, the operators of the bigger plants combusting coal began to systematically address the laboratory determined emission factors for different types of coal, combusted in these plants according to the prescribed requirements of the European Directive 82/2003 EC including the relevant guidelines, regarding the methodology of monitoring. Some operators gradually extended this assessment also by the determination of oxidation factors, whose values depend not only on the type of coal, but also on the nature of the combustion source.

Data from the coal analysis from 1999 naturally was not so extensive. Further the coal base in the beginning of the 90s in the Czech Republic largely changed - production in less efficient mines have been gradually phased out and the in the existing mines now often is extracted on different places for example, in deeper coal layers. For these reasons, the research team of the Czech national inventory decided in the frame of its improvement plan to revise the emission factors, used until now and to determine new oxidation factors. Detailed description of the used approach, input data and discussion of the reached results, can be found in the study of authors E. Krtková, P. Fott and V. Neužil, prepared for publication in scientific journal. In the further text of this Annex clarification of the principle of the used method is reported and the reached results from the above-mentioned paper are presented.

1. Revision and updating of nationally specific emission factors

In the last years, lignite (brown coal) is extracted mostly in the North Bohemia (Mostecko), where is the most significant brown coal area in the Czech Republic, and to a lesser extent in the West Bohemian region (Sokolovsko). Bituminous coal is currently quarried only in Ostrava-Karvina district, in the large coalfield, whose greater part is situated in the neighbouring country Poland. Lignite (brown coal) is in the Czech Republic extracted from the surface mines, while bituminous coal is extracted from the underground mines.

Overview of data sets for updating emission factors

Set "ČEZ"

The most extensive collection of data with the results of chemical analyses, including calorific values, gained the national inventory team from the company ČEZ, which operates most of the coal-fired power plants in CR, burning in particular energy (pulverized) lignite (brown coal). The set contains 29 samples of bituminous energy (pulverized) coal and 146 samples of lignite (brown coal), mainly energy one and to a lesser extent also sorted one - 25 samples and this is mostly from North Bohemian region, and in to a lesser extent from West Bohemian region.

Set "Dalkia"

Except from the company ČEZ, the research team received extended set of relevant coal data from the company Dalkia, which operates particularly power and heat plants, combusting mostly bituminous energy coal in the east part of the Czech Republic and with a lesser extent lignite (brown coal). The set "Dalkia" contains analyses mostly of bituminous coal (143 samples) and 36 samples of lignite (brown coal).

Combined set of aggregated data

In order to evaluate the parameters, required for determining of country specific emission factors, the primary data was aggregated as it follows: aggregated items from the above-mentioned sets ("ČEZ" and "Dalkia") were acquired as average of calorific value and the percentage of carbon content from six to twelve analysed samples (i.e. analysis of monthly collected samples).

Combined set was extended by 3 aggregated items (yearly average for 2012) by lignite (brown coal) from West Bohemian region (Sokolovská uhelná).

The combined set included three major operators of combustion sources in the Czech Republic and contains of 37 aggregated items altogether, from which 19 from the set "ČEZ", 15 from set "Dalkia", three were obtained as described in the previous paragraph. This set contains 23 aggregated items of lignite (brown coal) (from which 4 from set "Dalkia") and 14 for bituminous coal (3 items come from the set "ČEZ", the rest 11 items are from the set "Dalkia"). 18 aggregated items for lignite (brown coal) come from a larger North Bohemian region, 5 items of lignite (brown coal) – from smaller West Bohemian region.

The range of the net calorific value for lignite (brown coal) is, from this set, between 9.9 and 18.5 MJ/kg, while the range of the net calorific value for black coal is between (16.2 and 26.4 MJ/kg).

Set "ETS"

The set contains data from the ETS database created in CHMI, to which have been saved certified forms, filled by the operators of energy installations in the Czech Republic under the ETS. These forms, containing data for 2011, were provided to CHMI from the Ministry of Environment. For the processing there were taken into account only those installations whose annual emissions exceeded 50 kt CO_2 and which, in

accordance with monitoring guidelines of EU, determined emission factors from the laboratory data. In this way there were processed 34 sources, combusting lignite (brown coal) and 13 – combusting bituminous coal.

The range of net calorific value for lignite (brown coal) was in this case between 10.4 and 18.8 MJ/kg, while for bituminous coal - was between 17.1 and 26.8 MJ/kg.

The procedure for evaluating of the emission factors

In the above-mentioned article from 1999 (Fott, 1999) it was demonstrated linear correlation between the carbon content C^r [%] in the coal and its calorific value Q_i^r [MJ/kg].

$$C^r = a \cdot Q_i^r + b \qquad \text{(A3-4)}$$

with a correlation coefficient r^2 higher than 0.99. This correlation equation fits for bituminous and lignite (brown coal), therefore both types of coal can be described by one equation (i.e. a single pair of parameters a, b).

Considering the equation (A3-2), dependence between the carbon content CC (t C/TJ) and the calorific value Q_i^r [MJ/kg] is obtained.

$$CC = 10 \cdot \left(a + \frac{b}{Q_i^r}\right) \qquad \text{(A3-5)}$$

In this way a country specific parameters a, b were evaluated in equation (A3-4), (A3-5) instead of two separate values of country specific factor for lignite (brown coal) and for bituminous coal.

This procedure was applied also on current data. For the process there were used the two most representative sets: combined set of aggregated data, hereinafter referred as “Comb” and “ETS”.

In Fig. A3 1 it can be seen, that for the combined data set “Comb” a correlation between carbon content and net calorific value can be described for both types of coal with a regression line (see equation (A3-4)) with parameters a = 2.4142 and b = 4.0291, while the correlation coefficient value r^2 = 0.997 is close to one.



Fig. A3 1 Combined set of aggregated data “Comb”. Correlation between carbon content (%C) and net calorific value for lignite (brown coal) (indicated with brown squares) and bituminous coal (indicated with black squares)

In terms of the uncertainty of emission determination, it is necessary to assess the extent to which the carbon content factor values differ from the values determined by the curve (5). This is graphically illustrated on Fig. A3 2. Numerically, the difference between the individual points from the calculated curve can be characterized with the mean relative error, which is 1.14% for lignite (brown coal) and 1.30% for

bituminous coal. Nevertheless, the mean relative error of any kind of coal does not exceed 3%. Therefore, the uncertainty of the carbon content factors and thus the uncertainty of CO_2 emission factors can be considered as acceptable.



Fig. A3 2 Combined set of aggregated data "Comb". Correlation between the factor of carbon content CC and net calorific value for brown coal (indicated as brown squares) and black coal (indicated as black squares), found through the eq. A3-5.

In the set "ETS" values Q_i^r and factors for CC were available, but the carbon content in percentages was not given. Therefore, the parameters a, b were assessed with non-liner regression, using the equation (A3-5). In this way the parameters a = 2.4211 and b = 3.9539 were determined. In this case the mean relative error for lignite (brown coal) was equal to 1.59% and for bituminous coal was equal to 1.73%.

The parameters a, b, evaluated from both sets are very similar. However, statistical indicators characterizing uncertainty are in the case of set "ETS" somewhat higher, than for the combined set.

2. Determination of country specific oxidation factors

Formula for calculation of oxidation factor from analytical data

Oxidation factor from analytical data is calculated using the following formula.

$$OF = 1 - \frac{A}{C \cdot \left(\frac{1}{C,out} - 1\right)} = 1 - \frac{A \cdot C,out}{C \cdot (1 - C,out)}$$

where OF is oxidation factor (with value somewhat lower than 1), A is the mass fraction of ash, C is the mass fraction of carbon and C,out is the mass fraction of carbon on the exit of the combustion device (the mass fractions are values in the interval between 0 and 1, e.g. 40% corresponds to mass fraction of 0.4). In case, that on the exit both forms of ash are present (slag and dry ash), C,out is calculated as weighted average of the fraction of non-combusted carbon in both forms of ash.

Sets of data used for determination of oxidation factors and their processing

Set "ČEZ"

This is the set "ČEZ", which is described above, containing 146 samples of lignite (brown coal) and 29 samples of bituminous coal. This set contains also all data occurring in the resulting equation (A3-6), used for the calculation of oxidation factor.

Results from the processed data from the set "ČEZ" are these values of oxidation factors:

OF for lignite (brown coal): 0.9857

OF for bituminous coal: 0.9696

Set "Dalkia"

As a matter of fact, the set "Dalkia" is that described above. The set contains analysis of mostly bituminous coal (143 samples). Representative value in case of the bituminous coal from the set "Dalkia" is 0.9719.

OF for lignite (brown coal) was possible to be obtained from the set "Dalkia", using only the part of the samples, combusted at not so important combustion installations (i.e. with relatively low emissions). From these was calculated average (0.979) considered only as approximate value for comparison purposes.

Set "ETS"

The set contains data from the ETS database, created in CHMI (see above), into which have been saved proven forms, provided by the energy operators, falling under ETS. For processing there were considered only these plants (installations), whose emissions exceeded 50 kt and where the indicated oxidation factors were identified based on chemical analysis. In this way were processed 10 sources combusting bituminous coal and 18 sources, combusting lignite (brown coal). From the set "ETS" were calculated the following representative values of OF for bituminous and lignite (brown coal).

Resulting values of OF from set "ETS" are:

OF for lignite (brown coal): 0.9835

OF for bituminous coal: 0.9708

For lignite (brown coal) was taken as the most representative current country value for OF, the value of **OF = 0.9846** determined as average of the two average values from sets "ČEZ" and "ETS":

$$OF = \frac{0.9857 + 0.9835}{2} = 0.9846$$

For bituminous coal was taken as the most representative current country value for OF, the value of **OF = 0.9707** determined as average of the three average values from sets "ČEZ", "Dalkia" and "ETS":

$$OF = \frac{0.9696 \ + \ 0.9719 \ + \ 0.9708}{3} = 0.9707$$

3. The method of determining carbon dioxide emissions, using country specific parameters

Carbon dioxide emissions for specific category sources is determined as a product of consumed fuel, expressed as the amount of energy contained in the fuel defined on the basis of calorific value (TJ), emission factor for CO_2 (t CO_2/TJ) and oxidation factor. CzSO provides annual fuel consumption for each category of sources, both in weight units and in energy units determined using the net calorific value. The national inventory research team uses this data as an input activity data.

For determination of the CO_2 emission factor it is necessary to define appropriate emission and oxidation factor for individual categories and for the whole time series. Regarding the updating of the country specific emission factors, the research team decided to determine them as an average of two values: emission factor, calculated using the eq. A3-5, using the parameters **a = 2.4142** and **b = 4.0291**, determined from the combined file "Comb" and emission factor calculated using the parameters **a =2.4211** and **b = 3.9539**, calculated from the file "ETS". The reason for this decision is the very good correspondence of the relevant curves calculated from equation (A3-5) of these two representative sets.

In the case of the oxidation factors the research team decided to use till 2010 so far used oxidation factor of 0.98 and from year 2011 the newly determined country specific oxidation factor presented in section 3. The reason for this decision is the fact that the current values were determined, based on data recorded between 2011 and 2012, while the data for the previous years was not available. However, the newly established oxidation factors suggest that so far used value 0.98 corresponds better to reality than the default value of 1 pursuant to 2006 Guidelines.

Examples of setting of CO_2 emission factors, 2013

a) Lignite (brown coal)

In tab. 3-11, chapter "Energy" is provided average calorific value of 13.409 MJ/kg, CC factor is calculated as:

$$\frac{10 \cdot \left(\frac{2.4142 + 4.0291}{13.409}\right) + 10 \cdot \left(\frac{2.4211 + 3.9539}{13.409}\right)}{2} = \frac{27.147 + 27.160}{2} = 27.153 \ \frac{t\ C}{TJ}$$

To this corresponds emission factor for CO_2

$$27.153 \cdot 3.664 = 99.489 \ \frac{t\ CO_2}{TJ}$$

27.153 • 3.664= 99.489 t CO_2/TJ. Resultant emission factor for CO_2 including the oxidation factor has a value of.

$$99.489 \cdot 0.9846 = 97.957 \frac{t\ CO_2}{TJ}$$

b) Bituminous coal

In tab. 3-11, chapter "Energy" is provided average calorific value of 25.502 MJ/kg, CC factor is calculated as:

$$\frac{10 \cdot \left(\frac{2.4142 + 4.0291}{25.502}\right) + 10 \cdot \left(\frac{2.4211 + 3.9539}{25.502}\right)}{2} = \frac{25.722 + 25.761}{2} = 25.742 \ \frac{t\ C}{TJ}$$

To this corresponds emission factor for CO_2

$$25.742 \cdot 3.664 = 94.317 \frac{t\ CO_2}{TJ}$$

Resultant emission factor for CO_2 including the oxidation factor has a value of

$$94.317 \cdot 0.9707 = 91.554 \frac{t\ CO_2}{TJ}$$

A 3.2 Country specific CO_2 emission factor for LPG

To enhance the accuracy of emission estimates from Energy sector the research with aim to develop country specific emission factor for LPG was carried out in 2014. LPG is the mixture of propane and butane and other C2 – C5 hydrocarbons and is available in two versions – summer and winter mixture. The basic qualitative parameters are available in the official Czech Standard ČSN EN ISO 4256. These parameters are given in Tab. A3 1.

Tab. A3 1 Qualitative parameters of LPG – summer and winter mixture

PARAMETER*)	summer mixture	winter mixture
C2-hydrocarbons and inerts -%, max.	7	7
C3- hydrocarbons -%, min.	30	55
C4- hydrocarbons -%	30 - 60	15 - 40
C5-and higher hydrocarbons -%, max.	3	2
Unsaturated hydrocarbons -%, max.	60	65
Hydrogen sulfide - $mg.kg^{-1}$, max.	0.2	0.2
Content of sulphur - $mg.kg^{-1}$, max.	200	200

*)% in the table mean mass percents

For the determination of country specific emission factor was necessary to obtain data about composition of LPG, which is distributed in the territory of the Czech Republic. These data were obtained from the Česká rafinérská, a.s., which is the major distributor of the LPG in the CR. The quality of distributed LPG is based on the above-mentioned official standard (ČSN EN ISO 4256) and so also the data provided by Česká rafinérská, a.s. are in line with this standard. The specific composition is listed in Tab. A3 2.

Tab. A3 2 Composition of LPG distributed in the Czech Republic (in mass percent)

Composition	summer mixture	winter mixture
C2+inerts	0.2	0.1
propane	38.5	58.7
propylene	7.2	4.5
iso-butane	25.6	27.9
n-butane	15.7	5.9
sum of butens	12.2	2.8
C5 and higher	0.6	0.1
Ratio of the production of summer: winter mixture = circa 1 : 1.1		

This elementary composition of LPG (given in Tab. A3 2) was used for the calculations of country specific emission factor (based on the carbon content in each component). At first carbon emission factors related to the mass of LPG (kg C/kg LPG) were computed. For the summer mixture is the carbon emission factor

equal to 0.8287 kg C/kg; for winter mixture 0.8232 kg C/kg. Final value computed using weighted average taking in consideration the summer: winter mixture ratio is equal to 0.8258 kg C/kg.

The net calorific value related to the mass (MJ/kg) was computed using equation A2-2. For the summer mixture is net calorific value equal to 45.853 MJ/kg; for the winter mixture to 46.029 MJ/kg. Final value computed using weighted average taking in consideration the summer: winter mixture ratio is equal to 45.945 MJ/kg. This net calorific value was also used for the conversion of activity data from kilotons to TJ.

Final emission factor was determined using equation A3-6

$$\frac{1000 \cdot 0.8258}{45.945} = 17.974 \ \frac{t\ C}{TJ} \qquad \text{(A3-6)}$$

This value is in very good agreement with the value 17.9 t C/TJ determined in Harmelen and Koch (2002); corresponded net calorific value is 45.5 MJ/kg (Harmelen and Koch, 2002), which is also in a good agreement with the value determined as Czech country specific.

Tab. A3 3 indicates comparison of the newly developed country specific CO_2 emission factor and the default one provided either in Revised 1996 Guidelines (IPCC, 1997) or in 2006 Guidelines (IPCC, 2006). It is necessary to keep in mind, that 2006 Guidelines states the range of default emission factors, which for LPG is 16.8 – 17.9 t C/TJ. It is apparent that default emission factors slightly underestimate the emission estimates. The country specific emission factor does not fit into the default interval, which also supports this conclusion. Since country specific emission factor was evaluated based on the specific composition of LPG distributed in the Czech Republic, the newly developed emission factor will evaluate the emission estimates more accurate than the default emission factor.

Tab. A3 3 Comparison of country specific CO_2 and default emission factors for LPG

	[t C/TJ]	[t CO_2/TJ]
Revised 1996 Guidelines	17.2	63.07
2006 Guidelines	17.2	63.1
CO_2 country specific emission factor for CR	17.97	65.90

Based on the composition of LPG was also net calorific value computed, which agreed better to the specific conditions of CR then the net calorific value presented in CzSO questionnaire. The updated net calorific value was used for the computation of fuel consumption in TJ; the value 45 945 kJ/kg was used (conversion from kt to TJ).

A 3.3 Country specific CO_2 emission factor for Refinery Gas

Another improvement concerning emission factor from combustion of Refinery Gas was accomplished in 2013. Refinery gas is defined as non-condensable gas obtained during distillation of crude oil or treatment id oil products in refineries. It consists mainly of hydrogen, methane, ethane and olefins (IPCC, 2006).

Refinery Gas in CR is also used mainly by Česká rafinérská, a.s. This company is also included in the EU ETS and in terms of this obligation also carries out the analyses of molar composition of Refinery Gas. These analyses were provided to the inventory team for the purposes of the development of country specific CO_2 emission factor from combustion of Refinery Gas. These analyses obtain the information about content of hydrogen, content of CO_2, content of CO, content of methane, ethane, propane, iso-butane, n-butane, butenes, iso-pentanes, n-pentanes, ethylene, propylene, C6 and higher hydrocarbons, content of oxygen,

nitrogen, hydrogen sulphide and water in the Refinery Gas. The analyses are available for the 2008–2012 in the time step 3 – 4 days.

It is apparent that the available analyses are sufficiently detailed, so it allowed the inventory to team to develop country specific emission factor for the Czech Republic. The approach of 'carbon content in the fuel', which was fully attested in case of determination of country specific emission factor from combustion of Natural Gas (Krtková et al., 2014), was also used for determination of Refinery Gas emission factor. Based on the molar composition of the gas mixture the country specific emission factors for years 2008–2012 were determined. For the years before the average value of the 2008–2012 values was used. The table below shows the used values.

Tab. A3 4 Country specific carbon emission factors from combustion of Refinery Gas (t C/TJ)

1990 - 2007	2008	2009	2010	2011	2012
15.03	15.06	14.93	14.58	15.24	15.34

All values in the table lies within the default range 13.1 – 18.8 t C/TJ specified in the 2006 Guidelines and further more are close to the default value 15.7 t C/TJ (IPCC, 2006). However, the previously used default value provided by the 1996 Guidelines (IPCC, 1997) was somewhat higher, 18. 2 t C/TJ.

Also net calorific value of Refinery Gas was computed based on the available analyses of the molar composition. CzSO has updated this value based on the request of the inventory team. The updated value is 46.023 MJ/kg. This value was used for the whole time series.

A 3.4 Country specific CO_2 emission factor for Natural Gas combustion

Extensive research was carried out in 2012 with aim to develop the country-specific emission factor for Natural Gas combustion (CHMI, 2012b). This research was part of a project of The Technical Assistance of the Green Savings programme. Final evaluation of the CO_2 emission factor for Natural Gas combustion is based on its correlation with the net calorific value. Detailed description of the research is given in the following paragraphs.

Complete description of this research will be published in Greenhouse Gas Measurement & Management journal, the manuscript is entitled Carbon dioxide emissions from natural gas combustion – country specific emission factors for the Czech Republic (Krtková et al., 2014).

The net calorific value of Natural Gas can be computed on the basis of the molar composition according to:

$$Qm = \sum wi \bullet Qmi \quad \text{(A3-8)}$$

$$Qv = Qm \bullet d \quad \text{(A3-9)}$$

where Q_m [MJ/kg] is the net calorific value of Natural Gas related to its mass, w [kg/kg] is the mass fraction, Q_{mi} [MJ/kg] is the net calorific value of different components of Natural Gas related to their mass, Q_v [MJ/m^3] is the net calorific values of Natural Gas related to its volume and d [kg/m^3] is its density.

Tab. A3 5 lists the net calorific values of the basic components of Natural Gas.

Tab. A3 5 Net calorific values of the basic components of Natural Gas (ČSN EN ISO 6976, 2006)

Net calorific values of basic components of Natural Gas [MJ/kg]	
methane	50.035
ethane	47.52
propane	46.34
iso-butane	45.57
n-butane	45.72
iso-pentane	45.25
n-pentane	45.35
sum C>6 (like heptane)	44.93

The carbon emission factor for Natural Gas related to its energy content (CEF_{TJ} [t C/TJ]) is computed according to

$$CEFTJ = CEF_m/Q_m \quad \text{(A3-10)}$$

where CEF_m is carbon emission factor related to the mass.

Carbon dioxide emission factor (EF (CO_2) [t CO_2/TJ]) is then calculated

$$EF\ (CO_2) = CEFTJ \bullet M_{CO2}/M_C \quad \text{(A3-11)}$$

where M_{CO_2} and M_C are the molecular weight of carbon dioxide and atomic weight of carbon, respectively.

A similar method (to the one described here) of computing EF (CO_2) and Q_v for 10 characteristic samples of Natural Gas was used in the article (Čapla and Havlát, 2006). Samples 1 – 4 were chosen based on their place of origin: sample 1 – Natural Gas from Russian gas fields distributed in Czech Republic in 2001; sample 2 – Natural Gas from Norwegian gas fields in the North Sea; sample 3 – Natural Gas coming from Dutch gas fields; sample 4 – Natural Gas mined in Southern Moravia. Samples 5 – 10 represented the composition of the Natural Gas distributed in the Czech Republic in 2005–2006.

This rather representative dataset was used to determine the regression curve, which was similar to the line

$$EF\ (CO_2) = 0.269 \bullet (Qv/3.6)^2 - 2.988 \bullet (Qv/3.6) + 59.212 \qquad \text{(A3-12)}$$

which was tightly fit to all 10 points (correlation coefficient $R^2 = 0.999$). In this correlation expression Q_v represents the net calorific value related to the volume under "trade conditions" (101.3 kPa, 15° C).

The calculations of the regression curve for the samples 5 – 10 indicated in particularly close range of Qv: 34.11 – 34.27 MJ/m^3. The lowest net calorific value (31.31 MJ/m^3) was determined for sample number 3 (Dutch field) and the highest (38.28 MJ/m^3) for Norwegian gas type. The low net calorific value of Dutch Natural Gas is caused by relatively high content of nitrogen; the high net calorific value of the Norwegian Natural Gas is a result of the higher content of C2, C3 and C4 hydrocarbons (especially ethane).

The above-described methodology was tested on a relatively small dataset. To obtain sufficiently reliable correlation, this methodology had to be tested on a dataset which would provide composition of Natural Gas in sufficient time series. In cooperation with CzSO a dataset comprising analyses of Natural Gas composition was obtained. These analyses are continuously evaluated in the laboratory of NET4GAS, Ltd. Daily average values on the Natural Gas composition from the first day in the month were available for evaluation of the CO_2 emission factor. The dataset of these analyses began on 1st January 2007 and the last data are from 1st September 2011. Furthermore, data for 1st February 2012 were also available. The report on each analysis contains data on the molar composition of the Natural Gas, physical characteristics and conditions during which the analysis was performed. Overall, 58 analyses were available. Fig. A3 3 depicts the trend of net calorific values in time.



Fig. A3 3 Net calorific values given in NET4GAS Ltd. reports and net calorific values calculated on the basis of composition of Natural Gas in 1.1.2007–1.2.2012 (both values are given at 15°C)

The figure indicates a good match between the two depicted values; the deviation is almost constant and reaches an average value of 0.16%. The deviation is probably caused by the fact that the measured values correspond to the non-state gas behaviour; however, the calculation is based on the assumption of ideal

gas behaviour. For this reason, the net calorific values from the NET4GAS Ltd. reports were used for calculation of the emission factor. The reports contain data related to the reference temperature 20° C; thus, it was necessary to recalculate net calorific values and densities for 15° C.

The results of the calculations are depicted in Fig. A3 4. This figure also contains computation of the correlation

$$EF\ (CO_2) = 0.787 \bullet Qv + 28.21 \qquad \text{(A3-13)}$$

where Q_v [MJ/m^3] is the net calorific value of Natural Gas at "trade conditions": temperature 15°C and pressure of 101.3 kPa.

These findings were compared with the results obtained during preparation of this research. First, the data about analyses of Natural Gas obtained from RWE Transgas were used for comparison. This dataset contains data from 2003, 2004 and 2009 and evaluation of these data resulted in the correlation

$$EF\ (CO_2) = 0.6876 \bullet Qv + 31.619 \qquad \text{(A3-14)}$$

The second source for comparison is the paper of Čapla and Havlát (2006), where the correlation resulted in equation (A3-13).



Fig. A3 4 Correlation of EF [t CO_2/TJ] and net calorific value of Natural Gas and Comparison of three approaches used for calculation

Fig. A3 4 indicates good correlation between all three approaches in the region of 34.1 – 34.3 MJ/m^3, where the deviation between the results is 0.3% in maximum.

Each year in its energy balance, the Czech Statistical Office reports the average value of net calorific value of Natural Gas. Fig. A3 4 indicates the trend of these calorific values. It is apparent that NCV is continuously slightly increasing.

The dark line in Fig. A3 4 indicates the lowest net calorific value determined in the dataset provided by NET4GAS Ltd in 2007 - 2012. For the period of 2007 towards all the net calorific values are lower than 34.1 MJ/m^3. For this reason, it is more accurate to use the correlation obtained from the dataset representing the data before this year, i.e. the correlation evaluated by Čapla and Havlát (2006).

Fig. A3 5 depicts the correlation curve combined on the basis of both correlations. It is given for the whole range of net calorific values, which was identified in Natural Gas in the Czech Republic in the 1990–2010 period. The value 34.1 MJ/m^3 is depicted by the dashed line.



Fig. A3 5 Trend in Natural Gas NCV 1990–2010 and Correlation between NCV and EF combined from two approaches – Čapla and Havlát (NCV lower than 34.1 MJ/m³) and computed correlation on the basis of NET4GAS dataset (NCV higher than 34.1 MJ/m³)

Evaluation of CO_2 emission factors for Natural Gas combustion is based on the computational approach described above. There are two correlation relations; each of them is used for a different range of net calorific values. As depicted in Fig. A3 5, both correlations follow each other closely. Tab. A3 6 lists all the calculated emission factors for both correlations; the recommended values are in bold.

Tab. A3 6 Comparison of both recommended correlations

year	Average net calorific value of NG reported by CzSO	EF CO_2 calculated on the basis of Čapla and Havlát correlation (eq. A2-5)	EF CO_2 calculated on the basis of NET4GAS, Ltd. dataset correlation (eq. A2-6)
	[MJ/m³]	[t CO_2/TJ]	[t CO_2/TJ]
1990	33.794	**54.87**	*54.81*
1991	33.807	**54.87**	*54.82*
1992	33.820	**54.88**	*54.83*
1993	33.832	**54.89**	*54.84*
1994	33.845	**54.90**	*54.85*
1995	33.975	**54.97**	*54.95*
1996	33.957	**54.96**	*54.93*
1997	33.966	**54.97**	*54.94*
1998	34.046	**55.01**	*55.00*
1999	33.965	**54.97**	*54.94*
2000	33.980	**54.97**	*54.95*
2001	33.986	**54.98**	*54.96*
2002	34.023	**55.00**	*54.99*
2003	33.997	**54.98**	*54.97*
2004	33.962	**54.96**	*54.94*
2005	33.938	**54.95**	*54.92*
2006	34.105	*55.05*	**55.05**
2007	34.167	*55.08*	**55.10**
2008	34.164	*55.08*	**55.10**
2009	34.288	*55.16*	**55.19**
2010	34.328	*55.18*	**55.23**

The deviations between the two calculations are less than 0.15%. The values written in bold were used for recalculation of CO_2 emissions from Natural Gas combustion for the 1990–2010 time series (held in 2013 submission). Former submissions employed the default emission factor 56.1 t CO_2/TJ, which overestimated the CO_2 emissions from Natural Gas combustion, especially at the beginning of the nineteen nineties (about 2.4% in 1990).

For years 2011 and 2012 the correlation relation based on the NET4GAS, Ltd. dataset was used (eq. A3-15):

$$EF\ (CO_2) = 0.787 \bullet Qv + 28.21 \qquad \text{(A3-15)}$$

The availability of analyses of the Natural Gas composition should be ensured in the coming years. The validity of equation (A3-15) will be continuously tested using new data, and if necessary, the correlation equation will be modified to fit the new data as best as possible.

Starting with submission 2013 updated emission factors are be used for all categories in 1A Energy for the whole time series.

For other detailed discussion of methodology and data for estimating CO_2 emissions from fossil fuel combustion please see the discussion of methodology in Chapter 3.4 and in the Annex 4.

A 3.5 Country specific CO_2 emission factor for Lime Production

Emissions of GHG from lime production are classified into two different categories. The first category relates to the combustion processes, ongoing in the production of lime, and emissions from it are reported in sector "Energy" in the Czech National Inventory Document. In the second category are included emissions from decomposition of carbonates, of decomposition of organic carbon, contained in the raw material, used to produce lime. These emissions are described in sector "Industrial processes", in subsector 'Mineral industry'. The following calculations apply only to the second category of emissions.

Production of lime is based on heating limestone, during which decomposition (calcination) of carbonates, contained in limestone, occurs and carbon dioxide is released. In limestone mainly calcium carbonate and magnesium carbonate mixture is present in range of 75.0 to 98.5% of weight, of which the magnesium carbonate is 0.5 to 15.0% of weight. Detailed chemical composition and the division into classes of limestone, according to the national standards are shown in Tab. A3 7 (ČSN, 1992).

Tab. A3 7 Division of limestone, according to chemical composition

Chemical composition in% weight		Quality class							
		I	II	III	IV	V	VI	VII	VIII
$CaCO_3 + MgCO_3$	min	98.5	97.5	96.0	95.0	93.0	85.0	80.0	75.0
from which $MgCO_3$	min	0.5	0.8	2.0	4.0	6.0	10.0	15.0	
SiO_2	max	0.3	0.8	1.5	3.0	4.5	6.0	8.0	18.0
$Al_2O_3 + Fe_2O_3$	max	0.2	0.4	0.8	2.0	3.5	5.0	6.0	6.0
from which Fe_2O_3	max	0.03	0.1	0.03	1.0	2.0	2.5	2.5	
MnO	max	0.01	0.03	0.03	0.03				
SO_3	max	0.08	0.1	0.2	0.2	0.3	0.5	0.5	2.0

The composition of limestone is closely associated with the emission factor. As calcium carbonate and magnesium carbonate have different emission factor, the ratio between the two emission factors is reflected in the resulting emission factor. Emission factor derived from $CaCO_3$ or $MgCO_3$ is defined as emission factor of method A. This method is based on the input materials in the process of lime production. Further emission factor can be determined for outgoing materials or for CaO and MgO in lime. This procedure is called method B. Emission factors from method A and B are described in Tab. A3 8 (Commission Regulation (EU) № 601/2012).

Tab. A3 8 Emission factors for method A and B

Method	Material	EF [t CO_2/ t material]
A (input)	$CaCO_3$	0.440
	$MgCO_3$	0.522
B (output)	CaO	0.785
	MgO	1.092

Additional ingredients (other carbonates and organic carbon), which occur in limestone in very small quantities, may also be a source of emissions. These small amounts will affect to a minor extent the total emission factor; therefore, for the inventory of GHG can be considered as negligible.

Thus, the most significant impact on the emission factor has the composition of the input material, which subsequently is reflected in the composition of lime. Therefore, we can affirm that, it is inessential, if we calculate from the composition of the input material (Method A) or the composition of the output material (Method B), both ways would lead to the same emission factor for the given process.

The best way to do that is to observe the relation between the emission factor and mass in % of $MgCO_3$ in the input material (Method A). This dependence can be observed on Fig. A3 6.



Fig. A3 6 Correlation between emission factor and mass representation of $MgCO_3$ in input material

Dependence between emission factor and output material (weight% MgO) occurs naturally, even when using method B, as you can see on Fig. A3 7.



Fig. A3 7 Correlation of emission factor in mass representation of MgO in output material

As Fig. A3 6 and Fig. A3 7 show, the emission factor varies with the amount of MgCO3 or MgO only very slightly. Limestone, which is processed in the Czech Republic, is supplied to the lime plants from the same source and the composition of it for the individual sources does not change much with time. These facts reveal that, similarly, the emission factor for lime production will move only within a narrow range, which will have a small impact on the calculation of the emissions. As it is evident from Fig. A3 6 the emissions calculated, using Tier 1 approach, which adopts country specific emission factor (Vacha, 2004), are only very slightly overestimated compared to emissions from the ETS, which are obtained by measuring or Tier 3 approach.

Fig. A3 8 shows oscillating weighted total emission factor derived from the ETS which fluctuates near the country specific emission factor values.



Fig. A3 8 Development of emissions of CO_2 from production of lime in CR for period 1990–2014

From Fig. A3 9 it is observed that there could be a slight decrease in the emission factor since 2009, but it will be rather an incidental drop. For the period 1990–2004, for which ETS data are not available, the emission factors could be calculated as the average of the available data from the ETS. The average of these values is 0.7885 t CO_2/t lime, and it differs from the country specific emission factor only by one ten-thousandth. For this reason, for this time period it is considered to keep the country specific emission factor.



Fig. A3 9 Development of EF for production of lime in CR for period 1990–2014 (method B)

Since the composition of limestone from 1990 to the present has not changed significantly, the emission factor does not undergo any major change. Therefore, for the period 1990–2009 the country specific emission factor (0.7884 t CO_2/t lime; Vacha, 2004) can be used and for the remaining period 2010–2014 will be applied emission factors derived from the ETS.

Due to the very small variation of $MgCO_3$ content in limestone, the emission factor changes slightly over time. We can use as an emission factor for the period 1990–2009 the proposed country specific, which is equal to 0.7884 t CO_2/t lime (Method B) and activity data for emission calculations utilize the Czech

Statistical Office and Czech Lime Association. Since 2010 it is possible to use ETS data that have greater accuracy than the country specific EF together with data from the CSO and CLA.

A 3.6 CBM-CFS3 model – calibration, use and verification

A 3.6.1 Introduction

The earlier (NIR 2022) inventory submission introduced a Tier 3 model carbon stock change estimation in emission categories associated with forestry using a specifically calibrated Carbon Budget Model of the Canadian Forest Sector (CBM-CFS3, further denoted as CBM; Kurz et al. 2009, Kull et al. 2019). Since then, CBM has been used to facilitate the estimation of carbon stock pool changes in forests for the successive NIR submissions. Specifically, the CBM model estimates are used to derive CO_2 emissions resulting from carbon stock changes in living (aboveground and belowground) biomass, dead organic matter including both deadwood and litter, and organic soil carbon in mineral soils (except land conversions). This aids the emission reporting for categories 4.A.1 Forest Land remaining Forest Land, 4.A.2 Land converted to Forest Land, 4.B.2.a Forest Land converted to Cropland, 4.C.2.a Forest Land converted to Grassland, 4.D.2.a Forest Land converted to Wetlands, 4.E.2.a Forest Land converted to Settlements (Tab. A3 9). Correspondingly, CBM was earlier (NIR 2022) used for emission estimations for the former KP LULUCF activities, namely Afforestation/Reforestation (AR), Deforestation (D) and Forest Management (FM), as well as the technical correction applicable to FM accounting under KP II (2013–2020). There is a retained methodological link for estimates under UNFCCC and that for the former KP LULUCF activities AR and D in this inventory submission (NID 2026), which is detailed below.

Tab. A3 9 Methodological tier indicating use of CBM in estimating carbon pools under UNFCCC and KP LULUCF for the concerned land use categories and the former KP LULUCF activities. *Carbon stock change in organic soil is not included in this table, but it is estimated with T1/T2 methodologies.

Emission category (UNFCCC) or Activity (KP LULUCF)	Carbon pool UNFCCC	Carbon pool KP LULUCF	Methodological tier and comment
4.A.1 FL remaining FL Forest Management	Living biomass	Aboveground biomass	T3, CBM
		Belowground biomass	T3, CBM
	Dead organic matter (DOM)	Deadwood	T3, CBM
		Litter	T3, CBM
	Soil (Mineral soils)*	Soil (Mineral soils)	T3, CBM
4.A.2 Land converted to FL Afforestation/Reforestation	Living biomass	Aboveground biomass	T3, CBM
		Belowground biomass	T3, CBM
	Dead organic matter (DOM)	Deadwood	T2, T3, CBM
		Litter	T2, T3, CBM
	Soil (Mineral soils)*	Soil (Mineral soils)	T2/T3, Soil carbon maps
4.B.2.1 FL converted to Cropland 4.C.2.1 FL converted to Grassland 4.D.2.1 FL converted to Wetland 4.E.2.1 FL converted to Settlements Deforestation	Living biomass	Aboveground biomass	T2/T3, CBM
		Belowground biomass	T2/T3, CBM
	Dead organic matter (DOM)	Deadwood	T2/T3, CBM
		Litter	T2/T3, CBM
	Soil (Mineral soils)*	Soil (Mineral soils)	T2/T3, Soil carbon maps
Harvested Wood Products	Harvested Wood Products	Harvested Wood Products	T2, Production approach

CBM represents a flexible modelling framework that has also been applied for carbon-accounting purposes in other European countries (Pilli et al., 2017, 2013). Additionally, Pilli et al. (2017, 2018) prepared an extensive database of model parameters and biomass equations applicable to European conditions, which was also used as a basis for this country-specific application. CBM is an inventory based, yield-data driven model that simulates the stand- and landscape-level carbon (C) dynamics of above- and below-ground biomass, and dead organic matter (DOM) including soil (Kurz et al., 2009; Fig. A3 10). In its spatial representation beyond single stands, it can be flexibly set up to represent administrative and climate

regions. CBM was previously used to construct the Forest Reference Level (FRL) for the Czech Republic and its National Forest Accounting Plan under the LULUCF Regulation of EU 2018/841 (https://www.mzp.cz/cz/opatreni_v_ramci_lulucf). The current CBM calibration is in part similar, but in several aspects significantly enhanced, as described in this document. An overview of the emission categories and carbon pools affected by the improved methodological tier for the UNFCCC land use categories concerned as well as the corresponding former KP LULUCF activities is shown in Tab. A3 9.

CBM uses in total 21 carbon pools, which are linked to IPCC carbon pools as shown in Tab. A3 10 and in the conceptual diagram in Fig. A3 10.



Fig. A3 10 Conceptual diagram of CBM carbon pools and their relationships (straight arrows showing transfers between pools, curved arrows showing transfer to atmosphere), with categorization of relative decay rates (very fast, fast, medium, slow), for softwoods (formulated and used from Kull et al. 2019).

Tab. A3 10 IPCC carbon pools and their equivalents in CBM (adapted from Kurz et al. 2009). *Merchantable size wood limit uses the Czech standard of min. 7 cm in diameter.

IPCC carbon pool	Pool name in CBM-CFS3	Description
Living Biomass		
Aboveground biomass	Merchantable stemwood and bark	Live stemwood of merchantable size* plus bark
	Other wood and bark	Live branches, stumps and small trees including bark
	Foliage	Live foliage
Belowground biomass	Coarse roots	Live roots, 5 mm and larger diameter
	Fine roots	Live roots, less than 5 mm diameter
Dead organic matter		
Deadwood	Snag stems DOM	Dead standing stemwood of merchantable size incl. bark
	Snag branches DOM	Dead branches, stumps and small trees
	Medium DOM	Coarse woody debris on the ground
	Belowground fast DOM	Dead coarse roots (diam. 5 mm and more) in mineral soil
Litter	Aboveground fast DOM	Fine and small woody debris and dead coarse (submerch. size) roots in the forest floor
	Aboveground slow DOM	F, H and O horizons

	Aboveground very fast DOM	L horizon incl. foliar litter and dead fine roots (<5 mm diam.)
Soil		
Soil organic matter	Belowground very fast DOM	Dead fine roots (<5 mm diam.) in the mineral soil
	Belowground slow DOM	Humified organic matter in the mineral soil

CBM simulates the transfer of carbon between pools and the atmosphere (Fig. A3 10). Specifically, it simulates mortality and litter fall representing transfers from biomass to other dead organic matter (DOM) pools resulting from tree, foliage, branch and root mortality (Kurz et al. 2009). The calibrated country-specific equations to convert volumes to biomass components, turnover and transfer rates between DOM pools are specified in the AIDB database (CBM-specific database in MS Access format, Kull et al. 2019). The detailed model handling of carbon turnover including DOM pools was one of the fundamental reasons for implementing this tier-3 modelling approach, to ensure that the complete carbon cycling in forest ecosystems is captured. This is important specifically in the conditions of significantly changing wood harvest and mortality, which directly affect inputs into and emissions from the DOM pools. Decomposition of all DOM pools is modelled using a temperature-dependent decay rate function (Kurz et al. 2009). This is the only climate-depended relationship used in CBM. Earlier, the annual mean temperature to represent all forest regions in Czech Republic was set to 8.0 °C in the AIDB database of CBM. For NID 2026, this was replaced by the annual observation data relevant to forest area in the country approximated by a lowess smoother. This temperature trend originates at 7.3 °C at the beginning of the reporting period (1990) and ends at 9.1 °C for the most reporting year (2024). Disturbances including forest management interventions such as thinning, harvest and afforestation are each defined in a matrix describing the proportion of carbon transferred between pools, fluxes to the atmosphere, and transfers to the DOM pools and the timber sector.

A 3.6.2 Input data and calibration

In general, the use of the CBM model tool was set up to resemble the NID/NIR reporting strategy (key input data use, stratification) adopted in the Czech emission inventory of the LULUCF sector earlier. The CBM simulation run is set to start in 1990 and progresses in an annual step until 2024, i.e., for the entire reporting period. The model integrates the key activity data as used in the emission inventory so far. These include land-use areas related to forests, data on growing stocks by tree species and age class from the national stand-wise inventory compilation of forest management plans and guidelines (FMPG, administereded centrally at the Czech Forestry Institute - CFI) and the related volume increment data (also from CFI), and data on disturbances (management practices) as centrally collected by CzSO. At same time, CBM requires a specific calibration of biomass component functions, specifying turnover rates of biomass components and defining disturbance matrices describing the adopted forest management interventions and included natural disturbances.

A 3.6.2.1 Land area matrices and species groups

Activity data on land use areas of Forest Land, land use conversion to Forest Land (and the corresponding former KP LULUCF activity Afforestation/Reforestation, AR) and from Forest Land (former KP LULUCF Deforestation, D) are described in NID Section 6.2 and 6.4.1. These activity data come from the Czech Office for Surveying, Mapping and Cadastre (COSMC).

Tree species grouping used in the entire inventory for category 4.A Forest Land and the AR, D activities representing land use change and forest management (FM) on 4.A.1 Forest land remaining Forest land, follows the country specific approach as described in Section 6.4.1. Namely, four groups of tree species are used as the basic forest strata in CBM: i-beech: all broadleaved species except oaks, ii-oak: all oak species, iii-pines: all pine species, iv-spruce: all conifers except pines. For land-use transitions involving forest land, CBM requires additional information on the share of tree species in its input file. For AR events

(and the related 4.A.2 category), four species groups were included, specifically beech, oak, pine and spruce, using area shares of 40, 10, 20 and 30%, respectively. For D events (and the related land use categories 4.B.2.a, 4.C.2.a, 4.D.2.a and 4.E.2.a), the spruce species group was exclusively used in CBM. This basically matched the observed species change in share for the reporting period (Fig. 6-6 in Section 6.4.1). Additionally, disturbance of salvage logging including species change (DIST 3, see section A 3.6.2.5) in category 4.A.1 (and FM) included species change involving pine and spruce. This allowed the fine-tuning of tree species share on forest land, replacing a part of pine in favor of beech (15%) and oak (25%), and a part of spruce in favor of beech (30%), oak (5%) and pine (15%), making the share of species consistent with the observed activity data on forest lands for the entire reporting period.

A 3.6.2.2 Growing stock volume and increment

The state of forest resources in terms of growing stock by age classes and species groups as of 1990 served as the initial year for the CBM run (

Fig. A3 11) for the entire reporting period of 35 years (1990 to 2024). The forest area increased by AR activities decreased by D activities according to the known activity data described in Section A 3.6.2.1.



Fig. A3 11 Forest area by age class and tree species groups as of 1990, the initial year of the reporting period and CBM simulation.



Fig. A3 12 Mean merchantable growing stock volume per hectare (from the database of FMPG, CFI) and age class for individual tree species groups, as of 1990.

Volume increment data used in CBM are derived from the identical source as described in Section 6.4.2.2. CBM (CBM-CFS3) uses merchantable volume data over age to simulate growth. The entire CBM growth concept is described in detail by Kurz et al. 2009 and Pilli et al. 2013. In essence, the process involves two steps. First, it requires data on the growing stock per age class and tree species as the initial standing volume to run the simulation – in our case, the observed standing volume data per age class and tree species groups as of 1990 was used (Fig. A3 12). Second, the age-dependent gross merchantable volume curves resembling current yield tables (CYTs) are used to simulate growth. Note, however, that these curves cannot include natural mortality, and hence they still represent net annual increment in ecological sence. CYTs were expressed for individual species groups based on the official current annual increment estimates (shown in Fig. 6-11 and Fig. A3 13) as provided by Czech Forestry Instirute (CFI, formerly Forest Management Institute), Brandys n. L. (Section 6.4.1). CYTs were fitted as a function of age, using the flexible combined exponential and power function (Sit 1994; Pilli et al., 2013), namely.

$$CYT_t = a \times t^b \times c^t \qquad \text{(A3-16)}$$

where t is age (years), and a, b, c are the parameters to be fitted. These functions were fitted based on current increment data (CAI) as of 2004 (Fig. A3 13). CAI data were accumulated to form volume curves (CYTs) including a stem mortality adjustment based on the NFI2 results (Adolt and Kučera 2019). The year 2004, representing the middle of the reporting period, was used for CAI and the corresponding CYT. Thereafter, a set of relative scaling factors applicable to individual tree species groups and the reporting period 1990 to 2024 (Fig. A3 15) were implemented within CBM to assure full coherence with the input activity data on growth based on the FMPG database, which are shown for the entire reporting period in in Fig. 6-11, Section 6.4.1.



Fig. A3 13 Current annual increment (CAI) for tree species groups and age class as of 2004

Tab. A3 11 Species-specific parameterization of CYT curves according to equation A3-16, including the parameter estimate and asymptotic standard error (ASE).

Species group	Estimate	Parameter of eq. A3-16		
		a	b	c
Beech	Parameter estimate	0.123	2.092	0.990
	ASE	0.060	0.132	0.001
Oak	Parameter estimate	0.335	1.884	0.990
	ASE	0.182	0.150	0.001
Pine	Parameter estimate	0.216	2.001	0.989
	ASE	0.083	0.106	0.001
Spruce	Parameter estimate	0.399	1.925	0.989
	ASE	0.168	0.116	0.001

Fig. A3 14 Fitted gross volume curves (CYT) for tree species groups and age class as of 2004



Fig. A3 15: Scaling factor applicable for CAI relative to 2004 for individual tree species groups and reporting/simulation period.

A 3.6.2.3 Biomass equations and CBM biomass component functions

The next essential step in CBM calibration is the implementation of appropriate biomass equations and conversion factors to facilitate growth estimation in carbon units and its distribution to individual tree parts and carbon pools. A complete, detailed description of these CBM processes is given in Kurz et al. 2009 and Kull et al. 2019. Here, we provide information on our country-specific application. To provide biomass estimates for individual tree parts, the set of relevant (national allometric studies and/or biomass compilations that include data from the Czech Republic) equations were used for beech (Vonderach et al. 2018, Wutzler et al., 2008 for leaves only), oak (Cienciala et al., 2008a), pine (Cienciala et al. 2006b), spruce (Vonderach et al. 2018) and complementarily birch (Marklund 1989, Repola 2008 for leaves only).

Until NID 2026, solely the data from the country-wide sample-based landscape inventory CzechTerra (Cienciala et al. 2016) were used to assess tree biomass components according to the above biomass equations and expressed on a per plot and ha basis. A threshold of at least n=5 trees per plot was used to qualify a CZT plot into the species -specific sample. Since this (NID 2026) inventory submission, the volume-to-biomass callibraiton data were newly represented by a significantly larger dataset of tree-level estimates of the National Forest Inventory (NFI2 and NFI3 campaigns, J. Máslo - CFI, personal communication 2025). These estimates were used as input to calibrate biomass component functions according to the procedure described by Boudewyn et al. (2007; Fig. A3 16). Estimation of the belowground biomass component of living trees in CBM is calculated using equations and parameters defined for deciduous and coniferous species by Li et al. (2003).



Fig. A3 16: Flowchart showing the development and application of biomass component functions in CBM (from Boudewyn et al. 2007). Note that the numbering of equations in the flowchart does not match that used in the NIR text, but the equation names do.

Tab. A3 12 Species-specific parameterization of merchantable biomass (*bm*) according to equation A3-17, including the parameter estimate, asymptotic standard error (ASE), coefficient of determination (R^2) and sample size (n).

Species	Estimate	Parameter of Eq. A3-17		R^2	n
		a	b		
Beech	Parameter estimate	0.715	0.986	1.000	512
	ASE	0.006	0.001		
Oak	Parameter estimate	0.842	0.982	1.000	358
	ASE	0.006	0.001		
Pine	Parameter estimate	0.568	0.973	1.000	698
	ASE	0.004	0.001		
Spruce	Parameter estimate	0.450	0.999	1.000	4 519
	ASE	0.001	0.000		
Birch	Parameter estimate	0.997	0.865	0.948	527
	ASE	0.060	0.010		

Of the seven equations outlined in the flowchart of Boudewyn *et al*. (2007, Fig. A3 16), we first parameterized Eq. 1. describing the dependence of total stem biomass (*bm*, t/ha) on wood merchantable wood volume (*v*, m^3/ha under bark), defined by a min. threshold 7 cm (measured over bark) that excludes stumps, tree tops and non-merchantable trees. This relation is written as

$$bm = a \times v^b \qquad \text{(A3-17)}$$

where *a*, *b* are the parameters to be fitted. The results of the fit are shown in Tab. A3 12.

In earlier submissions, the relations for the components of non-merchantable size trees and saplings (Eqs. 16, 17 in Fig. A3 16) were retained as prescribed in Pilli et al. (2018). Since this (NID 2026) submission, the

species-specific function for nonmerchantable factor relating nonmerchantable-sized biomass to total stem biomass of merchantable dimensions (A3-18) was re-parameterized using the calibration data from NFI2 and NFI3 sampling (CFI; Jan Máslo – personal communication 2025). The parameterization details of Eq. A3-18 is function is summarized in Tab. A3 13.

$$nonmerchfactor = k + a \times b_m^b \quad \text{(A3-18)}$$

where *nonmerchfactor* equals *b_nm/b_m*, *b_nm* is the sum *b_m+b_n,* where *b_n* is stem wood biomass of live, nonmerchantable-sized trees (t/ha), and *k*, *a*, *b* are parameters fit by tree species (Tab A3-13).

Tab. A3 13 Species-specific parameterization of non-merchantable biomass fraction (*bm*) according to equation A3-17, including the parameter estimate, asymptotic standard error (ASE), coefficient of determination (R^2) and sample size (n).

Species	Estimate	Parameter of Eq. A3-17			R^2	N
		a	b	k		
Beech	Parameter estimate	21.75	-1.335	0.994	0.704	512
	ASE	2.910	0.062	0.008		
Oak	Parameter estimate	37.51	-1.512	0.898	0.692	358
	ASE	8.427	0.088	0.007		
Pine	Parameter estimate	185.8	-1.898	1.006	0.733	698
	ASE	27.81	0.065	0.007		
Spruce	Parameter estimate	761.6	-2.508	1.011	0.439	4 519
	ASE	117.0	0.061	0.002		
Birch	Parameter estimate	33.99	-1.496	0.989	0.406	527
	ASE	11.63	0.119	0.007		

Next, using the NFI data as described above, we parameterized the set of biomass proportion equations (Eqs. A3-19, A3-20, A3-21, A3-22). A multinominal modelling approach was used to derive the parameters of the proportion equations according to Boudewyn et al. (2007):

$$p_{stemwood} = \frac{1}{1 + e^{a1+a2\times vol+a3\times lvol} + e^{b1+b2\times vol+b3\times lvol} + e^{c1+c2\times vol+c3\times lvol}} \quad \text{(A3-19)}$$

$$p_{bark} = \frac{e^{a1+a2\times vol+a3\times lvol}}{1 + e^{a1+a2\times vol+a3\times lvol} + e^{b1+b2\times vol+b3\times lvol} + e^{c1+c2\times vol+c3\times lvol}} \quad \text{(A3-20)}$$

$$p_{branches} = \frac{e^{a1+a2\times vol+a3\times lvol}}{1 + e^{a1+a2\times vol+a3\times lvol} + e^{b1+b2\times vol+b3\times lvol} + e^{c1+c2\times vol+c3\times lvol}} \quad \text{(A3-21)}$$

$$p_{foliage} = \frac{e^{a1+a2\times vol+a3\times lvol}}{1 + e^{a1+a2\times vol+a3\times lvol} + e^{b1+b2\times vol+b3\times lvol} + e^{c1+c2\times vol+c3\times lvol}} \quad \text{(A3-22)}$$

where $p_{stemwood}$, p_{bark}, $p_{branches}$, $p_{foliage}$ are proportions of total tree biomass in stemwood, stembark, branches and foliage, respectively, *vol* is merchantable volume (m^3/ha under bark), *lvol* is the natural logarithm of (*vol+5*) and *a1*, *a2*, *a3*, *b1*, *b2*, *b3*, *c1*, *c2*, *c3* are model parameters to be fitted by region/ecozone (Czech Republic) and lead tree species. The resulting fits are shown in Tab. A3 14.

Tab. A3 14 Species-specific parameters of the biomass proportion functions (Eqs. A3-19, A3-20, A3-21, A3-22) for individual tree species and biomass components, volume limit (based on observations), root mean square error (RMSE) and plot sample size (n).

Cohort/ Species		1	2	3	Volume limit (m^3/ha)	Component	RMSE	n
Beech	**a**	-2.5284	-0.0002	-0.0014	1411	Stemwood	0.039	512
	b	1.2817	0.0009	-0.5906		Bark	0.006	

	c	-1.3766	0.0014	-0.8622		Branch	0.040	
						Foliage	0.002	
Oak	**a**	-1.4088	0.0003	-0.1066	729	Stemwood	0.031	362
	b	-0.6589	0.0016	-0.5420		Bark	0.007	
	c	0.3348	0.0052	-1.1340		Branch	0.033	
						Foliage	0.005	
Pine	**a**	-1.9294	-0.0001	-0.0631	686	Stemwood	0.037	698
	b	0.1939	0.0020	-0.5679		Bark	0.004	
	c	0.0480	0.0029	-0.7867		Branch	0.026	
						Foliage	0.012	
Spruce	**a**	-2.0109	-0.0001	-0.0608	1297	Stemwood	0.045	4 519
	b	-0.0359	0.0003	-0.3214		Bark	0.005	
	c	0.1913	0.0004	-0.5009		Branch	0.033	
						Foliage	0.018	
Birch	**a**	-1.6909	0.0000	-0.0016	754	Stemwood	0.023	527
	b	-0.9158	0.0000	-0.0686		Bark	0.002	
	c	-2.8094	-0.0003	-0.1095		Branch	0.020	
						Foliage	0.003	

The resulting biomass proportions for individual tree species as a function of merchantable-sized tree stem wood volume are also visualized in Fig. A3 17.



Fig. A3 17 Share of aboveground biomass components for individual tree species from the parameterized proportion equations as in Tab. A3 13.

A 3.6.2.4 Turnover and transfer rates of carbon pools

The biomass turnover and litterfall transfer rates used in CBM are summarized in Tab. A3 15, according to pools illustrated in Fig. A3 10.

Tab. A3 15 Biomass turnover rates, designated DOM pools and litterfall transfer share (a – Bertini et al. 2019; b – Rock et al. 2008; c – Kurz et al. 1992 adj.; d – Li et al. 2003).

CBM pool	Turnover rates (%C/yr)	DOM pool receiving turnover	Literfall transfers (% transferred to DOM pool)
Merchantable stem (SW, HW)[a]	0.3	Snag stem	100
Other wood (SW, HW)[b]	4.0	Snag branches	25
		AG fast	75
Foliage (SW)[b]	18	AG very fast	100
Foliage (HW)[c]	95	AG very fast	100
Fine roots (HW, SW)[d]	64.1	AG very fast	50
		BG very fast	50
Coarse roots (HW, SW)[d]	2	AG fast	50
		BG fast	50

A 3.6.2.5 Land use change considerations

CBM is designed to facilitate estimations of land use change impacts in term of areas and carbon pool changes (Kurz et al. 2009). Land use conversions representing afforestation and deforestation events are represented by their specific matrices (see below) and transition rules. All disturbance impacts following land use conversion are attributed to the new land-use class as required by IPCC guidelines. A mean reference soil carbon stock for the land use classes of Forest Land, Cropland, Grassland, Wetland and Settlements are estimated from the respective soil carbon maps used in this NID, i.e., 66.2, 53.1, 74.1, 78.3 and 59.7 t/ha, respectively. A detailed description of CBM processes and assumptions related to land use conversions is provided by Kurz et al. (2009).

A 3.6.2.6 Forest management interventions and other disturbances

Changes in forest ecosystems are prescribed by disturbance matrices, which define the applied forest management interventions and natural disturbances in terms of the changes in carbon pools and transfers of carbon between them. The following set of disturbances were applied in CBM:

- DISTID 1 Wildfire – This represents ground fires affecting mainly the litter and deadwood layer with a slight effect on the main tree stand, used only to initialize DOM pools.
- DISTID 2 Thinning – Commercial thinning of merchantable-size trees in age classes 2-5 (species-dependent) resulting in a 10-30% reduction in biomass carbon.
- DISTID 3a (Salvage A) Salvage with Clearcut – Stand replacing salvage harvesting induced by natural abiotic and biotic disturbances affecting continuous areas. All merchantable biomass is extracted, a part of the residues is extracted (noted under CO*). Used either with or without tree species changes following the harvest.

- DISTID 3b (Salvage B) Salvage without Clearcut - Salvage harvesting induced by natural (both abiotic and biotic) disturbances affecting disperse smaller areas not resulting in opened clearcut areas.
- DISTID 4 Final Cut – Commercial clearcut of mature forest stands leaving 3% of merchantable trees as reserved seed trees. All merchantable biomass is extracted, a part of the residues is extracted (noted under CO*).
- DISTID 5 Slash and burn – Final cut disturbance used during the initialization of forest stands as the last event to build up DOM pools.
- DefCL (GL, SL) – Deforestation disturbances extracting wood or transforming living biomass to DOM pools. Transition of Forest Land (deforestation) to other IPCC land use classes (CL – Cropland, GL – Grassland, SL – Settlements). Salvage, uprooting and decay of biomass.
- DefWL - Deforestation disturbance transitioning forest land to wetlands, extracting wood, or transforming living biomass to DOM pools with salvage, uprooting and decay.

Scheduling the timing of timber harvest (thinning, salvaging, final cut) for each species group is organized in the model input file and disturbance event tables, which define the minimum forest age and biomass for clearcut, minimum and maximum age for thinning and the thinning interval. The harvested amount of each harvest type is prescribed for each time step (year) using the observed (reported) harvest data per species groups (see Section 6.4.2). Merchantable wood volume entering the requested disturbance quantity in the CBM input file was converted first to biomass using the prescribed species-specific wood densities (IPCC 2006) for beech and oak (0.58 t/m^3), pine (0.42 t/m^3) and spruce (0.40 t/m^3). Secondly, a carbon fraction of 0.5 was used for converting dry biomass to carbon for all species groups.

The individual disturbances (except Afforestation/Reforestation, which does not contain a specific redistribution of carbon between pools) are documented in detail by the corresponding disturbance matrices included below.

DISTID 2 Thinning	SW merchantable	SW foliage	SW other	SW sub-merch	SW coarse roots	SW fine roots	HW merchantable	HW foliage	HW other	HW sub-merch	HW coarse roots	HW fine roots	Above ground very fast soil C	Below ground very fast soil C	Above ground fast soil C	Below ground fast soil C	Medium soil C	Above ground slow soil C	Below ground slow soil C	SW stem snag	SW branch snag	HW stem snag	HW branch snag	Black C	peat	CO2	CH4	Resid. extract.	NO2	products
SW merchantable	0.80																0.01													0.19
SW foliage		0.80											0.20																	
SW other			0.80																		0.15							0.05		
SW sub-merch				0.80																	0.15							0.05		
SW coarse roots					0.80										0.05	0.15														
SW fine roots						0.80							0.05	0.15																
HW merchantable							0.80										0.01													0.19
HW foliage								0.80					0.20																	
HW other									0.80														0.15					0.05		
HW sub-merch										0.80													0.15					0.05		
HW coarse roots											0.80				0.05	0.15														
HW fine roots												0.80	0.05	0.15																
Above ground very fast soil C													1.00																	
Below ground very fast soil C														1.00																
Above ground fast soil C															1.00															
Below ground fast soil C																1.00														
Medium soil C																	1.00													
Above ground slow soil C																		1.00												
Below ground slow soil C																			1.00											
SW stem snag																				1.00										
SW branch snag																					1.00									
HW stem snag																						1.00								
HW branch snag																							1.00							
Black C																								1.00						
peat																									1.00					

DISTID 3(a) Salvage with clearcut	SW merchantable	SW foliage	SW other	SW sub-merch	SW coarse roots	SW fine roots	HW merchantable	HW foliage	HW other	HW sub-merch	HW coarse roots	HW fine roots	Above ground very fast soil C	Below ground very fast soil C	Above ground fast soil C	Below ground fast soil C	Medium soil C	Above ground slow soil C	Below ground slow soil C	SW stem snag	SW branch snag	HW stem snag	HW branch snag	Black C	peat	CO2	CH4	Resid. extract.	NO2	products
SW merchantable																	0.02													0.98
SW foliage													0.50															0.50		
SW other																		0.30			0.20							0.50		
SW sub-merch																		0.30			0.20							0.50		
SW coarse roots															0.40	0.60														
SW fine roots													0.40	0.60																
HW merchantable																	0.02													0.98
HW foliage													0.50															0.50		
HW other																		0.30					0.20					0.50		
HW sub-merch																		0.30					0.20					0.50		
HW coarse roots															0.40	0.60														
HW fine roots													0.40	0.60																
Above ground very fast soil C													1.00																	
Below ground very fast soil C														1.00																
Above ground fast soil C															1.00															
Below ground fast soil C																1.00														
Medium soil C																	1.00													
Above ground slow soil C																		1.00												
Below ground slow soil C																			1.00											
SW stem snag																				1.00										
SW branch snag																					1.00									
HW stem snag																						1.00								
HW branch snag																							1.00							
Black C																								1.00						
peat																									1.00					

DISTID 3b Salvage without clearcut	SW merchantable	SW foliage	SW other	SW sub-merch	SW coarse roots	SW fine roots	HW merchantable	HW foliage	HW other	HW sub-merch	HW coarse roots	HW fine roots	Above ground very fast soil C	Below ground very fast soil C	Above ground fast soil C	Below ground fast soil C	Medium soil C	Above ground slow soil C	Below ground slow soil C	SW stem snag	SW branch snag	HW stem snag	HW branch snag	Black C	peat	CO2	CH4	CO	NO2	products
SW merchantable	0.80																													0.20
SW foliage		0.80											0.20																	
SW other			0.80																		0.20									
SW sub-merch				0.80																	0.20									
SW coarse roots					0.80										0.05	0.15														
SW fine roots						0.80							0.05	0.15																
HW merchantable							0.80																							0.20
HW foliage								0.80					0.20																	
HW other									0.80														0.20							
HW sub-merch										0.80													0.20							
HW coarse roots											0.80				0.05	0.15														
HW fine roots												0.80	0.05	0.15																
Above ground very fast soil C													1.00																	
Below ground very fast soil C														1.00																
Above ground fast soil C															1.00															
Below ground fast soil C																1.00														
Medium soil C																	1.00													
Above ground slow soil C																		1.00												
Below ground slow soil C																			1.00											
SW stem snag																				1.00										
SW branch snag																					1.00									
HW stem snag																						1.00								
HW branch snag																							1.00							
Black C																								1.00						
peat																									1.00					

DISTID 4 Final cut	SW merchantable	SW foliage	SW other	SW sub-merch	SW coarse roots	SW fine roots	HW merchantable	HW foliage	HW other	HW sub-merch	HW coarse roots	HW fine roots	Above ground very fast soil C	Below ground very fast soil C	Above ground fast soil C	Below ground fast soil C	Medium soil C	Above ground slow soil C	Below ground slow soil C	SW stem snag	SW branch snag	HW stem snag	HW branch snag	Black C	peat	CO2	CH4	Resid. extract.	NO2	products
SW merchantable	0.02																0.01													0.97
SW foliage		0.03											0.97																	
SW other			0.03															0.27			0.20							0.50		
SW sub-merch				0.03														0.27			0.20							0.50		
SW coarse roots					0.03										0.37	0.60														
SW fine roots						0.03							0.37	0.60																
HW merchantable							0.02										0.01													0.97
HW foliage								0.03					0.97																	
HW other									0.03									0.27					0.20					0.50		
HW sub-merch										0.03								0.27					0.20					0.50		
HW coarse roots											0.03				0.37	0.60														
HW fine roots												0.03	0.37	0.60																
Above ground very fast soil C													1.00																	
Below ground very fast soil C														1.00																
Above ground fast soil C															1.00															
Below ground fast soil C																1.00														
Medium soil C																	1.00													
Above ground slow soil C																		1.00												
Below ground slow soil C																			1.00											
SW stem snag																				1.00										
SW branch snag																					1.00									
HW stem snag																						1.00								
HW branch snag																							1.00							
Black C																								1.00						
peat																									1.00					

Defor. to CL, GL, SL salvage uprooting and decay	SW merchantable	SW foliage	SW other	SW sub-merch	SW coarse roots	SW fine roots	HW merchantable	HW foliage	HW other	HW sub-merch	HW coarse roots	HW fine roots	Above ground very fast soil C	Below ground very fast soil C	Above ground fast soil C	Below ground fast soil C	Medium soil C	Above ground slow soil C	Below ground slow soil C	SW stem snag	SW branch snag	HW stem snag	HW branch snag	Black C	peat	CO2	CH4	Resid. extract.	NO2	products
SW merchantable																	0.15													0.85
SW foliage														1.00																
SW other															1.00															
SW sub-merch															1.00															
SW coarse roots															1.00															
SW fine roots														1.00																
HW merchantable																	0.15													0.85
HW foliage														1.00																
HW other															1.00															
HW sub-merch															1.00															
HW coarse roots															1.00															
HW fine roots														1.00																
Above ground very fast soil C														1.00																
Below ground very fast soil C														1.00																
Above ground fast soil C															1.00															
Below ground fast soil C															1.00															
Medium soil C																	1.00													
Above ground slow soil C																		1.00												
Below ground slow soil C																		1.00												
SW stem snag																	0.50													0.50
SW branch snag															1.00															
HW stem snag																	0.50													0.50
HW branch snag															1.00															
Black C																								1.00						
peat																									1.00					

Defor. to WL hydro-reservoir, salvage and decay	SW merchantable	SW foliage	SW other	SW sub-merch	SW coarse roots	SW fine roots	HW merchantable	HW foliage	HW other	HW sub-merch	HW coarse roots	HW fine roots	Above ground very fast soil C	Below ground very fast soil C	Above ground fast soil C	Below ground fast soil C	Medium soil C	Above ground slow soil C	Below ground slow soil C	SW stem snag	SW branch snag	HW stem snag	HW branch snag	Black C	peat	CO2	CH4	Resid. extract.	NO2	products
SW merchantable																	0.15													0.85
SW foliage														1.00																
SW other															1.00															
SW sub-merch															1.00															
SW coarse roots															1.00															
SW fine roots														1.00																
HW merchantable																	0.15													0.85
HW foliage														1.00																
HW other															1.00															
HW sub-merch															1.00															
HW coarse roots															1.00															
HW fine roots														1.00																
Above ground very fast soil C														1.00																
Below ground very fast soil C														1.00																
Above ground fast soil C															1.00															
Below ground fast soil C															1.00															
Medium soil C																	1.00													
Above ground slow soil C																		1.00												
Below ground slow soil C																		1.00												
SW stem snag																	0.50													0.50
SW branch snag															1.00															
HW stem snag																	0.50													0.50
HW branch snag															1.00															
Black C																								1.00						
peat																									1.00					

A 3.6.3 CBM verification – consistency with Tier 2 estimates

Biomass carbon stock changes in Forest Land remaining Forest Land (category 4.A.1) qualify as a key category in the Czech NIR/NID, similarly to other comparable countries. However, this is not the only reason considerable attention was paid to these estimates. The earlier country-specific Tier 2 (T2) methodology estimates for this category, used until NIR 2021, may serve to check the consistency of the currently used CBM-aided Tier-3 (T3) estimates. Both T2 and T3 approaches use the same basic activity data, such as forest areas, categorization by four major tree species, current annual increment, harvest intensity, and the fundamental species-specific tree biomass equations. Nevertheless, the implementation of these data and calculations differs substantially in these two approaches, and hence they can be considered fully independent.

Specifically, a comparison is presented here of carbon stock changes using three complementary statistical tests (all tests using Systat v. 13.2, Systat Inc., USA): namely, linear regression statistics, a two sample (group) t-test, and a paired t-test. The comparison includes the Tier 3 estimates aided by CBM of carbon stock changes in living biomass for the category 4.A.1 Forest Land remaining Forest Land as included in the former (NID 2025) submission, and the independent estimates by the Tier 2 methodology used earlier until NIR 2021 applied for the same period of 1990–2023 (n=34). The linear regression (Fig. A3 18) showed a tight, significant ($p<0.001$) relationship, with an adjusted coefficient of determination of $R^2=0.99$, and intercept and slope parameters of $p_1=22.2$ and $p_2=0.959$, respectively. The two samples were not statistically different by the two-sample t-test ($p=0.951$), meaning the difference between the samples was not large enough with respect to the overall data variability. Also, the more stringent paired t-test confirmed an insignifican difference of 27.5 kt C between the samples ($p=0.425$). Hence, this comparison between the T2 and T3 estimates provides overall confidence that the T2 and T3 approaches for estimating carbon stock changes in living biomass are comparable and consistent. This also applies to the absolute values, which do not differ substantially, especially with respect to the uncertainties related to the earlier T2 estimates (54% as reported in NIR 2021).



Fig. A3 18 A regression (and its statistics) between the estimates of carbon stock change in living biomass (Δ LB) by the Tier 2 (T2; x axis) approach as used until NIR 2021 and by the Tier 3 approach by CBM (T3; y axis) as implemented since NIR 2022 inventory submission.

A complementary, additional consistency check of biomass estimates by CBM was provided earlier in the NIR 2022 submission, Chapter 11(12), containing the final accounting of the former KP LULUCF activities. It includes an evaluation of Tier 2 (NIR 2021) and Tier 3 (CBM, NIR 2022) estimates for total carbon stock changes for the LULUCF activities of Afforestation/Reforestation, Deforestation and Forest Management.

These include both living biomass and – where applicable – DOM carbon pools of litter and deadwood, and mineral soil. Chapter 12.3.1.4 of the NIR 2022 submission summarized the effect of implementing Tier 3 estimates aided by CBM for the former KP LULUCF activities AR and D relative to the carbon stock estimates by Tier 2 methods used until NIR 2021. It stated that there were no significant differences for AR when comparing the independent estimates applicable for all carbon pools except soil (which was methodologically unchanged). Similarly, a tight correspondence was found between the two (Tier 3 and Tier 2) estimates of carbon stock changes under D events. These checks provided a coherency substantiation for both living biomass and dead organic matter (litter and deadwood) carbon pools. That submission (NIR 2022) and the final carbon and emission accounting under KP were endorsed by the UNFCCC review (see the Czech ARR 2022).

A 3.6.4 CBM verification – consistency with spatially stratified CBM runs



Fig. A3 19 Selected input data for the spatially stratified CBM run: species composition and harvest intensity by CZ NUTS3 regions and individual years 2010 to 2021, including the information of total harvest (salvage and planned, upper right), forest share (%, bottom left), and volume quantity of standing stock as of 2021 (bottom right). Abbreviation of species groups: SP – spruce, BE – beech, PI – pine, OA – oaks, AP - silver fir, OLB – other long-lived broadleaves, OSB – other short-lived broadleaves.

A different type of consistency check for the CBM estimates was conducted for the earlier NIR (2023) and is still retained here. Namely, we checked the default CBM estimate as described in that inventory report against estimates originating from a regionally stratified CBM simulation using the *Nomenclature des Unités Territoriales Statistiques* CZ-NUTS3 country categorization of 14 regions (IFER 2022). At the same time, instead of four species strata as used in the default CBM run, we used a more detailed categorization using seven species groups – in addition to beech, oak, pine and spruce, we discerned fir, other long-lived broadleaves and short-lived broadleaves tree categories. This resulted in 98 'species group by region' combinations. That study (Cienciala and Melichar 2022) covered the period from 2010 to 2030, of which

2010–2021 also included explicit available input data coherent with those used in the comparable earlier emission inventory (NIR 2023). Aside from the more detailed spatial and tree species stratification, the study of Cienciala and Melichar (2022) differed in base-year data, using the year 2010 for calibration of the growth curves (A3-16) as well as for the initial state of the forest resources (growing stock by age classes for the strata used), while the default NIR calibration year was 2004 and the starting state of forest resources was 1990. Next, the harvest intensity was specific for each region and species (Fig. A3 19). This fundamental model input set-up makes the two runs suitable for a consistency check.

The two model estimates for the components of aboveground biomass (AGB) and belowground biomass (BGB) carbon stock changes are shown in Fig. A3 20. There was a very strong correlation between these two independent CBM estimates (R^2=1 in both cases). There were no significant differences in the means as shown by the two-sample t-test (p=0.909), though the paired t-test did identify a small mean difference of -129.7 kt C/year for total living biomass (AGB+BGB). This is, relative to the quantities concerned, a fractional difference that is explained mostly (but not only) by differences in handling of increments in the two model set-ups. Hence, this consistency check also indicates the robustness of the CBM set-up and consistency in its performance.



Fig. A3 20 A two CBM model runs estimating AGB and BGB carbon pool changes for the period 2010–2021 – comparing the outputs of the default run for Forest Management (FM) with the spatially distributed CBM set-up that also used a different species stratification and calibration year for increment. The two runs (FM vs. Distributed) are barely graphically distinguishable, as the results for AGB and BGB mostly overlap (retained from NIR 2023).

A 3.6.5 Additional verification for DOM and soil carbon pools

As noted in the current NID Chapter 6.4.6, the inventory team is currently adopting new activity data from sample-based National Forest Inventory (NFI) and its recently conducted third campaign (NFI3, Máslo et al. 2023). These data will serve as a basis for a revised CBM-CFS3 model calibration at NUTS3 spatial resolution reassessing carbon stock changes in forestry. This would represent a major revision of the current inventory for the land-use categories involving Forest land. It would also marginally affect the non-forest land use categories due to changes associated with re-attributing land-use areas containing forest by FAO definition (NFI standard).

The above changes and new empirical evidence allow for more rigorous verification of DOM carbon pools, including deadwood and litter. For example, the very recently released NFI results on deadwood (Máslo et al. 2024) contain information on standing and lying deadwood at NUTS3 spatial resolution. We have

indicatively used these data to cross-check the current estimates of aboveground deadwood by CBM-CFS3 (Fig. A3 21). The model estimates are shown for the period 2011–2023, and the observations tentatively recalculated from the reported data on deadwood volume from NFI (Máslo et al. 2024) are also included. We note that the estimated carbon must consider the likely decomposition characteristics. As the data on decomposition categories were not available, we used the reported share of decomposition categories from the project CzechTerra (Černý et al. 2015, Cienciala et al. 2015). Based on these outputs, we applied a reduction coefficient of 0.8 and 0.6 to account for the respiratory losses of the deadwood components standing dead trees and lying deadwood components, respectively. Fig. A3 21 suggests a good match between the model run and the observed data (retained from NID 2025).



Fig. A3 21 A crosscheck of the modelled aboveground deadwood carbon pool (bars) by CBM-CFS3 and the comparative deadwood carbon stock (lines) including standing dead trees, aboveground part of stumps and lying deadwood, that were tentatively estimated from the observed mean merchantable volume from the NFI2 and NFI3 campaigns (Máslo et al. 2024).

At the same time, the verification of DOM pools remains provisional. There are several issues with the tentative comparison that need to be addressed. Specifically, the volume conversion to biomass and carbon units requires better information on decomposition, which can be retrieved from decomposition categories for individual deadwood carbon pools. Secondly, carbon pools as defined in the models must be carefully aligned with measurable information from NFI sampling. Next to consider, due to the extreme development of spruce dieback in recent years (specifically 2017–2020, as described in the main text of the chapter on LULUCF), the comparison must specifically consider time attribution of standing deadwood and delayed harvest during the most challenging calamity years. Finally, there is an ongoing effort at JRC to recalibrate the base decay rates used in the CBM-CFS3 model with the available empirical observation across European countries (V. Blujdea, personal communication Jan. 2025) that may further constrain the uncertainty associated with DOM carbon pools. The LULUCF inventory team will address these issues in more detail in the coming NID submissions (2027) in line with the ongoing recalibration of the model using the available NFI data in collaboration with the experts from the Czech Forestry Institute (CFI), Brandýs n. Labem (Chapter 6.4.6), which collects and processes the NFI data and prepares the repoting on forests to FAO and Forest Europe.

Regarding the soil carbon pool, the inventory team already implemented the interim results of the current project funded by the Technology Agency of the Czech Republic (SS06010148) that revised the available activity data on forest soil carbon stock in the country, including organic (FHO litter layers) and mineral (30 cm) soil. Further tuning and verification of the calibrated CBM-CFS3 as used in the Czech emission inventory for all DOM pools including soil will be conducted once the relevant results of the NFI4 campaing will become available.

A 3.7 Collection of F-gases activity data in the Czech Republic

Emissions of F-gases (HFCs, PFCs, SF_6, NF_3) in the Czech Republic are at relatively low levels due to the absence of large industrial sources. Furthermore, all F-gases in the Czech Republic are imported, so there are no fugitive emissions from manufacturing. For the needs of inventory, three independent data sources are used. A methodology of data verification utilized to prevent duplicate values is described in this chapter.

The methodology is divided into three parts. The first describes the sources of F-gas activity data available in the Czech Republic. The second introduces a designed process of data verification, particularly a comparison of data sources. And the last describes an automatic system of data sorting according to their area of application.

A 3.7.1 Description of data sources

For the inventory, three sources of activity data are used:

- ISPOP (the "Integrated system of reporting obligations"),
- F-gas register (a questionnaire on the production, import, export, feedstock use, and destruction of the substances listed in Annexes I or II of the F-gas regulation),
- Custom data (a database on the cross-border movements of goods).

ISPOP provides data about the import, export and disposal of F-gases considering the EU market. The reporting obligation is enshrined in Act No. 73/2012. The threshold for submitting data to ISPOP by importers, exporters and users is 200 t CO_2 eq. of F-gases. Manufacturers do not report those F-gases that are already charged into equipment. In ISPOP, only base gases are reported. If manufacturers need to report blends of F-gases, they have to calculate the amount of each F-gas contained therein.

Elementary reported information contains:

- the name of the company,
- the type of the activity (Import, Export, Disposal),
- the name of the F-gas,
- the amount of the gas [kg],
- the amount of the gas [t CO_2 eq.],
- the dispatch country / destination country (not disposed gases),
- the name of the company which handed over the F-gas for destruction (only for disposed gases).

The F-gas register provides data about imported, exported and disposed amounts of F-gases. The reporting obligation is enshrined in EU regulation No. 517/2014. Information in the F-gas register is related to the trade between EU countries and non-EU countries. The threshold for submitting data to the F-gas register is more than 1 t of F-gases or 1 000 t of CO_2 eq. of F-gases. This threshold refers to the sum of F-gases, not each imported/exported F-gas separately.

Two types of report can be distinguished. In the first the amount of bulk F-gases is reported, while in the second the amount of equipment containing F-gases is reported. In the second type of report, information about the average specific charge into equipment is also included.

Elementary reported information contains:

- the name of the company,
- the type of activity (Import, Export, Disposal),
- the name of the F-gas,
- the amount of the F-gas [t],
- the area of the application,
- the number of products (only for F-gases in equipment),
- the average charging amount (only for F-gases in equipment).

Custom data provides information about the movement of goods across the borders of the Czech Republic. The Czech Statistical Office is responsible for this database. These data provide information about imported and exported F-gases that are classified according to the combined nomenclature, which is regularly updated. Thanks to the latest update, performed in 2024, comparisons of the database with other sources are now more accurate.

Reporting rules are different for movement within the EU and for movement from/to non-EU countries; the first is covered by the Intrastat system, and the second by the Extrastat system.

In **Intrastat**, the movement of Union goods between Member States of the European Union is monitored. The reporting obligation is enshrined in EC regulation No. 638/2004. Data are provided by companies (reporting units) who reached a threshold 12 million CZK of traded goods, which is calculated from the beginning of each year. If a company reaches the threshold for the first time, they start to provide their data from the beginning of the month when they reached the threshold (CzSO 2020b).

Extrastat is based on collecting data from customs declarations (Single Administrative Documents - SADs) (CzSO 2020b). Any trade with a non-EU country must be reported in these documents, therefore the import and export of bulk F-gases (specified in combined nomenclature) is covered.

Elementary reported information contains:

- the name of the company,
- the type of activity (Import, Export),
- the name of the F-gas,
- the amount of the F-gas [kg],
- the name of the country of origin.

A 3.7.2 Comparison of the data sources

It can be seen from the description of sources that the data from the Intrastat and ISPOP, and the Extrastat and F-gas registers can partially overlap. However, since the reporting conditions slightly differ and each company applies its own reporting approach, the sources do not overlap completely. This highlighted the need for a sorting system. Therefore, a mathematical model was designed, with all available data imported into the model and compared. Finally, data from all sources are summed together.

Comparison of ISPOP and Intrastat data

While comparing ISPOP and Intrastat data, there are some issues that need to be noted:

- In ISPOP information about base gases is reported, while in Intrastat mainly blends are reported,

- in the case of imported goods, in ISPOP information about the country of dispatch is provided, while in Intrastat information about the country of origin is provided,
- in Intrastat, data can be reported only for part of the year and not for the whole year.

Because of these issues, the comparison of the two data sources is rather complicated. To help solve this, the largest importers of F-gases, the Kovoslužba and Schiessl companies, were contacted and provided more detailed information. Kovoslužba declared that the data reported to Instastat comes from the same sources as the data reported to ISPOP, thus differences are caused only by the issues mentioned above. In the case of Schiessl, there is another issue that results in differences between Intrastat and ISPOP data. Their company in the Czech Republic is a central distribution center for the Czech Republic, Slovakia, Germany and Austria, therefore in ISPOP gases are reported that are distributed not only to the Czech Republic but to all these countries. According to the information provided, the amounts of F-gases that are placed on the Czech market are reported as imported goods in Intrastat.

The final system of data comparison and selection was based on a detailed data analysis of the largest importers and on information provided by selected companies. Preference is given in the system to data from ISPOP (except for data from Schiessl), since it is ensured that companies provide data for the whole year and that any existing F-gas can be reported, whereas in Intrastat only F-gases from combined nomenclature can be reported. Therefore, only data where there is no risk of duplication are selected from Intrastat according to the following procedure.

The data from Intrastat are divided into three groups:

1. pure HFC gases.
2. blends of HFC gases;
3. unspecified gases (for the need of the inventory) – these are not considered.

Then, each value in Intrastat is compared with data from ISPOP, and it is determined whether the company reports in ISPOP and whether it reports the given gas. As can be seen, only pure HFC gases can be fully compared with ISPOP data. Therefore, different scenarios are made for every situation that may arise, as shown in Table A3 15.

Tab. A3 16 Overview of possible situations and their solutions

Will the value be taken into count?	Can the company be found in ISPOP? / Does the company report the given gas?		
	YES / YES	YES / NO	NO / NO
HFC gases	×	✓	✓
blends	NA	×	✓
unspecified gases	NA	×	×

Except for data from Schiessl, every gas reported in Intrastat – import is considered.

Comparison of F-gas register and Extrastat data

In the case of the F-gas register and Extrastat, differences between these databases do not cause serious issues for the purposed considered here. Their comparison is therefore less complicated than for ISPOP and Intrastat and gives accurate results despite the fact that there are fewer criteria that can be compared between these two sources. Since only a few companies report exported F-gases to non-EU countries, data sources can be compared using only a visual check. The comparison process described below is thus only meant for import.

Comparison process:

1. A search for potential duplicate values is performed for the F-gas register database

   For each value in the F-gas register, a potential duplicate value in Extrastat is searched according to the following criteria:

   - The name of the company
   - The name of the gas or blend

2. Comparisons of found values

   If the value in F-gas register and value found from Extrastat are the same, they are automatically considered to be duplicates. If values differ, the decision is based on expert judgment.

3. Removal of duplicates

   Duplicate values are excluded from calculations of overall values from the F-gas register.

Since data sources provide information not only about the amount of F-gases but also some additional information, several options for data sorting by application have been devised, generally based on two principles. The first, used for all data sources, is based on information about the companies. Some reporting companies are distributors of products containing F-gases, and according to the type of products they offer, the area of F-gas application can be identified. The second principle is according to the area of application itself. This is only applicable to the F-gas register, since manufacturers only directly provide information about the area of application in this register.

Based on these principles, F-gases are automatically sorted into three groups:

1. F-gases used for mobile air conditioning (CRT category 2.F.1.e)
2. F-gases used for fire protection (CRT category 2.F.3)
3. Other F-gases

As can be seen, there is still a large group of unsorted F-gases remaining, and more detailed research will be needed to sort these F-gases. However, based on the data available, activity data could be recalculated back to the year 2016 (the year when the combined nomenclature classification was updated, allowing custom data to be fully compared).

The calculation of F-gas consumption is now more accurate, and a risk of potential calculation errors is reduced. As can be seen from Figure A3 21 with values from 2018, the largest amount of data on the share



of consumed F-gases are from ISPOP. The graph also shows the amount of F-gases excluded from the calculation of total consumption.

Fig. A3 22 Amounts of imported and exported F-gases in 2018 divided according to the data sources

Due to the system described above, the risk of double counting is eliminated to a minimum. Furthermore, F-gases within CRT category 2.F.1.e and 2.F.3 are automatically sorted. Since the F-gas activity data are more accurate, F-gas emissions estimates are more accurate as well.

A 3.8 Agricultural soils (ETF 3D) – additional information on climatic analysis

From Submission 2025, N_2O emissions from agricultural land management are estimated and analyzed using the Tier 2 approach of the IPCC 2019 Guidelines. The newly designed estimate considers the regional climate conditions of the given year. For estimates of N_2O emissions from nitrogen fertilizer application to agricultural land, it is important to determine whether the application occurs in a wet or dry climate zone. The climate classification procedure for individual zones is prescribed by the IPCC (IPCC 2019) in Chapter 3, Volume 4 (AFOLU). The classification is based on data including average annual temperature, total precipitation, number of days with temperatures below 0°C, and the ratio between annual total precipitation and potential evapotranspiration.

CzechGlobe prepared an analysis of climatic conditions in the Czech Republic for the period 1990–2024, which enabled the specification of agricultural land areas falling into wet or dry climate zones. Due to the geographical location of the Czech Republic and the topographical complexity of its territory, climatic conditions change significantly from year to year (Tab. A3 18 - Tab. A3 21, Fig. A3 23 - Fig. A3 26). This has a significant impact on the use of synthetic and organic fertilizers and consequently on N_2O emissions.

For each reporting year, emission factors were derived considering the proportion of agricultural land corresponding to wet and dry climate zones in that specific year.

Climatic analyses were also prepared for long-term averages in accordance with IPCC 2019 methodological requirements (Tab. A3 17). Results show that, based on long-term averages, the territory of the Czech Republic is equally distributed between wet and dry zones. However, agricultural experts note that long-term climatic averages mask annual fluctuations in nitrogen fertilizer application.

Tab. A3 17 Czech Republic agricultural land climate zones, long-term average for different period [%]

Year	Warm Temperate		Cool Temperate		Temperate	Temperate
	Moist	Dry	Moist	Dry	Moist	Dry
			[%]			
1985–2015		1.00	53.68	45.32	53.68	46.32
1991–2020		5.06	47.36	47.58	47.36	52.64
2000–2020	0.09	10.95	47.17	41.79	47.26	52.74

**Data source: Global Change Research Institute AS CR, v. v. i. (GCRI, CzechGlobe)*



Fig. A3 23 ***Distribution of wet and dry climatic zones in the territory of the Czech Republic in years 1990–1999***

Tab. A3 18 Czech Republic agricultural land climate zones, percentile representation 1990–1999 [%]

Year	Warm Temperate		Cool Temperate		Temperate	Temperate
	Moist	Dry	Moist	Dry	Moist	Dry
			[%]			
1990		5.80	22.13	72.08	22.13	77.88
1991			38.68	61.32	38.68	61.32
1992		10.46	16.87	72.66	16.87	83.12
1993		0.01	44.65	55.34	44.65	55.35
1994	0.10	18.72	32.76	48.42	32.86	67.14
1995		0.41	75.90	23.69	75.90	24.10
1996			78.75	21.25	78.75	21.25
1997			57.40	42.60	57.40	42.60
1998		2.68	49.53	47.79	49.53	50.47
1999	0.04	5.76	33.38	60.82	33.42	66.58

**Data source: Global Change Research Institute AS CR, v. v. i. (GCRI, CzechGlobe)*



Fig. A3 24 ***Distribution of wet and dry climatic zones in the territory of the Czech Republic in years 2000–2009***

Tab. A3 19 Czech Republic agricultural land climate zones, percentile representation 2000–2009 [%]

Year	Warm Temperate		Cool Temperate		Temperate	Temperate
	Moist	Dry	Moist	Dry	Moist	Dry
			[%]			
2000	1.48	27.12	41.24	30.16	42.72	57.28
2001		0.06	84.46	15.48	84.46	15.54
2002	2.60	8.68	76.50	12.22	79.10	20.90
2003		4.69	5.94	89.37	5.940	94.06
2004		0.08	49.78	50.15	49.78	50.23
2005		0.05	57.79	42.17	57.79	42.22
2006		2.19	53.86	43.95	53.86	46.14
2007	2.14	25.39	48.83	23.64	50.97	49.03
2008	0.79	19.93	29.14	50.14	29.93	70.07
2009	0.07	8.66	62.71	28.56	62.78	37.22

**Data source: Global Change Research Institute AS CR, v. v. i. (GCRI, CzechGlobe)*



Fig. A3 25 Distribution of wet and dry climatic zones in the territory of the Czech Republic in years 2010–2019

Tab. A3 20 Czech Republic agricultural land climate zones, percentile representation 2010–2019 [%]

Year	Warm Temperate		Cool Temperate		Temperate	Temperate
	Moist	Dry	Moist	Dry	Moist	Dry
			[%]			
2010			98.55	1.45	98.55	1.45
2011	0.01	8.74	33.84	57.41	33.85	66.15
2012		7.17	46.39	46.44	46.39	53.61
2013		0.85	77.80	21.36	77.80	22.21
2014	6.98	31.91	44.59	16.52	51.57	48.43
2015	0.05	41.86	8.64	49.44	8.69	91.30
2016	0.32	13.13	36.57	49.98	36.89	63.11
2017	0.11	10.94	39.76	49.19	39.87	60.13
2018	0.17	51.10	5.79	42.93	5.96	94.03
2019	3.60	41.93	19.09	35.38	22.69	77.31

**Data source: Global Change Research Institute AS CR, v. v. i. (GCRI, CzechGlobe)*



Fig. A3 26 ***Distribution of wet and dry climatic zones in the territory of the Czech Republic in years 2020–2024***

Tab. A3 21 Czech Republic agricultural land climate zones, percentile representation 2020–2024 [%]

Year	Warm Temperate		Cool Temperate		Temperate	Temperate
	Moist	Dry	Moist	Dry	Moist	Dry
	[%]					
2020	7.90	20.93	51.52	19.64	59.42	40.57
2021	0.01	3.12	57.18	39.69	57.19	42.81
2022	1.73	37.39	25.70	35.18	27.43	72.57
2023	15.85	46.09	32.63	5.43	48.48	51.52
2024	27.68	45.56	25.82	0.94	53.50	46.50

**Data source: Global Change Research Institute AS CR, v. v. i. (GCRI, CzechGlobe)*

Annex 4 The national energy balance for the most recent inventory year

A 4.1 Energy balance

Following tables present energy balance for the Czech Republic for 2024.

Tab. A4 1 Energy balance for solid fuels 2024

SOLID FUELS	Coking Coal [kt/year]	Bituminous Coal [kt/year]	Lignite/Brown Coal [kt/year]	Coke Oven Coke [kt/year]	Coal Tar [kt/year]
Indigenous Production	612	739	23 681	1 366	57
Total Imports (Balance)	1 819	976	5	256	232
Total Exports (Balance)	540	877	210	589	5
International Marine Bunkers	0	0	0	0	0
Stock Changes (National Territory)	-60	285	1 118	46	-10
Inland Consumption (Calculated)	1 830	1 295	24 594	1 080	274
Statistical Differences	149	-19	167	3	
Transformation Sector	1 681	1 154	22 699	896	1
Main Activity Producer Electricity Plants	0	378	17 092	0	0
Main Activity Producer CHP Plants	0	545	4 236	0	0
Main Activity Producer Heat Plants	0	3	58	0	0
Autoproducer Electricity Plants	0	0	0	0	0
Autoproducer CHP Plants	0	2	966	0	1
Autoproducer Heat Plants	0	0	23	0	0
Patent Fuel Plants (Transformation)	0	0	0	0	0
Coke Ovens (Transformation)	1 681	0	0	99	0
BKB Plants (Transformation)	0	0	299	0	0
Gas Works (Transformation)	0	0	26	0	0
Blast Furnaces (Transformation)	0	227	0	797	0
Coal Liquefaction Plants (Transformation)	0	0	0	0	0
Non-specified (Transformation)	0	0	0	0	0
Energy Sector	0	0	214	0	0
Own Use in Electricity, CHP and Heat Plants	0	0	0	0	0
Coal Mines	0	0	214	0	0
Patent Fuel Plants (Energy)	0	0	0	0	0
Coke Ovens (Energy)	0	0	0	0	0
BKB Plants (Energy)	0	0	0	0	0
Gas Works (Energy)	0	0	0	0	0
Blast Furnaces (Energy)	0	0	0	0	0
Petroleum Refineries	0	0	0	0	0
Coal Liquefaction Plants (Energy)	0	0	0	0	0
Non-specified (Energy)	0	0	0	0	0
Distribution Losses	0	0	4	0	0
Total Final Consumption	0	159	1 508	181	273
Total Non-Energy Use	0	6	0	0	273
Final Energy Consumption	0	154	1 508	181	0
Industry Sector	0	92	816	175	0
Iron and Steel	0	0	10	116	0
Chemical (including Petrochemical)	0	0	648		0
Non-Ferrous Metals	0	0	0	4	0
Non-Metallic Minerals	0	75	4	45	0
Transport Equipment	0	0	7	0	0
Machinery	0	0	6	1	0
Mining and Quarrying	0	0	0	0	0
Food, Beverages and Tobacco	0	16	78	8	0
Paper, Pulp and Printing	0	0	58		0
Wood and Wood Products	0	0	0		0
Construction	0	0	1		0

SOLID FUELS	Coking Coal [kt/year]	Bituminous Coal [kt/year]	Lignite/Brown Coal [kt/year]	Coke Oven Coke [kt/year]	Coal Tar [kt/year]
Textiles and Leather	0	0	1	0	0
Non-specified (Industry)	0	0	2	0	0
Transport Sector	0	0	0	0	0
Other Sectors	0	61	692	6	0
Commercial and Public Services	0	0	22	0	0
Residential	0	60	657	6	0
Agriculture/Forestry	0	0	12	0	0
Fishing	0	0	0	0	0
Non-specified (Other)	0	0	0	0	0

Tab. A4 2 Energy balance for solid fuels 2024

SOLID FUELS	BKB-PB [kt/year]	Gas Works Gas [TJ/year]	Coke Oven Gas [TJ/year]	Blast Furnace Gas [TJ/year]	Other Recovered Gases [TJ/year]
Indigenous Production	168	0	10 812	9 144	3 831
Total Imports (Balance)	116	0	0	0	0
Total Exports (Balance)	127	0	0	0	0
International Marine Bunkers	0	0	0	0	0
Stock Changes (National Territory)		0	0	0	0
Inland Consumption (Calculated)	157	0	10 812	9 144	3 831
Statistical Differences	2.7	0	2	-2	1
Transformation Sector	0	0	3 919	2 957	884
Main Activity Producer Electricity Plants	0	0	0	0	0
Main Activity Producer CHP Plants	0	0	3 919	2 957	663
Main Activity Producer Heat Plants	0	0	0	0	0
Autoproducer Electricity Plants	0	0	0	0	0
Autoproducer CHP Plants	0	0	0	0	222
Autoproducer Heat Plants	0	0	0	0	0
Patent Fuel Plants (Transformation)	0	0	0	0	0
Coke Ovens (Transformation)	0	0	0	0	0
BKB Plants (Transformation)	0	0	0	0	0
Gas Works (Transformation)	0	0	0	0	0
Blast Furnaces (Transformation)	0	0	0	0	0
Coal Liquefaction Plants (Transformation)	0	0	0	0	0
Non-specified (Transformation)	0	0	0	0	0
Energy Sector	0	0	4 122	5 245	0
Own Use in Electricity, CHP and Heat Plants	0	0	0	0	0
Coal Mines	0	0	0	0	0
Patent Fuel Plants (Energy)	0	0	0	0	0
Coke Ovens (Energy)	0	0	4 122	1 442	0
BKB Plants (Energy)	0	0	0		0
Gas Works (Energy)	0	0	0		0
Blast Furnaces (Energy)	0	0	0	3 803	0
Petroleum Refineries	0	0	0		0
Coal Liquefaction Plants (Energy)	0	0	0		0
Non-specified (Energy)	0	0	0		0
Distribution Losses		0	178	352	256
Total Final Consumption	154	0	2 591	592	2 689
Total Non-Energy Use	0	0	0	0	681
Final Energy Consumption	154	0	2 591	592	2 008
Industry Sector	66	0	2 591	592	2 008
Iron and Steel	0	0	2 508	589	765
Chemical (including Petrochemical)	0	0	0	0	1 237
Non-Ferrous Metals	0	0	0	0	0
Non-Metallic Minerals	54	0	84	0	6
Transport Equipment		0	0	0	0
Machinery	0	0	0	3	0
Mining and Quarrying	7	0	0	0	0

SOLID FUELS	BKB-PB [kt/year]	Gas Works Gas [TJ/year]	Coke Oven Gas [TJ/year]	Blast Furnace Gas [TJ/year]	Other Recovered Gases [TJ/year]
Food, Beverages and Tobacco		0	0	0	0
Paper, Pulp and Printing		0	0	0	0
Wood and Wood Products		0	0	0	0
Construction	5	0	0	0	0
Textiles and Leather	0	0	0	0	0
Non-specified (Industry)	0	0	0	0	0
Transport Sector	0	0	0	0	0
Other Sectors	88	0	0	0	0
Commercial and Public Services	2	0	0	0	0
Residential	86	0	0	0	0
Agriculture/Forestry	0	0	0	0	0
Fishing	0	0	0	0	0
Non-specified (Other)	0	0	0	0	0

Tab. A4 3 Energy balance for Crude Oil, Refinery Gas and Additives/Oxygenates for 2024

LIQUID FUELS	Crude Oil [kt/year]	Refinery Feedstocks [kt/year]	Additives Oxygenates [kt/year]
Indigenous Production	69		2
From Other Sources			476
From Other Sources - Solid fuels			
From Other Sources - Natural Gas			
From Other Sources - Renewables			476
Backflows		115	
Primary Product Receipts			
Refinery Gross Output			
Inputs of Recycled Products			
Refinery Fuel			
Total Imports (Balance)	6 501		
Total Exports (Balance)			
International Marine Bunkers			
Interproduct Transfers			
Products Transferred		80	
Direct Use			435
Stock Changes (National Territory)	-1		1
Refinery Intake (Calculated)	6 569	195	44
Gross Inland Deliveries (Calculated)	0		
Statistical Differences	0	0	0
Gross Inland Deliveries (Observed)	0	0	
Refinery Intake (Observed)	6 569	195	44

Tab. A4 4 Energy balance for liquid fuels 2024

LIQUID FUELS	Refinery Gas [kt/year]		LPG [kt/year]		Naphtha [kt/year]		Motor Gasoline* [kt/year]		Biogasoline [kt/year]		Aviation Gasoline [kt/year]	
Refinery Gross Output	141		387		860		1 421		0		0	
Refinery Fuel	123		0		0		0		0		0	
Total Imports (Balance)	0		117		47		709		22		2	
Total Exports (Balance)	0		98		57		513		43		0	
International Marine Bunkers	0		0		0		0		0		0	
Stock Changes (National Territory)	0				4		10		4		0	
Gross Inland Deliveries (Calculated)	18		406		854		1 787		143		2	
Statistical Differences	0		0		0		1 787		0		0	
Gross Inland Deliveries (Observed)	18		406		854				143		2	
Refinery Intake (Observed)	0		0		0		0		0		0	
Non-energy use in Petrochemical industry	0		180		854		0		0		0	
	Energy Use	Non Energy Use	Energy Use	Non Energy Use	Energy Use	Non Energy Use	Energy Use	Non Energy Use	Energy Use	Non Energy Use	Energy Use	Non Energy Use
Transformation Sector	18	0	8	0	0	0	0	0	0	0	0	0
Main Activity Producer Electricity Plants												
Autoproducer Electricity Plants												
Main Activity Producer CHP Plants	18		7									
Autoproducer CHP Plants												
Main Activity Producer Heat Plants												
Autoproducer Heat Plants			1									
Gas Works (Transformation)												
For Blended Natural Gas												
Coke Ovens (Transformation)												
Blast Furnaces (Transformation)												
Petrochemical Industry												
Patent Fuel Plants (Transformation)												
Non-specified (Transformation)												
Energy Sector	0	0	0	0	0	0	0	0	0	0	0	0
Coal Mines												
Oil and Gas Extraction												
Coke Ovens (Energy)												
Blast Furnaces (Energy)												
Gas Works (Energy)												
Own Use in Electricity, CHP and Heat Plants												
Non-specified (Energy)												
Distribution Losses												
Total Final Consumption	0	0	218	180	0	854	1 787	0	143	0	2	0
Transport Sector	0	0	89	0	0	0	1 787	0	143	0	2	0
International Aviation												
Domestic Aviation											2	
Road			89				1 787		143			
Rail												
Domestic Navigation												
Pipeline Transport												
Non-specified (Transport)												
Industry Sector	0	0	61	180	0	854	0	0	0	0	0	0
Iron and Steel												
Chemical (including Petrochemical)			5	180		854						
NonFerrous Metals												
NonMetallic Minerals			4									
Transport Equipment			3									
Machinery			9									
Mining and Quarrying												
Food, Beverages and Tobacco			8									
Paper, Pulp and Printing			3									
Wood and Wood Products			4									
Construction			5									
Textiles and Leather			3									
Non-specified (Industry)			17									
Other Sectors	0	0	68	0	0	0	0	0	0	0	0	0
Commercial and Public Services			9									
Residential			51									
Agriculture/Forestry			8									
Fishing												
Non-specified (Other)												

*Sum of Biogasoline and Motor gasoline.

Tab. A4 5 Energy balance for liquid fuels 2024

LIQUID FUELS	Kerosene Type Jet Fuel [kt/year]		Other Kerosene [kt/year]		Transport Diesel** [kt/year]		Biodiesel [kt/year]		Heating and Other Gasoil [kt/year]		Residual Fuel Oil [kt/year]	
Refinery Gross Output	286		0		2 658		0		76		102	
Refinery Fuel	0		0		0		0		0		0	
Total Imports (Balance)	157		2		3 017		51		32		5	
Total Exports (Balance)			0		633		34		3		65	
International Marine Bunkers	0		0		0		0		0		0	
Stock Changes (National Territory)	4		0		-15		7		-2		18	
Gross Inland Deliveries (Calculated)	447		2		5 316		299		89		60	
Statistical Differences	447		0		0		0		0		60	
Gross Inland Deliveries (Observed)	0		2		5 316		299		89		0	
Refinery Intake (Observed)	0		0		0		0		0		0	
Non-energy use in Petrochemical industry	0		0		0		0		0		0	
	Energy Use	Non Energy Use	Energy Use	Non Energy Use	Energy Use	Non Energy Use	Energy Use	Non Energy Use	Energy Use	Non Energy Use	Energy Use	Non Energy Use
Transformation Sector	0	0	0	0	0	0	0	0	6	0	6	0
Main Activity Producer Electricity Plants												0
Autoproducer Electricity Plants									0			0
Main Activity Producer CHP Plants									2		4	0
Autoproducer CHP Plants									2		0	0
Main Activity Producer Heat Plants									1		2	0
Autoproducer Heat Plants									1		0	0
Gas Works (Transformation)											0	0
For Blended Natural Gas											0	0
Coke Ovens (Transformation)											0	0
Blast Furnaces (Transformation)											0	0
Petrochemical Industry											0	0
Patent Fuel Plants (Transformation)											0	0
Non-specified (Transformation)											0	0
Energy Sector	0	0	0	0	2	0	0	0	0	0	0	0
Coal Mines					2						0	0
Oil and Gas Extraction											0	0
Coke Ovens (Energy)											0	0
Blast Furnaces (Energy)											0	0
Gas Works (Energy)											0	0
Own Use in Electricity, CHP and Heat Plants											0	0
Non-specified (Energy)											0	0
Distribution Losses											0	0
Total Final Consumption	454	0	2	0	5 314	0	299	0	83	0	54	0
Transport Sector	440	0	0	0	4 951	0	275	0	73	0	0	0
International Aviation	434										0	0
Domestic Aviation	6										0	0
Road					4 948		270				0	0
Rail							5		73		0	0
Domestic Navigation					3						0	0
Pipeline Transport											0	0
Non-specified (Transport)											0	0
Industry Sector	0	0	0	0	40	0	3	0	8	6	42	0
Iron and Steel											0	0
Chemical (including Petrochemical)										6	2	0
Non-Ferrous Metals												0
Non-Metallic Minerals									2		6	0
Transport Equipment											3	0
Machinery									2		4	0
Mining and Quarrying											5	0
Food, Beverages and Tobacco									1		4	0
Paper, Pulp and Printing									0		4	0
Wood and Wood Products									1		5	0
Construction					38		3		2		5	0
Textiles and Leather												0
Non-specified (Industry)					2						4	0
Other Sectors	14	0	2	0	323	0	21	0	2	0	12	0
Commercial and Public Services	3				7				1		6	0
Residential											0	0
Agriculture/Forestry					307		21		1		6	0
Fishing											0	0
Non-specified (Other)	11		2		9						0	0

**Sum of Biodiesel and Transport diesel.

Tab. A4 6 Energy balance for liquid fuels 2024

LIQUID FUELS	White Spirit SBP [kt/year]		Lubricants [kt/year]		Bitumen [kt/year]		Paraffin Wax [kt/year]		Petroleum Coke [kt/year]		Other Products [kt/year]	
Refinery Gross Output	0		15		441		3		93		464	
Refinery Fuel	0		0		0		0		93		0	
Total Imports (Balance)	14		173		318		14		8		101	
Total Exports (Balance)	0		45		269		3		2		73	
International Marine Bunkers	0		0		0		0		0		0	
Stock Changes (National Territory)	0				0		0		0			
Gross Inland Deliveries (Calculated)	13		143		489		14		6		427	
Statistical Differences	0		0		0		0		0		0	
Gross Inland Deliveries (Observed)	13		143		489		14		6		427	
Refinery Intake (Observed)	0		0		0		0		0		0	
Non-energy use in Petrochemical industry	0		0		0		0		0		325	
	Energy Use	Non Energy Use	Energy Use	Non Energy Use	Energy Use	Non Energy Use	Energy Use	Non Energy Use	Energy Use	Non Energy Use	Energy Use	Non Energy Use
Transformation Sector	0	0	0	0	0	0	0	0	0	0	0	115
Main Activity Producer Electricity Plants												
Autoproducer Electricity Plants												
Main Activity Producer CHP Plants												
Autoproducer CHP Plants												
Main Activity Producer Heat Plants												
Autoproducer Heat Plants												
Gas Works (Transformation)												
For Blended Natural Gas												
Coke Ovens (Transformation)												
Blast Furnaces (Transformation)												
Petrochemical Industry												115
Patent Fuel Plants (Transformation)												
Non-specified (Transformation)												
Energy Sector	0	0	0	0	0	0	0	0	0	0	0	0
Coal Mines												
Oil and Gas Extraction												
Coke Ovens (Energy)												
Blast Furnaces (Energy)												
Gas Works (Energy)												
Own Use in Electricity, CHP and Heat Plants												
Non-specified (Energy)												
Distribution Losses												
Total Final Consumption	0	13	0	143	0	489	0	14	0	6	85	342
Transport Sector	0	0	0	136	0	0	0	0	0	0	0	0
International Aviation												
Domestic Aviation												
Road				130								
Rail				6								
Domestic Navigation												
Pipeline Transport												
Non-specified (Transport)												
Industry Sector	0	13	0	7	0	489	0	14	0	6	85	227
Iron and Steel										0		
Chemical (including Petrochemical)		1									85	227
Non-Ferrous Metals										1		
Non-Metallic Minerals				1						2		
Transport Equipment												
Machinery				1						2		
Mining and Quarrying												
Food, Beverages and Tobacco												
Paper, Pulp and Printing												
Wood and Wood Products								2				
Construction						489						
Textiles and Leather												
Non-specified (Industry)		12		5				12		1		
Other Sectors	0	0	0	0	0	0	0	0	0	0	0	0
Commercial and Public Services												
Residential												
Agriculture/Forestry												
Fishing												
Non-specified (Other)												

Tab. A4 7 Energy balance for Natural Gas 2024 [TJ] in GCV

Indigenous Production	6 948
Associated Gas	4 207
Non-Associated Gas	0
Colliery Gas	2 742
From Other Sources	260
Total Imports (Balance)	224 971
Total Exports (Balance)	0
International Marine Bunkers	0
Stock Changes (National Territory)	35 358
Inland Consumption (Calculated)	267 537
Statistical Differences	617
Inland Consumption (Observed)	266 921
Recoverable Gas	0
Opening Stock Level (National Territory)	119 856
Closing Stock Level (National Territory)	84 498
Opening stock level (Held abroad)	
Closing stock level (Held abroad)	
Memo:	
Gas Vented	0
Gas Flared	0
Memo: Cushion Gas	
Cushion Gas Opening Stock Level	59 787
Cushion Gas Closing Stock Level	59 787
Memo: From other sources	
From Other Sources - Oil	0
From Other Sources - Coal	0
From Other Sources - Renewables	260

Transformation Sector	59 963
Main Activity Producer Electricity Plants	13 976
Autoproducer Electricity Plants	40
Main Activity Producer CHP Plants	20 195
Autoproducer CHP Plants	2 168
Main Activity Producer Heat Plants	16 976
Autoproducer Heat Plants	6 788
Gas Works (Transformation)	0
Coke Ovens (Transformation)	0
Blast Furnaces (Transformation)	0
Gas-to-Liquids (GTL) Plants (Transformation)	0
Non-specified (Transformation)	0
Energy Sector	3 819
Coal Mines	0
Oil and Gas Extraction	105
Oil Refineries	3 714
Coke Ovens (Energy)	0
Blast Furnaces (Energy)	0
Gas Works (Energy)	0
Own Use in Electricity, CHP and Heat Plants	0
Liquefaction (LNG)/Regasification Plants	0
Gas-to-Liquids (GTL) Plants (Energy)	0
Non-specified (Energy)	0
Distribution Losses	2 404
Transport Sector	3 644
Road	3 625
of which Biogas	0
Pipeline Transport	19
Non-specified (Transport)	0
Industry Sector	81 590
Iron and Steel	6 504
Chemical (including Petrochemical)	10 758
Non-Ferrous Metals	2 242
Non-Metallic Minerals	19 253
Transport Equipment	8 429
Machinery	8 695
Mining and Quarrying	1 636
Food, Beverages and Tobacco	10 505
Paper, Pulp and Printing	3 484
Wood and Wood Products	652
Construction	2 860
Textiles and Leather	3 470
Non-specified (Industry)	3 100
Other Sectors	112 631
Commercial and Public Services	42 769
Residential	67 921
Agriculture/Forestry	1 935
Fishing	7
Non-specified (Other)	

A 4.2 Differences between statistical data reported in Eurostat and CzSO

During processing of the data reported in the Energy sector, we are using data reported in the official statistics of the Czech Statistical Office. Following Annex B of Regulation (EC) No 1099/2008 of the European Parliament and of the council of 22 October 2008 on energy statistics the countries are reporting to the Eurostat the data about energy statistics.

During preparation of the national inventory, the team is receiving statistical data from energy statistics in the official IEA-Eurostat-UNECE questionnaires. The format of the data is clearly given by the above-mentioned regulation. The CHMI has an agreement with CzSO due to which CzSO is providing data in the questionnaires annually before for the preparation of the inventory. As it is mentioned in the Chapter 3 Energy, CzSO questionnaires are the main source of data used for the inventory of greenhouse gas emissions in Energy sector – stationary combustion. However, during various review, we are receiving questions regarding data in Eurostat and data in inventory, which are not the same.

In the inventory of greenhouse gases in Energy sector there are few changes in data use, where we are using EU ETS data or other more detailed statistics. Those are all explained in relevant subchapters of the Energy chapter. However generally the data in Eurostat and Czech inventory in Energy sector should be on most cases the same.

We have carried out extensive research to find out where are the differences between energy statistics in Eurostat and data in CzSO coming from. On the website of Eurostat, we have downloaded the data from energy balance for the years 2020-2023. We have compared the data and the structure of the data. First, there is apparent difference in the structure of the data, some of the items are named differently, some are missing and some are summed up in the Eurostat's energy balances. The details about differences between Eurostat's energy balance and the CzSO data are summarized in the following table. As of March 23, the data for the year 2024 were not available on the Eurostat website.

Tab. A4 8 Differences between Eurostat's energy balance and the CzSO data

Solid fuels	
item	description of the difference
autoproducer electricity	The NCV used for transfer to TJ is different in Eurostat and in the national inventory. In the national inventory is used NCV for "industry", in Eurostat data is used NCV for "other uses".
autoproducer CHP	The NCV used for transfer to TJ is different in Eurostat and in the national inventory. In the national inventory is used NCV for "industry", in Eurostat data is used NCV for "other uses".
autoproducers heat	The NCV used for transfer to TJ is different in Eurostat and in the national inventory. In the national inventory is used NCV for "industry", in Eurostat data is used NCV for "other uses".
summary values	Summary values should be sum of specific items, which is the case in the CzSO data, however not in the Eurostat data
Gas Works Gas	Difference in applied coefficient GCV/NCV. In the national inventory is used country specific coefficient (please see Annex 5 of NID). In order to get the values reported for Gas Works Gas in Eurostat, we would need to used coefficient 0.9, which is default one.
Coke Oven Gas	Difference in applied coefficient GCV/NCV. In the national inventory is used country specific coefficient (please see Annex 5 of NID). In order to get the values reported for Gas Works Gas in Eurostat, we would need to used coefficient 0.9, which is default one.
Liquid Fuels	
item	description of the difference
Road Diesel	This fuel is completely missing in the Eurostat's energy balance, however in CzSO questionnaire is separate sheet for this fuel
Heating and other gasoil	This fuel is completely missing in the Eurostat's energy balance, however in CzSO questionnaire is separate sheet for this fuel

Fuel oil - low sulphur	This fuel is completely missing in the Eurostat's energy balance, however in CzSO questionnaire is separate sheet for this fuel
Fuel oil - high sulphur	This fuel is completely missing in the Eurostat's energy balance, however in CzSO questionnaire is separate sheet for this fuel
Fuel Oil	This fuel is only in Eurostat's energy balance; the data are representing sum of the Fuel oil - low sulphur and Fuel oil - high sulphur from the CzSO questionnaire
Non-energy use - transport sector	In the Eurostat energy balance is available this summary value, however in the CzSO questionnaire there are detailed data for few subcategories under this item
Non-energy use - industry	In the Eurostat energy balance is available this summary value, however in the CzSO questionnaire there are detailed data for few subcategories under this item
Non-energy use - other sector	In the Eurostat energy balance is available this summary value, however in the CzSO questionnaire there are detailed data for few subcategories under this item
Gas Diesel Oil	In Eurostat's energy balance this fuel is named Gas oil and diesel oil (excluding biofuel portion). In comparison the data in the CzSO questionnaire is about 1% higher than data in the Eurostat's energy balance.
Biodiesel	In Eurostat's energy balance are missing data for Energy consumption - Road, Energy consumption - Rail; data for Industry sector - Construction; data for Agriculture/forestry. In CzSO questionnaire the data are available.
Other Products	The data in both databases varies for the category Transformation Sector - Petrochemical industry
Natural Gas	
item	description of the difference
all subcategories	Difference in applied coefficient GCV/NCV. In the national inventory is used country specific coefficient (please see Annex 5 of NID). In order to get the values reported for Gas Works Gas in Eurostat, we would need to used coefficient 0.9, which is default one.
Biofuels	
item	description of the difference
Biogases	Data for subcategory Non-energy use - transport - road are missing in the Eurostat's energy balance

Except of above mentioned differences, we have carried out also emissions calculation using the same calculation model but applying strictly data from Eurostat. However, the further assumptions in the model, such as approach applied for emission calculation of autoproducers or applying specific calorific values, we left without the change. The specific differences in the data and in the CO_2 emissions are apparent from the tables bellow.

Tab. A4 9 Differences in final summed up data for fuel consumptions

[TJ/year]	2020	2021	2022	2023
1A1 Energy industries	1.233	1.619	1.418	1.547
liquid fuels	4.168	2.872	1.733	1.105
solid fuels	1.498	2.010	1.726	1.952
1A1a Main Activity Electricity and Heat Production	0.330	0.295	0.302	0.287
liquid fuels	2.850	4.571	-0.059	-0.055
solid fuels	0.411	0.351	0.372	0.363
1A1ai Electricity generation	0.000	0.000	0.000	0.000
liquid fuels	0.000	0.000	-0.456	0.000
solid fuels	0.000	0.000	0.000	0.000
1A1aii Combinated Heat and Power generation	0.320	0.357	0.362	0.351
liquid fuels	-0.037	-0.027	-0.029	-0.048
solid fuels	0.488	0.561	0.591	0.593
1A1aiii Heat Plants	4.747	3.747	4.827	3.792
liquid fuels	100.000	100.000	-0.072	-0.078
solid fuels	95.938	88.081	97.552	100.000
1A1c Manufacture of solid fuels and Other energy industries	9.945	38.933	28.430	31.239
liquid fuels	100.000	100.000	100.000	100.000
solid fuels	9.547	38.696	28.123	31.071

1A2 Manufacturing Industries and Construction	0.098	-0.305	-0.562	0.407
liquid fuels	0.906	1.839	1.887	-0.206
solid fuels	-0.151	-2.025	-2.860	1.298
Biomass	0.377	0.407	0.343	0.399
1A2a Iron and Steel	1.870	1.706	1.972	1.746
solid fuels	2.817	2.804	2.879	2.703
1A2b Non-Ferrous Metals	5.836	4.982	5.772	5.593
solid fuels	100.000	100.000	100.000	100.000
1A2c Chemicals	-2.082	-3.724	-4.088	-0.211
liquid fuels	-0.036	-0.051	0.000	0.000
solid fuels	-6.054	-7.120	-7.586	-0.370
Biomass	1.141	1.108	0.989	0.977
1A2d Pulp, Paper and Print	0.060	-0.267	-0.364	0.304
liquid fuels	7.845	8.043	0.000	0.169
solid fuels	-6.135	-7.150	-7.575	-0.369
Biomass	0.370	0.412	0.383	0.409
1A2e Food Processing, Beverages and Tobacco	-0.021	-0.420	-0.941	0.176
liquid fuels	0.163	0.660	1.413	-3.213
solid fuels	-3.996	-5.693	-6.259	-0.267
Biomass	1.121	1.213	1.013	1.139
1A2f Non-Metallic Minerals	-0.017	-0.046	-0.037	0.174
liquid fuels	0.241	-0.771	1.623	9.469
solid fuels	-0.140	-0.254	-0.292	0.198
1A2g Non-specified Industry	0.398	0.716	0.642	0.486
liquid fuels	2.677	6.306	9.610	-1.907
solid fuels	13.633	19.219	11.922	21.581
Biomass	0.040	0.023	0.000	0.000
1A3 Transport	-0.635	-0.604	-0.529	-0.522
liquid fuels	-0.647	-0.613	-0.537	-0.522
1A4 Other sectors	-29.915	3.647	-2.131	-4.061
liquid fuels	2.450	2.931	2.779	2.674
solid fuels	0.000	0.000	0.000	0.000
Biomass	-86.354	9.563	-6.112	-10.839
1A4a Commercial/Institutional	1.532	1.194	1.124	1.248
liquid fuels	60.938	62.067	83.465	56.728
solid fuels	0.000	0.000	0.000	0.000
Biomass	24.652	3.510	0.236	0.107
1A4b Residential	-43.644	4.529	-3.071	-5.798
solid fuels	0.000	0.000	0.000	0.000
Biomass	-99.397	10.157	-6.594	-11.762
1A4c Agriculture/Forestry/Fishing/Fish Farms	21.698	0.256	-0.006	-0.100
liquid fuels	0.000	0.000	0.000	0.000
solid fuels	0.000	0.000	0.000	0.000
Biomass	87.211	1.009	-0.024	-0.382
1A4ci Stationary	55.931	0.659	-0.017	-0.272
liquid fuels	-0.001	0.000	0.000	0.000
solid fuels	0.000	0.000	0.000	0.000
Biomass	87.211	1.009	-0.024	-0.382

*values 0.000 in the table are indicating differences on fifth and further decimal points

Tab. A4 10 Differences in final summed up data in CO_2 emissions

[kt/year]	2020	2021	2022	2023
1A1 Energy industries	0.506	0.807	0.675	0.840
liquid fuels	5.397	3.769	2.192	1.417
solid fuels	0.555	0.931	0.775	1.002

1A1a Main Activity Electricity and Heat Production	**0.309**	**0.259**	**0.274**	**0.259**
liquid fuels	3.484	5.573	-0.065	-0.062
solid fuels	0.335	0.269	0.298	0.284
1A1ai Electricity generation	**0.000**	**0.000**	**0.000**	**0.000**
liquid fuels	0.000	0.000	-0.446	
solid fuels	0.000	0.000	0.000	0.000
1A1aii Combinated Heat and Power generation	**0.155**	**0.174**	**0.176**	**0.170**
liquid fuels	-0.045	-0.032	-0.034	-0.057
solid fuels	0.228	0.264	0.278	0.279
1A1aiii Heat Plants	**7.548**	**5.827**	**7.452**	**5.913**
liquid fuels	100.000	100.000	-0.070	-0.075
solid fuels	96.518	89.842	97.956	100.000
1A1c Manufacture of solid fuels and Other energy industries	**2.653**	**20.309**	**12.479**	**16.982**
liquid fuels	100.000	100.000	100.000	100.000
solid fuels	2.290	19.792	12.004	16.672
1A2 Manufacturing Industries and Construction	**-0.097**	**-0.624**	**-0.933**	**0.358**
liquid fuels	0.981	1.975	2.019	-0.215
solid fuels	-0.877	-2.651	-3.438	0.976
Biomass	0.221	0.239	0.202	0.236
1A2a Iron and Steel	**1.052**	**0.939**	**1.034**	**0.997**
solid fuels	1.393	1.329	1.343	1.339
1A2b Non-Ferrous Metals	**10.593**	**9.084**	**10.369**	**10.031**
solid fuels	100.000	100.000	100.000	100.000
1A2c Chemicals	**-2.826**	**-4.579**	**-4.955**	**-0.255**
liquid fuels	-0.038	-0.054	0.000	0.000
solid fuels	-6.060	-7.123	-7.586	-0.370
Biomass	1.140	0.996	0.950	0.843
1A2d Pulp, Paper and Print	**-0.089**	**-0.458**	**-0.556**	**0.177**
liquid fuels	8.687	8.904	0.000	0.180
solid fuels	-6.136	-7.150	-7.575	-0.369
Biomass	0.216	0.242	0.230	0.243
1A2e Food Processing, Beverages and Tobacco	**-0.258**	**-0.884**	**-1.581**	**0.081**
liquid fuels	0.153	0.649	1.450	-3.509
solid fuels	-4.025	-5.713	-6.273	-0.269
Biomass	1.100	1.185	0.996	1.127
1A2f Non-Metallic Minerals	**-0.036**	**-0.075**	**-0.069**	**0.175**
liquid fuels	0.234	-0.847	1.645	9.982
solid fuels	-0.206	-0.331	-0.364	0.113
1A2g Non-specified Industry	**0.532**	**0.974**	**0.829**	**0.708**
liquid fuels	2.968	6.918	10.536	-2.147
solid fuels	13.643	19.259	11.952	21.574
Biomass	0.020	0.011	0.000	0.000
1A3 Transport	**-0.650**	**-0.617**	**-0.541**	**-0.532**
liquid fuels	-0.660	-0.625	-0.547	-0.532
1A4 Other sectors	**-20.506**	**5.011**	**-3.016**	**-5.725**
liquid fuels	2.509	3.012	2.848	2.752
solid fuels	0.000	0.000	0.000	0.000
Biomass	-43.559	9.848	-6.339	-11.263
1A4a Commercial/Institutional	**1.758**	**1.598**	**1.276**	**1.537**
liquid fuels	63.756	64.618	86.803	59.155
solid fuels	0.000	0.000	0.000	0.000
Biomass	17.658	4.860	-3.633	-1.277
1A4b Residential	**-27.562**	**5.883**	**-3.888**	**-7.373**
solid fuels	0.000	0.000	0.000	0.000
Biomass	-48.456	10.157	-6.594	-11.762

1A4c Agriculture/Forestry/Fishing/Fish Farms	**17.532**	**0.327**	**0.114**	**-0.168**
liquid fuels	0.000	0.000	0.000	0.000
solid fuels	0.000	0.000	0.000	0.000
Biomass	81.717	1.490	0.504	-0.743
1A4ci Stationary	**51.750**	**0.956**	**0.353**	**-0.521**
liquid fuels	-0.001	0.000	0.000	0.000
solid fuels	0.000	0.000	0.000	0.000
Biomass	81.717	1.490	0.504	-0.743

*values 0.000 in the table are indicating differences on fifth and further decimal points

Differences between default coefficient NCV/GCV and country specific one is presented in the Tab. A4 11.

Tab. A4 12 Percentual change in coefficient NCV/GCV – country specific and default one

	2020	2021	2022	2023
Country specific GCV/NCV	1.1086	1.1086	1.1080	1.1077
Share NCV/GCV	0.9021	0.9020	0.9025	0.9027
default coefficient	0.9	0.9	0.9	0.9
% difference	0.23	0.23	0.28	0.30

The differences between net calorific values, which are differently applied for subcategories "autoproducers" are apparent from Tab. A4 13.

Tab. A4 14 Differences between net calorific values for solid fuels for "used in industry" and "for other uses".

		2020	2021	2022	2023
Other Bituminous Coal	NCV "Used in industry"	26 509	26 533	26 599	27 860
	NCV "For other uses"	27 743	27 426	26 323	26 809
	% difference	4.45	3.26	-1.05	-3.92
Lignite	NCV "Used in industry"	13 410	13 858	14 122	154 81
	NCV "For other uses"	15 088	15 507	15 813	15 484
	% difference	11.12	10.63	10.69	0.02
Coke Oven Coke	NCV "Used in industry"	28 914	28 595	28 037	26 753
	NCV "For other uses"	27 280	27 588	27 728	27 373
	% difference	-5.99	-3.65	-1.11	2.27
Coal Tar	NCV "Used in industry"	37 818	37 820	37 818	37 820
	NCV "For other uses"	37 759	37 200	38 341	38 971
	% difference	-0.16	-1.67	1.36	2.95
BKB	NCV "Used in industry"	22 878	23 346	22 590	23 746
	NCV "For other uses"	20 210	20 210	20 050	20 028
	% difference	-13.20	-15.52	-12.67	-18.56

Annex 5 Any additional information, as applicable

Information provided in A 5.1 – A 5.2 are related to emission estimation in Energy sector.

A 5.1 Improved ratio NCV/GCV for Natural Gas

Default ratio NCV/GCV for natural gas according to the IPCC methodology (IPCC 2006) is equal to 0.9

For more accurate determination of the ratio, data set NET4GAS was used. This data set contains, among other values, NCV and GCV in MJ/m^3 for reference temperature of 20˚C, for each month and for the time period of 5 years (1997 to 2011). All monthly values for NCV and GCV were recalculated for temperature of 15 ˚C (i.e. trading conditions), and further it was determined annual average of the monthly values for NCV and GCV and their ratio NCV/GCV, see Tab. A5 1.

Tab. A5 1 Annual average NCV, GCV and their ratio (determined and calculated using correlation)

MJ/m^3	2007	2008	2009	2010	2011	Average	Standard deviation	%Standard deviation
NCV, 15 ˚C	34.2236	34.2498	34.4267	34.3921	34.4469	34.3478	0.0927	0.27%
GCV, 15 ˚C	37.9572	37.9841	38.1724	38.1363	38.1942	38.0888	0.0986	0.26%
Ratio NCV/GCV	0.90164	0.90169	0.90187	0.90182	0.90189	0.90178	0.0001	0.01%
0.001011*GCV + 0.863274 [a)]	0.90165	0.90168	0.90187	0.90183	0.90189			

[a)] *Precise calculation of the ratio NCV/GCV*

As CzSO reports mainly yearly gross calorific values for natural gas (GCV), while data expressing net calorific value (NCV) is needed, correlation for the calculation of NCV from known values for GCV, reported every year from CzSO, was determined by linear regression, see. Fig. A5 1.



Fig. A5 1 Regression line corresponds with the data shown in Tab. A5-1.

The resulting equation for exact calculation of NCV from known values for GCV is:

NCV = (0.001011 * GCV + 0.863274) * GCV (A5 – 1)

where NCV and GCV are expressed in MJ/m^3 in the reference temperatures of 15 ˚C (i.e. trading conditions)

A 5.2 Improved ratio NCV/GCV for coke oven gas

Recommended ratio NCV/GCV for coke oven gas according to the CzSO is equal to 0.9

For more accurate determination of the ratio, the data set obtained from the one of the significant coke producer in the Czech Republic, was mostly used. This data set uses calculation sheets developed by CHMI for determination of emission factors for CO_2, density and NCV for gaseous fuels, calculated from its composition, etc.

This calculation sheet uses for calculation of NCV and GCV for fuels in gaseous state, calorific value and GCV, based on the weight of the individual components that are listed in regulation ČSN 38 5509 (DIN 1872), so it enables also the calculation of the ratio NCV/GCV.

Unlike in natural gas, in industrially produced fuels NCV and GCV are usually provided in reference temperature of 0˚C (273.15 K), i.e. in "normal conditions". The same is used in the above-mentioned data set. Default ratio NCV/GCV does not depend on the reference temperature, because recalculation coefficients for different reference temperatures in the ratio NCV/GCV are canceled out. The ratio NCV/GCV is calculated for each month in 2010, i.e. 12 times, from which the ratio, standard deviation and its relative value are calculated.

Results are presented in Tab. A5 2.

Tab. A5 2 Annual averages of NCV, GCV under normal condition (i.e. 0˚C) and their ratio

Month	1	2	3	4	5	6	7	
NCV. MJ/Nm^3	16.935	17.108	16.847	16.040	16.459	17.210	17.162	
GCV, MJ/NM^3	19.053	19.251	18.953	18.059	18.530	19.342	19.270	
NCV/GCV	0.8888	0.8886	0.8889	0.8882	0.8883	0.8898	0.8906	
Month	**8**	**9**	**10**	**11**	**12**	**Average**	**Standard deviation**	**%**
NVC. MJ/Nm^3	17.177	16.832	17.056	17.218	17.312	16.946	0.353	2.1%
GCV, MJ/NM^3	19.309	18.925	19.183	19.357	19.443	19.056	0.386	2.0%
NCV/GCV	0.8896	0.8894	0.8891	0.8895	0.8904	0.8893	0.0007	0.1%

Average value of the ratio NCV/GCV is **0.8893** (precisely 0.88926).

In addition to this, a control calculation was conducted, based on the data obtained from another significant coke producer. Due to the incompleteness of the data in comparison with the dataset mentioned above, the ratio NCV/GCV was determined from the average of 4 values (January, April, July, October) and the value is 0.8861, which is relatively close to the more precisely identified value above.

A 5.3 Net calorific values of individual types of fuels in the period 1990–2023

Net Calorific Values (NCV) of each individual fossil fuel in the period 1990–2023 used in the Energy sector were taken from the standard CzSO Questionnaires (IEA/OECD, Eurostat, UN Questionnaires). For liquid

fuels, CzSO provides for each year one net calorific value for all sectors, while for solid fuels, generally indicates three values: for 1A1, 1A2 and 1A4 which were used in the sectoral approach. In Tab. A5 3 are shown for clarity aggregated values, calculated as a weighted average of these three values.

In case of solid and liquid fuels are calorific values expressed in kJ/kg. For natural gas CzSO presents primarily Gross Calorific Values (GCV) in kJ/m^3 (volume related to the trading conditions: 15 ° C and 101.3 kPa). Conversion GCV to NCV, derived in the Czech Hydrometeorological Institute in cooperation with KONEKO, is shown in this Annex above. For the COG (Coke Oven Gas) CzSO presents activity data directly in energy units TJ related to GCV (marked as TJ_{Gross}), but without GCV values for individual years. Conversion to TJ related to NCV (marked as TJ_{Net}), which is required for the calculation of emissions with respect to the definition of emission factors, also appears in this Annex. It is visible that the ratio NCV/GCV = 0.8893 is equal to the ratio TJ_{Net}/TJ_{Gross}.

In Tab. A5 3 are shown the net calorific values of solid and liquid fuels in the period 1990–2023. The symbol "NO" means, as in CRT, that the fuel was not used, “NE” symbol indicates that the value of NCV has not been estimated. Table A5-3 provides definitions of fuels used by CzSO. In most cases, these definitions of fuel are identical to the definitions of IPCC (IPCC 2006). It is noted, however, that fuels marked as "Fuel oil - high sulfur" and "Fuel oil - low sulfur" in the table, according to the terminology of CzSO, fall according to the IPCC under "Residual Fuel Oil". Similarly, fuels marked as "Road diesel" and "Heating and other gas oil" are covered by the IPCC under "Gas/Diesel Oil".

Tab. A5 3a Net calorific values for fossil fuels

NCV [kJ/kg]	1990	1991	1992	1993	1994	1995	1996
Anthracite	NO	NO	NO	NO	NO	NO	NO
Bituminous Coal	18 405	18 405	21 420	21 781	21 846	22 122	22 252
Coking Coal	28 468	28 468	28 468	28 468	28 468	28 468	28 468
Lignite	12 000	12 000	12 000	12 000	12 180	12 540	12 693
Coke Oven Coke	27 009	27 009	27 457	27 457	27 457	27 457	27 457
Coal Tar	NE	NE	NE	NE	NE	NE	NE
BKB	22 868	23 058	21 854	22 922	23 136	22 941	22 918
Crude Oil	41 646	41 646	41 650	41 652	41 652	41 652	41 650
Refinery gas	46 023	46 023	46 023	46 023	46 023	46 023	46 023
LPG	45 945	45 945	45 945	45 945	45 945	45 945	45 945
Naphtha	43 300	43 300	43 300	43 300	43 300	43 352	43 416
Motor gasoline	43 340	43 332	43 342	43 340	43 308	43 320	43 320
Aviation gasoline	43 836	43 836	43 836	43 836	43 836	43 836	43 836
Biogasoline	27 000	27 000	27 000	27 000	27 000	27 000	27 000
Kerosene Jet Fuel	43 454	43 454	43 454	43 454	43 454	43 445	43 433
Other kerosene	42 800	42 800	42 800	42 800	42 800	42 800	42 800
Road diesel	42 485	42 473	42 490	42 502	42 517	42 506	42 528
Heating and other gas oil	42 300	42 300	42 300	42 300	42 300	42 279	42 310
Biodiesel	37 000	37 000	37 000	37 000	37 000	37 000	37 000
Fuel Oil - low sulphur	38 850	38 850	38 850	38 850	38 850	38 825	37 041
Fuel Oil - high sulphur	40 700	40 700	40 700	40 700	40 700	40 863	40 804
Residential Fuel Oil	40 576	40 589	40 619	40 626	40 635	40 738	40 258
Petroleum coke	37 500	37 500	37 500	37 500	37 500	37 500	37 500
Other products*)	40 193	40 193	40 193	40 193	40 193	41 530	39 373

**) The same values of NCV as for Other products are reported by CzSO also for White spirit and SPB, Paraffin waxes, Lubricants and Bitumen*

Tab. A5 3b Net calorific values for fossil fuels

NCV [kJ/kg]	1997	1998	1999	2000	2001	2002	2003
Anthracite	NO	NO	NO	NO	NO	32 000	32 000
Bituminous Coal	21 556	23 981	24 373	21 229	21 962	23 011	23 643
Coking Coal	28 608	28 608	28 527	28 392	28 596	28 752	28 971
Lignite	12 045	12 073	12 811	12 392	12 423	12 411	12 371
Coke Oven Coke	28 241	28 241	28 894	28 488	28 735	28 742	28 712
Coal Tar	NE	NE	NE	NE	NE	36 979	36 979

NCV [kJ/kg]	1997	1998	1999	2000	2001	2002	2003
BKB	22 924	24 080	24 620	24 912	24 243	23 766	25 667
Crude Oil	41 650	41 622	41 628	41 543	41 889	41 483	41 991
Refinery gas	46 023	46 023	46 023	46 023	46 023	46 023	46 023
LPG	45 945	45 945	45 945	45 945	45 945	45 945	45 945
Naphtha	43 391	43 709	43 686	43 669	42 837	42 858	42 940
Motor gasoline	43 300	43 300	43 300	43 300	43 300	43 300	43 300
Aviation gasoline	43 800	43 800	43 800	43 800	43 800	43 800	43 793
Biogasoline	27 000	27 000	27 000	27 000	27 000	27 000	27 000
Kerosene Jet Fuel	43 116	43 000	43 000	43 000	42 800	42 800	42 800
Other kerosene	42 800	42 800	42 800	42 800	42 800	42 800	42 800
Road diesel	42 552	42 555	42 686	42 691	41 920	41 940	41 929
Heating and other gas oil	42 300	42 300	42 412	42 461	41 764	41 748	41 711
Biodiesel	37 000	37 000	37 000	37 000	37 000	37 000	37 000
Fuel Oil - low sulphur	38 784	38 890	39 639	39 694	39 286	39 313	40 000
Fuel Oil - high sulphur	40 783	40 775	40 917	40 893	39 636	40 316	40 371
Residential Fuel Oil	40 595	40 538	40 544	40 659	39 511	39 670	40 182
Petroleum coke	37 500	37 500	37 500	37 500	37 500	37 500	37 500
Other products*)	39 392	38 387	39 290	39 398	40 754	40 711	40 660

*) The same values of NCV as for Other products are reported by CzSO also for White spirit and SPB, Paraffin waxes, Lubricants and Bitumen

Tab. A5 3c Net calorific values for fossil fuels

NCV [kJ/kg]	2004	2005	2006	2007	2008	2009	2010
Anthracite	32 000	32 000	30 941	30 000	30 000	30 000	30 000
Bituminous Coal	23 167	22 399	22 444	22 795	23 455	22 455	23 033
Coking Coal	28 745	28 818	29 148	29 279	29 326	29 381	29 385
Lignite	12 539	12 676	12 680	12 448	12 592	12 414	12 526
Coke Oven Coke	27 991	27 911	28 805	28 472	28 512	28 690	27 865
Coal Tar	36 979	37 336	35 400	37 000	37 000	37 161	36 936
BKB	24 025	22 919	23 500	23 591	22 000	24 000	20 732
Crude Oil	41 980	41 980	41 986	42 259	42 357	42 353	42 400
Refinery gas	46 023	46 023	46 023	46 023	46 023	46 023	46 023
LPG	45 945	45 945	45 945	45 945	45 945	45 945	45 945
Naphtha	42 841	42 841	42 841	43 935	43 951	43 947	43 961
Motor gasoline	43 300	43 300	43 817	43 800	43 839	44 165	44 235
Aviation gasoline	43 790	43 790	43 790	43 790	43 790	43 790	43 790
Biogasoline	27 000	27 000	27 000	27 000	27 000	27 000	27 000
Kerosene Jet Fuel	42 800	42 800	43 300	43 300	43 300	43 300	43 300
Other kerosene	42 800	42 800	42 800	42 800	42 800	42 800	42 800
Road diesel	41 873	41 829	42 779	42 749	42 870	42 976	43 037
Heating and other gas oil	41 718	41 800	42 600	42 600	42 600	42 600	42 600
Biodiesel	37 000	37 000	37 000	37 000	37 000	37 000	37 000
Fuel oil - low sulphur	39 584	39 538	39 599	41 484	39 718	39 700	39 696
Fuel oil - high sulphur	40 519	39 869	39 663	39 758	39 700	39 695	39 489
Residential Fuel Oil	39 997	39 686	39 628	40 594	39 710	39 698	39 603
Petroleum coke	37 500	37 500	37 500	37 500	37 500	37 500	37 500
Other products*)	40 820	40 894	39 300	39 300	40 000	40 074	39 821

*) The same values of NCV as for Other products are reported by CzSO also for White spirit and SPB, Paraffin waxes, Lubricants and Bitumen

Tab. A5 3d Net calorific values for fossil fuels

NCV [kJ/kg]	2011	2012	2013	2014	2015	2016	2017
Anthracite	29 809	28 170	28 944	28 756	28 476	27 976	28 393
Bituminous Coal	23 007	23 278	22 791	22 280	21 485	21 915	21 302
Coking Coal	29 207	29 373	29 244	29 468	29 536	29 509	29 580
Lignite	12 083	12 159	12 019	11 996	11 938	11 955	12 091
Coke Oven Coke	27 774	28 160	28 465	28 594	28 775	28 776	29 145
Coal Tar	36 995	38 000	37 750	36 738	36 801	35 124	36 474
BKB	19 500	19 500	19 500	19 500	19 793	20 005	20 008
Crude Oil	42 370	42 392	42 400	42 400	42 400	42 400	42 400
Refinery gas	46 023	46 023	46 023	46 023	46 023	46 023	46 023
LPG	45 945	45 945	45 945	45 945	45 945	45 945	45 945

Naphtha	43 971	43 993	43 600	43 600	43 600	43 600	43 600
Motor gasoline	44 308	44 302	44 315	44 433	44 487	44 203	44 400
Aviation gasoline	43 790	43 790	43 790	43 790	43 790	43 790	43 790
Biogasoline	27 000	27 000	27 000	27 000	27 000	27 000	27 000
Kerosene Jet Fuel	43 300	43 300	43 300	43 300	43 300	43 300	43 300
Other kerosene	42 800	42 800	42 800	42 800	42 800	42 800	42 800
Road diesel	42 985	42 958	42 962	42 991	42 943	42 957	42 949
Heating and other gas oil	42 600	42 600	42 600	42 600	42 600	42 600	42 600
Biodiesel	37 000	37 000	37 000	37 000	37 000	37 000	37 000
Fuel oil - low sulphur	39 522	39 436	39 439	39 500	39 500	39 500	39 500
Fuel oil - high sulphur	39 427	39 581	39 500	39 500	39 500	39 500	39 500
Residential Fuel Oil	39 482	39 509	39 475	39 500	39 500	39 500	39 500
Petroleum coke	37 500	38 500	38 500	38 500	38 500	39 400	39 400
Other products*)	40 189	40 354	40 179	39 910	39 438	39 220	39 203

**) The same values of NCV as for Other products are reported by CzSO also for White spirit and SPB, Paraffin waxes, Lubricants and Bitumen*

Tab. A5 3e Net calorific values for fossil fuels

NCV [kJ/kg]	2018	2019	2020	2021	2022	2023	2024
Anthracite	28 000	26 607	27 342	27 482	26 889	28 964	28 998
Bituminous Coal	22 109	22 775	22 208	22 102	21 899	23 189	22 540
Coking Coal	29 592	29 498	29 504	29 411	29 343	29 207	29 112
Lignite	12 166	12 097	12 272	12 406	12 140	12 201	11 994
Coke Oven Coke	28 971	28 953	28 821	28 677	28 285	28 246	28 087
Coal Tar	36 214	36 237	38 888	38 613	38 050	0	0
BKB	21 959	20 452	22 224	21 976	21 333	22 000	22 000
Crude Oil	42 800	42 500	42 500	42 500	42 500	42 500	42 500
Refinery gas	46 023	46 023	46 023	46 023	46 023	46 023	46 023
LPG	45 945	45 945	45 945	45 945	45 945	45 945	45 945
Naphtha	43 600	43 600	43 600	43 600	43 600	43 600	43 600
Motor gasoline	44 432	44 646	44 625	44 387	44 479	44 404	44 718
Aviation gasoline	43 790	43 790	43 790	43 790	43 790	43 790	43 790
Biogasoline	27 000	27 000	27 000	27 000	27 000	27 000	27 000
Kerosene Jet Fuel	43 300	43 300	43 300	43 300	43 300	43 300	43 300
Other kerosene	42 800	42 800	42 800	42 800	42 800	42 800	42 800
Road diesel	42 935	42 957	43 037	43 219	43 175	43 144	43 034
Heating and other gas oil	42 600	42 600	42 600	42 600	42 600	42 600	42 600
Biodiesel	37 000	37 000	37 000	37 000	37 000	37 000	37 000
Fuel oil - low sulphur	39 500	39 500	39 500	39 500	39 500	39 500	39 500
Fuel oil - high sulphur	39 500	39 500	39 500	39 500	39 500	39 500	39 500
Residual Fuel Oil	39 500	39 500	39 500	39 500	39 500	39 500	39 500
Petroleum coke	39 400	39 400	39 400	39 400	39 400	39 400	39 400
Other products*)	39 001	29 290	38 778	38 493	38 931	38 495	38 434

**) The same values of NCV as for Other products are reported by CzSO also for White spirit and SPB, Paraffin waxes, Lubricants and Bitumen*

Tab. A5 4 Net calorific values for Natural Gas

NCV [MJ/m3]	1990	1991	1992	1993	1994	1995	1996	1997	1998
Natural Gas	33 436	33 431	33 458	33 908	33 962	34 037	34 008	34 020	34 104
NCV [MJ/m³]	**1999**	**2000**	**2001**	**2002**	**2003**	**2004**	**2005**	**2006**	**2007**
Natural Gas	34 021	34 035	34 041	34 079	34 052	34 015	34 029	34 165	34 235
NCV [MJ/m³]	**2008**	**2009**	**2010**	**2011**	**2012**	**2013**	**2014**	**2015**	**2016**
Natural Gas	34 227	34 264	34 405	34 371	34 295	34 424	34 484	34 574	34 679
NCV [MJ/m3]	**2017**	**2018**	**2019**	**2020**	**2021**	**2022**	**2023**	**2024**	
Natural Gas	34 627	34 627	34 588	34 611	34 596	35 026	35 240	35 419	

***) 15 °C, 101.3 kPa*

A 5.4 Oxidation factor for waste incineration (CRT Sector 5.C)

In the sector 5C equation for CO_2 estimation apply OFj – oxidation factor how much carbon from total carbon content is oxidized. Official methodology IPCC 2006 suggested new oxidation factor for waste incineration. Change of the factor in previous methodologies is shown in Tab. A5 5a.

Tab. A5 5a Overview of oxidation factors in IPCC methodology

Methodology	IPCC 1996	GPG 2000	IPCC 2006
Name	NA	EFi	OFj
Value	NA (effectively 1)	MSW: 0.95 CW: 0.95 ISW: NA HW: 0.995	MSW: 1.00 CW: 1.00 ISW: 1.00 HW: 1.00

OF set to 1 (or 100%) means that all carbon in fuel is incinerated. This is safe assumption that might not lead to underestimation of emission from the source category, but it will make much harder to correctly estimate uncertainty, however. We argue that using less than 100% as oxidation gives much better starting point should we do proper uncertainty assessment that is planned for next submission. Also, there is an existence of various measurement showing unburned carbon in bottom ash of the waste incinerator.

Tab. A5 5b Selected studies focusing of carbon in bottom ash

Study	Value of TOC in bottom ash	Note
Rendek E. et al. (2006a)	3.74 – 0.88 (wt %)	5 WI facilities
Ferrari S. et al. (2001)	17.3 - 6.0 g/kg	11 WI facilities
Van Zomeren, A., Comans R.N.J. (2009)	29.4- 19.8 g/kg	3 WWI
Rendek E. et al. (2006b)	1.5 (wt %)	Sample mix
Bjurström H. (2014)	3.9 (wt %)	Multiple samples, averaged
Straka P. et al.(2014)	0.64 – 22.06 (wt %)	10 facilities

National studies are limited (only one focused on unburnt carbon from biomaterials), however all the studies show that OFj is less than 1. Overview of reviewed studies is in Tab A5 5b. Please note that studies in table reviewed several facilities and/or samples from various places. They show consistently that oxidation of carbon in waste (fossil or organic) is not 100%. We argue that by using default factor methodology suggest we would overestimate real emission from waste incineration, hence we are using factors presented in particular chapters in NID to produce results that have managed uncertainty of estimate.

Related references

André van Zomeren, Rob N.J. Comans, Carbon speciation in municipal solid waste incinerator (MSWI) bottom ash in relation to facilitated metal leaching, Waste Management, Volume 29, Issue 7, July 2009, Pages 2059-2064, ISSN 0956-053X, http://dx.doi.org/10.1016/j.wasman.2009.01.005.

Eva Rendek, Gaëlle Ducom, Patrick Germain, Assessment of MSWI bottom ash organic carbon behavior: A biophysicochemical approach, Chemosphere, Volume 67, Issue 8, April 2007, Pages 1582-1587, ISSN 0045-6535, http://dx.doi.org/10.1016/j.chemosphere.2006.11.054.

Eva Rendek, Gaëlle Ducom, Patrick Germain, Carbon dioxide sequestration in municipal solid waste incinerator (MSWI) bottom ash, Journal of Hazardous Materials, Volume 128, Issue 1, 16 January 2006, Pages 73-79, ISSN 0304-3894, http://dx.doi.org/10.1016/j.jhazmat.2005.07.033.

H. Bjurström, B.B. Lind, A. Lagerkvist, Unburned carbon in combustion residues from solid biofuels, Fuel, Volume 117, Part A, 30 January 2014, Pages 890-899, ISSN 0016-2361, http://dx.doi.org/10.1016/j.fuel.2013.10.020.

Pavel Straka, Jana Náhunková, Margit Žaloudková, Analysis of unburned carbon in industrial ashes from biomass combustion by thermogravimetric method using Boudouard reaction, Thermochimica Acta, Volume 575, 10 January 2014, Pages 188-194, ISSN 0040-6031, http://dx.doi.org/10.1016/j.tca.2013.10.033.

Stefano Ferrari, Hasan Belevi, Peter Baccini, Chemical speciation of carbon in municipal solid waste incinerator residues, Waste Management, Volume 22, Issue 3, June 2002, Pages 303-314, ISSN 0956-053X, http://dx.doi.org/10.1016/S0956-053X(01)00049-6.

A 5.5 General quality control protocol used in NIS

The following table shows general QC form for NID, which is used for QC procedures in each specific sector. The QC form follows the guidance provided in IPCC 2006 GI.

Detailed checklist for Inventory Document

(NIR)

Reviewed documents: (e.g. relevant chapter in NIR)

Responsible compiler of reviewed category: ...

Persons, who carried out the controls: autocontrol – ..., control – ...

Date of finalization of control:

Instructions for filling

This form should be fulfilled after finalizing the whole chapter of the NIR. This form should be fulfilled in line with QA/QC plan. In case when it is not clear how to solve founded discrepancies the worker responsible for control should problematic issues discuss with the sector compiler and if needed with other relevant experts.

The table should be fulfilled according to each listed item. In the form can be added additional issues which are characteristic for the relevant chapter.

Checklist for Inventory Document

Activities	Task completed	
	Name	Date
Tables and Figures		
All numbers in tables match numbers in spreadsheets		
Check that all tables have correct number of significant digits		
Check alignment in columns and labels		
Check that table formatting is consistent		
Check that all tables and figures are updated with new data and referenced in the text		
Check table and figure titles for accuracy and consistency with content		
Check that figure formatting is consistent		
Check that coloring of figures is consistent		
Other (specify)		
Equations		
Check for consistency in equation formatting		
Check that variables used in equations are defined following the equation		
Other (specify)		
References		
Check consistency of references		
Check that in text citations and references match		
Other (specify)		

General Format		
All acronyms and abbreviations are spelled out first time and not subsequent times throughout each chapter		
All headings, titles and subheadings are kept the same as the original structure		
All fonts in the text are consistent		
All highlighting, notes and comments are removed from the final document		
Size, style and indenting of bullets are consistent		
Spell check is complete		
Check the consistency in names and numbering of CRF categories		
Other (specify)		
Other Issues		
Check that each section is updated with current year (or most recent year that inventory report includes)		
Check that the most recent relevant IPCC methodology is used		
Check that all sections and subchapters follow the provided structure		
Other (specify)		

Notes or comments:

....

The following table shows QC form for general technical control (Tier 1). The QC form follows the guidance provided in IPCC 2006 GI.

QC form for general technical control

QC (Tier 1)

Source category/ removals: (e.g. 2A Mineral Products)

Reviewed documents: (e.g. CRF Reporter, computational spreadsheet for 2A, relevant chapter in NIR)

Responsible compiler of reviewed category: ...

Persons, who carried out the controls: autocontrol – ..., control – ...

Date of finalization of control:

Instructions for filling

This form should be completed for each source/sink category and provides a record of the checks which were carried out and possible consequent corrections. This form should be fulfilled in line with QA/QC plan. In case when it is not clear how to solve founded discrepancies the worker responsible for control should discuss the problematic issues with the sector compiler and if needed with other relevant experts.

The first part of the form summarizes results of the controls (once completed) and highlights all significant findings or actions. The second part should be fulfilled according to each listed item. Some explanations of items are given below the checklist. For particular categories not all checks (items) will be applicable - these items are then noted as not relevant (n.r.) or not available (n.a.). This way no check and no row should be left blank or deleted. On the contrary, rows for additional checks that are relevant to the source/sink category can be added to the form.

Summary of control results

Overview of findings and corrections:

description of findings

Suggested corrections, which should be realized in the next submission:

description of suggested corrections

Issues remaining after the corrections:

description of remaining issues

QC form for general and technical control (QC, Tier 1)

	Item	Checked completed			Corrective action		
		Date	Individual (first initial, last name)	Errors (Y/N)	Date	Individual (first initial, last name)	Supporting documents
Input data QC							
1	Cross-check activity data from each category (either measurements or parameters used in calculations) for transcription error (errors between the source of data and spreadsheets).						
2	Check that units are properly labelled in calculation sheets.						
3	Check that units are correctly carried through from beginning to end of calculations.						
4	Check that conversion factors are correct.						
5	Check that temporal and spatial adjustment factors are used correctly.						
6	Cross-check activity data between calculation spreadsheets and **CRF** tables (and if needed in **NIR**).						
7	Other (please specify)						
Calculation							
8	Reproduce a set of emissions and removals calculations.						
9	Use a simple approximation method that gives similar results to the original and more complex calculation to ensure that there is no data input error or calculation error.						
10	Identify parameters (e.g., activity data, constants) that are common to multiple categories and confirm that there is consistency in the values used for these parameters in the emission/removal calculations.						
11	Check that emissions and removals data are correctly aggregated from lower reporting levels to higher reporting levels when preparing summaries (also in **CRF** tables)						

12	Check that emissions and removals data are correctly transcribed between different intermediate products, including calculation spreasheets, **CRF** tables and **NIR**						
13	Other (please specify)						
Database files							
14	Confirm that the appropriate data processing steps are correctly represented in the database.						
15	Confirm that data relationships are correctly represented in the database.						
16	Ensure that data fields are properly labelled and have the correct design specifications.						
17	Ensure that adequate documentation of database and model structure and operation are archived.						
18	Other (please specify)						
Consistency							
19	Check for temporal consistency in time series input data for each category.						
20	Check for consistency in the algorithm/method used for calculations throughout the time series.						
21	Check methodological and data changes resulting in recalculations.						
22	Check that the effects of mitigation activities have been appropriately reflected in time series calculations.						
23	Other (please specify)						
Completeness							
24	Confirm that estimates are reported for all categories and for all years from the appropriate base year to the period of the current inventory.						
25	For subcategories, confirm that entire category is being covered.						
26	Provide clear definition of 'Other' type categories (**NIR** and spreadsheets)						

27	Check that known data gaps that result in incomplete estimates are documented, including a qualitative evaluation of the importance of the estimate in relation to total emissions (e.g., subcategories classified as 'not estimated').						
28	Other (please specify)						
Trend QC							
29	For each category, current inventory estimates should be compared to previous estimates, if available.						
30	If there are significant changes from expected trends, re-check estimates and explain any differences.						
31	Check value of implied emission factors (aggregate emissions divided by activity data) across time series.						
32	Do any years show outliers that are not explained?						
33	If they remain static across time series, are changes in emissions or removals being captured?						
34	Check if there are any unusual and unexplained trends noticed for activity data or other parameters across the time series.						
35	Other (please specify)						
Data documentation (NIR + DATA)							
36	Check of data file (e.g. importing tables) from the view of completeness						
37	Confirm that bibliographical data references are properly cited in the internal documentation						
38	Check of the references on source of input data in the spreadsheets						
39	Check that all references in spreadsheets are documented						
40	Check of completeness of references on the sources of input data in the computational spreadsheets						
41	Random check of referred materials, if they really contains referred data						

42	Check that assumptions and criteria for the selection of activity data, emission factors and other estimation parameters are properly recorded and archived.						
43	Check that the changes in data or methodology (e.g. recalculations) are described and documented						
44	Check that quotes are realized uniformly						
45	Other (please specify)						

Explanations of some items:

5. Spatial adjustment factors refer to factors used to adjust average data, obtained from one or more locations within the Member State to national average data.

22. Check that effects of actions/activities taken to avoid or minimize environmental damage are considered and reflected in time series.

General notes to controls

description

Notes for each parts and founded issues

notes which are needed to add in order to finish adequate control

The following table shows QC form for category – specific technical control (QC Tier 2). The QC form follows the guidance provided in IPCC 2006 GI.

QC form for category-specific technical control

QC (Tier 2)

Source category/ removals: (e.g. 2A Mineral Products)

Reviewed documents: (e.g. CRF Reporter, computational spreadsheet for 2A, relevant chapter in NIR)

Responsible compiler of reviewed category: ...

Persons, who carried out the controls: autocontrol – ..., control – ...

Date of finalization of control:

Instructions for filling

This form should be completed for key categories or categories where significant methodological and data revision have taken place and provides a record of the checks which were carried out and possible consequent corrections. This form should be fulfilled in line with QA/QC plan. In case when it is not clear how to solve founded discrepancies the worker responsible for control should problematic issues discuss with the sector compiler and if needed with other relevant experts.

The first part of the form summarizes results of the controls (once completed) and highlights all significant findings or actions. The second part should be fulfilled according to each listed item. Some explanations of items are given below the checklist. For particular categories not all checks (items) will be applicable - these items are then noted as not relevant (n.r.) or not available (n.a.). This way no check and no row should be left blank or deleted. On the contrary, rows for additional checks that are relevant to the source/sink category can be added to the form.

Summary of control results

Overview of findings and corrections:

description of findings

Suggested corrections, which should be realized in the next submission:

description of suggested corrections

Issues remaining after the corrections:

description of remaining issues

QC form for category-specific and technical control (QC, Tier 2)

Item		Checked completed			Corrective action		
		Date	Individual (first initial, last name)	Errors (Y/N)	Date	Individual (first initial, last name)	Supporting documents
EMISSION DATA QUALITY CHECKS							
1	Are emission comparisons for historical data source performed						
2	Are emission comparisons for significant sub-source categories performed						
3	If applicable, are checks against independent estimates or estimates based on alternative methods performed						
4	Are reference calculations performed						
5	Is completeness check performed						
6	Other (detailed checks)						
EMISSION FACTOR QUALITY CHECKS							
IPCC default emission factors							
7	Are the national conditions comparable to the context of the IPCC default emission factors study						
8	Are default IPCC factors compared with site or plant-level factors						
Country-specific emission factors							
QC on models							
9	Are the model assumptions appropriate and applicable to the GHG inventory methods and national circumstances						
10	Are the extrapolations/interpolations appropriate and applicable to the GHG inventory methods and national circumstances						
11	Are the calibration-based modifications appropriate and applicable to the GHG inventory methods and national circumstances						

12	Are the data characteristics appropriate and applicable to the GHG inventory methods and national circumstances						
13	Are the model documentation (including descriptions, assumptions, rationale, and scientific evidence and references supporting the approach and parameters used for modelling) available						
14	Are model validation steps performed by model developers and data suppliers						
15	Are QA/QC procedures performed by model developers and data suppliers						
16	Are the responses to these results documented						
17	Are plans to periodically evaluate and update or replace assumptions with appropriate new measurements prepared						
18	Is there completeness in relation to the IPCC source/sink categories						
Comparisons							
19	Are country-specific factors compared with IPCC default factors						
20	Is comparison between countries, including historical trends, min and max value, base and most recent year value, IEF performed						
21	If applicable, is comparison to plant-level emission factors performed						
22	Other (detailed checks)						
ACTIVITY DATA QUALITY CHECKS							
National level activity data							
23	Are alternative activity data sets based on independent data available						
24	Were comparisons with independently compiled data sets performed						
25	Were the national data compared with extrapolated samples or partial data at sub-national level						
26	Was a historical trend check performed						

27	Are any sharp increases/decreases detected and checked for calculation errors						
28	Are any sharp increases/decreases explained and documented						
Site-specific activity data							
29	Are there any inconsistencies between the sites						
30	If yes, was a QC check performed to identify the cause of the inconsistency (errors, different measurement techniques or real differences in emissions, operating conditions or technology)						
31	Are the activity data compared between different reference sources and geographic scales (national production statistics vs. aggregated activity data)						
32	Are the differences explained						
33	If applicable, is a comparison between bottom up (site-specific) and top down (national level) account balance performed						
34	Are large differences explained						
35	Other (please specify)						
CALCULATION RELATED QUALITY CHECKS							
36	Are checks of the calculation algorithm (duplications, unit conversion, calculation errors) performed						
37	Are the calculations reproducible						
38	Are all calculation procedures recorded						
39	Other (please specify)						

Explanations of some items:

3. For example comparisons can be made to similar statistics prepared by FAO (for agriculture), IEA (for energy) etc.

8. Compare IPCC default emission factors with site or plant-level factor to determine their representativeness relative to actual sources in the country. This check is good practice even if data are only available for a small percentage of sites or plants.

18. If the model computes and comprises all data covered/required by the IPCC category.

19. Comparison should be made, taking into consideration the characteristics and properties on which the default factors are based. The intent is to determine whether country-specific factors are reasonable, given the similarities or differences between the national category and the "average" category, represented by the default.

25. For example, if national production data are being used to calculate the inventory, it may also be possible to obtain plant-specific production or capacity data for a subset of the total population of plants. The effectiveness of this check depends on how representative the sub-sample is of the national population, and how well the extrapolation technique captures the national population.

General notes to controls

description

Notes for each parts and founded issues

notes which are needed to add in order to finish adequate control

A 5.6 Completeness check for controlling CRT tables and data in the ETF reporting tool

Disclaimer; due to the completeness check function not being fully and correctly available in the ETF reporting tool at the time of preparation of current 2024 submission (5.3.2026), Tab. A5 6 provided by the ETF reporting tool does not correctly reflect the status of the NID and shows lower completeness percentages. The ETF reporting tool shows all the subcategories and categories as incomplete orange even when in a single subcategory or in a category as 6. Other all the cells have been filled and when required, the additional information regarding NKs, comments or documentation box, has been provided.

After ETF reporting tool hotfix and exporting JSON file to create a new submission version, all the information in all the cells have not been exported correctly or have been changed to empty cells by the ETF reporting tool. Still, measures have been taken to ensure completeness of the submission; CRT data entry sheets have been QC checked after hot fix has been released by the ETF reporting tool, and multitude of errors due to the ETF reporting tool bugs regarding completeness has been corrected, namely notation keys missing, parameters missing in the summary sheets, where these should have been automatically filled by the ETF tool from the sectoral background sheets, which sector experts have successfully filled in. Completeness and correctness has been ensured by comparing previous and new versions of data entry sheets and reporting tables, and performing a sum test between the previous and the new version.

The ETF reporting tool bugs have placed excessive burden to the national GHG team, hence in CRT table cells, which do not affect the national total, may still be an empty cell instead of NA or NO or Tier and method parameters are missing in the automated summary sheets. All the cells having IE or NE have been filled, which can be seen in the CRT Table 9 and also below in A5 7 for NE and A5 8 for IE.

Tab. A5 6 Completeness check



The following table A5 7 shows categories that are not estimated (NE) including relevant explanations of the reasons. Categories that are included elsewhere (IE) are shown in similar way in Tab. A5 8.

Tab. A5 7 Sources and sink not estimated ("NE")

GHG	Sector1	Source/sink category1	Explanation
CO_2	1. Energy	Fugitive emissions from fuels > Solid fuels > Coal mining and handling > Underground mines > Post-mining activities	Relevant data for emission factors are not available. Emissions are expected to be very low. Relevant EF was not found in existing IPCC methodology.
CO_2	1. Energy	Fugitive emissions from fuels > Solid fuels > Coal mining and handling > Surface mines > Post-mining activities	Relevant data for emission factors are not available. Emissions are expected to be very low. Relevant EF was not found in existing IPCC methodology.
CO_2	1. Energy	Fugitive emissions from fuels > Oil and natural gas and other emissions from energy production > Oil > Exploration	Level of emissions is well below TofS 0.00003% of the total annual emissions (inventory 2021–2023). For the whole explanation see the chap. 3.3.2.1.1
CO_2	1. Energy	Fugitive emissions from fuels > Oil and natural gas and other emissions from energy production > Oil > Distribution of oil products	Emission factor is not available. Emissions are expected to be very low.Relevant EF was not found in existing IPCC methodology.
CO_2	1. Energy	Fugitive emissions from fuels > Oil and natural gas and other emissions from energy production > Oil > Distribution of oil products	Emission factor is not available. Emissions are expected to be very low.Relevant EF was not found in existing IPCC methodology.
CO_2	1. Energy	Fugitive emissions from fuels > Solid fuels > Coal mining and handling > Underground mines > Abandoned underground mines (number of mines)	Relevant data for emission factors are not available. Emissions are expected to be very low. Relevant EF was not found in existing IPCC methodology.
CO_2	1. Energy	Fugitive emissions from fuels > Oil and natural gas and other emissions from energy production > Natural gas > Exploration	This activity is not performed in the Czech Republic, or only completely random. See also explanation on 1.B.2.a.iii.1.
CO_2	1. Energy	Fugitive emissions from fuels > Solid fuels > Coal mining and handling > Underground mines > Post-mining activities	Relevant data for emission factors are not available. Emissions are expected to be very low. Relevant EF was not found in existing IPCC methodology.
CO_2	1. Energy	Fugitive emissions from fuels > Oil and natural gas and other emissions from energy production > Oil > Refining/storage	Emission factor is not available. Emissions are expected to be very low.Relevant EF was not found in existing IPCC methodology.
CH_4	1. Energy	Fugitive emissions from fuels > Oil and natural gas and other emissions from energy production > Oil > Exploration	Level of emissions is well below TofS 0.00003% of the total annual emissions (inventory 2021–2023). For the whole explanation see the chap. 3.3.2.1.1.
CH_4	1. Energy	Fugitive emissions from fuels > Oil and natural gas and other emissions from energy production > Natural gas > Exploration	This activity is not performed in the Czech Republic, or only completely random. See also explanation on 1.B.2.a.iii.1.
CH_4	1. Energy	Fugitive emissions from fuels > Oil and natural gas and other emissions from	Emission factor is not available. Emissions are expected to be very low.Relevant EF was not found in existing IPCC methodology.

GHG	Sector1	Source/sink category1	Explanation
		energy production > Oil > Distribution of oil products	
N_2O	5. Waste	Wastewater treatment and discharge > Industrial wastewater	Reliable data is not available. Emissions are expected to be very low. Rough estimate 8.85 kt is under TofS. See EJ-G-2024-001.
N_2O	1. Energy	Fugitive emissions from fuels > Oil and natural gas and other emissions from energy production > Oil > Refining/storage	Emission factor is not available. Emissions are expected to be very low.Relevant EF was not found in existing IPCC methodology.
HFC-13_4a	2. IPPU	Product uses as substitutes for ODS > Refrigeration and air-conditioning > Mobile air-conditioning > HFC-134a	Reliable data is not available. Emissions are expected to be very low.

[1]*Indicate omitted source/sink category*

Tab. A5 8 Sources and sinks reported elsewhere ("IE")

GHG	Source/sink category	Allocation used by the Party	Explanation
CO_2	Energy > Fuel combustion activities (sectoral approach) > Energy industries > Public electricity and heat production > Combined heat and power generation > Gaseous fuels		Reported in 1A1a i Electricity generation
CO_2	Waste > Incineration and open burning of waste > Waste incineration > Biogenic > Other > Hazardous waste		Every other reported waste category (MSW, industrial, clinical and sewage sludge) has its part of waste which is hazardous (and is counted and reported together with the non-hazardous part)
CO_2	Industrial processes and product use > Metal industry > Iron and steel production > Steel	Reported under 2.C.1.f Metallurgical coke.	Reported under 2.C.1.f Metallurgical coke. All CO2 from 2.C.1. are calculated from coke consumption in the blast furnace.
CO_2	Energy > Fuel combustion activities (sectoral approach) > Energy industries > Public electricity and heat production > Heat plants > Gaseous fuels		Reported in 1A1a i Electricity generation

CO_2	Industrial processes and product use > Metal industry > Iron and steel production > Pig iron	Reported under 2.C.1.f Metallurgical coke.	Reported under 2.C.1.f Metallurgical coke. All CO2 from 2.C.1. are calculated from coke consumption in the blast furnace.
CO_2	Energy > Fuel combustion activities (sectoral approach) > Energy industries > Public electricity and heat production > Combined heat and power generation > Biomass		Reported in 1A1a i Electricity generation
CO_2	Industrial processes and product use > Metal industry > Iron and steel production > Sinter	Reported under 2.C.1.f Metallurgical coke.	Reported under 2.C.1.f Metallurgical coke. All CO2 from 2.C.1. are calculated from coke consumption in the blast furnace.
CO_2	Waste > Incineration and open burning of waste > Open burning of waste > Non-biogenic > Municipal solid waste		Reported in 5.C.2.b.ii.Other waste
CO_2	Energy > Fuel combustion activities (sectoral approach) > Energy industries > Public electricity and heat production > Combined heat and power generation > Other fossil fuels		Reported in 1A1a i Electricity generation
CO_2	Waste > Incineration and open burning of waste > Waste incineration > Non-biogenic > Other > Hazardous waste		Every other reported waste category (MSW, industrial, clinical and sewage sludge) has its part of waste which is hazardous (and is counted and reported together with the non-hazardous part)
CO_2	Energy > Fuel combustion activities (sectoral approach) > Energy industries > Public electricity and heat production > Combined heat and power generation > Liquid fuels		Reported in 1A1a i Electricity generation
CO_2	Energy > Fuel combustion activities (sectoral approach) > Energy industries > Public electricity and heat production > Heat plants > Solid fuels		Reported in 1A1a i Electricity generation
CO_2	Energy > Fuel combustion activities (sectoral approach) > Energy industries > Public electricity and heat production > Combined heat and power generation > Solid fuels		Reported in 1A1a i Electricity generation

CO_2	Energy > Fuel combustion activities (sectoral approach) > Energy industries > Public electricity and heat production > Heat plants > Liquid fuels		Reported in 1A1a i Electricity generation
CO_2	Energy > Fuel combustion activities (sectoral approach) > Energy industries > Public electricity and heat production > Heat plants > Biomass		Reported in 1A1a i Electricity generation
CO_2	Energy > Fuel combustion activities (sectoral approach) > Energy industries > Public electricity and heat production > Heat plants > Other fossil fuels		Reported in 1A1a i Electricity generation
CO_2	Waste > Incineration and open burning of waste > Waste incineration > Non-biogenic > Other > Fossil liquid waste		Included in 5.C.1.2.b.i Other (Industrial Waste)
CO_2	Land use, land-use change and forestry > Forest land > Biomass burning (CO_2, CH_4, N_2O) > Forest land remaining forest land > Controlled burning > Controlled burning of biomass		IE - included within biomass loss in 4.A.1
CH_4	Waste > Biological treatment of solid waste > Anaerobic digestion at biogas facilities > Municipal solid waste		Data reported under Energy sector, 1.A.1.a
CH_4	Waste > Incineration and open burning of waste > Waste incineration > Non-biogenic > Other > Fossil liquid waste		Included in 5.C.1.2.b.i Other (Industrial Waste)

CH_4	Energy > Fuel combustion activities (sectoral approach) > Energy industries > Public electricity and heat production > Combined heat and power generation > Solid fuels		Reported in 1A1a i Electricity generation
CH_4	Waste > Incineration and open burning of waste > Waste incineration > Biogenic > Other > Hazardous waste		Every other reported waste category (MSW, industrial, clinical and sewage sludge) has its part of waste which is hazardous (and is counted and reported together with the non-hazardous part)
CH_4	Energy > Fuel combustion activities (sectoral approach) > Energy industries > Public electricity and heat production > Combined heat and power generation > Liquid fuels		Reported in 1A1a i Electricity generation
CH_4	Waste > Incineration and open burning of waste > Waste incineration > Non-biogenic > Other > Hazardous waste		Every other reported waste category (MSW, industrial, clinical and sewage sludge) has its part of waste which is hazardous (and is counted and reported together with the non-hazardous part)
CH_4	Energy > Fuel combustion activities (sectoral approach) > Energy industries > Public electricity and heat production > Heat plants > Solid fuels		Reported in 1A1a i Electricity generation
CH_4	Energy > Fuel combustion activities (sectoral approach) > Energy industries > Public electricity and heat production > Heat plants > Liquid fuels		Reported in 1A1a i Electricity generation
CH_4	Energy > Fuel combustion activities (sectoral approach) > Energy industries > Public electricity and heat production > Combined heat and power generation > Gaseous fuels		Reported in 1A1a i Electricity generation
CH_4	Energy > Fuel combustion activities (sectoral approach) > Energy industries > Public electricity and heat production > Combined heat and power generation > Biomass		Reported in 1A1a i Electricity generation
CH_4	Energy > Fuel combustion activities (sectoral approach) > Energy industries > Public electricity and heat production > Heat plants > Gaseous fuels		Reported in 1A1a i Electricity generation

CH_4	Waste > Incineration and open burning of waste > Open burning of waste > Biogenic > Municipal solid waste		Reported in 5.C.2.a.ii.Other waste
CH_4	Energy > Fuel combustion activities (sectoral approach) > Energy industries > Public electricity and heat production > Combined heat and power generation > Other fossil fuels		Reported in 1A1a i Electricity generation
CH_4	Energy > Fuel combustion activities (sectoral approach) > Energy industries > Public electricity and heat production > Heat plants > Other fossil fuels		Reported in 1A1a i Electricity generation
CH_4	Energy > Fuel combustion activities (sectoral approach) > Energy industries > Public electricity and heat production > Heat plants > Biomass		Reported in 1A1a i Electricity generation
CH_4	Waste > Incineration and open burning of waste > Open burning of waste > Non-biogenic > Municipal solid waste		Reported in 5.C.2.b.ii.Other waste
N_2O	Waste > Incineration and open burning of waste > Waste incineration > Non-biogenic > Other > Hazardous waste		Every other reported waste category (MSW, industrial, clinical and sewage sludge) has its part of waste which is hazardous (and is counted and reported together with the non-hazardous part)
N_2O	Energy > Fuel combustion activities (sectoral approach) > Energy industries > Public electricity and heat production > Combined heat and power generation > Solid fuels		Reported in 1A1a i Electricity generation

N_2O	Energy > Fuel combustion activities (sectoral approach) > Energy industries > Public electricity and heat production > Heat plants > Solid fuels		Data reported under Energy sector, 1.A.1.a
N_2O	Waste > Biological treatment of solid waste > Anaerobic digestion at biogas facilities > Municipal solid waste		Included in 5.C.1.2.b.i Other (Industrial Waste)
N_2O	Waste > Incineration and open burning of waste > Waste incineration > Non-biogenic > Other > Fossil liquid waste		Reported in 1A1a i Electricity generation
N_2O	Energy > Fuel combustion activities (sectoral approach) > Energy industries > Public electricity and heat production > Combined heat and power generation > Other fossil fuels		Reported in 1A1a i Electricity generation
N_2O	Energy > Fuel combustion activities (sectoral approach) > Energy industries > Public electricity and heat production > Combined heat and power generation > Liquid fuels		Reported in 5.C.2.a.ii.Other waste
N_2O	Waste > Incineration and open burning of waste > Open burning of waste > Biogenic > Municipal solid waste		Reported in 1A1a i Electricity generation
N_2O	Energy > Fuel combustion activities (sectoral approach) > Energy industries > Public electricity and heat production > Heat plants > Other fossil fuels		Reported in 1A1a i Electricity generation
N_2O	Energy > Fuel combustion activities (sectoral approach) > Energy industries > Public electricity and heat production > Combined heat and power generation > Biomass		Every other reported waste category (MSW, industrial, clinical and sewage sludge) has its part of waste which is hazardous (and is counted and reported together with the non-hazardous part)

N_2O	Waste > Incineration and open burning of waste > Waste incineration > Biogenic > Other > Hazardous waste		Reported in 1A1a i Electricity generation
N_2O	Energy > Fuel combustion activities (sectoral approach) > Energy industries > Public electricity and heat production > Heat plants > Biomass		Reported in 5.C.2.b.ii.Other waste
N_2O	Waste > Incineration and open burning of waste > Open burning of waste > Non-biogenic > Municipal solid waste		Reported in 1A1a i Electricity generation
N_2O	Energy > Fuel combustion activities (sectoral approach) > Energy industries > Public electricity and heat production > Combined heat and power generation > Gaseous fuels		Reported in 1A1a i Electricity generation
N_2O	Energy > Fuel combustion activities (sectoral approach) > Energy industries > Public electricity and heat production > Heat plants > Gaseous fuels		Reported in 1A1a i Electricity generation
N_2O	Energy > Fuel combustion activities (sectoral approach) > Energy industries > Public electricity and heat production > Heat plants > Liquid fuels		Reported in 1A1a i Electricity generation
N_2O	Sectors/Totals > Energy > Memo items > International bunkers > International navigation > Gas/Diesel oil		Relevant emissions are reported under category 1.A.3.d.